www.forgottenbooks.com

Copyright © 2016 FB &c Ltd.
All rights reserved. No part of this publication may be reproduced, distributed, or transmitted in any form or by any means, including photocopying, recording, or other electronic or mechanical methods, without the prior written permission of the publisher, except in the case of brief quotations embodied in critical reviews and certain other noncommercial uses permitted by copyright law.

HIGHER ALGEBRA

A SEQUEL TO

ELEMENTARY ALGEBRA FOR SCHOOLS.

HIGHER ALGEBRA

A SEQUEL TO

ELEMENTARY ALGEBRA FOR SCHOOLS

BY

H. S. HALL, M.A.,

FORMERLY SCHOLAR OF CHRIST'S COLLEGE, CAMBRIDGE,
MASTER OF THE MILITARY AND ENGINEERING SIDE, CLIFTON COLLEGE;

AND

S. R. KNIGHT, B.A.,

FORMERLY SCHOLAR OF TRINITY COLLEGE, CAMBRIDGE,
LATE ASSISTANT-MASTER AT MARLBOROUGH COLLEGE.

FOURTH EDITION.

London:
MACMILLAN AND CO.
AND NEW YORK.
1891

[*The Right of Translation is reserved.*]

42212

First Printed 1887.
Second Edition with corrections 1888.
Third Edition revised and enlarged 1889.
Reprinted 1890. *Fourth Edition* 1891.



PREFACE.

THE present work is intended as a sequel to our *Elementary Algebra for Schools.* The first few chapters are devoted to a fuller discussion of Ratio, Proportion, Variation, and the Progressions, which in the former work were treated in an elementary manner; and we have here introduced theorems and examples which are unsuitable for a first course of reading.

From this point the work covers ground for the most part new to the student, and enters upon subjects of special importance: these we have endeavoured to treat minutely and thoroughly, discussing both bookwork and examples with that fulness which we have always found necessary in our experience as teachers.

It has been our aim to discuss all the essential parts as completely as possible within the limits of a single volume, but in a few of the later chapters it has been impossible to find room for more than an introductory sketch; in all such cases our object has been to map out a suitable first course of reading, referring the student to special treatises for fuller information.

In the chapter on Permutations and Combinations we are much indebted to the Rev. W. A. Whitworth for permission to make use of some of the proofs given in his *Choice and Chance.* For many years we have used these proofs in our own teaching, and we are convinced that this

part of Algebra is made far more intelligible to the beginner by a system of common sense reasoning from first principles than by the proofs usually found in algebraical text-books.

The discussion of Convergency and Divergency of Series always presents great difficulty to the student on his first reading. The inherent difficulties of the subject are no doubt considerable, and these are increased by the place it has ordinarily occupied, and by the somewhat inadequate treatment it has hitherto received. Accordingly we have placed this section somewhat later than is usual; much thought has been bestowed on its general arrangement, and on the selection of suitable examples to illustrate the text; and we have endeavoured to make it more interesting and intelligible by previously introducing a short chapter on Limiting Values and Vanishing Fractions.

In the chapter on Summation of Series we have laid much stress on the "Method of Differences" and its wide and important applications. The basis of this method is a well-known formula in the Calculus of Finite Differences, which in the absence of a purely algebraical proof can hardly be considered admissible in a treatise on Algebra. The proof of the Finite Difference formula which we have given in Arts. 395, 396, we believe to be new and original, and the development of the Difference Method from this formula has enabled us to introduce many interesting types of series which have hitherto been relegated to a much later stage in the student's reading.

We have received able and material assistance in the chapter on Probability from the Rev. T. C. Simmons of Christ's College, Brecon, and our warmest thanks are due to him, both for his aid in criticising and improving the text, and for placing at our disposal several interesting and original problems.

It is hardly possible to read any modern treatise on Analytical Conics or Solid Geometry without some know-

ledge of Determinants and their applications. We have therefore given a brief elementary discussion of Determinants in Chapter XXXIII., in the hope that it may provide the student with a useful introductory course, and prepare him for a more complete study of the subject.

The last chapter contains all the most useful propositions in the Theory of Equations suitable for a first reading. The Theory of Equations follows so naturally on the study of Algebra that no apology is needed for here introducing propositions which usually find place in a separate treatise. In fact, a considerable part of Chapter XXXV. may be read with advantage at a much earlier stage, and may conveniently be studied before some of the harder sections of previous chapters.

It will be found that each chapter is as nearly as possible complete in itself, so that the order of their succession can be varied at the discretion of the teacher; but it is recommended that all sections marked with an asterisk should be reserved for a second reading.

In enumerating the sources from which we have derived assistance in the preparation of this work, there is one book to which it is difficult to say how far we are indebted. Todhunter's *Algebra for Schools and Colleges* has been the recognised English text-book for so long that it is hardly possible that any one writing a *text-book* on Algebra at the present day should not be largely influenced by it. At the same time, though for many years Todhunter's *Algebra* has been in constant use among our pupils, we have rarely adopted the order and arrangement there laid down; in many chapters we have found it expedient to make frequent use of alternative proofs; and we have always largely supplemented the text by manuscript notes. These notes, which now appear scattered throughout the present work, have been collected at different times during the last twenty

years, so that it is impossible to make definite acknowledgement in every case where assistance has been obtained from other writers. But speaking generally, our acknowledgements are chiefly due to the treatises of Schlömilch, Serret, and Laurent; and among English writers, besides Todhunter's *Algebra*, we have occasionally consulted the works of De Morgan, Colenso, Gross, and Chrystal.

To the Rev. J. Wolstenholme, D.Sc., Professor of Mathematics at the Royal Indian Engineering College, our thanks are due for his kindness in allowing us to select questions from his unique collection of problems; and the consequent gain to our later chapters we gratefully acknowledge.

It remains for us to express our thanks to our colleagues and friends who have so largely assisted us in reading and correcting the proof sheets; in particular we are indebted to the Rev. H. C. Watson of Clifton College for his kindness in revising the whole work, and for many valuable suggestions in every part of it.

May, 1887.

H. S. HALL,
S. R. KNIGHT.

PREFACE TO THE THIRD EDITION.

In this edition the text and examples are substantially the same as in previous editions, but a few articles have been recast, and all the examples have been verified again. We have also added a collection of three hundred Miscellaneous Examples which will be found useful for advanced students. These examples have been selected mainly but not exclusively from Scholarship or Senate House papers; much care has been taken to illustrate every part of the subject, and to fairly represent the principal University and Civil Service Examinations.

March, 1889.

CONTENTS.

CHAPTER I. RATIO.

PAGE

Commensurable and incommensurable quantities 2

Ratio of greater and less inequality 3

$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=\ldots=\left(\frac{pa^n+qc^n+re^n+\ldots}{pb^n+qd^n+rf^n+\ldots}\right)^{\frac{1}{n}}$ 4

$\frac{a_1+a_2+a_3+\ldots+a_n}{b_1+b_2+b_3+\ldots+b_n}$ lies between greatest and least of fractions $\frac{a^1}{b_1},\ldots\frac{a_n}{b_n}$ 6

Cross multiplication 8

Eliminant of three linear equations 9

Examples I. 10

CHAPTER II. PROPORTION.

Definitions and Propositions 13

Comparison between algebraical and geometrical definitions . . . 16

Case of incommensurable quantities 17

Examples II. 19

CHAPTER III. VARIATION.

If $A \propto B$, then $A=mB$ 21

Inverse variation 22

Joint variation 23

If $A \propto B$ when C is constant, and $A \propto C$ when B is constant, then

$A=mBC$ 23

Illustrations. Examples on joint variation 24

Examples III. 26

CHAPTER IV. ARITHMETICAL PROGRESSION.

PAGE

Sum of n terms of an arithmetical series 28
Fundamental formulæ 29
Insertion of arithmetic means 31
Examples IV. a. 31
Discussion of roots of $dn^2+(2a-d)n-2s=0$ 33
Examples IV. b. 35

CHAPTER V. GEOMETRICAL PROGRESSION.

Insertion of geometric means 38
Sum of n terms of a geometrical series 39
Sum of an infinite geometrical series 40
Examples V. a. 41
Proof of rule for the reduction of a recurring decimal 43
Sum of n terms of an arithmetico-geometric series 44
Examples V. b. 45

CHAPTER VI. HARMONICAL PROGRESSION. THEOREMS CONNECTED WITH THE PROGRESSIONS.

Reciprocals of quantities in H. P. are in A. P. 47
Harmonic mean 48
Formulæ connecting A.M., G.M., H.M. 49
Hints for solution of questions in Progressions 49
Sum of squares of the natural numbers 50
Sum of cubes of the natural numbers 51
Σ notation 52
Examples VI. a. 52
Number of shot in pyramid on a square base 54
Pyramid on a triangular base 54
Pyramid on a rectangular base 54
Incomplete pyramid 55
Examples VI. b. 56

CHAPTER VII. SCALES OF NOTATION.

Explanation of systems of notation 57
Examples VII. a. 59
Expression of an integral number in a proposed scale 59
Expression of a radix fraction in a proposed scale 61

PAGE

The difference between a number and the sum of its digits is divisible by $r-1$ 62
Proof of rule for "casting out the nines" 63
Test of divisibility by $r+1$ 64
Examples VII. b. 65

CHAPTER VIII. SURDS AND IMAGINARY QUANTITIES.

Rationalising the denominator of $\frac{a}{\sqrt{b}+\sqrt{c}+\sqrt{d}}$ 67
Rationalising factor of $\sqrt[p]{a}\pm\sqrt[q]{b}$ 68
Square root of $a+\sqrt{b}+\sqrt{c}+\sqrt{d}$ 69
Cube root of $a+\sqrt{b}$ 70
Examples VIII. a. 72
Imaginary quantities 74
$\sqrt{-a}\times\sqrt{-b}=-\sqrt{ab}$ 75
If $a+ib=0$, then $a=0$, $b=0$ 75
If $a+ib=c+id$, then $a=c$, $b=d$ 75
Modulus of product is equal to product of moduli 77
Square root of $a+ib$ 77
Powers of i 79
Cube roots of unity; $1+\omega+\omega^2=0$ 79
Powers of ω 80
Examples VIII. b. 81

CHAPTER IX. THE THEORY OF QUADRATIC EQUATIONS.

A quadratic equation cannot have more than two roots 83
Conditions for real, equal, imaginary roots 84
Sum of roots $=-\frac{b}{a}$, product of roots $=\frac{c}{a}$ 85
Formation of equations when the roots are given 86
Conditions that the roots of a quadratic should be (1) equal in magnitude and opposite in sign, (2) reciprocals 88
Examples IX. a. 88
For real values of x the expression ax^2+bx+c has in general the same sign as a; exceptions 90
Examples IX. b. 92
Definitions of *function*, *variable*, *rational integral function* . . . 93
Condition that $ax^2+2hxy+by^2+2gx+2fy+c$ may be resolved into two linear factors 94
Condition that $ax^2+bx+c=0$ and $a'x^2+b'x+c'=0$ may have a common root 95
Examples IX. c. 96

CHAPTER X. MISCELLANEOUS EQUATIONS.

PAGE

Equations involving one unknown quantity 97
Reciprocal equations 100
Examples X. a. 101
Equations involving two unknown quantities 103
Homogeneous equations 104
Examples X. b. 106
Equations involving several unknown quantities 107
Examples X. c. 109
Indeterminate equations; easy numerical examples 111
Examples X. d. 113

CHAPTER XI. PERMUTATIONS AND COMBINATIONS.

Preliminary proposition 115
Number of permutations of n things r at a time 115
Number of combinations of n things r at a time 117
The number of combinations of n things r at a time is equal to the number of combinations of n things $n-r$ at a time 119
Number of ways in which $m+n+p+\ldots$ things can be divided into classes containing m, n, p, ... things severally 120
Examples XI. a. 122
Signification of the terms 'like' and 'unlike' 124
Number of arrangements of n things taken all at a time, when p things are alike of one kind, q things are alike of a second kind, &c. . 125
Number of permutations of n things r at a time, when each may be repeated 126
The total number of combinations of n things 127
To find for what value of r the expression ${}^nC_r$ is greatest . . 127
Ab initio proof of the formula for the number of combinations of n things r at a time 128
Total number of selections of $p+q+r+\ldots$ things, whereof p are alike of one kind, q alike of a second kind, &c. 129
Examples XI. b. 131

CHAPTER XII. MATHEMATICAL INDUCTION.

Illustrations of the method of proof 133
Product of n binomial factors of the form $x+a$ 134
Examples XII. 135

CHAPTER XIII. BINOMIAL THEOREM. POSITIVE INTEGRAL INDEX.

PAGE

Expansion of $(x+a)^n$, when n is a positive integer 137
General term of the expansion 139
The expansion may be made to depend upon the case in which the first term is unity 140
Second proof of the binomial theorem 141
Examples XIII. a. 142
The coefficients of terms equidistant from the beginning and end are equal. 143
Determination of the greatest term 143
Sum of the coefficients 146
Sum of coefficients of odd terms is equal to sum of coefficients of even terms 146
Expansion of multinomials 146
Examples XIII. b. 147

CHAPTER XIV. BINOMIAL THEOREM. ANY INDEX.

Euler's proof of the binomial theorem for any index . 150
General term of the expansion of $(1+x)^n$ . . . 153
Examples XIV. a. 155
Expansion of $(1+x)^n$ is only arithmetically intelligible when $x<1$ 155
The expression $(x+y)^n$ can always be expanded by the binomial theorem 157
General term of the expansion of $(1-x)^{-n}$ 157
Particular cases of the expansions of $(1-x)^{-n}$ 158
Approximations obtained by the binomial theorem 159
Examples XIV. b. 161
Numerically greatest term in the expansion of $(1+x)^n$. 162
Number of homogeneous products of r dimensions formed out of n letters 164
Number of terms in the expansion of a multinomial 165
Number of combinations of n things r at a time, repetitions being allowed 166
Examples XIV. c. 167

CHAPTER XV. MULTINOMIAL THEOREM.

General term in the expansion of $(a+bx+cx^2+dx^3+\ldots)^p$, when p is a positive integer 170
General term in the expansion of $(a+bx+cx^2+dx^3+\ldots)^n$, when n is a rational quantity 171
Examples XV. 173

CHAPTER XVI. LOGARITHMS.

PAGE

Definition. $N = a^{\log_a N}$ 175
Elementary propositions 176
Examples XVI. a. 178
Common Logarithms 179
Determination of the characteristic by inspection 180
Advantages of logarithms to base 10 181
Advantages of always keeping the mantissa positive 182
Given the logarithms of all numbers to base a, to find the logarithms to base b 183
$\log_a b \times \log_b a = 1$ 183
Examples XVI. b. 185

CHAPTER XVII. EXPONENTIAL AND LOGARITHMIC SERIES.

Expansion of a^x. Series for e 187
e is the limit of $\left(1+\frac{1}{n}\right)^n$, when n is infinite 188
Expansion of $\log_e(1+x)$ 191
Construction of Tables of Logarithms 192
Rapidly converging series for $\log_e(n+1) - \log_e n$ 194
The quantity e is incommensurable 195
Examples XVII. 195

CHAPTER XVIII. INTEREST AND ANNUITIES.

Interest and Amount of a given sum at simple interest 198
Present Value and Discount of a given sum at simple interest 198
Interest and Amount of a given sum at compound interest . 199
Nominal and true annual rates of interest 200
Case of compound interest payable every moment . . 200
Present Value and Discount of a given sum at compound interest. 201
Examples XVIII. a. 202
Annuities. Definitions 202
Amount of unpaid annuity, simple interest 203
Amount of unpaid annuity, compound interest 203
Present value of an annuity, compound interest 204
Number of years' purchase 204
Present value of a deferred annuity, compound interest. 205
Fine for the renewal of a lease 206
Examples XVIII. b. 206

CHAPTER XIX. INEQUALITIES.

PAGE

Elementary Propositions 208

Arithmetic mean of two positive quantities is greater than the geometric mean 209

The sum of two quantities being given, their product is greatest when they are equal: product being given, the sum is least when they are equal 210

The arithmetic mean of a number of positive quantities is greater than the geometric mean 211

Given sum of $a, b, c, \ldots$; to find the greatest value of $a^m b^n c^p \ldots$ 212

Easy cases of maxima and minima 212

Examples XIX. a. 213

The arithmetic mean of the m^{th} powers of a number of positive quantities is greater than m^{th} power of their arithmetic mean, except when m lies between 0 and 1 214

If a and b are positive integers, and $a>b$, $\left(1+\frac{x}{a}\right)^a > \left(1+\frac{x}{b}\right)^b$ 216

If $1>x>y>0$, $\sqrt[x]{\frac{1+x}{1-x}} > \sqrt[y]{\frac{1+y}{1-y}}$ 217

$a^a b^b > \left(\frac{a+b}{2}\right)^{a+b}$ 217

Examples XIX. b. 218

CHAPTER XX. LIMITING VALUES AND VANISHING FRACTIONS.

Definition of *Limit* 220

Limit of $a_0+a_1x+a_2x^2+a_3x^3+\ldots$ is a_0 when x is zero . . 222

By taking x small enough, any term of the series $a_0+a_1x+a_2x^2+\ldots$ may be made as large as we please compared with the sum of all that follow it; and by taking x large enough, any term may be made as large as we please compared with the sum of all that precede it 222

Method of determining the limits of vanishing fractions 224

Discussion of some peculiarities in the solution of simultaneous equations 226

Peculiarities in the solution of quadratic equations 227

Examples XX. 228

CHAPTER XXI. CONVERGENCY AND DIVERGENCY OF SERIES.

Case of terms alternately positive and negative 230

Series is convergent if $Lim\ \frac{u_n}{u_{n-1}}$ is less than 1 232

PAGE

Comparison of Σu_n with an auxiliary series Σv_n 234

The auxiliary series $\frac{1}{1^p}+\frac{1}{2^p}+\frac{1}{3^p}+\dots$ 235

Application to Binomial, Exponential, Logarithmic Series 237

Limits of $\frac{\log n}{n}$ and nx^n when n is infinite 238

Product of an infinite number of factors 238

Examples XXI. a. 241

u-series is convergent when v-series is convergent, if $\frac{u_n}{u_{n-1}} > \frac{v_n}{v_{n-1}}$. 243

Series is convergent if $Lim\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)\right\}>1$ . . 244

Series is convergent if $Lim\left(n\log\frac{u_n}{u_{n+1}}\right)>1$ 245

Series $\Sigma\phi(n)$ compared with series $\Sigma a^n\phi(n)$ 247

The auxiliary series $\Sigma\frac{1}{n(\log n)^p}$ 248

Series is convergent if $Lim\left[\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)-1\right\}\log n\right]>1$ . . . 248

Product of two infinite series 249

Examples XXI. b.. 252

CHAPTER XXII. UNDETERMINED COEFFICIENTS.

If the equation $f(x)=0$ has more than n roots, it is an identity 254

Proof of principle of undetermined coefficients for finite series 254

Examples XXII. a. 256

Proof of principle of undetermined coefficients for infinite series 257

Examples XXII. b. 260

CHAPTER XXIII. PARTIAL FRACTIONS.

Decomposition into partial fractions 261

Use of partial fractions in expansions 265

Examples XXIII. 265

CHAPTER XXIV RECURRING SERIES.

Scale of relation 267

Sum of a recurring series 269

Generating function 269

Examples XXIV. 272

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

PAGE

Solution of $x^2 - Ny^2 = -1$ 305
General solution of $x^2 - Ny^2 = 1$ 306
Solution of $x^2 - n^2y^2 = a$ 308
Diophantine Problems 309
Examples XXVIII. 311

CHAPTER XXIX. SUMMATION OF SERIES.

Summary of previous methods 312
u_n the product of n factors in A. P. 314
u_n the reciprocal of the product of n factors in A. P. 316
Method of Subtraction 318
Expression of u_n as sum of factorials 318
Polygonal and Figurate Numbers 319
Pascal's Triangle 320
Examples XXIX. a. 321
Method of Differences 322
Method succeeds when u_n is a rational integral function of n 326
If a_n is a rational integral function of n, the series $\Sigma a_n x^n$ is a recurring series 327
Further cases of recurring series 329
Examples XXIX. b. 332
Miscellaneous methods of summation 334
Sum of series $1^r + 2^r + 3^r + \ldots + n^r$ 336
Bernoulli's Numbers 337
Examples XXIX. c. 338

CHAPTER XXX. THEORY OF NUMBERS.

Statement of principles 341
Number of primes is infinite 342
No rational algebraical formula can represent primes only . 342
A number can be resolved into prime factors in only one way 342
Number of divisors of a given integer 343
Number of ways an integer can be resolved into two factors 343
Sum of the divisors of a given integer 344
Highest power of a prime contained in $\lfloor n$ . . . 345
Product of r consecutive integers is divisible by $\lfloor r$ . . 345
Fermat's Theorem $N^{p-1} - 1 = M(p)$ where p is prime and N prime to p 347
Examples XXX. a. 348
Definition of *congruent* 350

PAG

If a is prime to b, then a, $2a$, $3a$, ... $(b-1)a$ when divided by b leave different remainders 35

$\phi(abcd...) = \phi(a)\,\phi(b)\,\phi(c)\,\phi(d)...$ 35

$\phi(N) = N\left(1-\frac{1}{a}\right)\left(1-\frac{1}{b}\right)\left(1-\frac{1}{c}\right)...$ 35

Wilson's Theorem: $1+\lfloor\underline{p-1} = M(p)$ where p is a prime 35

A property peculiar to prime numbers 35

Wilson's Theorem (second proof) 35

Proofs by induction 35

Examples XXX. b. 35

CHAPTER XXXI. THE GENERAL THEORY OF CONTINUE FRACTIONS.

Law of formation of successive convergents 35

$\frac{b_1}{a_1+}\ \frac{b_2}{a_2+}$ ... has a definite value if $Lim\ \frac{a_n a_{n+1}}{b_{n+1}} > 0$ 36

The convergents to $\frac{b_1}{a_1-}\ \frac{b_2}{a_2-}$ .. are positive proper fractions in ascending order of magnitude, if $a_n \nless 1+b_n$ 36

General value of convergent when a_n and b_n are constant 36

Cases where general value of convergent can be found 36

$\frac{b_1}{a_1+}\ \frac{b_2}{a_2+}$ .. is incommensurable, if $\frac{b_n}{a_n} < 1$ 36

Examples XXXI. a. 36

Series expressed as continued fractions 36

Conversion of one continued fraction into another 37

Examples XXXI. b. 37

CHAPTER XXXII. PROBABILITY.

Definitions and illustrations. Simple Events . . 37

Examples XXXII. a. 37

Compound Events 37

Probability that two independent events will both happen is pp' 37

The formula holds also for dependent events 37

Chance of an event which can happen in mutually exclusive ways 38

Examples XXXII. b. 38

Chance of an event happening exactly r times in n trials 38

Expectation and probable value 38

"Problem of points" 38

PAGE

Examples XXXII. c. 389
Inverse probability 391
Statement of Bernoulli's Theorem 392
Proof of formula $Q_r = \frac{p_r P_r}{\Sigma (pP)}$ 392
Concurrent testimony 396
Traditionary testimony 398
Examples XXXII. d. 399
Local Probability. Geometrical methods 401
Miscellaneous examples 402
Examples XXXII. e. 405

CHAPTER XXXIII. DETERMINANTS.

Eliminant of two homogeneous linear equations 409
Eliminant of three homogeneous linear equations 410
Determinant is not altered by interchanging rows and columns 410
Development of determinant of third order . . . 411
Sign of a determinant is altered by interchanging two adjacent rows or columns 412
If two rows or columns are identical, the determinant vanishes 412
A factor common to any row or column may be placed outside 412
Cases where constituents are made up of a number of terms . 413
Reduction of determinants by simplification of rows or columns 414
Product of two determinants 417
Examples XXXIII. a. 419
Application to solution of simultaneous equations 422
Determinant of fourth order 423
Determinant of any order 423
Notation $\Sigma \pm a_1 b_2 c_3 d_4$ 425
Examples XXXIII. b. 427

CHAPTER XXXIV. MISCELLANEOUS THEOREMS AND EXAMPLES.

Review of the fundamental laws of Algebra 429
$f(x)$ when divided by $x - a$ leaves remainder $f(a)$ 432
Quotient of $f(x)$ when divided by $x - a$ 433
Method of Detached Coefficients 434
Horner's Method of Synthetic Division 434
Symmetrical and Alternating Functions 435
Examples of identities worked out 437
List of useful formulæ 438

Examples XXXIV. a. . . . . .
Identities proved by properties of cube roots of unity . . . .
Linear factors of $a^3+b^3+c^3-3abc$ . . . . . .
Value of $a^n+b^n+c^n$ when $a+b+c=0$ . . . . . .
Examples XXXIV. b. . . . . .
Elimination . . . . . .
Elimination by symmetrical functions . . . . . .
Euler's method of elimination . . . . . .
Sylvester's Dialytic Method . . . . . .
Bezout's method . . . . . .
Miscellaneous examples of elimination . . . . . .
Examples XXXIV. c. . . . . .

CHAPTER XXXV. THEORY OF EQUATIONS.

Every equation of the n^{th} degree has n roots and no more
Relations between the roots and the coefficients . . . . .
These relations are not sufficient for the solution . . . . .
Cases of solution under given conditions . . . . . .
Easy cases of symmetrical functions of the roots . . . . .
Examples XXXV. a. . . . . .
Imaginary and surd roots occur in pairs . . . . . .
Formation and solution of equations with surd roots . . . .
Descartes' Rule of Signs . . . . . .
Examples XXXV. b. . . . . .
Value of $f(x+h)$. Derived Functions . . . . . .
Calculation of $f(x+h)$ by Horner's process . . . . . .
$f(x)$ changes its value gradually . . . . . .
If $f(a)$ and $f(b)$ are of contrary signs, $f(x)=0$ has a root between a and b 4
An equation of an odd degree has one real root 4
An equation of an even degree with its last term negative has two real roots 4
If $f(x)=0$ has r roots equal to a, $f'(x)=0$ has $r-1$ roots equal to a . 4
Determination of equal roots 4
$\frac{f'(x)}{f(x)}=\frac{1}{x-a}+\frac{1}{x-b}+\frac{1}{x-c}+\ldots$ . . . . . .
Sum of an assigned power of the roots 4
Examples XXXV. c. 4
Transformation of equations 4
Equation with roots of sign opposite to those of $f(x)=0$. 4
Equation with roots multiples of those of $f(x)=0$. 4

PAGE

Equation with roots reciprocals of those of $f(x)=0$ 472
Discussion of reciprocal equations 473
Equation with roots squares of those of $f(x)=0$ 475
Equation with roots exceeding by h those of $f(x)=0$ 475
Removal of an assigned term. 476
Equation with roots given functions of those of $f(x)=0$ 477
Examples XXXV. d. 478
Cubic equations. Cardan's Solution 480
Discussion of the solution 481
Solution by Trigonometry in the irreducible case 482
Biquadratic Equations. Ferrari's Solution 483
Descartes' Solution 484
Undetermined multipliers 486
Discriminating cubic; roots all real 486
Solution of three simultaneous equations $\frac{x}{a+\lambda}+\frac{y}{b+\lambda}+\frac{z}{c+\lambda}=1$, &c. . 487
Examples XXXV. e. 488
Miscellaneous Examples 490
Answers 525

HIGHER ALGEBRA.

CHAPTER I.

RATIO.

1. DEFINITION. **Ratio** is the relation which one quantity bears to another of the *same* kind, the comparison being made by considering what multiple, part, or parts, one quantity is of the other.

The ratio of A to B is usually written $A : B$. The quantities A and B are called the *terms* of the ratio. The first term is called the **antecedent**, the second term the **consequent**.

2. To find what multiple or part A is of B, we divide A by B; hence the ratio $A : B$ may be measured by the fraction $\frac{A}{B}$, and we shall usually find it convenient to adopt this notation.

In order to compare two quantities they must be expressed in terms of the same unit. Thus the ratio of £2 to 15*s.* is measured by the fraction $\frac{2 \times 20}{15}$ or $\frac{8}{3}$.

NOTE. A ratio expresses the *number* of times that one quantity contains another, and therefore *every ratio is an abstract quantity.*

3. Since by the laws of fractions,

$$\frac{a}{b} = \frac{ma}{mb},$$

it follows that the ratio $a : b$ is equal to the ratio $ma : mb$; that is, *the value of a ratio remains unaltered if the antecedent and the consequent are multiplied or divided by the same quantity.*

4. Two or more ratios may be compared by reducing their equivalent fractions to a common denominator. Thus suppose $a : b$ and $x : y$ are two ratios. Now $\frac{a}{b} = \frac{ay}{by}$, and $\frac{x}{y} = \frac{bx}{by}$, hence the ratio $a : b$ is greater than, equal to, or less than the ratio $x : y$ according as ay is greater than, equal to, or less than bx.

5. The ratio of two fractions can be expressed as a ratio of two integers. Thus the ratio $\frac{a}{b} : \frac{c}{d}$ is measured by the fraction $\frac{\frac{a}{b}}{\frac{c}{d}}$, or $\frac{ad}{bc}$; and is therefore equivalent to the ratio $ad : bc$.

6. If either, or both, of the terms of a ratio be a surd quantity, then no two integers can be found which will *exactly* measure their ratio. Thus the ratio $\sqrt{2} : 1$ cannot be exactly expressed by any two integers.

7. DEFINITION. If the ratio of any two quantities can be expressed exactly by the ratio of two integers, the quantities are said to be **commensurable**; otherwise, they are said to be **incommensurable.**

Although we cannot find two integers which will exactly measure the ratio of two incommensurable quantities, we can always find two integers whose ratio differs from that required by as small a quantity as we please.

Thus $$\frac{\sqrt{5}}{4} = \frac{2{\cdot}236068\ldots}{4} = {\cdot}559017\ldots$$

and therefore $$\frac{\sqrt{5}}{4} > \frac{559017}{1000000} \text{ and } < \frac{559018}{1000000};$$

so that the difference between the ratios 559017 : 1000000 and $\sqrt{5} : 4$ is less than ·000001. By carrying the decimals further, a closer approximation may be arrived at.

8. DEFINITION. Ratios are *compounded* by multiplying together the fractions which denote them; or by multiplying together the antecedents for a new antecedent, and the consequents for a new consequent.

Example. Find the ratio compounded of the three ratios

$$2a : 3b,\ 6ab : 5c^2,\ c : a$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

The proof of the following important theorem will illustrate the method of procedure.

If $$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=\ldots\ldots,$$

each of these ratios $=\left(\dfrac{pa^n+qc^n+re^n+\ldots}{pb^n+qd^n+rf^n+\ldots}\right)^{\frac{1}{n}}$,

where p, q, r, n *are any quantities whatever.*

Let $$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=\ldots=k;$$

then $$a=bk,\ \ c=dk,\ \ e=fk,\ldots;$$

whence $$pa^n=pb^nk^n,\ \ qc^n=qd^nk^n,\ \ re^n=rf^nk^n,\ldots;$$

$$\therefore\ \frac{pa^n+qc^n+re^n+\ldots}{pb^n+qd^n+rf^n+\ldots}=\frac{pb^nk^n+qd^nk^n+rf^nk^n+\ldots}{pb^n+qd^n+rf^n+\ldots}$$

$$=k^n;$$

$$\therefore\ \left(\frac{pa^n+qc^n+re^n+\ldots}{pb^n+qd^n+rf^n+\ldots}\right)^{\frac{1}{n}}=k=\frac{a}{b}=\frac{c}{d}=\ldots$$

By giving different values to p, q, r, n many particular cases of this general proposition may be deduced; or they may be proved independently by using the same method. For instance,

if $$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=\ldots,$$

each of these ratios $=\dfrac{a+c+e+\ldots}{b+d+f+\ldots}$;

a result of such frequent utility that the following verbal equivalent should be noticed: *When a series of fractions are equal, each of them is equal to the sum of all the numerators divided by the sum of all the denominators.*

Example 1. If $\dfrac{a}{b}=\dfrac{c}{d}=\dfrac{e}{f}$, shew that

$$\frac{a^3b+2c^2e-3ae^2f}{b^4+2d^2f-3bf^3}=\frac{ace}{bdf}.$$

Let $$\frac{a}{b}=\frac{c}{d}=\frac{e}{f}=k;$$

then $$a=bk,\ c=dk,\ e=fk;$$

$$\therefore \quad \frac{a^3b+2c^2e-3ae^2f}{b^4+2d^2f-3bf^3}=\frac{b^4k^3+2d^2fk^3-3bf^3k^3}{b^4+2d^2f-3bf^3}$$

$$=k^3=\frac{a}{b}\times\frac{c}{d}\times\frac{e}{f}$$

$$=\frac{ace}{bdf}.$$

Example 2. If $\frac{x}{a}-\frac{y}{b}-\frac{z}{c}$, prove that

$$\frac{x^2+a^2}{x+a}+\frac{y^2+b^2}{y+b}+\frac{z^2+c^2}{z+c}=\frac{(x+y+z)^2+(a+b+c)^2}{x+y+z+a+b+c}.$$

Let $\frac{x}{a}=\frac{y}{b}-\frac{z}{c}=k$, so that $x=ak$, $y=bk$, $z=ck$;

then
$$\frac{x^2+a^2}{x+a}=\frac{a^2k^2+a^2}{ak+a}=\frac{(k^2+1)\,a}{k+1};$$

$$\therefore \quad \frac{x^2+a^2}{x+a}+\frac{y^2+b^2}{y+b}+\frac{z^2+c^2}{z+c}=\frac{(k^2+1)\,a}{k+1}+\frac{(k^2+1)\,b}{k+1}+\frac{(k^2+1)\,c}{k+1}$$

$$=\frac{(k^2+1)\,(a+b+c)}{k+1}$$

$$=\frac{k^2\,(a+b+c)^2+(a+b+c)^2}{k\,(a+b+c)+a+b+c}$$

$$=\frac{(ka+kb+kc)^2+(a+b+c)^2}{(ka+kb+kc)+a+b+c}$$

$$=\frac{(x+y+z)^2+(a+b+c)^2}{x+y+z+a+b+c}.$$

13. If an equation is homogeneous with respect to certain quantities, we may for these quantities substitute in the equation any others proportional to them. For instance, the equation

$$lx^3y+mxy^2z+ny^2z^2=0$$

is homogeneous in x, y, z. Let α, β, γ be three quantities proportional to x, y, z respectively.

Put $k=\frac{x}{\alpha}-\frac{y}{\beta}=\frac{z}{\gamma}$, so that $x=\alpha k$, $y=\beta k$, $z=\gamma k$;

then
$$l\alpha^3\beta k^4+m\alpha\beta^2\gamma k^4+n\beta^2\gamma^2k^4=0,$$

that is,
$$l\alpha^3\beta+m\alpha\beta^2\gamma+n\beta^2\gamma^2=0;$$

an equation of the same form as the original one, but with α, β, γ in the places of x, y, z respectively.

14. The following theorem is important.

If $\frac{a_1}{b_1}, \frac{a_2}{b_2}, \frac{a_3}{b_3}, \ldots \frac{a_n}{b_n}$ *be unequal fractions, of which the denominators are all of the same sign, then the fraction*

$$\frac{a_1 + a_2 + a_3 + \ldots + a_n}{b_1 + b_2 + b_3 + \ldots + b_n}$$

lies in magnitude between the greatest and least of them.

Suppose that all the denominators are positive. Let $\frac{a_r}{b_r}$ be the least fraction, and denote it by k; then

$$\frac{a_r}{b_r} = k; \qquad a_r = kb_r;$$

$$\frac{a_1}{b_1} > k; \qquad \therefore\ a_1 > kb_1;$$

$$\frac{a_2}{b_2} > k; \qquad \therefore\ a_2 > kb_2;$$

and so on;

$\therefore$ by addition,

$$a_1 + a_2 + a_3 + \ldots\ldots + a_n > (b_1 + b_2 + b_3 + \ldots\ldots + b_n)\, k;$$

$$\therefore\ \frac{a_1 + a_2 + a_3 + \ldots\ldots + a_n}{b_1 + b_2 + b_3 + \ldots\ldots + b_n} > k; \text{ that is, } > \frac{a_r}{b_r}.$$

Similarly we may prove that

$$\frac{a_1 + a_2 + a_3 + \ldots\ldots + a_n}{b_1 + b_2 + b_3 + \ldots\ldots + b_n} < \frac{a_s}{b_s},$$

where $\frac{a_s}{b_s}$ is the greatest of the given fractions.

In like manner the theorem may be proved when all the denominators are negative.

15. The ready application of the *general principle* involved in Art. 12 is of such great value in all branches of mathematics, that the student should be able to use it with some freedom in any particular case that may arise, without necessarily introducing an auxiliary symbol.

Example 1. If $\frac{x}{b+c-a} = \frac{y}{c+a-b} = \frac{z}{a+b-c}$,

prove that $\frac{x+y+z}{a+b+c} = \frac{x(y+z)+y(z+x)+z(x+y)}{2(ax+by+cz)}$.

$$\text{Each of the given fractions} = \frac{\text{sum of numerators}}{\text{sum of denominators}}$$

$$= \frac{x+y+z}{a+b+c} \text{ ....(1).}$$

Again, if we multiply both numerator and denominator of the three given fractions by $y+z$, $z+x$, $x+y$ respectively,

$$\text{each fraction} = \frac{x(y+z)}{(y+z)(b+c-a)} = \frac{y(z+x)}{(z+x)(c+a-b)} = \frac{z(x+y)}{(x+y)(a+b-c)}$$

$$= \frac{\text{sum of numerators}}{\text{sum of denominators}}$$

$$= \frac{x(y+z)+y(z+x)+z(x+y)}{2ax+2by+2cz} \text{ ..... (2).}$$

from (1) and (2),

$$\frac{x+y+z}{a+b+c} = \frac{x(y+z)+y(z+x)+z(x+y)}{2(ax+by+cz)}.$$

Example 2. If $\dfrac{x}{l(mb+nc-la)} = \dfrac{y}{m(nc+la-mb)} = \dfrac{z}{n(la+mb-nc)}$,

prove that $\dfrac{l}{x(by+cz-ax)} = \dfrac{m}{y(cz+ax-by)} = \dfrac{n}{z(ax+by-cz)}$.

We have $\dfrac{\frac{x}{l}}{mb+nc-la} = \dfrac{\frac{y}{m}}{nc+la-mb} = \dfrac{\frac{z}{n}}{la+mb-nc}$

$$= \frac{\frac{y}{m}+\frac{z}{n}}{2la}$$

= two similar expressions;

$$\therefore \quad \frac{ny+mz}{a} = \frac{lz+nx}{b} = \frac{mx+ly}{c}.$$

Multiply the first of these fractions above and below by x, the second by y, and the third by z; then

$$\frac{nxy+mxz}{ax} = \frac{lyz+nxy}{by} = \frac{mxz+lyz}{cz}$$

$$= \frac{2lyz}{by+cz-ax}$$

= two similar expressions;

$$\therefore \quad \frac{l}{x(by+cz-ax)} = \frac{m}{y(cz+ax-by)} = \frac{n}{z(ax+by-cz)}.$$

16. If we have *two* equations containing *three* unknown quantities in the first degree, such as

$$a_1x + b_1y + c_1z = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1),$$

$$a_2x + b_2y + c_2z = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2),$$

we cannot solve these completely; but by writing them in the form

$$a_1\left(\frac{x}{z}\right) + b_1\left(\frac{y}{z}\right) + c_1 = 0,$$

$$a_2\left(\frac{x}{z}\right) + b_2\left(\frac{y}{z}\right) + c_2 = 0,$$

we can, by regarding $\frac{x}{z}$ and $\frac{y}{z}$ as the unknowns, solve in the ordinary way and obtain

$$\frac{x}{z} = \frac{b_1c_2 - b_2c_1}{a_1b_2 - a_2b_1}, \qquad \frac{y}{z} = \frac{c_1a_2 - c_2a_1}{a_1b_2 - a_2b_1};$$

or, more symmetrically,

$$\frac{x}{b_1c_2 - b_2c_1} = \frac{y}{c_1a_2 - c_2a_1} = \frac{z}{a_1b_2 - a_2b_1} \quad \ldots\ldots\ldots\ldots(3).$$

It thus appears that when we have two equations of the type represented by (1) and (2) we may always by the above formula write down the *ratios* $x : y : z$ in terms of the coefficients of the equations by the following rule:

Write down the coefficients of x, y, z in order, beginning with those of y; and repeat these as in the diagram.



Multiply the coefficients across in the way indicated by the arrows, remembering that in forming the products any one obtained by descending is positive, and any one obtained by ascending is negative. The three results

$$b_1c_2 - b_2c_1, \quad c_1a_2 - c_2a_1, \quad a_1b_2 - a_2b_1$$

are proportional to x, y, z respectively.

This is called the **Rule of Cross Multiplication.**

Example 1. Find the ratios of $x : y : z$ from the equations

$$7x = 4y + 8z, \quad 3z = 12x + 11y.$$

By transposition we have $7x - 4y - 8z = 0,$

$$12x + 11y - 3z = 0.$$

Write down the coefficients, thus

$$\begin{matrix} -4 & -8 & 7 & -4 \\ 11 & -3 & 12 & 11, \end{matrix}$$

whence we obtain the products

$$(-4)\times(-3) - 11\times(-8), \quad (-8)\times 12 - (-3)\times 7, \quad 7\times 11 \quad 12\times(-4),$$

or

$$100, \quad -75, \quad 125;$$

$$\therefore \quad \frac{x}{100} = \frac{y}{-75} = \frac{z}{125},$$

that is,

$$\frac{x}{4} = \frac{y}{-3} = \frac{z}{5}.$$

Example 2. Eliminate x, y, z from the equations

$$a_1x + b_1y + c_1z = 0 \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1),$$

$$a_2x + b_2y + c_2z = 0 \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2),$$

$$a_3x + b_3y + c_3z = 0 \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(3).$$

From (2) and (3), by cross multiplication,

$$\frac{x}{b_2c_3 - b_3c_2} = \frac{y}{c_2a_3 - c_3a_2} = \frac{z}{a_2b_3 - a_3b_2};$$

denoting each of these ratios by k, by multiplying up, substituting in (1), and dividing out by k, we obtain

$$a_1(b_2c_3 - b_3c_2) + b_1(c_2a_3 - c_3a_2) + c_1(a_2b_3 - a_3b_2) = 0.$$

This relation is called the **eliminant** of the given equations.

Example 3. Solve the equations

$$ax + by + cz = 0 \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1),$$

$$x + y + z = 0 \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2),$$

$$bcx + cay + abz = (b-c)(c-a)(a-b) \ldots\ldots\ldots\ldots\ldots (3).$$

From (1) and (2), by cross multiplication,

$$\frac{x}{b-c} = \frac{y}{c-a} = \frac{z}{a-b} = k, \text{ suppose};$$

$$x = k(b-c), \; y = k(c-a), \; z = k(a-b).$$

Substituting in (3),

$$k\{bc(b-c) + ca(c-a) + ab(a-b)\} = (b-c)(c-a)(a-b),$$

$$k\{-(b-c)(c-a)(a-b)\} = (b-c)(c-a)(a-b);$$

$$\therefore \; k = -1;$$

whence

$$x = c-b, \; y = a-c, \; z = b-a.$$

17. If in Art. 16 we put $z = 1$, equations (1) and (2) become

$$a_1x + b_1y + c_1 = 0,$$
$$a_2x + b_2y + c_2 = 0;$$

and (3) becomes

$$\frac{x}{b_1c_2 - b_2c_1} = \frac{y}{c_1a_2 - c_2a_1} = \frac{1}{a_1b_2 - a_2b_1};$$

or
$$x = \frac{b_1c_2 - b_2c_1}{a_1b_2 - a_2b_1},\ y = \frac{c_1a_2 - c_2a_1}{a_1b_2 - a_2b_1}.$$

Hence any two simultaneous equations involving two unknowns in the first degree may be solved by the rule of cross multiplication.

Example. Solve $5x - 3y - 1 = 0,\ x + 2y = 12.$

By transposition,
$$5x - 3y - 1 = 0,$$
$$x + 2y - 12 = 0;$$

$$\therefore\ \frac{x}{36+2} = \frac{y}{-1+60} = \frac{1}{10+3};$$

whence
$$x = \frac{38}{13},\ y - \frac{59}{13}.$$

EXAMPLES. I.

1. Find the ratio compounded of

(1) the ratio $2a : 3b$, and the duplicate ratio of $9b^2 \quad ab$.

(2) the subduplicate ratio of $64 : 9$, and the ratio $27 : 56$.

(3) the duplicate ratio of $\frac{2a}{b} : \frac{\sqrt{6a^2}}{b^2}$, and the ratio $3ax : 2by$.

2. If $x+7 : 2(x+14)$ in the duplicate ratio of $5 : 8$, find x.

3. Find two numbers in the ratio of $7 : 12$ so that the greater exceeds the less by 275.

4. What number must be added to each term of the ratio $5 : 37$ to make it equal to $1 : 3$?

5. If $x : y = 3 : 4$, find the ratio of $7x - 4y : 3x + y$.

6. If $15(2x^2 - y^2) = 7xy$, find the ratio of $x : y$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

18. If $x=cy+bz,\ y=az+cx,\ z=bx+ay,$

shew that $$\frac{x^2}{1-a^2}=\frac{y^2}{1-b^2}=\frac{z^2}{1-c^2}.$$

19. Given that $a(y+z)=x,\ b(z+x)=y,\ c(x+y)=z,$

prove that $$bc+ca+ab+2abc=1.$$

Solve the following equations:

20.
$$3x-4y+7z=0,$$
$$2x-y-2z=0,$$
$$3x^3-y^3+z^3=18.$$

21.
$$x+y=z,$$
$$3x-2y+17z=0$$
$$x^3+3y^3+2z^3=167.$$

22.
$$7yz+3zx=4xy,$$
$$21yz-3zx=4xy,$$
$$x+2y+3z=19.$$

23.
$$3x^2-2y^2+5z^2=0,$$
$$7x^2-3y^2-15z^2=0,$$
$$5x-4y+7z=6.$$

24. If $$\frac{l}{\sqrt{a}-\sqrt{b}}+\frac{m}{\sqrt{b}-\sqrt{c}}+\frac{n}{\sqrt{c}-\sqrt{a}}=0,$$
$$\frac{l}{\sqrt{a}+\sqrt{b}}+\frac{m}{\sqrt{b}+\sqrt{c}}+\frac{n}{\sqrt{c}+\sqrt{a}}=0,$$

shew that $$\frac{l}{(a-b)(c-\sqrt{ab})}=\frac{m}{(b-c)(a-\sqrt{bc})}=\frac{n}{(c-a)(b-\sqrt{ac})}.$$

Solve the equations:

25.
$$ax+by+cz=0,$$
$$bcx+cay+abz=0,$$
$$xyz+abc(a^3x+b^3y+c^3z)=0.$$

26.
$$ax+by+cz=a^2x+b^2y+c^2z=0,$$
$$x+y+z+(b-c)(c-a)(a-b)=0.$$

27. If $a(y+z)=x,\ b(z+x)=y,\ c(x+y)=z,$

prove that $$\frac{x^2}{a(1-bc)}=\frac{y^2}{b(1-ca)}=\frac{z^2}{c(1-ab)}.$$

28. If $ax+hy+gz=0,\ hx+by+fz=0,\ gx+fy+cz=0,$

prove that

(1) $$\frac{x^2}{bc-f^2}=\frac{y^2}{ca-g^2}=\frac{z^2}{ab-h^2}.$$

(2) $$(bc-f^2)(ca-g^2)(ab-h^2)=(fg-ch)(gh-af)(hf-bg).$$

CHAPTER II.

PROPORTION.

18. DEFINITION. When two ratios are equal, the four quantities composing them are said to be **proportionals.** Thus if $\frac{a}{b} = \frac{c}{d}$, then a, b, c, d are proportionals. This is expressed by saying that a is to b as c is to d, and the proportion is written

$$a : b :: c : d;$$

or

$$a : b = c : d.$$

The terms a and d are called the *extremes*, b and c the *means*.

19. *If four quantities are in proportion, the product of the extremes is equal to the product of the means.*

Let a, b, c, d be the proportionals.

Then by definition $$\frac{a}{b} = \frac{c}{d};$$

whence $$ad = bc.$$

Hence if any three terms of a proportion are given, the fourth may be found. Thus if a, c, d are given, then $b = \frac{ad}{c}$.

Conversely, if there are any four quantities, a, b, c, d, such that $ad = bc$, then a, b, c, d are proportionals; a and d being the extremes, b and c the means; or vice versâ.

20. DEFINITION. Quantities are said to be in **continued proportion** when the first is to the second, as the second is to the third, as the third to the fourth; and so on. Thus a, b, c, d,..... are in continued proportion when

$$\frac{a}{b} = \frac{b}{c} = \frac{c}{d} = \text{.....}$$

If three quantities a, b, c are in continued proportion, then

$$a : b = b : c;$$

$$ac = b^2. \qquad \text{[Art. 18.]}$$

In this case b is said to be a **mean proportional** between a and c; and c is said to be a **third proportional** to a and b.

21. *If three quantities are proportionals the first is to the third in the duplicate ratio of the first to the second.*

Let the three quantities be a, b, c; then $\frac{a}{b} = \frac{b}{c}$.

Now
$$\frac{a}{c} = \frac{a}{b} \times \frac{b}{c}$$

$$= \frac{a}{b} \times \frac{a}{b} = \frac{a^2}{b^2};$$

that is,
$$a : c = a^2 : b^2.$$

It will be seen that this proposition is the same as the *definition* of duplicate ratio given in Euclid, Book v.

22. If $a : b = c : d$ and $e : f = g : h$, then will $ae : bf = cg : dh$.

For
$$\frac{a}{b} = \frac{c}{d} \text{ and } \frac{e}{f} = \frac{g}{h};$$

$$\therefore \frac{ae}{bf} = \frac{cg}{dh},$$

or
$$ae : bf = cg : dh.$$

Cor. If
$$a : b = c : d,$$

and
$$b : x = d : y,$$

then
$$a : x = c : y.$$

This is the theorem known as *ex æquali* in Geometry.

23. If four quantities a, b, c, d form a proportion, many other proportions may be deduced by the properties of fractions. The results of these operations are very useful, and some of them are often quoted by the annexed names borrowed from Geometry.

(1) If $a : b = c : d$, then $b : a = d : c$. [*Invertendo.*]

For $\frac{a}{b} - \frac{c}{d}$; therefore $1 \cdot \frac{a}{b} = 1 \div \frac{c}{d}$;

that is $$\frac{b}{a} = \frac{d}{c};$$

or $$b : a = d : c.$$

(2) If $a : b = c : d$, then $a : c = b : d$. [*Alternando.*]

For $ad = bc$; therefore $\frac{ad}{cd} = \frac{bc}{cd}$,

that is, $$\frac{a}{c} = \frac{b}{d};$$

or $$a : c = b : d.$$

(3) If $a : b = c : d$, then $a + b : b = c + d \quad d$. [*Componendo.*]

For $\frac{a}{b} = \frac{c}{d}$; therefore $\frac{a}{b} + 1 = \frac{c}{d} + 1$;

that is $$\frac{a+b}{b} = \frac{c+d}{d};$$

or $$a + b : b = c + d : d.$$

(4) If $a : b = c : d$, then $a - b : b = c - d : d$. [*Dividendo.*]

For $\frac{a}{b} = \frac{c}{d}$, therefore $\frac{a}{b} - 1 = \frac{c}{d} - 1$;

that is, $$\frac{a-b}{b} = \frac{c-d}{d};$$

or $$a - b : b = c - d : d.$$

(5) If $a : b = c : d$, then $a + b : a - b = c + d \quad c \quad d$.

For by (3) $$\frac{a+b}{b} = \frac{c+d}{d};$$

and by (4) $$\frac{a-b}{b} = \frac{c-d}{d};$$

by division, $$\frac{a+b}{a-b} = \frac{c+d}{c-d};$$

or $$a + b : a - b = c + d : c - d.$$

This proposition is usually quoted as *Componendo and Dividendo.*

Several other proportions may be proved in a similar way.

24. The results of the preceding article are the algebraical equivalents of some of the propositions in the fifth book of Euclid, and the student is advised to make himself familiar with them in their verbal form. For example, *dividendo* may be quoted as follows

When there are four proportionals, the excess of the first above the second is to the second, as the excess of the third above the fourth is to the fourth.

25. We shall now compare the algebraical definition of proportion with that given in Euclid.

Euclid's definition is as follows:

Four quantities are said to be proportionals when if *any equimultiples whatever* be taken of the first and third, and also *any equimultiples whatever* of the second and fourth, the multiple of the third is greater than, equal to, or less than the multiple of the fourth, according as the multiple of the first is greater than, equal to, or less than the multiple of the second.

In algebraical symbols the definition may be thus stated:

Four quantities a, b, c, d are in proportion when $pc \gtreqless qd$ according as $pa \gtreqless qb$, p and q being *any positive integers whatever.*

I. To deduce the geometrical definition of proportion from the algebraical definition.

Since $\frac{a}{b} = \frac{c}{d}$, by multiplying both sides by $\frac{p}{q}$, we obtain

$$\frac{pa}{qb} = \frac{pc}{qd};$$

hence, from the properties of fractions,

$$pc \gtreqless qd \text{ according as } pa \gtreqless qb,$$

which proves the proposition.

II. To deduce the algebraical definition of proportion from the geometrical definition.

Given that $pc \gtreqless qd$ according as $pa \gtreqless qb$, to prove

$$\frac{a}{b} = \frac{c}{d}.$$

If $\frac{a}{b}$ is not equal to $\frac{c}{d}$, one of them must be the greater. Suppose $\frac{a}{b} > \frac{c}{d}$; then it will be possible to find some fraction $\frac{q}{p}$ which lies between them, q and p being positive integers.

Hence $$\frac{a}{b} > \frac{q}{p} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1),$$

and $$\frac{c}{d} < \frac{q}{p} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

From (1) $$pa > qb\,;$$

from (2) $$pc < qd\,;$$

and these contradict the hypothesis.

Therefore $\frac{a}{b}$ and $\frac{c}{d}$ are not unequal; that is $\frac{a}{b} = \frac{c}{d}$; which proves the proposition.

26. It should be noticed that the geometrical definition of proportion deals with *concrete* magnitudes, such as lines or areas, represented geometrically but not referred to any common unit of measurement. So that Euclid's definition is applicable to incommensurable as well as to commensurable quantities; whereas the algebraical definition, strictly speaking, applies only to commensurable quantities, since it tacitly assumes that a is the same determinate multiple, part, or parts, of b that c is of d. But the proofs which have been given for commensurable quantities will still be true for incommensurables, since the ratio of two incommensurables can always be made to differ from the ratio of two integers *by less than any assignable quantity*. This has been shewn in Art. 7; it may also be proved more generally as in the next article.

27. Suppose that a and b are incommensurable; divide b into m equal parts each equal to β, so that $b = m\beta$, where m is a positive integer. Also suppose β is contained in a more than n times and less than $n+1$ times;

then $$\frac{a}{b} > \frac{n\beta}{m\beta} \text{ and } < \frac{(n+1)\beta}{m\beta},$$

that is, $\frac{a}{b}$ lies between $\frac{n}{m}$ and $\frac{n+1}{m}$;

so that $\frac{a}{b}$ differs from $\frac{n}{m}$ by a quantity less than $\frac{1}{m}$. And since we

can choose β (our unit of measurement) as small as we please, m can be made as great as we please. Hence $\frac{1}{m}$ can be made as small as we please, and two integers n and m can be found whose ratio will express that of a and b to any required degree of accuracy.

28. The propositions proved in Art. 23 are often useful in solving problems. In particular, the solution of certain equations is greatly facilitated by a skilful use of the operations *componendo* and *dividendo*.

Example 1.

If $(2ma+6mb+3nc+9nd)(2ma-6mb-3nc+9nd)$
$-(2ma-6mb+3nc-9nd)(2ma+6mb-3nc-9nd)$,

prove that a, b, c, d are proportionals.

We have $$\frac{2ma+6mb+3nc+9nd}{2ma-6mb+3nc-9nd}=\frac{2ma+6mb-3nc-9nd}{2ma-6mb-3nc+9nd};$$

componendo and dividendo,

$$\frac{2(2ma+3nc)}{2(6mb+9nd)}=\frac{2(2ma-3nc)}{2(6mb-9nd)}.$$

Alternando, $$\frac{2ma+3nc}{2ma-3nc}=\frac{6mb+9nd}{6mb-9nd}.$$

Again, componendo and dividendo,

$$\frac{4ma}{6nc}=\frac{12mb}{18nd};$$

whence $$\frac{a}{c}=\frac{b}{d},$$

or $$a:b=c:d.$$

Example 2. Solve the equation

$$\frac{\sqrt{x+1}+\sqrt{x-1}}{\sqrt{x+1}-\sqrt{x-1}}=\frac{4x-1}{2}.$$

We have, componendo and dividendo,

$$\frac{\sqrt{x+1}}{\sqrt{x-1}}=\frac{4x+1}{4x-3};$$

$$\therefore \frac{x+1}{x-1}=\frac{16x^2+8x+1}{16x^2-24x+9}.$$

Again, componendo and dividendo,

$$\frac{2x}{2}=\frac{32x^2-16x+10}{32x-8},$$

$$\therefore x=\frac{16x^2-8x+5}{16x-4};$$

whence $$16x^2-4x=16x^2-8x+5;$$

$$\therefore x=\frac{5}{4}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

18. If the work done by $x-1$ men in $x+1$ days is to the work done by $x+2$ men in $x-1$ days in the ratio of 9 : 10, find x.

19. Find four proportionals such that the sum of the extremes is 21, the sum of the means 19, and the sum of the squares of all four numbers is 442.

20. Two casks A and B were filled with two kinds of sherry, mixed in the cask A in the ratio of 2 : 7, and in the cask B in the ratio of 1 : 5. What quantity must be taken from each to form a mixture which shall consist of 2 gallons of one kind and 9 gallons of the other?

21. Nine gallons are drawn from a cask full of wine; it is then filled with water, then nine gallons of the mixture are drawn, and the cask is again filled with water. If the quantity of wine now in the cask be to the quantity of water in it as 16 to 9, how much does the cask hold?

22. If four positive quantities are in continued proportion, shew that the difference between the first and last is at least three times as great as the difference between the other two.

23. In England the population increased 15·9 per cent. between 1871 and 1881; if the town population increased 18 per cent. and the country population 4 per cent., compare the town and country populations in 1871.

24. In a certain country the consumption of tea is five times the consumption of coffee. If a per cent. more tea and b per cent. more coffee were consumed, the aggregate amount consumed would be $7c$ per cent. more; but if b per cent. more tea and a per cent. more coffee were consumed, the aggregate amount consumed would be $3c$ per cent. more: compare a and b.

25. Brass is an alloy of copper and zinc; bronze is an alloy containing 80 per cent. of copper, 4 of zinc, and 16 of tin. A fused mass of brass and bronze is found to contain 74 per cent. of copper, 16 of zinc, and 10 of tin: find the ratio of copper to zinc in the composition of brass.

26. A crew can row a certain course up stream in 84 minutes; they can row the same course down stream in 9 minutes less than they could row it in still water: how long would they take to row down with the stream?

CHAPTER III.

VARIATION.

29. DEFINITION. One quantity A is said to **vary directly** as another B, when the two quantities depend upon each other in such a manner that if B is changed, A is changed *in the same ratio.*

NOTE. The word *directly* is often omitted, and A is said to vary as B.

For instance: if a train moving at a uniform rate travels 40 miles in 60 minutes, it will travel 20 miles in 30 minutes, 80 miles in 120 minutes, and so on; the distance in each case being increased or diminished in the same ratio as the time. This is expressed by saying that when the velocity is uniform *the distance is proportional to the time*, or *the distance varies as the time.*

30. The symbol $\propto$ is used to denote variation; so that $A \propto B$ is read "A varies as B."

31. *If* A *varies as* B, *then* A *is equal to* B *multiplied by some constant quantity.*

For suppose that $a, a_1, a_2, a_3 \ldots, b, b_1, b_2, b_3 \ldots$ are corresponding values of A and B.

Then, by definition, $\frac{a}{a_1} = \frac{b}{b_1}$; $\frac{a}{a_2} = \frac{b}{b_2}$; $\frac{a}{a_3} = \frac{b}{b_3}$; and so on,

$$\therefore \frac{a_1}{b_1} = \frac{a_2}{b_2} = \frac{a_3}{b_3} = \ldots, \text{ each being equal to } \frac{a}{b}.$$

Hence $\dfrac{\text{any value of } A}{\text{the corresponding value of } B}$ is always the same;

that is, $\dfrac{A}{B} = m$, where m is constant.

$$\therefore A = mB.$$

If any pair of corresponding values of A and B are known, the constant m can be determined. For instance, if $A = 3$ when $B = 12$,

we have $$3 = m \times 12;$$

$$m = \tfrac{1}{4},$$

and $$A = \tfrac{1}{4} B.$$

32. DEFINITION. One quantity A is said to **vary inversely** as another B, when A varies *directly* as the reciprocal of B.

Thus if A varies inversely as B, $A = \frac{m}{B}$, where m is constant.

The following is an illustration of inverse variation: If 6 men do a certain work in 8 hours, 12 men would do the same work in 4 hours, 2 men in 24 hours; and so on. Thus it appears that when the number of men is increased, the time is proportionately decreased; and vice-versâ.

Example 1. The cube root of x varies inversely as the square of y; if $x = 8$ when $y = 3$, find x when $y = 1\frac{1}{2}$.

By supposition $\sqrt[3]{x} = \frac{m}{y^2}$, where m is constant.

Putting $x = 8$, $y = 3$, we have $$2 = \frac{m}{9},$$

$$\therefore m = 18,$$

and $$\sqrt[3]{x} = \frac{18}{y^2};$$

hence, by putting $y = \frac{3}{2}$, we obtain $x = 512$.

Example 2. The square of the time of a planet's revolution varies as the cube of its distance from the Sun; find the time of Venus' revolution, assuming the distances of the Earth and Venus from the Sun to be $91\frac{1}{4}$ and 66 millions of miles respectively.

Let P be the periodic time measured in days, D the distance in millions of miles; we have $$P^2 \propto D^3,$$

or $$P^2 = kD^3,$$

where k is some constant.

For the Earth, $$365 \times 365 = k \times 91\tfrac{1}{4} \times 91\tfrac{1}{4} \times 91\tfrac{1}{4},$$

whence $$k = \frac{4 \times 4 \times 4}{365};$$

$$P^2 = \frac{4 \times 4 \times 4}{365} D^3.$$

For Venus, $$P^2=\frac{4\times4\times4}{365}\times66\times66\times66;$$

whence $$P=4\times66\times\sqrt{\frac{264}{365}}$$

$$-264\times\sqrt{\cdot7233}, \text{ approximately,}$$
$$-264\times\cdot85$$
$$-224\cdot4.$$

Hence the time of revolution is nearly $224\frac{1}{2}$ days.

33. DEFINITION. One quantity is said to **vary jointly** as a number of others, when it varies directly as their product.

Thus A varies jointly as B and C, when $A=mBC$. For instance, the interest on a sum of money varies jointly as the principal, the time, and the rate per cent.

34. DEFINITION. A is said to vary directly as B and inversely as C, when A varies as $\frac{B}{C}$.

35. *If* A *varies as* B *when* C *is constant, and* A *varies as* C *when* B *is constant, then will* A *vary as* BC *when both* B *and* C *vary.*

The variation of A depends partly on that of B and partly on that of C. Suppose these latter variations to take place separately, each in its turn producing its own effect on A; also let a, b, c be certain simultaneous values of A, B, C.

1. *Let C be constant* while B changes to b; then A must undergo a partial change and will assume some intermediate value a', where

$$\frac{A}{a'}=\frac{B}{b} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

2. *Let B be constant*, that is, let it retain its value b, while C changes to c; then A must complete its change and pass from its intermediate value a' to its final value a, where

$$\frac{a'}{a}=\frac{C}{c} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$$

From (1) and (2) $$\frac{A}{a'}\times\frac{a'}{a}=\frac{B}{b}\times\frac{C}{c};$$

that is, $$A=\frac{a}{bc}\,.\,BC,$$

or A varies as BC.

36. The following are illustrations of the theorem proved in the last article.

The amount of work done by *a given number of men* varies directly as the number of days they work, and the amount of work done *in a given time* varies directly as the number of men; therefore when the number of days and the number of men are both variable, the amount of work will vary as the product of the number of men and the number of days.

Again, in Geometry the area of a triangle varies directly as its base when the height is constant, and directly as the height when the base is constant; and when both the height and base are variable, the area varies as the product of the numbers representing the height and the base.

Example. The volume of a right circular cone varies as the square of the radius of the base when the height is constant, and as the height when the base is constant. If the radius of the base is 7 feet and the height 15 feet, the volume is 770 cubic feet; find the height of a cone whose volume is 132 cubic feet and which stands on a base whose radius is 3 feet.

Let h and r denote respectively the height and radius of the base measured in feet; also let V be the volume in cubic feet.

Then $V = mr^2h$, where m is constant.

By supposition, $$770 = m \times 7^2 \times 15;$$

whence $$m = \frac{22}{21};$$

$$V = \frac{22}{21} r^2 h.$$

$\therefore$ by substituting $V = 132$, $r = 3$, we get

$$132 = \frac{22}{21} \times 9 \times h;$$

whence $$h = 14;$$

and therefore the height is 14 feet.

37. The proposition of Art. 35 can easily be extended to the case in which the variation of A depends upon that of more than two variables. Further, the variations may be either direct or inverse. The principle is interesting because of its frequent occurrence in Physical Science. For example, in the theory of gases it is found by experiment that the pressure (p) of a gas varies as the "absolute temperature" (t) when its volume (v) is constant, and that the pressure varies inversely as the volume when the temperature is constant; that is

$p \propto t$, when v is constant;

and $$p \propto \frac{1}{v}, \text{ when } t \text{ is constant.}$$

From these results we should expect that, when both t and v are variable, we should have the formula

$$p \propto \frac{t}{v}, \text{ or } pv = kt, \text{ where } k \text{ is constant;}$$

and by actual experiment this is found to be the case.

Example. The duration of a railway journey varies directly as the distance and inversely as the velocity; the velocity varies directly as the square root of the quantity of coal used per mile, and inversely as the number of carriages in the train. In a journey of 25 miles in half an hour with 18 carriages 10 cwt. of coal is required; how much coal will be consumed in a journey of 21 miles in 28 minutes with 16 carriages?

Let t be the time expressed in hours,
d the distance in miles,
v the velocity in miles per hour,
q the quantity of coal in cwt.,
c the number of carriages.

We have $$t \propto \frac{d}{v},$$

and $$v \propto \frac{\sqrt{q}}{c},$$

whence $$t \propto \frac{cd}{\sqrt{q}},$$

or $$t = \frac{kcd}{\sqrt{q}}, \text{ where } k \text{ is constant.}$$

Substituting the values given, we have

$$\frac{1}{2} = \frac{k \times 18 \times 25}{\sqrt{10}};$$

that is, $$k = \frac{\sqrt{10}}{25 \times 36}.$$

Hence $$t = \frac{\sqrt{10} \,.\, cd}{25 \times 36 \sqrt{q}}.$$

Substituting now the values of t, c, d given in the second part of the question, we have

$$\frac{28}{60} = \frac{\sqrt{10} \times 16 \times 21}{25 \times 36 \sqrt{q}};$$

that is, $$\sqrt{q} = \frac{\sqrt{10} \times 16 \times 21}{15 \times 28} = \frac{4}{5}\sqrt{10};$$

whence $$q = \frac{32}{5} = 6\tfrac{2}{5}.$$

Hence the quantity of coal is $6\frac{2}{5}$ cwt.

EXAMPLES. III.

1. If x varies as y, and $x=8$ when $y=15$, find x when $y=10$.

2. If P varies inversely as Q, and $P=7$ when $Q=3$, find P when $Q=2\frac{1}{3}$.

3. If the square of x varies as the cube of y, and $x=3$ when $y=4$, find the value of y when $x=\frac{1}{\sqrt{3}}$.

4. A varies as B and C jointly; if $A=2$ when $B=\frac{3}{5}$ and $C=\frac{10}{27}$, find C when $A=54$ and $B=3$.

5. If A varies as C, and B varies as C, then $A+B$ and $\sqrt{AB}$ will each vary as C.

6. If A varies as BC, then B varies inversely as $\frac{C}{A}$.

7. P varies directly as Q and inversely as R; also $P=\frac{2}{3}$ when $Q=\frac{3}{7}$ and $R=\frac{9}{14}$: find Q when $P=\sqrt{48}$ and $R=\sqrt{75}$.

8. If x varies as y, prove that x^2+y^2 varies as x^2-y^2

9. If y varies as the sum of two quantities, of which one varies directly as x and the other inversely as x; and if $y=6$ when $x=4$, and $y=3\frac{1}{3}$ when $x=3$; find the equation between x and y.

10. If y is equal to the sum of two quantities one of which varies as x directly, and the other as x^2 inversely; and if $y=19$ when $x=2$, or 3; find y in terms of x.

11. If A varies directly as the square root of B and inversely as the cube of C, and if $A=3$ when $B=256$ and $C=2$, find B when $A=24$ and $C=\frac{1}{2}$.

12. Given that $x+y$ varies as $z+\frac{1}{z}$, and that $x-y$ varies as $z-\frac{1}{z}$, find the relation between x and z, provided that $z=2$ when $x=3$ and $y=1$.

13. If A varies as B and C jointly, while B varies as D^2, and C varies inversely as A, shew that A varies as D.

14. If y varies as the sum of three quantities of which the first is constant, the second varies as x, and the third as x^2; and if $y=0$ when $x=1$, $y=1$ when $x=2$, and $y=4$ when $x=3$; find y when $x=7$.

15. When a body falls from rest its distance from the starting point varies as the square of the time it has been falling: if a body falls through $402\frac{1}{2}$ feet in 5 seconds, how far does it fall in 10 seconds? Also how far does it fall in the 10^{th} second?

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

CHAPTER IV.

ARITHMETICAL PROGRESSION.

38. DEFINITION. Quantities are said to be in **Arithmetical Progression** when they increase or decrease by a *common difference.*

Thus each of the following series forms an Arithmetical Progression:

$3,\ 7,\ 11,\ 15,\ldots\ldots\ldots\ldots\ldots$

$8,\ 2,\ -4,\ -10,\ldots\ldots\ldots\ldots\ldots$

$a,\ a+d,\ a+2d,\ a+3d,\ \ldots\ldots\ldots$

The common difference is found by subtracting *any* term of the series from that which *follows* it. In the first of the above examples the common difference is 4; in the second it is -6; in the third it is d.

39. If we examine the series

$$a,\ a+d,\ a+2d,\ a+3d,\ldots$$

we notice that *in any term the coefficient of* d *is always less by one than the number of the term in the series.*

Thus the 3^{rd} term is $a+2d$;

6^{th} term is $a+5d$;

20^{th} term is $a+19d$;

and, generally, the p^{th} term is $a+(p-1)d$.

If n be the number of terms, and if l denote the last, or n^{th} term, we have $l=a+(n-1)d$.

40. *To find the sum of a number of terms in Arithmetical Progression.*

Let a denote the first term, d the common difference, and n the number of terms. Also let l denote the last term, and s

the required sum; then

$$s = a + (a+d) + (a+2d) + \ldots + (l-2d) + (l-d) + l;$$

and, by writing the series in the reverse order,

$$s = l + (l-d) + (l-2d) + \ldots + (a+2d) + (a+d) + a.$$

Adding together these two series,

$$2s = (a+l) + (a+l) + (a+l) + \ldots \text{ to } n \text{ terms}$$
$$= n(a+l),$$
$$\therefore\ s = \frac{n}{2}(a+l) \ldots\ldots (1);$$

and
$$l = a + (n-1)d \ldots\ldots (2),$$

$$s = \frac{n}{2}\{2a + (n-1)d\} \ldots\ldots (3).$$

41. In the last article we have three useful formulæ (1), (2), (3); in each of these any one of the letters may denote the unknown quantity when the three others are known. For instance, in (1) if we substitute given values for s, n, l, we obtain an equation for finding a; and similarly in the other formulæ. But it is necessary to guard against a too mechanical use of these general formulæ, and it will often be found better to solve simple questions by a mental rather than by an actual reference to the requisite formula.

Example 1. Find the sum of the series $5\frac{1}{2}$, $6\frac{3}{4}$, 8,.....to 17 terms.
Here the common difference is $1\frac{1}{4}$; hence from (3),

the sum
$$= \frac{17}{2}\left\{2 \times \frac{11}{2} + 16 \times 1\tfrac{1}{4}\right\}$$
$$= \frac{17}{2}(11+20)$$
$$= \frac{17 \times 31}{2}$$
$$= 263\tfrac{1}{2}.$$

Example 2. The first term of a series is 5, the last 45, and the sum 400: find the number of terms, and the common difference.

If n be the number of terms, then from (1)

$$400 = \frac{n}{2}(5+45);$$

whence
$$n = 16.$$

If d be the common difference

$$45 = \text{the } 16^{\text{th}} \text{ term} = 5 + 15d;$$

whence $$d = 2\tfrac{2}{3}.$$

42. If *any two* terms of an Arithmetical Progression be given, the series can be completely determined; for the data furnish *two* simultaneous equations, the solution of which will give the first term and the common difference.

Example. The 54^{th} and 4^{th} terms of an A. P. are -61 and 64; find the 23^{rd} term.

If a be the first term, and d the common difference,

$$61 = \text{the } 54^{\text{th}} \text{ term} = a + 53d;$$

and

$$64 = \text{the } 4^{\text{th}} \text{ term} = a + 3d;$$

whence we obtain $$d = -\frac{5}{2},\ a = 71\tfrac{1}{2};$$

and the 23^{rd} term $= a + 22d = 16\tfrac{1}{2}$.

43. DEFINITION. When three quantities are in Arithmetical Progression the middle one is said to be the **arithmetic mean** of the other two.

Thus a is the arithmetic mean between $a - d$ and $a + d$.

44. *To find the arithmetic mean between two given quantities.*

Let a and b be the two quantities; A the arithmetic mean. Then since a, A, b are in A.P. we must have

$$b - A = A - a,$$

each being equal to the common difference;

whence $$A = \frac{a + b}{2}.$$

45. Between two given quantities it is always possible to insert any number of terms such that the whole series thus formed shall be in A.P.; and by an extension of the definition in Art. 43, the terms thus inserted are called the *arithmetic means.*

Example. Insert 20 arithmetic means between 4 and 67.

Including the extremes, the number of terms will be 22; so that we have to find a series of 22 terms in A.P., of which 4 is the first and 67 the last.

Let d be the common difference;

then $$67 = \text{the } 22^{\text{nd}} \text{ term} = 4 + 21d;$$

whence $d = 3$, and the series is 4, 7, 10,.....61, 64, 67;
and the required means are 7, 10, 13,.....58, 71, 64.

46. *To insert a given number of arithmetic means between two given quantities.*

Let a and b be the given quantities, n the number of means.

Including the extremes the number of terms will be $n+2$; so that we have to find a series of $n+2$ terms in A.P., of which a is the first, and b is the last.

Let d be the common difference;

then $$b = \text{the } (n+2)^{\text{th}} \text{ term}$$

$$= a + (n+1)\,d;$$

whence $$d = \frac{b-a}{n+1};$$

and the required means are

$$a + \frac{b-a}{n+1}, \quad a + \frac{2\,(b-a)}{n+1}, \ldots\ldots a + \frac{n\,(b-a)}{n+1}$$

Example 1. The sum of three numbers in A.P. is 27, and the sum of their squares is 293; find them.

Let a be the *middle* number, d the common difference; then the three numbers are $a-d$, a, $a+d$.

Hence $$a-d+a+a+d=27;$$

whence $a=9$, and the three numbers are $9-d$, 9, $9+d$.

$$\therefore\ (9-d)^2+81+(9+d)^2=293;$$

whence $$d=\pm 5;$$

and the numbers are 4, 9, 14.

Example 2. Find the sum of the first p terms of the series whose n^{th} term is $3n-1$.

By putting $n=1$, and $n=p$ respectively, we obtain

$$\text{first term}=2, \quad \text{last term}=3p-1;$$

$$\therefore\ \text{sum}=\frac{p}{2}(2+3p-1)=\frac{p}{2}(3p+1).$$

EXAMPLES. IV. a.

1. Sum $2, 3\frac{1}{4}, 4\frac{1}{2}, \ldots$ to 20 terms.
2. Sum 49, 44, 39,... to 17 terms.
3. Sum $\frac{3}{4}, \frac{2}{3}, \frac{7}{12}, \ldots$ to 19 terms.

4. Sum 3, $\frac{7}{3}$, $1\frac{2}{3}$,... to n terms.

5. Sum 3·75, 3·5, 3·25,... to 16 terms.

6. Sum $-7\frac{1}{2}$, -7, $-6\frac{1}{2}$,... to 24 terms.

7. Sum 1·3, $-3\cdot1$, $-7\cdot5$,... to 10 terms.

8. Sum $\frac{6}{\sqrt{3}}$, $3\sqrt{3}$, $\frac{12}{\sqrt{3}}$,... to 50 terms.

9. Sum $\frac{3}{\sqrt{5}}$, $\frac{4}{\sqrt{5}}$, $\sqrt{5}$,... to 25 terms.

10. Sum $a-3b$, $2a-5b$, $3a-7b$,... to 40 terms.

11. Sum $2a-b$, $4a-3b$, $6a-5b$,... to n terms.

12. Sum $\frac{a+b}{2}$, a, $\frac{3a-b}{2}$,... to 21 terms.

13. Insert 19 arithmetic means between $\frac{1}{4}$ and $-9\frac{3}{4}$.

14. Insert 17 arithmetic means between $3\frac{1}{2}$ and $-41\frac{1}{2}$.

15. Insert 18 arithmetic means between $-35x$ and $3x$.

16. Insert x arithmetic means between x^2 and 1.

17. Find the sum of the first n odd numbers.

18. In an A. P. the first term is 2, the last term 29, the sum 155; find the difference.

19. The sum of 15 terms of an A. P. is 600, and the common difference is 5; find the first term.

20. The third term of an A. P. is 18, and the seventh term is 30; find the sum of 17 terms.

21. The sum of three numbers in A. P. is 27, and their product is 504; find them.

22. The sum of three numbers in A. P. is 12, and the sum of their cubes is 408; find them.

23. Find the sum of 15 terms of the series whose n^{th} term is $4n+1$.

24. Find the sum of 35 terms of the series whose p^{th} term is $\frac{p}{7}+2$.

25. Find the sum of p terms of the series whose n^{th} term is $\frac{n}{a}+b$.

26. Find the sum of n terms of the series

$$\frac{2a^2-1}{a},\ 4a-\frac{3}{a},\ \frac{6a^2-5}{a},\ldots$$

47. In an Arithmetical Progression when s, a, d are given, to determine the values of n we have the quadratic equation

$$s = \frac{n}{2}\left\{2a + (n-1)d\right\};$$

when both roots are positive and integral there is no difficulty in interpreting the result corresponding to each. In some cases a suitable interpretation can be given for a negative value of n.

Example. How many terms of the series -9, -6, -3,... must be taken that the sum may be 66?

Here $$\frac{n}{2}\{-18 + (n-1)\,3\} = 66;$$

that is, $$n^2 - 7n - 44 = 0,$$

or $$(n-11)\,(n+4) = 0;$$

$$n = 11 \text{ or } -4.$$

If we take 11 terms of the series, we have

$$-9,\ -6,\ -3,\ 0,\ 3,\ 6,\ 9,\ 12,\ 15,\ 18,\ 21;$$

the sum of which is 66.

If we begin at the *last* of these terms and *count backwards* four terms, the sum is also 66; and thus, although the negative solution does not directly answer the question proposed, we are enabled to give it an intelligible meaning, and we see that it answers a question closely connected with that to which the positive solution applies.

48. We can justify this interpretation in the general case in the following way.

The equation to determine n is

$$dn^2 + (2a - d)\,n - 2s = 0 \ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Since in the case under discussion the roots of this equation have opposite signs, let us denote them by n_1 and $-n_2$. The last term of the series corresponding to n_1 is

$$a + (n_1 - 1)\,d;$$

if we begin at this term and count *backwards*, the common difference must be denoted by $-d$, and the sum of n_2 terms is

$$\frac{n_2}{2}\left\{2\,(a + \overline{n_1 - 1}d) + (n_2 - 1)\,(-d)\right\},$$

and we shall shew that this is equal to s.

$$\text{For the expression} = \frac{n_2}{2}\left\{2a + (2n_1 - n_2 - 1)\,d\right\}$$

$$= \frac{1}{2}\left\{2an_2 + 2n_1n_2d - n_2(n_2 + 1)\,d\right\}$$

$$= \frac{1}{2}\left\{2n_1n_2d - (dn_2^2 - \overline{2a - d}\,.\,n_2)\right\}$$

$$= \frac{1}{2}(4s - 2s) = s,$$

since $-n_2$ satisfies $dn^2 + (2a - d)\,n - 2s = 0$, and $-n_1n_2$ is the product of the roots of this equation.

49. When the value of n is fractional there is no exact number of terms which corresponds to such a solution.

Example. How many terms of the series 26, 21, 16,...must be taken to amount to 74?

Here $$\frac{n}{2}\{52 + (n-1)(-5)\} = 74;$$

that is, $$5n^2 - 57n + 148 = 0$$

or $$(n-4)(5n-37) = 0;$$

$$n = 4 \text{ or } 7\tfrac{2}{5}.$$

Thus the number of terms is 4. It will be found that the sum of 7 terms is greater, while the sum of 8 terms is less than 74.

50. We add some Miscellaneous Examples.

Example 1. The sums of n terms of two arithmetic series are in the ratio of $7n+1 : 4n+27$; find the ratio of their 11th terms.

Let the first term and common difference of the two series be a_1, d_1 and a_2, d_2 respectively.

We have $$\frac{2a_1 + (n-1)\,d_1}{2a_2 + (n-1)\,d_2} = \frac{7n+1}{4n+27}.$$

Now we have to find the value of $\dfrac{a_1 + 10d_1}{a_2 + 10d_2}$; hence, by putting $n = 21$, we obtain

$$\frac{2a_1 + 20d_1}{2a_2 + 20d_2} = \frac{148}{111} = \frac{4}{3};$$

thus the required ratio is 4 : 3.

Example 2. If S_1, S_2, S_3,...S_p are the sums of n terms of arithmetic series whose first terms are 1, 2, 3, 4,... and whose common differences are 1, 3, 5, 7,...; find the value of

$$S_1 + S_2 + S_3 + \ldots + S_p.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

9. Sum the series $\frac{1}{1+\sqrt{x}}, \frac{1}{1-x}, \frac{1}{1-\sqrt{x}}$, ... to n terms.

10. If the sum of 7 terms is 49, and the sum of 17 terms is 289, find the sum of n terms.

11. If the p^{th}, q^{th}, r^{th} terms of an A. P. are a, b, c respectively, shew that
$$(q-r)\,a+(r-p)\,b+(p-q)\,c=0.$$

12. The sum of p terms of an A. P. is q, and the sum of q terms is p; find the sum of $p+q$ terms.

13. The sum of four integers in A. P. is 24, and their product is 945; find them.

14. Divide 20 into four parts which are in A. P., and such that the product of the first and fourth is to the product of the second and third in the ratio of 2 to 3.

15. The p^{th} term of an A. P. is q, and the q^{th} term is p; find the m^{th} term.

16. How many terms of the series 9, 12, 15,... must be taken to make 306?

17. If the sum of n terms of an A. P. is $2n+3n^2$, find the r^{th} term.

18. If the sum of m terms of an A. P. is to the sum of n terms as m^2 to n^2, shew that the m^{th} term is to the n^{th} term as $2m-1$ is to $2n-1$.

19. Prove that the sum of an odd number of terms in A. P. is equal to the middle term multiplied by the number of terms.

20. If $s=n\,(5n-3)$ for all values of n, find the p^{th} term.

21. The number of terms in an A. P. is even; the sum of the odd terms is 24, of the even terms 30, and the last term exceeds the first by $10\frac{1}{2}$: find the number of terms.

22. There are two sets of numbers each consisting of 3 terms in A. P. and the sum of each set is 15. The common difference of the first set is greater by 1 than the common difference of the second set, and the product of the first set is to the product of the second set as 7 to 8: find the numbers.

23. Find the relation between x and y in order that the r^{th} mean between x and $2y$ may be the same as the r^{th} mean between $2x$ and y, n means being inserted in each case.

24. If the sum of an A. P. is the same for p as for q terms, shew that its sum for $p+q$ terms is zero.

CHAPTER V.

GEOMETRICAL PROGRESSION.

51. DEFINITION. Quantities are said to be in **Geometrical Progression** when they increase or decrease by a *constant factor*.

Thus each of the following series forms a Geometrical Progression:

$$3,\ 6,\ 12,\ 24,\ \ldots\ldots\ldots\ldots$$

$$1,\ \frac{1}{3},\ \frac{1}{9},\ -\frac{1}{27},\ \ldots\ldots\ldots$$

$$a,\ ar,\ ar^2,\ ar^3,\ \ldots\ldots\ldots\ldots$$

The constant factor is also called the *common ratio*, and it is found by dividing *any* term by that which immediately *precedes* it. In the first of the above examples the common ratio is 2; in the second it is $-\frac{1}{3}$; in the third it is r.

52. If we examine the series

$$a,\ ar,\ ar^2,\ ar^3,\ ar^4,\quad \ldots$$

we notice that *in any term the index of* r *is always less by one than the number of the term in the series.*

Thus the 3rd term is ar^2;

the 6th term is ar^5;

the 20th term is ar^{19};

and, generally, the p^{th} term is ar^{p-1}

If n be the number of terms, and if l denote the last, or n^{th} term, we have $l = ar^{n-1}$

53. DEFINITION. When three quantities are in Geometrical Progression the middle one is called the **geometric mean** between the other two.

To find the geometric mean between two given quantities.

Let a and b be the two quantities; G the geometric mean. Then since a, G, b are in G. P.,

$$\frac{b}{G} = \frac{G}{a},$$

each being equal to the common ratio;

$$\therefore \quad G^2 = ab;$$

whence $$G = \sqrt{ab}.$$

54. *To insert a given number of geometric means between two given quantities.*

Let a and b be the given quantities, n the number of means.

In all there will be $n+2$ terms; so that we have to find a series of $n+2$ terms in G. P., of which a is the first and b the last.

Let r be the common ratio;

then $$b = \text{the } (n+2)^{\text{th}} \text{ term}$$

$$= ar^{n+1};$$

$$r^{n+1} = \frac{b}{a};$$

$$\therefore \ r = \left(\frac{b}{a}\right)^{\frac{1}{n+1}} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Hence the required means are ar, ar^2,... ar^n, where r has the value found in (1).

Example. Insert 4 geometric means between 160 and 5.

We have to find 6 terms in G. P. of which 160 is the first, and 5 the sixth.

Let r be the common ratio;

$$\text{then } 5 = \text{the sixth term}$$

$$= 160r^5;$$

$$\therefore \ r^5 = \frac{1}{32};$$

whence $$r = \frac{1}{2};$$

and the means are 80, 40, 20, 10.

55. *To find the sum of a number of terms in Geometrical Progression.*

Let a be the first term, r the common ratio, n the number of terms, and s the sum required. Then

$$s = a + ar + ar^2 + \quad . + ar^{n-2} + ar^{n-1};$$

multiplying every term by r, we have

$$rs = ar + ar^2 + \ldots\ldots + ar^{n-2} + ar^{n-1} + ar^n$$

Hence by subtraction,

$$rs - s = ar^n - a;$$

$$\therefore (r-1)s = a(r^n - 1);$$

$$\therefore s = \frac{a(r^n-1)}{r-1} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Changing the signs in numerator and denominator,

$$s = \frac{a(1-r^n)}{1-r} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

NOTE. It will be found convenient to remember both forms given above for s, using (2) in all cases except when r is *positive and greater than* 1.

Since $ar^{n-1} = l$, the formula (1) may be written

$$s = \frac{rl-a}{r-1};$$

a form which is sometimes useful.

Example. Sum the series $\frac{2}{3}, -1, \frac{3}{2}, \ldots\ldots$ to 7 terms.

The common ratio $= -\frac{3}{2}$; hence by formula (2)

the sum

$$= \frac{\frac{2}{3}\left\{1 - \left(-\frac{3}{2}\right)^7\right\}}{1 + \frac{3}{2}}$$

$$= \frac{\frac{2}{3}\left\{1 + \frac{2187}{128}\right\}}{\frac{5}{2}}$$

$$= \frac{2}{3} \times \frac{2315}{128} \times \frac{2}{5}$$

$$= \frac{463}{96}.$$

56. Consider the series $1, \frac{1}{2}, \frac{1}{2^2}, \frac{1}{2^3}, \ldots\ldots$

The sum to n terms $= \dfrac{1-\frac{1}{2^n}}{1-\frac{1}{2}}$

$$= 2\left(1-\frac{1}{2^n}\right)$$

$$= 2-\frac{1}{2^{n-1}}.$$

From this result it appears that however many terms be taken the sum of the above series is always less than 2. Also we see that, by making n sufficiently large, we can make the fraction $\frac{1}{2^{n-1}}$ as small as we please. Thus by taking a sufficient number of terms the sum can be made to differ by as little as we please from 2.

In the next article a more general case is discussed.

57. From Art. 55 we have $s = \dfrac{a(1-r^n)}{1-r}$

$$= \frac{a}{1-r} - \frac{ar^n}{1-r}.$$

Suppose r is a proper fraction; then the greater the value of n the smaller is the value of r^n, and consequently of $\frac{ar^n}{1-r}$; and therefore by making n sufficiently large, we can make the sum of n terms of the series differ from $\frac{a}{1-r}$ by as small a quantity as we please.

This result is usually stated thus: *the sum of an infinite number of terms of a decreasing Geometrical Progression is* $\frac{a}{1-r}$; or more briefly, *the sum to infinity is* $\frac{a}{1-r}$.

Example 1. Find three numbers in G. P. whose sum is 19, and whose product is 216.

Denote the numbers by $\frac{a}{r}, a, ar$; then $\frac{a}{r} \times a \times ar = 216$; hence $a = 6$, and the numbers are $\frac{6}{r}, 6, 6r$.

$$\cdot \quad \frac{6}{r}+6+6r=19;$$

$$\cdot \quad 6-13r+6r^2=0;$$

whence $$r=\frac{3}{2} \text{ or } \frac{2}{3}.$$

Thus the numbers are 4, 6, 9.

Example 2. The sum of an infinite number of terms in G. P. is 15, and the sum of their squares is 45; find the series.

Let a denote the first term, r the common ratio; then the sum of the terms is $\frac{a}{1-r}$; and the sum of their squares is $\frac{a^2}{1-r^2}$.

Hence $$\frac{a}{1-r}=15 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1),$$

$$\frac{a^2}{1-r^2}=45 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

Dividing (2) by (1) $$\frac{a}{1+r}=3 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (3),$$

and from (1) and (3) $$\frac{1+r}{1-r}=5;$$

whence $r=\frac{2}{3}$, and therefore $a=5$.

Thus the series is 5, $\frac{10}{3}$, $\frac{20}{9}$,.....

EXAMPLES. V. a.

1. Sum $\frac{1}{2}, \frac{1}{3}, \frac{2}{9}$,... to 7 terms.
2. Sum $-2,\ 2\frac{1}{2},\ -3\frac{1}{8}$,... to 6 terms.
3. Sum $\frac{3}{4},\ 1\frac{1}{2},\ 3$,... to 8 terms.
4. Sum $2,\ -4,\ 8$,... to 10 terms.
5. Sum $16{\cdot}2,\ 5{\cdot}4,\ 1{\cdot}8$,... to 7 terms.
6. Sum $1,\ 5,\ 25$,... to p terms.
7. Sum $3,\ -4, \frac{16}{3}$,... to $2n$ terms.
8. Sum $1,\ \sqrt{3},\ 3$,... to 12 terms.
9. Sum $\frac{1}{\sqrt{2}},\ -2,\ \frac{8}{\sqrt{2}}$,... to 7 terms.

10. Sum $-\frac{1}{3}, \frac{1}{2}, -\frac{3}{4}, \ldots$ to 7 terms.

11. Insert 3 geometric means between $2\frac{1}{4}$ and $\frac{4}{9}$.

12. Insert 5 geometric means between $3\frac{5}{9}$ and $40\frac{1}{2}$.

13. Insert 6 geometric means between 14 and $-\frac{7}{64}$.

Sum the following series to infinity:

14. $\frac{8}{5}, -1, \frac{5}{8}, \ldots$

15. ·45, ·015, ·0005

16. 1·665, −1·11, ·74, ...

17. $3^{-1}, 3^{-2}, 3^{-3}, \ldots$

18. $3, \sqrt{3}, 1, \ldots$

19. $7, \sqrt{42}, 6, \ldots$

20. The sum of the first 6 terms of a G. P. is 9 times the sum of the first 3 terms; find the common ratio.

21. The fifth term of a G. P. is 81, and the second term is 24; find the series.

22. The sum of a G. P. whose common ratio is 3 is 728, and the last term is 486; find the first term.

23. In a G. P. the first term is 7, the last term 448, and the sum 889; find the common ratio.

24. The sum of three numbers in G. P. is 38, and their product is 1728; find them.

25. The continued product of three numbers in G. P. is 216, and the sum of the product of them in pairs is 156; find the numbers.

26. If S_p denote the sum of the series $1+r^p+r^{2p}+\ldots$ *ad inf.*, and s_p the sum of the series $1-r^p+r^{2p}-\ldots$ *ad inf.*, prove that

$$S_p + s_p = 2S_{2p}.$$

27. If the p^{th}, q^{th}, r^{th} terms of a G. P. be a, b, c respectively, prove that

$$a^{q-r} b^{r-p} c^{p-q} = 1.$$

28. The sum of an infinite number of terms of a G. P. is 4, and the sum of their cubes is 192; find the series.

58. Recurring decimals furnish a good illustration of infinite Geometrical Progressions.

Example. Find the value of $\cdot 4\dot{2}\dot{3}$.

$$\cdot 4\dot{2}\dot{3} = \cdot 4232323$$

$$= \frac{4}{10} + \frac{23}{1000} + \frac{23}{100000} + \ldots\ldots$$

$$= \frac{4}{10} + \frac{23}{10^3} + \frac{23}{10^5} + \ldots\ldots;$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

60. *To find the sum of* n *terms of the series*

$$a,\ (a+d)\,r,\ (a+2d)\,r^2,\ (a+3d)\,r^3,\ldots\ldots\ldots$$

in which each term is the product of corresponding terms in an arithmetic and geometric series.

Denote the sum by S; then

$$S = a + (a+d)\,r + (a+2d)\,r^2 + \ldots + (a+\overline{n-1}d)\,r^{n-1};$$

$$rS = \qquad ar + (a+d)r^2 + \ldots + (a+\overline{n-2}d)r^{n-1} + (a+\overline{n-1}d)r^n.$$

By subtraction,

$$S(1-r) = a + (dr + dr^2 + \ldots + dr^{n-1}) - (a+\overline{n-1}d)\,r^n$$

$$= a + \frac{dr\,(1-r^{n-1})}{1-r} - (a+\overline{n-1}d)\,r^n;$$

$$\therefore\ S = \frac{a}{1-r} + \frac{dr\,(1-r^{n-1})}{(1-r)^2} - \frac{(a+\overline{n-1}d)\,r^n}{1-r}.$$

Cor. Write S in the form

$$\frac{a}{1-r} + \frac{dr}{(1-r)^2} - \frac{dr^n}{(1-r)^2} - \frac{(a+\overline{n-1}d)\,r^n}{1-r};$$

then if $r<1$, we can make r^n as small as we please by taking n sufficiently great. In this case, *assuming that all the terms which involve* r^n *can be made so small that they may be neglected*, we obtain $\dfrac{a}{1-r} + \dfrac{dr}{(1-r)^2}$ for the sum to infinity. We shall refer to this point again in Chap. XXI.

In summing to infinity series of this class it is usually best to proceed as in the following example.

Example 1. If $x<1$, sum the series

$$1 + 2x + 3x^2 + 4x^3 + \ldots\ldots \text{ to infinity.}$$

Let

$$S = 1 + 2x + 3x^2 + 4x^3 + \ldots\ldots;$$

$$xS - \qquad x + 2x^2 + 3x^3 + \ldots\ldots;$$

$$\therefore\ S(1-x) = 1 + x + x^2 + x^3 +$$

$$= \frac{1}{1-x};$$

$$\therefore\ S = \frac{1}{(1-x)^2}.$$

Example 2. Sum the series $1+\frac{4}{5}+\frac{7}{5^2}+\frac{10}{5^3}+\ldots$ to n terms.

Let $$S=1+\frac{4}{5}+\frac{7}{5^2}+\frac{10}{5^3}+\ldots\ldots+\frac{3n-2}{5^{n-1}};$$

$$\frac{1}{5}S=\quad\frac{1}{5}+\frac{4}{5^2}+\frac{7}{5^3}+\ldots\ldots+\frac{3n-5}{5^{n-1}}+\frac{3n-2}{5^n};$$

$$\frac{4}{5}S=1+\left(\frac{3}{5}+\frac{3}{5^2}+\frac{3}{5^3}+\ldots\ldots+\frac{3}{5^{n-1}}\right)-\frac{3n-2}{5^n}$$

$$=1+\frac{3}{5}\left(1+\frac{1}{5}+\frac{1}{5^2}+\ldots\ldots+\frac{1}{5^{n-2}}\right)-\frac{3n-2}{5^n}$$

$$=1+\frac{3}{5}\cdot\frac{1-\frac{1}{5^{n-1}}}{1-\frac{1}{5}}-\frac{3n-2}{5^n}$$

$$=1+\frac{3}{4}\left(1-\frac{1}{5^{n-1}}\right)-\frac{3n-2}{5^n}$$

$$=\frac{7}{4}-\frac{12n+7}{4\,.\,5^n};$$

$$\therefore\quad S=\frac{35}{16}-\frac{12n+7}{16\,.\,5^{n-1}}.$$

EXAMPLES. V. b.

1. Sum $1+2a+3a^2+4a^3+\ldots$ to n terms.

2. Sum $1+\frac{3}{4}+\frac{7}{16}+\frac{15}{64}+\frac{31}{256}+\ldots$ to infinity.

3. Sum $1+3x+5x^2+7x^3+9x^4+\ldots$ to infinity.

4. Sum $1+\frac{2}{2}+\frac{3}{2^2}+\frac{4}{2^3}+\ldots$ to n terms.

5. Sum $1+\frac{3}{2}+\frac{5}{4}+\frac{7}{8}+\ldots$ to infinity.

6. Sum $1+3x+6x^2+10x^3+\ldots$ to infinity.

7. Prove that the $(n+1)^{\text{th}}$ term of a G. P., of which the first term is a and the third term b, is equal to the $(2n+1)^{\text{th}}$ term of a G. P. of which the first term is a and the fifth term b.

8. The sum of $2n$ terms of a G. P. whose first term is a and common ratio r is equal to the sum of n of a G. P. whose first term is b and common ratio r^2. Prove that b is equal to the sum of the first two terms of the first series.

9. Find the sum of the infinite series

$$1+(1+b)\,r+(1+b+b^2)\,r^2+(1+b+b^2+b^3)\,r^3+\ldots,$$

r and b being proper fractions.

10. The sum of three numbers in G. P. is 70; if the two extremes be multiplied each by 4, and the mean by 5, the products are in A. P.; find the numbers.

11. The first two terms of an infinite G. P. are together equal to 5, and every term is 3 times the sum of all the terms that follow it; find the series.

Sum the following series :

12. $x+a,\ x^2+2a,\ x^3+3a\ldots$ to n terms.

13. $x\,(x+y)+x^2\,(x^2+y^2)+x^3\,(x^3+y^3)+\ldots$ to n terms.

14. $a+\frac{1}{3},\ 3a-\frac{1}{6},\ 5a+\frac{1}{1^2}+\ldots$ to $2p$ terms.

15. $\frac{2}{3}+\frac{3}{3^2}+\frac{2}{3^3}+\frac{3}{3^4}+\frac{2}{3^5}+\frac{3}{3^6}+\ldots$ to infinity.

16. $\frac{4}{7}-\frac{5}{7^2}+\frac{4}{7^3}-\frac{5}{7^4}+\frac{4}{7^5}-\frac{5}{7^6}+\ldots$ to infinity.

17. If $a,\ b,\ c,\ d$ be in G. P., prove that

$$(b-c)^2+(c-a)^2+(d-b)^2=(a-d)^2.$$

18. If the arithmetic mean between a and b is twice as great as the geometric mean, shew that $a\ :\ b=2+\sqrt{3}\ :\ 2-\sqrt{3}$.

19. Find the sum of n terms of the series the r^{th} term of which is

$$(2r+1)\,2^r.$$

20. Find the sum of $2n$ terms of a series of which every even term is a times the term before it, and every odd term c times the term before it, the first term being unity.

21. If S_n denote the sum of n terms of a G. P. whose first term is a, and common ratio r, find the sum of $S_1,\ S_3,\ S_5,\ldots S_{2n-1}$.

22. If $S_1,\ S_2,\ S_3,\ldots S_p$ are the sums of infinite geometric series, whose first terms are 1, 2, 3,...p, and whose common ratios are

$$\frac{1}{2},\ \frac{1}{3},\ \frac{1}{4},\ldots\ \frac{1}{p+1}\ \text{respectively,}$$

prove that $S_1+S_2+S_3+\ldots+S_p=\frac{p}{2}\,(p+3)$.

23. If $r<1$ and positive, and m is a positive integer, shew that

$$(2m+1)\,r^m\,(1-r)<1-r^{2m+1}.$$

Hence shew that nr^n is indefinitely small when n is indefinitely great.

CHAPTER VI.

HARMONICAL PROGRESSION. THEOREMS CONNECTED WITH THE PROGRESSIONS.

61. DEFINITION. Three quantities a, b, c are said to be in **Harmonical Progression** when $\frac{a}{c} = \frac{a-b}{b-c}$.

Any number of quantities are said to be in Harmonical Progression when every three consecutive terms are in Harmonical Progression.

62. *The reciprocals of quantities in Harmonical Progression are in Arithmetical Progression.*

By definition, if a, b, c are in Harmonical Progression,

$$\frac{a}{c} = \frac{a-b}{b-c};$$

$$a(b-c) = c(a-b),$$

dividing every term by abc,

$$\frac{1}{c} - \frac{1}{b} = \frac{1}{b} - \frac{1}{a},$$

which proves the proposition.

63. Harmonical properties are chiefly interesting because of their importance in Geometry and in the Theory of Sound in Algebra the proposition just proved is the only one of any importance. There is no general formula for the sum of any number of quantities in Harmonical Progression. Questions in H. P. are generally solved by inverting the terms, and making use of the properties of the corresponding A. P.

64. *To find the harmonic mean between two given quantities.*

Let a, b be the two quantities, H their harmonic mean; then $\frac{1}{a}$, $\frac{1}{H}$, $\frac{1}{b}$ are in A. P.;

$$\therefore \frac{1}{H}-\frac{1}{a}=\frac{1}{b}-\frac{1}{H},$$

$$\frac{2}{H}=\frac{1}{a}+\frac{1}{b},$$

$$H=\frac{2ab}{a+b}.$$

Example. Insert 40 harmonic means between 7 and $\frac{1}{6}$.

Here 6 is the 42nd term of an A. P. whose first term is $\frac{1}{7}$; let d be the common difference; then

$$6=\frac{1}{7}+41d; \text{ whence } d=\frac{1}{7}.$$

Thus the arithmetic means are $\frac{2}{7}$, $\frac{3}{7}$,..... $\frac{41}{7}$; and therefore the harmonic means are $3\frac{1}{2}$, $2\frac{1}{3}$,... $\frac{7}{41}$.

65. If A, G, H be the arithmetic, geometric, and harmonic means between a and b, we have proved

$$A=\frac{a+b}{2} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

$$G=\sqrt{ab} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

$$H=\frac{2ab}{a+b} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (3).$$

Therefore $$AH=\frac{a+b}{2}\cdot\frac{2ab}{a+b}=ab=G^2;$$

that is, G is the geometric mean between A and H.

From these results we see that

$$A-G=\frac{a+b}{2}-\sqrt{ab}=\frac{a+b-2\sqrt{ab}}{2}$$

$$=\left(\frac{\sqrt{a}-\sqrt{b}}{\sqrt{2}}\right)^2;$$

which is positive if a and b are positive; therefore *the arithmetic mean of any two positive quantities is greater than their geometric mean.*

Also from the equation $G^2 = AH$, we see that G is intermediate in value between A and H; and it has been proved that $A > G$, therefore $G > H$; that is, *the arithmetic, geometric, and harmonic means between any two positive quantities are in descending order of magnitude.*

66. Miscellaneous questions in the Progressions afford scope for skill and ingenuity, the solution being often neatly effected by some special artifice. The student will find the following hints useful.

1. If the same quantity be added to, or subtracted from, all the terms of an A P., the resulting terms will form an A.P. with the same common difference as before. [Art. 38.]

2. If all the terms of an A.P. be multiplied or divided by the same quantity, the resulting terms will form an A.P., but with a new common difference. [Art. 38.]

3. If all the terms of a G.P. be multiplied or divided by the same quantity, the resulting terms will form a G.P. with the same common ratio as before. [Art. 51.]

4. If $a, b, c, d\ldots$ are in G.P., they are also in *continued proportion*, since, by definition,

$$\frac{a}{b} = \frac{b}{c} = \frac{c}{d} = \ldots\ldots = \frac{1}{r}.$$

Conversely, a series of quantities in continued proportion may be represented by $x, xr, xr^2, \ldots\ldots$

Example 1. If a^2, b^2, c^2 are in A. P., shew that $b+c,\ c+a,\ a+b$ are in H. P.

By adding $ab+ac+bc$ to each term, we see that

$a^2+ab+ac+bc,\ b^2+ba+bc+ac,\ c^2+ca+cb+ab$ are in A.P.;

that is $(a+b)(a+c), (b+c)(b+a), (c+a)(c+b)$ are in A. P.

$\therefore$, dividing each term by $(a+b)(b+c)(c+a)$,

$$\frac{1}{b+c},\ \frac{1}{c+a},\ \frac{1}{a+b} \text{ are in A. P.:}$$

that is, $b+c, c+a, a+b$ are in H. P.

Example 2. If l the last term, d the common difference, and s the sum of n terms of an A. P. be connected by the equation $8ds=(d+2l)^2$, prove that

$$d=2a.$$

Since the given relation is true for any number of terms, put $n=1$; then

$$a=l=s.$$

Hence by substitution, $$8ad=(d+2a)^2,$$

or $$(d-2a)^2=0;$$

$$\therefore\ d=2a.$$

Example 3. If the $p^{th}, q^{th}, r^{th}, s^{th}$ terms of an A.P. are in G. P., shew that p q, $q-r$, $r-s$ are in G.P.

With the usual notation we have

$$\frac{a+(p-1)\,d}{a+(q-1)\,d}=\frac{a+(q-1)\,d}{a+(r-1)\,d}=\frac{a+(r-1)\,d}{a+(s-1)\,d} \qquad \text{[Art. 66. (4)]};$$

$\therefore$ each of these ratios

$$=\frac{\{a+(p-1)\,d\}-\{a+(q-1)\,d\}}{\{a+(q-1)\,d\}-\{a+(r-1)\,d\}}=\frac{\{a+(q-1)\,d\}-\{a+(r-1)\,d\}}{\{a+(r-1)\,d\}-\{a+(s-1)\,d\}}$$

$$=\frac{p-q}{q-r}=\frac{q-r}{r-s}.$$

Hence $p-q$, $q-r$, $r-s$ are in G.P.

67. The numbers 1, 2, 3,..... are often referred to as the *natural numbers*; the n^{th} term of the series is n, and the sum of the first n terms is $\frac{n}{2}(n+1)$.

68. *To find the sum of the squares of the first* n *natural numbers.*

Let the sum be denoted by S; then

$$S=1^2+2^2+3^2+\ldots\ldots+n^2.$$

We have $$n^3-(n-1)^3=3n^2-3n+1;$$

and by changing n into $n-1$,

$$(n-1)^3-(n-2)^3=3(n-1)^2-3(n-1)+1;$$

similarly $$(n-2)^3-(n-3)^3=3(n-2)^2-3(n-2)+1;$$

.....

$$3^3-2^3=3\,.\,3^2-3\,.\,3+1;$$

$$2^3-1^3=3\,.\,2^2-3\,.\,2+1;$$

$$1^3-0^3=3\,.\,1^2-3\,.\,1+1.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

70. In referring to the results we have just proved it will be convenient to introduce a notation which the student will frequently meet with in Higher Mathematics. We shall denote the series

$$1+2+3+\ldots+n \text{ by } \Sigma n;$$

$$1^2+2^2+3^2+\ldots+n^2 \text{ by } \Sigma n^2;$$

$$1^3+2^3+3^3+\ldots+n^3 \text{ by } \Sigma n^3;$$

where Σ placed before a term signifies the sum of all terms of which that term is the general type.

Example 1. Sum the series

$$1\,.\,2+2\,.\,3+3\,.\,4+\ldots \text{to } n \text{ terms.}$$

The n^{th} term $=n(n+1)=n^2+n$; and by writing down each term in a similar form we shall have two columns, one consisting of the first n natural numbers, and the other of their squares.

$$\text{the sum} = \Sigma n^2+\Sigma n$$

$$=\frac{n(n+1)(2n+1)}{6}+\frac{n(n+1)}{2}$$

$$=\frac{n(n+1)}{2}\left\{\frac{2n+1}{3}+1\right\}$$

$$=\frac{n(n+1)(n+2)}{3}.$$

Example 2. Sum to n terms the series whose n^{th} term is $2^{n-1}+8n^3-6n^2$.

Let the sum be denoted by S; then

$$S=\Sigma\, 2^{n-1}+8\Sigma n^3-6\Sigma n^2$$

$$=\frac{2^n\cdot 1}{2-1}+\frac{8n^2(n+1)^2}{4}-\frac{6n(n+1)(2n+1)}{6}$$

$$-2^n-1+n(n+1)\{2n(n+1)-(2n+1)\}$$

$$-2^n-1+n(n+1)(2n^2-1).$$

EXAMPLES. VI. a.

1. Find the fourth term in each of the following series:
   (1) $2,\ 2\frac{1}{2},\ 3\frac{1}{3}$
   (2) $2,\ 2\frac{1}{2},\ 3,.$
   (3) $2,\ 2\frac{1}{2},\ 3\frac{1}{8},\ldots$
2. Insert two harmonic means between 5 and 11.
3. Insert four harmonic means between $\frac{2}{3}$ and $\frac{2}{13}$

4. If 12 and $9\frac{3}{5}$ are the geometric and harmonic means, respectively, between two numbers, find them.

5. If the harmonic mean between two quantities is to their geometric means as 12 to 13, prove that the quantities are in the ratio of 4 to 9.

6. If a, b, c be in H. P., shew that

$$a : a-b = a+c : a-c.$$

7. If the m^{th} term of a H. P. be equal to n, and the n^{th} term he equal to m, prove that the $(m+n)^{\text{th}}$ term is equal to $\frac{mn}{m+n}$.

8. If the p^{th}, q^{th}, r^{th} terms of a H. P. be a, b, c respectively, prove that

$$(q-r)\,bc+(r-p)\,ca+(p-q)\,ab=0.$$

9. If b is the harmonic mean between a and c, prove that

$$\frac{1}{b-a}+\frac{1}{b-c}=\frac{1}{a}+\frac{1}{c}.$$

Find the sum of n terms of the series whose n^{th} term is

10. $3n^2-n$. **11.** $n^3+\frac{3}{2}n$. **12.** $n(n+2)$.

13. $n^2(2n+3)$. **14.** 3^n-2^n **15.** $3(4^n+2n^2)-4n^3$.

16. If the $(m+1)^{\text{th}}$, $(n+1)^{\text{th}}$, and $(r+1)^{\text{th}}$ terms of an A. P. are in G. P., and m, n, r are in H. P., shew that the ratio of the common difference to the first term in the A. P. is $-\frac{2}{n}$

17. If l, m, n are three numbers in G. P., prove that the first term of an A. P. whose l^{th}, m^{th}, and n^{th} terms are in H. P. is to the common difference as $m+1$ to 1.

18. If the sum of n terms of a series be $a+bn+cn^2$, find the n^{th} term and the nature of the series.

19. Find the sum of n terms of the series whose n^{th} term is

$$4n(n^2+1)-(6n^2+1).$$

20. If between any two quantities there be inserted two arithmetic means A_1, A_2; two geometric means G_1, G_2; and two harmonic means H_1, H_2; shew that $G_1G_2 : H_1H_2 = A_1+A_2 : H_1+H_2$.

21. If p be the first of n arithmetic means between two numbers, and q the first of n harmonic means between the same two numbers, prove that the value of q cannot lie between p and $\left(\frac{n+1}{n-1}\right)^2 p$.

22. Find the sum of the cubes of the terms of an A. P., and shew that it is exactly divisible by the sum of the terms.

Piles of Shot and Shells.

71. *To find the number of shot arranged in a complete pyramid on a square base.*

Suppose that each side of the base contains n shot; then the number of shot in the lowest layer is n^2; in the next it is $(n-1)^2$; in the next $(n-2)^2$; and so on, up to a single shot at the top.

$$S = n^2 + (n-1)^2 + (n-2)^2 + \ldots + 1$$

$$= \frac{n(n+1)(2n+1)}{6} \qquad \text{[Art. 68.]}$$

72. *To find the number of shot arranged in a complete pyramid the base of which is an equilateral triangle.*

Suppose that each side of the base contains n shot; then the number of shot in the lowest layer is

$$n + (n-1) + (n-2) + \ldots\ldots + 1;$$

that is $$\frac{n(n+1)}{2} \text{ or } \frac{1}{2}(n^2+n).$$

In this result write $n-1, n-2, \ldots\ldots$ for n, and we thus obtain the number of shot in the 2nd, 3rd, $\ldots\ldots$ layers.

$$\therefore\ S = \tfrac{1}{2}(\Sigma n^2 + \Sigma n)$$

$$= \frac{n(n+1)(n+2)}{6} \qquad \text{[Art. 70.]}$$

73. *To find the number of shot arranged in a complete pyramid the base of which is a rectangle.*

Let m and n be the number of shot in the long and short side respectively of the base.

The top layer consists of a single row of $m-(n-1)$, or $m-n+1$ shot;

in the next layer the number is $2(m-n+2)$;

in the next layer the number is $3(m-n+3)$;

and so on;

in the lowest layer the number is $n(m-n+n)$.

$$S = (m-n+1) + 2(m-n+2) + 3(m-n+3) + \ldots + n(m-n+n)$$
$$= (m-n)(1+2+3+\ldots+n) + (1^2+2^2+3^2+\ldots+n^2)$$
$$= \frac{(m-n)\,n\,(n+1)}{2} + \frac{n(n+1)}{6}\frac{(2n+1)}{}$$
$$= \frac{n\,(n+1)}{6}\{3\,(m-n) + 2n + 1\}$$
$$= \frac{n\,(n+1)\,(3m-n+1)}{6}.$$

74. *To find the number of shot arranged in an incomplete pyramid the base of which is a rectangle.*

Let a and b denote the number of shot in the two sides of the top layer, n the number of layers.

In the top layer the number of shot is ab;

in the next layer the number is $(a+1)(b+1)$;

in the next layer the number is $(a+2)(b+2)$;

and so on;

in the lowest layer the number is $(a+\overline{n-1})(b+\overline{n-1})$

or $$ab + (a+b)(n-1) + (n-1)^2.$$

$$S = abn + (a+b)\,\Sigma\,(n-1) + \Sigma\,(n-1)^2$$
$$= abn + \frac{(n-1)\,n\,(a+b)}{2} + \frac{(n-1)\,n\,(2\,.\,\overline{n-1}+1)}{6}$$
$$- \frac{n}{6}\{6ab + 3\,(a+b)\,(n-1) + (n-1)\,(2n-1)\}.$$

75. In numerical examples it is generally easier to use the following method.

Example. Find the number of shot in an incomplete square pile of 16 courses, having 12 shot in each side of the top.

If we place on the given pile a square pile having 11 shot in each side of the base, we obtain a complete square pile of 27 courses;

and number of shot in the complete pile $= \frac{27 \times 28 \times 55}{6} = 6930$; [Art. 71.]

also number of shot in the added pile $= \frac{11 \times 12 \times 23}{6} = 506$;

$\therefore$ number of shot in the incomplete pile $= 6424$.

EXAMPLES. VI. b.

Find the number of shot in

1. A square pile, having 15 shot in each side of the base.

2. A triangular pile, having 18 shot in each side of the base.

3. A rectangular pile, the length and the breadth of the base containing 50 and 28 shot respectively.

4. An incomplete triangular pile, a side of the base having 25 shot, and a side of the top 14.

5. An incomplete square pile of 27 courses, having 40 shot in each side of the base.

6. The number of shot in a complete rectangular pile is 24395; if there are 34 shot in the breadth of the base, how many are there in its length?

7. The number of shot in the top layer of a square pile is 169, and in the lowest layer is 1089; how many shot does the pile contain?

8. Find the number of shot in a complete rectangular pile of 15 courses, having 20 shot in the longer side of its base.

9. Find the number of shot in an incomplete rectangular pile, the number of shot in the sides of its upper course being 11 and 18, and the number in the shorter side of its lowest course being 30.

10. What is the number of shot required to complete a rectangular pile having 15 and 6 shot in the longer and shorter side, respectively, of its upper course?

11. The number of shot in a triangular pile is greater by 150 than half the number of shot in a square pile, the number of layers in each being the same; find the number of shot in the lowest layer of the triangular pile.

12. Find the number of shot in an incomplete square pile of 16 courses when the number of shot in the upper course is 1005 less than in the lowest course.

13. Shew that the number of shot in a square pile is one-fourth the number of shot in a triangular pile of double the number of courses.

14. If the number of shot in a triangular pile is to the number of shot in a square pile of double the number of courses as 13 to 175; find the number of shot in each pile.

15. The value of a triangular pile of 16 lb. shot is £51; if the value of iron be 10*s.* 6*d.* per cwt., find the number of shot in the lowest layer.

16. If from a complete square pile of n courses a triangular pile of the same number of courses be formed; shew that the remaining shot will be just sufficient to form another triangular pile, and find the number of shot in its side.

CHAPTER VII.

SCALES OF NOTATION.

76. The ordinary numbers with which we are acquainted in Arithmetic are expressed by means of multiples of powers of 10; for instance

$$25 = 2 \times 10 + 5;$$

$$4705 = 4 \times 10^3 + 7 \times 10^2 + 0 \times 10 + 5.$$

This method of representing numbers is called the **common** or **denary scale of notation**, and ten is said to be the **radix** of the scale. The symbols employed in this system of notation are the nine digits and zero.

In like manner any number other than ten may be taken as the radix of a scale of notation; thus if 7 is the radix, a number expressed by 2453 represents $2 \times 7^3 + 4 \times 7^2 + 5 \times 7 + 3$; and in this scale no digit higher than 6 can occur.

Again in a scale whose radix is denoted by r the above number 2453 stands for $2r^3 + 4r^2 + 5r + 3$. More generally, if in the scale whose radix is r we denote the digits, beginning with that in the units' place, by $a_0, a_1, a_2, \ldots a_n$; then the number so formed will be represented by

$$a_n r^n + a_{n-1} r^{n-1} + a_{n-2} r^{n-2} + \ldots + a_2 r^2 + a_1 r + a_0,$$

where the coefficients $a_n, a_{n-1}, \ldots a_0$ are integers, all less than r, of which any one or more after the first may be zero.

Hence in this scale the digits are r in number, their values ranging from 0 to $r - 1$.

77. The names Binary, Ternary, Quaternary, Quinary, Senary, Septenary, Octenary, Nonary, Denary, Undenary, and Duodenary are used to denote the scales corresponding to the values *two*, *three*, ...*twelve* of the radix.

In the undenary, duodenary,... scales we shall require symbols to represent the digits which are greater than nine. It is unusual to consider any scale higher than that with radix twelve; when necessary we shall employ the symbols t, e, T as digits to denote 'ten', 'eleven' and 'twelve'.

It is especially worthy of notice that in every scale 10 is the symbol not for 'ten', but for the radix itself.

78. The ordinary operations of Arithmetic may be performed in any scale; but, bearing in mind that the successive powers of the radix are no longer powers of ten, in determining the *carrying figures* we must not divide by ten, but by the radix of the scale in question.

Example 1. In the scale of eight subtract 371532 from 530225, and multiply the difference by 27.

530225	136473
371532	27
136473	1226235
	275166
	4200115

Explanation. After the first figure of the subtraction, since we cannot take 3 from 2 we add 8; thus we have to take 3 from ten, which leaves 7; then 6 from ten, which leaves 4; then 2 from eight which leaves 6; and so on.

Again, in multiplying by 7, we have

$$3 \times 7 = \text{twenty one} = 2 \times 8 + 5;$$

we therefore put down 5 and carry 2.

Next $$7 \times 7 + 2 = \text{fifty one} = 6 \times 8 + 3;$$

put down 3 and carry 6; and so on, until the multiplication is completed.

In the addition,

$$3 + 6 = \text{nine} = 1 \times 8 + 1;$$

we therefore put down 1 and carry 1.

Similarly $$2 + 6 + 1 = \text{nine} = 1 \times 8 + 1;$$

and $$6 + 1 + 1 = \text{eight} = 1 \times 8 + 0;$$

and so on.

Example 2. Divide $15et20$ by 9 in the scale of twelve.

$$9)\overline{15et20}$$
$$\overline{1ee96}...6.$$

Explanation. Since $15 = 1 \times T + 5 = \text{seventeen} = 1 \times 9 + 8$,

we put down 1 and carry 8.

Also $8 \times T + e = \text{one hundred and seven} = e \times 9 + 8$;

we therefore put down e and carry 8; and so on.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Divide N by r, then the remainder is a_0, and the quotient is

$$a_n r^{n-1} + a_{n-1} r^{n-2} + \ldots + a_2 r + a_1.$$

If this quotient is divided by r, the remainder is a_1;
if the next quotient .... a_2;
and so on, until there is no further quotient.

Thus all the required digits a_0, a_1, a_2,...a_n are determined by successive divisions by the radix of the proposed scale.

Example 1. Express the denary number 5213 in the scale of seven.

$$\begin{array}{r} 7)5213 \\ \hline 7)744 \ldots\ldots 5 \\ 7)106 \ldots\ldots 2 \\ 7)15 \ldots\ldots 1 \\ \hline 2 \ldots\ldots 1 \end{array}$$

Thus $5213 = 2 \times 7^4 + 1 \times 7^3 + 1 \times 7^2 + 2 \times 7 + 5$;
and the number required is 21125.

Example 2. Transform 21125 from scale seven to scale eleven.

$$\begin{array}{r} e)21125 \\ \hline e)1244 \ldots\ldots t \\ e)61 \ldots\ldots 0 \\ \hline 3 \ldots\ldots t \end{array}$$

the required number is $3t0t$.

Explanation. In the first line of work

$$21 = 2 \times 7 + 1 = \text{fifteen} = 1 \times e + 4;$$

therefore on dividing by e we put down 1 and carry 4.

Next $4 \times 7 + 1 = \text{twenty nine} = 2 \times e + 7$;
therefore we put down 2 and carry 7; and so on.

Example 3. Reduce 7215 from scale twelve to scale ten by working in scale ten, and verify the result by working in the scale twelve.

In scale of ten:

$$\begin{array}{r} 7215 \\ 12 \\ \hline 86 \\ 12 \\ \hline 1033 \\ 12 \\ \hline 12401 \end{array}$$

In scale of twelve:

$$\begin{array}{r} t)7215 \\ \hline t)874 \ldots\ldots 1 \\ t)t4 \ldots\ldots 0 \\ t)10 \ldots\ldots 4 \\ \hline 1 \ldots\ldots 2 \end{array}$$

Thus the result is 12401 in each case.

Explanation. 7215 in scale twelve means $7 \times 12^3 + 2 \times 12^2 + 1 \times 12 + 5$ in scale ten. The calculation is most readily effected by writing this expression in the form $[\{(7 \times 12 + 2)\} \times 12 + 1] \times 12 + 5$; thus we multiply 7 by 12, and add 2 to the product; then we multiply 86 by 12 and add 1 to the product; then 1033 by 12 and add 5 to the product.

80. Hitherto we have only discussed whole numbers; but fractions may also be expressed in any scale of notation; thus

$$\cdot 25 \text{ in scale ten denotes } \frac{2}{10} + \frac{5}{10^2};$$

$$\cdot 25 \text{ in scale six denotes } \frac{2}{6} + \frac{5}{6^2};$$

$$\cdot 25 \text{ in scale } r \text{ denotes } \frac{2}{r} + \frac{5}{r^2}.$$

Fractions thus expressed in a form analogous to that of ordinary decimal fractions are called **radix-fractions**, and the point is called the **radix-point.** The general type of such fractions in scale r is

$$\frac{b_1}{r} + \frac{b_2}{r^2} + \frac{b_3}{r^3} + \ldots\ldots;$$

where b_1, b_2, b_3,... are integers, all less than r, of which any one or more may be zero.

81. *To express a given radix fraction in any proposed scale.*

Let F be the given fraction, and r the radix of the proposed scale.

Let b_1, b_2, b_3,... be the required digits beginning from the left; then

$$F = \frac{b_1}{r} + \frac{b_2}{r^2} \quad \frac{b_3}{r^3} + \ldots\ldots$$

We have now to find the values of b_1, b_2, b_3, ...

Multiply both sides of the equation by r; then

$$rF = b_1 + \frac{b_2}{r} + \frac{b_3}{r^2} + \ldots\ldots,$$

Hence b_1 is equal to the integral part of rF; and, if we denote the fractional part by F_1, we have

$$F_1 = \frac{b_2}{r} + \frac{b_3}{r^2} + \ldots\ldots$$

Multiply again by r; then, as before, b_2 is the integral part of rF_1; and similarly by successive multiplications by r, each of the digits may be found, and the fraction expressed in the proposed scale.

If in the successive multiplications by r any one of the products is an integer the process terminates at this stage, and the given fraction can be expressed by a finite number of digits. But if none of the products is an integer the process will never terminate, and in this case the digits recur, forming a radix-fraction analogous to a recurring decimal.

Example 1. Express $\frac{13}{16}$ as a radix fraction in scale six.

$$\frac{13}{16}\times 6=\frac{13\times 3}{8}=4+\frac{7}{8};$$

$$\frac{7}{8}\times 6=\frac{7\times 3}{4}=5+\frac{1}{4},$$

$$\frac{1}{4}\times 6=\frac{1\times 3}{2}=1+\frac{1}{2};$$

$$\frac{1}{2}\times 6=3.$$

$$\therefore \text{ the required fraction}=\frac{4}{6}+\frac{5}{6^2}+\frac{1}{6^3}+\frac{3}{6^4}$$

$$=\cdot 4513.$$

Example 2. Transform 16064·24 from scale eight to scale five.

We must treat the integral and the fractional parts separately,

5)16064	·24
5)2644...0	5
5)440...4	1·44
5)71...3	5
5)13...2	2·64
2...1	5
	4·04
	5
	0·24

After this the digits in the fractional part recur; hence the required number is 212340·i24̇0̇.

82. *In any scale of notation of which the radix is* r, *the sum of the digits of any whole number divided by* r − 1 *will leave the same remainder as the whole number divided by* r − 1.

Let N denote the number, $a_0, a_1, a_2, \ldots\ldots a_n$ the digits beginning with that in the units' place, and S the sum of the digits; then

$$N=a_0+a_1r+a_2r^2+\ldots\ldots+a_{n-1}r^{n-1}+a_nr^n;$$

$$S=a_0+a_1+a_2+\ldots\ldots+a_{n-1}+a_n$$

$$\therefore\ N-S=a_1(r-1)+a_2(r^2-1)+\ldots\ldots+a_{n-1}(r^{n-1}-1)+a_n(r^n-1).$$

Now every term on the right hand side is divisible by $r-1$;

$$\therefore \frac{N-S}{r-1} = \text{an integer};$$

that is,
$$\frac{N}{r-1} = I + \frac{S}{r-1},$$

where I is some integer; which proves the proposition.

Hence a number in scale r will be divisible by $r-1$ when the sum of its digits is divisible by $r-1$.

83. By taking $r=10$ we learn from the above proposition that a number divided by 9 will leave the same remainder as the sum of its digits divided by 9. The rule known as "casting out the nines" for testing the accuracy of multiplication is founded on this property.

The rule may be thus explained:

Let two numbers be represented by $9a+b$ and $9c+d$, and their product by P; then

$$P = 81ac + 9bc + 9ad + bd.$$

Hence $\frac{P}{9}$ has the same remainder as $\frac{bd}{9}$; and therefore the *sum of the digits* of P, when divided by 9, gives the same remainder as the *sum of the digits* of bd, when divided by 9. If on trial this should not be the case, the multiplication must have been incorrectly performed. In practice b and d are readily found from the sums of the digits of the two numbers to be multiplied together.

Example. Can the product of 31256 and 8427 be 263395312?

The sums of the digits of the multiplicand, multiplier, and product are 17, 21, and 34 respectively; again, the sums of the digits of these three numbers are 8, 3, and 7, whence $bd = 8 \times 3 = 24$, which has 6 for the sum of the digits; thus we have two different remainders, 6 and 7, and the multiplication is incorrect.

84. *If* N *denote any number in the scale of* r, *and* D *denote the difference, supposed positive, between the sums of the digits in the odd and the even places; then* N − D *or* N + D *is a multiple of* r + 1.

Let $a_0, a_1, a_2, \ldots\ldots a_n$ denote the digits beginning with that in the units' place; then

$$N = a_0 + a_1 r + a_2 r^2 + a_3 r^3 + \ldots\ldots + a_{n-1} r^{n-1} + a_n r^n.$$

$N - a_0 + a_1 - a_2 + a_3 \ldots = a_1 (r+1) + a_2 (r^2 - 1) + a_3 (r^3 + 1) + \ldots;$
and the last term on the right will be $a_n (r^n + 1)$ or $a_n (r^n - 1)$ according as n is odd or even. Thus every term on the right is divisible by $r + 1$; hence

$$\frac{N - (a_0 - a_1 + a_2 - a_3 + \ldots\ldots)}{r+1} = \text{an integer.}$$

Now $$a_0 - a_1 + a_2 - a_3 + \ldots\ldots - \pm D;$$

$$\therefore \frac{N \mp D}{r+1} \text{ is an integer;}$$

which proves the proposition.

Cor. If the sum of the digits in the even places is equal to the sum of the digits in the odd places, $D = 0$, and N is divisible by $r + 1$.

Example 1. Prove that $4{\cdot}41$ is a square number in any scale of notation whose radix is greater than 4.

Let r be the radix; then

$$4{\cdot}41 = 4 + \frac{4}{r} + \frac{1}{r^2} = \left(2 + \frac{1}{r}\right)^2;$$

thus the given number is the square of $2{\cdot}1$.

Example 2. In what scale is the denary number $2{\cdot}4375$ represented by $2{\cdot}13$?

Let r be the scale; then

$$2 + \frac{1}{r} + \frac{3}{r^2} = 2{\cdot}4375 = 2\frac{7}{16};$$

whence $$7r^2 - 16r - 48 = 0;$$

that is, $$(7r + 12)(r - 4) = 0.$$

Hence the radix is 4.

Sometimes it is best to use the following method.

Example 3. In what scale will the nonary number 25607 be expressed by 101215?

The required scale must be less than 9, since the new number *appears* the greater; also it must be greater than 5; therefore the required scale must be 6, 7, or 8; and *by trial* we find that it is 7.

Example 4. By working in the duodenary scale, find the height of a rectangular solid whose volume is 364 cub. ft. 1048 cub. in., and the area of whose base is 46 sq. ft. 8 sq. in.

The volume is $364\frac{1}{17}\frac{0}{2}\frac{4}{8}\frac{8}{}$ cub. ft., which expressed in the scale of twelve is 264·734 cub. ft.

The area is $46\frac{8}{144}$ sq. ft., which expressed in the scale of twelve is $3t{\cdot}08$.

We have therefore to divide 264·734 by $3t{\cdot}08$ in the scale of twelve.

$$3t08)26473{\cdot}4(7{\cdot}e$$
$$\underline{22t48}$$
$$36274$$
$$\underline{\quad\quad\quad\quad}$$

Thus the height is 7ft. 11in.

EXAMPLES. VII. b.

1. Express 4954 in the scale of seven.
2. Express 624 in the scale of five.
3. Express 206 in the binary scale.
4. Express 1458 in the scale of three.
5. Express 5381 in powers of nine.
6. Transform 212231 from scale four to scale five.
7. Express the duodenary number $398e$ in powers of 10.
8. Transform $6t12$ from scale twelve to scale eleven.
9. Transform 213014 from the senary to the nonary scale.
10. Transform 23861 from scale nine to scale eight.
11. Transform 400803 from the nonary to the quinary scale.
12. Express the septenary number 20665152 in powers of 12.
13. Transform *ttteee* from scale twelve to the common scale.
14. Express $\frac{3}{10}$ as a radix fraction in the septenary scale.
15. Transform 17·15625 from scale ten to scale twelve.
16. Transform 200·211 from the ternary to the nonary scale.
17. Transform 71·03 from the duodenary to the octenary scale.
18. Express the septenary fraction $\frac{1552}{2626}$ as a denary vulgar fraction in its lowest terms.
19. Find the value of $\cdot\dot{4}$ and of $\cdot\dot{4}\dot{2}$ in the scale of seven.
20. In what scale is the denary number 182 denoted by 222?
21. In what scale is the denary fraction $\frac{25}{128}$ denoted by ·0302?

22. Find the radix of the scale in which 554 represents the square of 24.

23. In what scale is 511197 denoted by 1746335?

24. Find the radix of the scale in which the numbers denoted by 479, 698, 907 are in arithmetical progression.

25. In what scale are the radix-fractions ·16, ·20, ·28 in geometric progression?

26. The number 212542 is in the scale of six; in what scale will it be denoted by 17486?

27. Shew that 148·84 is a perfect square in every scale in which the radix is greater than eight.

28. Shew that 1234321 is a perfect square in any scale whose radix is greater than 4; and that the square root is always expressed by the same four digits.

29. Prove that 1·331 is a perfect cube in any scale whose radix is greater than three.

30. Find which of the weights 1, 2, 4, 8, 16,... lbs. must be used to weigh one ton.

31. Find which of the weights 1, 3, 9, 27, 81,... lbs. must be used to weigh ten thousand lbs., not more than one of each kind being used but in either scale that is necessary.

32. Shew that 1367631 is a perfect cube in every scale in which the radix is greater than seven.

33. Prove that in the ordinary scale a number will be divisible by 8 if the number formed by its last three digits is divisible by eight.

34. Prove that the square of $rrrr$ in the scale of s is $rrrq0001$, where q, r, s are any three consecutive integers.

35. If any number N be taken in the scale r, and a new number N' be formed by altering the order of its digits in any way, shew that the difference between N and N' is divisible by $r-1$.

36. If á number has an even number of digits, shew that it is divisible by $r+1$ if the digits equidistant from each end are the same.

37. If in the ordinary scale S_1 be the sum of the digits of a number N, and $3S_2$ be the sum of the digits of the number $3N$, prove that the difference between S_1 and S_2 is a multiple of 3.

38. Shew that in the ordinary scale any number formed by writing down three digits and then repeating them in the same order is a multiple of 7, 11, and 13.

39. In a scale whose radix is odd, shew that the sum of the digits of any number will be odd if the number be odd, and even if the number be even.

40. If n be odd, and a number in the denary scale be formed by writing down n digits and then repeating them in the same order, shew that it will be divisible by the number formed by the n digits, and also by 9090...9091 containing $n-1$ digits.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

86. *To find the factor which will rationalise any gives mial surd.*

CASE I. Suppose the given surd is $\sqrt[p]{a} - \sqrt[q]{b}$.

Let $\sqrt[p]{a} = x$, $\sqrt[q]{b} = y$, and let n be the L.C.M. of p and q x^n and y^n are both rational.

Now $x^n - y^n$ is divisible by $x - y$ for all values of n, and

$$x^n - y^n = (x-y)(x^{n-1} + x^{n-2}y + x^{n-3}y^2 + \ldots\ldots + y^{n-1}).$$

Thus the rationalising factor is

$$x^{n-1} + x^{n-2}y + x^{n-3}y^2 + \ldots\ldots + y^{n-1};$$

and the rational product is $x^n - y^n$

CASE II. Suppose the given surd is $\sqrt[p]{a} + \sqrt[q]{b}$.

Let x, y, n have the same meanings as before; then

(1) If n is even, $x^n - y^n$ is divisible by $x + y$, and

$$x^n - y^n = (x+y)(x^{n-1} - x^{n-2}y + \ldots\ldots + xy^{n-2} - y^{n-1}).$$

Thus the rationalising factor is

$$x^{n-1} - x^{n-2}y + \ldots\ldots + xy^{n-2} - y^{n-1};$$

and the rational product is $x^n - y^n$.

(2) If n is odd, $x^n + y^n$ is divisible by $x + y$, and

$$x^n + y^n = (x+y)(x^{n-1} - x^{n-2}y + \ldots\ldots \quad xy^{n-2} + y^{n-1}).$$

Thus the rationalising factor is

$$x^{n-1} - x^{n-2}y + \ldots\ldots \quad xy^{n-2} + y^{n-1};$$

and the rational product is $x^n + y^n$.

Example 1. Find the factor which will rationalise $\sqrt{3} + \sqrt[3]{5}$.

Let $x = 3^{\frac{1}{2}}$, $y = 5^{\frac{1}{3}}$; then x^6 and y^6 are both rational, and

$$x^6 - y^6 = (x+y)(x^5 - x^4y + x^3y^2 - x^2y^3 + xy^4 - y^5);$$

thus, substituting for x and y, the required factor is

$$3^{\frac{5}{2}} - 3^{\frac{4}{2}} \cdot 5^{\frac{1}{3}} + 3^{\frac{3}{2}} \cdot 5^{\frac{2}{3}} - 3^{\frac{2}{2}} \cdot 5^{\frac{3}{3}} + 3^{\frac{1}{2}} \cdot 5^{\frac{4}{3}} - 5^{\frac{5}{3}},$$

or

$$3^{\frac{5}{2}} - 9 \cdot 5^{\frac{1}{3}} + 3^{\frac{3}{2}} \cdot 5^{\frac{2}{3}} - 15 + 3^{\frac{1}{2}} \cdot 5^{\frac{4}{3}} - 5^{\frac{5}{3}};$$

and the rational product is $3^{\frac{6}{2}} - 5^{\frac{6}{3}} = 3^3 - 5^2 = 2$.

Example 2. Express $\left(5^{\frac{1}{2}}+9^{\frac{1}{8}}\right) \div \left(5^{\frac{1}{2}}-9^{\frac{1}{8}}\right)$ as an equivalent fraction with a rational denominator.

To rationalise the denominator, which is equal to $5^{\frac{1}{2}}-3^{\frac{1}{4}}$, put $5^{\frac{1}{2}}=x$, $3^{\frac{1}{4}}=y$; then since $x^4-y^4=(x-y)\,(x^3+x^2y+xy^2+y^3)$

the required factor is $5^{\frac{3}{2}}+5^{\frac{2}{2}}.3^{\frac{1}{4}}+5^{\frac{1}{2}}.3^{\frac{2}{4}}+3^{\frac{3}{4}}$;

and the rational denominator is $5^2-3^4=5^2-3=22$.

$$\therefore \text{ the expression } = \frac{\left(5^{\frac{1}{2}}+3^{\frac{1}{4}}\right)\left(5^{\frac{3}{2}}+5^{\frac{2}{2}}.3^{\frac{1}{4}}+5^{\frac{1}{2}}.3^{\frac{2}{4}}+3^{\frac{3}{4}}\right)}{22}$$

$$= \frac{5^{\frac{4}{2}}+2\,.\,5^{\frac{3}{2}}.3^{\frac{1}{4}}+2.5^{\frac{2}{2}}.3^{\frac{2}{4}}+2.5^{\frac{1}{2}}.3^{\frac{3}{4}}+3^{\frac{4}{4}}}{22}$$

$$= \frac{14+5^{\frac{3}{2}}.3^{\frac{1}{4}}+5\,.\,3^{\frac{1}{2}}+5^{\frac{1}{2}}.3^{\frac{3}{4}}}{11}$$

87. We have shewn in the *Elementary Algebra*, Art. 277, how to find the square root of a binomial quadratic surd. We may sometimes extract the square root of an expression containing more than two quadratic surds, such as $a+\sqrt{b}+\sqrt{c}+\sqrt{d}$.

Assume $\sqrt{a+\sqrt{b}+\sqrt{c}+\sqrt{d}}=\sqrt{x}+\sqrt{y}+\sqrt{z}$;

$$\therefore\ a+\sqrt{b}+\sqrt{c}+\sqrt{d}=x+y+z+2\sqrt{xy}+2\sqrt{xz}+2\sqrt{yz}.$$

If then $2\sqrt{xy}=\sqrt{b},\ 2\sqrt{xz}=\sqrt{c},\ 2\sqrt{yz}=\sqrt{d},$

and if, at the same time, the values of x, y, z thus found satisfy $x+y+z=a$, we shall have obtained the required root.

Example. Find the square root of $21-4\sqrt{5}+8\sqrt{3}-4\sqrt{15}$.

Assume $\sqrt{21-4\sqrt{5}+8\sqrt{3}-4\sqrt{15}}=\sqrt{x}+\sqrt{y}-\sqrt{z}$;

$$\therefore\ 21-4\sqrt{5}+8\sqrt{3}-4\sqrt{15}=x+y+z+2\sqrt{xy}-2\sqrt{xz}-2\sqrt{yz}.$$

Put $2\sqrt{xy}=8\sqrt{3},\ 2\sqrt{xz}=4\sqrt{15},\ 2\sqrt{yz}=4\sqrt{5};$

by multiplication, $xyz=240$; that is $\sqrt{xyz}=4\sqrt{15}$;
whence it follows that $\sqrt{x}=2\sqrt{3},\ \sqrt{y}=2,\ \sqrt{z}=\sqrt{5}.$

And since these values satisfy the equation $x+y+z=21$, the required root is $2\sqrt{3}+2-\sqrt{5}$.

88. *If* $\sqrt[3]{\mathrm{a}+\sqrt{\mathrm{b}}}=\mathrm{x}+\sqrt{\mathrm{y}}$, *then will* $\sqrt[3]{\mathrm{a}-\sqrt{\mathrm{b}}}=\mathrm{x}-\sqrt{\mathrm{y}}$.

For, by cubing, we obtain

$$a+\sqrt{b}=x^3+3x^2\sqrt{y}+3xy+y\sqrt{y}.$$

Equating rational and irrational parts, we have

$$a=x^3+3xy,\ \sqrt{b}=3x^2\sqrt{y}+y\sqrt{y};$$

$$a-\sqrt{b}=x^3-3x^2\sqrt{y}+3xy-y\sqrt{y};$$

that is, $$\sqrt[3]{a-\sqrt{b}}=x-\sqrt{y}.$$

Similarly, by the help of the Binomial Theorem, Chap. XIII., it may be proved that if

$$\sqrt[n]{a+\sqrt{b}}=x+\sqrt{y},\ \text{then}\ \sqrt[n]{a-\sqrt{b}}=x-\sqrt{y},$$

where n is any positive integer.

89. By the following method the cube root of an expression of the form $a\pm\sqrt{b}$ may sometimes be found.

Suppose $$\sqrt[3]{a+\sqrt{b}}=x+\sqrt{y};$$

then $$\sqrt[3]{a-\sqrt{b}}=x-\sqrt{y}.$$

$$\therefore\ \sqrt[3]{a^2-b}=x^2-y \quad\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

Again, as in the last article,

$$a=x^3+3xy. \quad\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$$

The values of x and y have to be determined from (1) and (2).

In (1) suppose that $\sqrt[3]{a^2-b}=c$; then by substituting for y in (2) we obtain

$$a=x^3+3x(x^2-c);$$

that is, $$4x^3-3cx=a.$$

If from this equation the value of x can be determined by trial, the value of y is obtained from $y=x^2-c$.

NOTE. We do not here assume $\sqrt{x}+\sqrt{y}$ for the cube root, as in the extraction of the square root; for with this assumption, on cubing we should have

$$a+\sqrt{b}=x\sqrt{x}+3x\sqrt{y}+3y\sqrt{x}+y\sqrt{y},$$

and since every term on the right hand side is irrational we cannot equate rational and irrational parts.

Example. Find the cube root of $72-32\sqrt{5}$.

Assume $$\sqrt[3]{72-32\sqrt{5}}=x-\sqrt{y};$$

then $$\sqrt[3]{72+32\sqrt{5}}=x+\sqrt{y}.$$

By multiplication, $$\sqrt[3]{5184-1024\times 5}=x^2-y;$$

that is, $$4=x^2-y \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Again $$72-32\sqrt{5}=x^3-3x^2\sqrt{y}+3xy-y\sqrt{y};$$

whence $$72=x^3+3xy \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

From (1) and (2), $$72=x^3+3x(x^2-4);$$

that is, $$x^3-3x=18.$$

By trial, we find that $x=3$; hence $y=5$, and the cube root is $3-\sqrt{5}$.

90. When the binomial whose cube root we are seeking consists of *two* quadratic surds, we proceed as follows.

Example. Find the cube root of $9\sqrt{3}+11\sqrt{2}$.

$$\sqrt[3]{9\sqrt{3}+11\sqrt{2}}=\sqrt[3]{3\sqrt{3}\left(3+\frac{11}{3}\sqrt{\frac{2}{3}}\right)}$$

$$=\sqrt{3}\sqrt[3]{3+\frac{11}{3}\sqrt{\frac{2}{3}}}.$$

By proceeding as in the last article, we find that

$$\sqrt[3]{3+\frac{11}{3}\sqrt{\frac{2}{3}}}=1+\sqrt{\frac{2}{3}};$$

the required cube root $$-\sqrt{3}\left(1+\sqrt{\frac{2}{3}}\right)$$

$$=\sqrt{3}+\sqrt{2}.$$

91. We add a few harder examples in surds.

Example 1. Express with rational denominator $\dfrac{4}{\sqrt[3]{9}-\sqrt[3]{3}+1}$.

The expression $$=\frac{4}{3^{\frac{2}{3}}-3^{\frac{1}{3}}+1}$$

$$=\frac{4\left(3^{\frac{1}{3}}+1\right)}{\left(3^{\frac{1}{3}}+1\right)\left(3^{\frac{2}{3}}-3^{\frac{1}{3}}+1\right)}$$

$$=\frac{4\left(3^{\frac{1}{3}}+1\right)}{3+1}=3^{\frac{1}{3}}+1.$$

Example 2. Find the square root of

$$\frac{3}{2}(x-1)+\sqrt{2x^2-7x-4}\,.$$

$$\text{The expression}=\frac{1}{2}\{3x-3+2\sqrt{(2x+1)(x-4)}\}$$

$$-\frac{1}{2}\{(2x+1)+(x-4)+2\sqrt{(2x+1)(x-4)}\}\,;$$

hence, by inspection, the square root is

$$\frac{1}{\sqrt{2}}(\sqrt{2x+1}+\sqrt{x-4}).$$

Example 3. Given $\sqrt{5}=2{\cdot}23607$, find the value of

$$\frac{\sqrt{3-\sqrt{5}}}{\sqrt{2}+\sqrt{7-3\sqrt{5}}}.$$

Multiplying numerator and denominator by $\sqrt{2}$,

$$\text{the expression}=\frac{\sqrt{6-2\sqrt{5}}}{2+\sqrt{14-6\sqrt{5}}}$$

$$=\frac{\sqrt{5}-1}{2+3-\sqrt{5}}$$

$$=\frac{1}{\sqrt{5}}=\frac{\sqrt{5}}{5}=\cdot44721.$$

EXAMPLES. VIII. a.

Express as equivalent fractions with rational denominator:

1. $\dfrac{1}{1+\sqrt{2}-\sqrt{3}}$.
2. $\dfrac{\sqrt{2}}{\sqrt{2}+\sqrt{3}-\sqrt{5}}$.
3. $\dfrac{1}{\sqrt{a}+\sqrt{b}+\sqrt{a+b}}$.
4. $\dfrac{2\sqrt{a+1}}{\sqrt{a-1}-\sqrt{2a}+\sqrt{a+1}}$.
5. $\dfrac{\sqrt{10}+\sqrt{5}-\sqrt{3}}{\sqrt{3}+\sqrt{10}-\sqrt{5}}$.
6. $\dfrac{(\sqrt{3}+\sqrt{5})(\sqrt{5}+\sqrt{2})}{\sqrt{2}+\sqrt{3}+\sqrt{5}}$.

Find a factor which will rationalise:

7. $\sqrt[3]{3}-\sqrt{2}$.
8. $\sqrt[6]{5}+\sqrt[3]{2}$.
9. $a^{\frac{1}{6}}+b^{\frac{1}{4}}$
10. $\sqrt[3]{3}-1$.
11. $2+\sqrt[4]{1}$.
12. $\sqrt[3]{5}-\sqrt[4]{3}$.

Express with rational denominator:

13. $\dfrac{\sqrt[3]{3}-1}{\sqrt[3]{3}+1}$.

14. $\dfrac{\sqrt[6]{9}-\sqrt[6]{8}}{\sqrt[6]{9}+\sqrt[6]{8}}$.

15. $\dfrac{\sqrt{2}.\sqrt[3]{3}}{\sqrt[3]{3}+\sqrt{2}}$.

16. $\dfrac{\sqrt[3]{3}}{\sqrt{3}+\sqrt[6]{9}}$.

17. $\dfrac{\sqrt{8}+\sqrt[3]{4}}{\sqrt{8}-\sqrt[3]{4}}$.

18. $\dfrac{\sqrt[6]{27}}{3-\sqrt[6]{9}}$.

Find the square root of

19. $16-2\sqrt{20}-2\sqrt{28}+2\sqrt{35}$.

20. $24+4\sqrt{15}-4\sqrt{21}-2\sqrt{35}$.

21. $6+\sqrt{12}-\sqrt{24}-\sqrt{8}$.

22. $5-\sqrt{10}-\sqrt{15}+\sqrt{6}$.

23. $a+3b+4+4\sqrt{a}-4\sqrt{3b}-2\sqrt{3ab}$.

24. $21+3\sqrt{8}-6\sqrt{3}-6\sqrt{7}-\sqrt{24}-\sqrt{56}+2\sqrt{21}$.

Find the cube root of

25. $10+6\sqrt{3}$.

26. $38+17\sqrt{5}$.

27. $99-70\sqrt{2}$.

28. $38\sqrt{14}-100\sqrt{2}$.

29. $54\sqrt{3}+41\sqrt{5}$.

30. $135\sqrt{3}-87\sqrt{6}$.

Find the square root of

31. $a+x+\sqrt{2ax+x^2}$.

32. $2a\cdot\sqrt{3a^2-2ab-b^2}$.

33. $1+a^2+(1+a^2+a^4)^{\frac{1}{2}}$

34. $1+(1-a^2)^{\frac{1}{2}}$

35. If $a=\dfrac{1}{2-\sqrt{3}}$, $b=\dfrac{1}{2+\sqrt{3}}$, find the value of $7a^2+11ab-7b^2$.

36. If $x=\dfrac{\sqrt{3}-\sqrt{2}}{\sqrt{3}+\sqrt{2}}$, $y=\dfrac{\sqrt{3}+\sqrt{2}}{\sqrt{3}-\sqrt{2}}$, find the value of $3x^2-5xy+3y^2$

Find the value of

37. $\dfrac{\sqrt{26-15\sqrt{3}}}{5\sqrt{2}-\sqrt{38+5\sqrt{3}}}$.

38. $\sqrt{\dfrac{6+2\sqrt{3}}{33-19\sqrt{3}}}$.

39. $(28-10\sqrt{3})^{\frac{1}{2}}-(7+4\sqrt{3})^{-\frac{1}{2}}$.

40. $(26+15\sqrt{3})^{\frac{2}{3}}-(26+15\sqrt{3})^{-\frac{2}{3}}$.

41. Given $\sqrt{5}=2{\cdot}23607$, find the value of

$$\frac{10\sqrt{2}}{\sqrt{18}-\sqrt{3+\sqrt{5}}}-\frac{\sqrt{10}+\sqrt{18}}{\sqrt{8}+\sqrt{3-\sqrt{5}}}.$$

42. Divide $x^3+1+3x\sqrt[3]{2}$ by $x-1+\sqrt[3]{2}$.

43. Find the cube root of $9ab^2+(b^2+24a^2)\sqrt{b^2-3a^2}$.

44. Evaluate $\dfrac{\sqrt{x^2-1}}{x-\sqrt{x^2-1}}$, when $2x=\sqrt{a}+\dfrac{1}{\sqrt{a}}$,

Imaginary Quantities.

92. Although from the rule of signs it is evident that a negative quantity cannot have a real square root, yet imaginary quantities represented by symbols of the form $\sqrt{-a}$, $\sqrt{-1}$ are of frequent occurrence in mathematical investigations, and their use leads to valuable results. We therefore proceed to explain in what sense such roots are to be regarded.

When the quantity under the radical sign is negative, we can no longer consider the symbol $\sqrt{\ }$ as indicating a possible arithmetical operation; but just as $\sqrt{a}$ may be defined as a symbol which obeys the relation $\sqrt{a} \times \sqrt{a} = a$, so we shall define $\sqrt{-a}$ to be such that $\sqrt{-a} \times \sqrt{-a} = -a$, and we shall accept the meaning to which this assumption leads us.

It will be found that this definition will enable us to bring imaginary quantities under the dominion of ordinary algebraical rules, and that through their use results may be obtained which can be relied on with as much certainty as others which depend solely on the use of real quantities.

93. By definition, $\sqrt{-1} \times \sqrt{-1} = -1$.

$$\therefore \sqrt{a} \,.\, \sqrt{-1} \times \sqrt{a} \,.\, \sqrt{-1} = a(-1);$$

that is, $$(\sqrt{a} \,.\, \sqrt{-1})^2 = -a.$$

Thus the product $\sqrt{a} \,.\, \sqrt{-1}$ may be regarded as equivalent to the imaginary quantity $\sqrt{-a}$.

94. It will generally be found convenient to indicate the imaginary character of an expression by the presence of the symbol $\sqrt{-1}$; thus

$$\sqrt{-4} = \sqrt{4 \times (-1)} = 2\sqrt{-1}.$$

$$\sqrt{-7a^2} = \sqrt{7a^2 \times (-1)} = a\sqrt{7}\sqrt{-1}.$$

95. We shall always consider that, in the absence of any statement to the contrary, of the signs which may be prefixed before a radical the positive sign is to be taken. But in the use of imaginary quantities there is one point of importance which deserves notice.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Thus in order that two imaginary expressions may be equal it is necessary and sufficient that the real parts should be equal, and the imaginary parts should be equal.

100. DEFINITION. When two imaginary expressions differ only in the sign of the imaginary part they are said to be **conjugate.**

Thus $a - b\sqrt{-1}$ is conjugate to $a + b\sqrt{-1}$.

Similarly $\sqrt{2} + 3\sqrt{-1}$ is conjugate to $\sqrt{2} - 3\sqrt{-1}$.

101. *The sum and the product of two conjugate imaginary expressions are both real.*

For $$a + b\sqrt{-1} + a - b\sqrt{-1} = 2a.$$

Again $$(a + b\sqrt{-1})(a - b\sqrt{-1}) = a^2 - (-b^2)$$
$$= a^2 + b^2.$$

102. DEFINITION. The positive value of the square root of $a^2 + b^2$ is called the **modulus** of each of the conjugate expressions

$$a + b\sqrt{-1} \text{ and } a - b\sqrt{-1}.$$

103. *The modulus of the product of two imaginary expressions is equal to the product of their moduli.*

Let the two expressions be denoted by $a + b\sqrt{-1}$ and $c + d\sqrt{-1}$.

Then their product $= ac - bd + (ad + bc)\sqrt{-1}$, which is an imaginary expression whose modulus

$$= \sqrt{(ac - bd)^2 + (ad + bc)^2}$$
$$= \sqrt{a^2c^2 + b^2d^2 + a^2d^2 + b^2c^2}$$
$$= \sqrt{(a^2 + b^2)(c^2 + d^2)}$$
$$= \sqrt{a^2 + b^2} \times \sqrt{c^2 + d^2};$$

which proves the proposition.

104. If the denominator of a fraction is of the form $a + b\sqrt{-1}$, it may be rationalised by multiplying the numerator and the denominator by the conjugate expression $a - b\sqrt{-1}$.

For instance

$$\frac{c+d\sqrt{-1}}{a+b\sqrt{-1}} = \frac{(c+d\sqrt{-1})(a-b\sqrt{-1})}{(a+b\sqrt{-1})(a-b\sqrt{-1})}$$

$$= \frac{ac+bd+(ad-bc)\sqrt{-1}}{a^2+b^2}$$

$$= \frac{ac+bd}{a^2+b^2} + \frac{ad-bc}{a^2+b^2}\sqrt{-1}.$$

Thus by reference to Art. 97, we see that *the sum, difference, product, and quotient of two imaginary expressions is in each case an imaginary expression of the same form.*

105. *To find the square root of* $a + b\sqrt{-1}$.

Assume $$\sqrt{a+b\sqrt{-1}} = x + y\sqrt{-1},$$

where x and y are real quantities.

By squaring, $a+b\sqrt{-1} = x^2 - y^2 + 2xy\sqrt{-1}$;

therefore, by equating real and imaginary parts,

$$x^2 - y^2 = a \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1),$$

$$2xy = b \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2);$$

$$\therefore \quad (x^2+y^2)^2 = (x^2-y^2)^2 + (2xy)^2$$

$$= a^2 + b^2;$$

$$\therefore \quad x^2 + y^2 = \sqrt{a^2+b^2} \ldots\ldots\ldots\ldots\ldots\ldots (3).$$

From (1) and (3), we obtain

$$x^2 = \frac{\sqrt{a^2+b^2}+a}{2}, \quad y^2 = \frac{\sqrt{a^2+b^2}-a}{2};$$

$$x = \pm\left\{\frac{\sqrt{a^2+b^2}+a}{2}\right\}^{\frac{1}{2}}, \quad y = \pm\left\{\frac{\sqrt{a^2+b^2}-a}{2}\right\}^{\frac{1}{2}}.$$

Thus the required root is obtained.

Since x and y are real quantities, x^2+y^2 is positive, and therefore in (3) the positive sign must be prefixed before the quantity $\sqrt{a^2+b^2}$.

Also from (2) we see that the product xy must have the same sign as b; hence x and y must have like signs if b is positive, and unlike signs if b is negative.

Example 1. Find the square root of $-7-24\sqrt{-1}$.

Assume $$\sqrt{-7-24\sqrt{-1}}=x+y\sqrt{-1};$$

then $$7-24\sqrt{-1}=x^2-y^2+2xy\sqrt{-1};$$

$$\therefore\ x^2-y^2=-7 \quad\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1),$$

and $$2xy=-24.$$

$$\therefore\ (x^2+y^2)^2=(x^2-y^2)^2+(2xy)^2$$

$$=49+576$$

$$=625;$$

$$\therefore\ x^2+y^2=25 \quad\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$$

From (1) and (2), $x^2=9$ and $y^2=16$;

$$x=\pm 3,\ y=\pm 4.$$

Since the product xy is negative, we must take

$$x=3,\ y=-4;\ \text{or } x=-3,\ y=4.$$

Thus the roots are $3-4\sqrt{-1}$ and $-3+4\sqrt{-1}$;

that is, $$\sqrt{-7-24\sqrt{-1}}=\pm(3-4\sqrt{-1}).$$

Example 2. To find the value of $\sqrt[4]{-64a^4}$.

$$\sqrt[4]{-64a^4}=\sqrt{\pm 8a^2\sqrt{-1}}$$

$$=2a\sqrt{2}\sqrt{\pm\sqrt{-1}}.$$

It remains to find the value of $\sqrt{\pm\sqrt{-1}}$.

Assume $$\sqrt{+\sqrt{-1}}=x+y\sqrt{-1};$$

then $$+\sqrt{-1}=x^2-y^2+2xy\sqrt{-1};$$

$$\therefore\ x^2-y^2=0 \text{ and } 2xy=1;$$

whence $$x=\frac{1}{\sqrt{2}},\ y=\frac{1}{\sqrt{2}};\ \text{or } x=-\frac{1}{\sqrt{2}},\ y=-\frac{1}{\sqrt{2}};$$

$$\therefore\ \sqrt{+\sqrt{-1}}=\pm\frac{1}{\sqrt{2}}(1+\sqrt{-1}).$$

Similarly $$\sqrt{-\sqrt{-1}}=\pm\frac{1}{\sqrt{2}}(1-\sqrt{-1})$$

$$\therefore\ \sqrt{\pm\sqrt{-1}}=\pm\frac{1}{\sqrt{2}}(1\pm\sqrt{-1});$$

and finally $$\sqrt[4]{-64a^4}=\pm 2a\,(1\pm\sqrt{-1}).$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Also ω satisfies the equation $x^2 + x + 1 = 0$;

$$\therefore\ 1 + \omega + \omega^2 = 0;$$

that is, *the sum of the three cube roots of unity is zero.*

Again, $$\omega \,.\, \omega^2 = \omega^3 = 1;$$

therefore (1) *the product of the two imaginary roots is unity;*
(2) *every integral power of* ω^3 *is unity.*

109. It is useful to notice that the successive positive integral powers of ω are 1, ω, and ω^2; for, if n be a multiple of 3, it must be of the form $3m$; and $\omega^n = \omega^{3m} = 1$.

If n be not a multiple of 3, it must be of the form $3m + 1$ or $3m + 2$.

If $n = 3m + 1$, $\omega^n = \omega^{3m+1} = \omega^{3m} \,.\, \omega = \omega$.

If $n = 3m + 2$, $\omega^n = \omega^{3m+2} = \omega^{3m} \,.\, \omega^2 = \omega^2$.

110. We now see that every quantity has three cube roots, two of which are imaginary. For the cube roots of a^3 are those of $a^3 \times 1$, and therefore are a, $a\omega$, $a\omega^2$. Similarly the cube roots of 9 are $\sqrt[3]{9}$, $\omega\sqrt[3]{9}$, $\omega^2\sqrt[3]{9}$, where $\sqrt[3]{9}$ is the cube root found by the ordinary arithmetical rule. In future, unless otherwise stated, the symbol $\sqrt[3]{a}$ will always be taken to denote the arithmetical cube root of a.

Example 1. Reduce $\dfrac{(2+3\sqrt{-1})^2}{2+\sqrt{-1}}$ to the form $A + B\sqrt{-1}$.

The expression
$$= \frac{4 - 9 + 12\sqrt{-1}}{2+\sqrt{-1}}$$
$$= \frac{(-5+12\sqrt{-1})(2-\sqrt{-1})}{(2+\sqrt{-1})(2-\sqrt{-1})}$$
$$= \frac{-10+12+29\sqrt{-1}}{4+1}$$
$$= \frac{2}{5} + \frac{29}{5}\sqrt{-1};$$

which is of the required form.

Example 2. *Resolve* $x^3 + y^3$ *into three factors of the first degree.*

Since $$x^3 + y^3 = (x+y)(x^2 - xy + y^2)$$
$$x^3 + y^3 = (x+y)(x+\omega y)(x+\omega^2 y);$$

for $\omega + \omega^2 = -1$, and $\omega^3 = 1$.

Example 3. Shew that

$$(a+\omega b+\omega^2 c)(a+\omega^2 b+\omega c)=a^2+b^2+c^2-bc-ca-ab.$$

In the product of $a+\omega b+\omega^2 c$ and $a+\omega^2 b+\omega c$,

the coefficients of b^2 and c^2 are ω^3, or 1;

the coefficient of bc $=\omega^2+\omega^4=\omega^2+\omega=-1$;

the coefficients of ca and $ab=\omega^2+\omega=-1$;

$$\therefore\ (a+\omega b+\omega^2 c)(a+\omega^2 b+\omega c)=a^2+b^2+c^2-bc-ca\quad ab.$$

Example 4. Shew that

$$(1+\omega-\omega^2)^3-(1-\omega+\omega^2)^3=0.$$

Since $1+\omega+\omega^2=0$, we have

$$\begin{aligned}(1+\omega-\omega^2)^3-(1-\omega+\omega^2)^3&=(-2\omega^2)^3-(-2\omega)^3\\&=-8\omega^6+8\omega^3\\&=-8+8\\&=0.\end{aligned}$$

EXAMPLES. VIII. b.

1. Multiply $2\sqrt{-3}+3\sqrt{-2}$ by $4\sqrt{-3}-5\sqrt{-2}$.
2. Multiply $3\sqrt{-7}-5\sqrt{-2}$ by $3\sqrt{-7}+5\sqrt{-2}$.
3. Multiply $e^{\sqrt{-1}}+e^{-\sqrt{-1}}$ by $e^{\sqrt{-1}}-e^{-\sqrt{-1}}$
4. Multiply $x-\dfrac{1+\sqrt{-3}}{2}$ by $x-\dfrac{1-\sqrt{-3}}{2}$.

Express with rational denominator:

5. $\dfrac{1}{3-\sqrt{-2}}$.
6. $\dfrac{3\sqrt{-2}+2\sqrt{-5}}{3\sqrt{-2}-2\sqrt{-5}}$.
7. $\dfrac{3+2\sqrt{-1}}{2-5\sqrt{-1}}+\dfrac{3-2\sqrt{-1}}{2+5\sqrt{-1}}$.
8. $\dfrac{a+x\sqrt{-1}}{a-x\sqrt{-1}}-\dfrac{a-x\sqrt{-1}}{a+x\sqrt{-1}}$.
9. $\dfrac{(x+\sqrt{-1})^2}{x-\sqrt{-1}}-\dfrac{(x-\sqrt{-1})^2}{x+\sqrt{-1}}$.
10. $\dfrac{(a+\sqrt{-1})^3-(a-\sqrt{-1})^3}{(a+\sqrt{-1})^2-(a-\sqrt{-1})^2}$.
11. Find the value of $(-\sqrt{-1})^{4n+3}$, when n is a positive integer.
12. Find the square of $\sqrt{9+40\sqrt{-1}}+\sqrt{9-40\sqrt{-1}}$.

Find the square root of

13. $-5+12\sqrt{-1}$. **14.** $-11-60\sqrt{-1}$. **15.** $47+8\sqrt{-3}$.

16. $-8\sqrt{-1}$. **17.** $a^2-1+2a\sqrt{-1}$.

18. $4ab-2(a^2-b^2)\sqrt{-1}$.

Express in the form $A+iB$

19. $\dfrac{3+5i}{2-3i}$. **20.** $\dfrac{\sqrt{3}-i\sqrt{2}}{2\sqrt{3}-i\sqrt{2}}$. **21.** $\dfrac{1+i}{1-i}$.

22. $\dfrac{(1+i)^2}{3-i}$. **23.** $\dfrac{(a+ib)^2}{a-ib}-\dfrac{(a-ib)^2}{a+ib}$.

If 1, ω, ω^2 are the three cube roots of unity, prove

24. $(1+\omega^2)^4=\omega$. **25.** $(1-\omega+\omega^2)(1+\omega-\omega^2)=4$.

26. $(1-\omega)(1-\omega^2)(1-\omega^4)(1-\omega^5)=9$.

27. $(2+5\omega+2\omega^2)^6=(2+2\omega+5\omega^2)^6=729$.

28. $(1-\omega+\omega^2)(1-\omega^2+\omega^4)(1-\omega^4+\omega^8)\ldots$ to $2n$ factors $=2^{2n}$

29. Prove that

$$x^3+y^3+z^3-3xyz=(x+y+z)(x+y\omega+z\omega^2)(x+y\omega^2+z\omega).$$

30. If $x=a+b,\ y=a\omega+b\omega^2,\ z=a\omega^2+b\omega,$

shew that

(1) $xyz=a^3+b^3$.

(2) $x^2+y^2+z^2=6ab$.

(3) $x^3+y^3+z^3=3(a^3+b^3)$.

31. If $ax+cy+bz=X,\ cx+by+az=Y,\ bx+ay+cz=Z,$

shew that $(a^2+b^2+c^2-bc-ca-ab)(x^2+y^2+z^2-yz-zx-xy)$

$$=X^2+Y^2+Z^2-YZ-XZ\quad XY.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

113. In Art. 111 let the two roots in (2) be denoted by α and β, so that

$$\alpha = \frac{-b+\sqrt{b^2-4ac}}{2a}, \quad \beta = \frac{-b-\sqrt{b^2-4ac}}{2a};$$

then we have the following results:

(1) If b^2-4ac (the quantity under the radical) is positive, α and β are real and unequal.

(2) If b^2-4ac is zero, α and β are real and equal, each reducing in this case to $-\frac{b}{2a}$.

(3) If b^2-4ac is negative, α and β are imaginary and unequal.

(4) If b^2-4ac is a perfect square, α and β are rational and unequal.

By applying these tests the nature of the roots of any quadratic may be determined without solving the equation.

Example 1. Shew that the equation $2x^2-6x+7=0$ cannot be satisfied by any real values of x.

Here $a=2,\ b=-6,\ c=7$; so that

$$b^2-4ac=(-6)^2-4\,.\,2\,.\,7=-20.$$

Therefore the roots are imaginary.

Example 2. If the equation $x^2+2(k+2)x+9k=0$ has equal roots, find k.

The condition for equal roots gives

$$(k+2)^2=9k,$$
$$k^2-5k+4=0,$$
$$(k-4)(k-1)=0;$$
$$\therefore\ k=4, \text{ or } 1.$$

Example 3. Shew that the roots of the equation

$$x^2-2px+p^2-q^2+2qr-r^2=0$$

are rational.

The roots will be rational provided $(-2p)^2-4(p^2-q^2+2qr-r^2)$ is a perfect square. But this expression reduces to $4(q^2-2qr+r^2)$, or $4(q-r)^2$ Hence the roots are rational.

114. Since $\alpha=\frac{-b+\sqrt{b^2-4ac}}{2a}, \quad \beta=\frac{-b-\sqrt{b^2-4ac}}{2a}$

we have by addition

$$\alpha+\beta=\frac{-b+\sqrt{b^2-4ac}-b-\sqrt{b^2-4ac}}{2a}$$

$$=-\frac{2b}{2a}=-\frac{b}{a} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1);$$

and by multiplication we have

$$\alpha\beta = \frac{(-b+\sqrt{b^2-4ac})(-b-\sqrt{b^2-4ac})}{4a^2}$$

$$= \frac{(-b)^2-(b^2-4ac)}{4a^2}$$

$$= \frac{4ac}{4a^2} = \frac{c}{a} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

By writing the equation in the form

$$x^2 + \frac{b}{a}x + \frac{c}{a} = 0,$$

these results may also be expressed as follows.

In a quadratic equation *where the coefficient of the first term is unity*,

(i) the sum of the roots is equal to the coefficient of x with its sign changed;

(ii) the product of the roots is equal to the third term.

NOTE. In any equation the term which does not contain the unknown quantity is frequently called *the absolute term*.

115. Since $-\frac{b}{a} = \alpha+\beta$, and $\frac{c}{a} = \alpha\beta$,

the equation $x^2+\frac{b}{a}x+\frac{c}{a}=0$ may be written

$$x^2-(\alpha+\beta)x+\alpha\beta=0 \quad \ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Hence any quadratic may also be expressed in the form

$$x^2-(\text{sum of roots})\,x+\text{product of roots}=0 \quad \ldots\ldots\ldots (2).$$

Again, from (1) we have

$$(x-\alpha)(x-\beta)=0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (3).$$

We may now easily form an equation with given roots.

Example 1. Form the equation whose roots are 3 and -2.

The equation is $$(x-3)(x+2)=0,$$

or $$x^2-x-6=0.$$

When the roots are irrational it is easier to use the following method.

Example 2. Form the equation whose roots are $2+\sqrt{3}$ and $2-\sqrt{3}$.

We have $$\text{sum of roots} = 4,$$
$$\text{product of roots} = 1;$$
the equation is $$x^2 - 4x + 1 = 0,$$
by using formula (2) of the present article.

116. By a method analogous to that used in Example 1 of the last article we can form an equation with three or more given roots.

Example 1. Form the equation whose roots are 2, -3, and $\frac{7}{5}$.

The required equation must be satisfied by each of the following suppositions:

$$x-2=0,\ \ x+3=0,\ \ x-\frac{7}{5}=0;$$

therefore the equation must be

$$(x-2)(x+3)\left(x-\frac{7}{5}\right)=0;$$

that is, $$(x-2)(x+3)(5x-7)=0,$$
or $$5x^3-2x^2-37x+42=0.$$

Example 2. Form the equation whose roots are $0,\ \pm a,\ \frac{c}{b}$.

The equation has to be satisfied by

$$x=0,\ \ x=a,\ \ x=-a,\ \ x-\frac{c}{b},$$

therefore it is

$$x(x+a)(x-a)\left(x-\frac{c}{b}\right)=0;$$

that is, $$x(x^2-a^2)(bx-c)=0,$$
or $$bx^4-cx^3-a^2bx^2+a^2cx=0.$$

117. The results of Art. 114 are most important, and they are generally sufficient to solve problems connected with the roots of quadratics. In such questions *the roots should never be considered singly*, but use should be made of the relations obtained by writing down the sum of the roots, and their product, in terms of the coefficients of the equation.

Example 1. If α and β are the roots of $x^2-px+q=0$, find the value of (1) $\alpha^2+\beta^2$, (2) $\alpha^3+\beta^3$

We have $$\alpha+\beta=p,$$
$$\alpha\beta=q.$$
$$\alpha^2+\beta^2=(\alpha+\beta)^2-2\alpha\beta$$
$$=p^2-2q.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

118. *To find the condition that the roots of the equation* $ax^2+bx+c=0$ *should be* (1) *equal in magnitude and opposite in sign,* (2) *reciprocals.*

The roots will be equal in magnitude and opposite in sign if their sum is zero; hence the required condition is

$$-\frac{b}{a}=0, \text{ or } b=0.$$

Again, the roots will be reciprocals when their product is unity; hence we must have

$$\frac{c}{a}=1, \text{ or } c=a.$$

The first of these results is of frequent occurrence in Analytical Geometry, and the second is a particular case of a more general condition applicable to equations of any degree.

E*xample.* Find the condition that the roots of $ax^2+bx+c=0$ may be (1) both positive, (2) opposite in sign, but the greater of them negative.

We have $$\alpha+\beta=-\frac{b}{a}, \quad \alpha\beta=\frac{c}{a}.$$

(1) If the roots are both positive, $\alpha\beta$ is positive, and therefore c and a have like signs.

Also, since $\alpha+\beta$ is positive, $-\frac{b}{a}$ is negative; therefore b and a have unlike signs.

Hence the required condition is that the signs of a and c should be like, and opposite to the sign of b.

(2) If the roots are of opposite signs, $\alpha\beta$ is negative, and therefore c and a have unlike signs.

Also since $\alpha+\beta$ has the sign of the greater root it is negative, and therefore $\frac{b}{a}$ is positive; therefore b and a have like signs.

Hence the required condition is that the signs of a and b should be like, and opposite to the sign of c.

EXAMPLES. IX. a.

Form the equations whose roots are

1. $\frac{4}{5}, \frac{3}{7}$.
2. $\frac{m}{n}, \frac{n}{m}$.
3. $\frac{p-q}{p+q}, -\frac{p+q}{p-q}$.
4. $7\pm2\sqrt{5}$.
5. $+2\sqrt{3}-5$.
6. $-p\pm2\sqrt{2q}$.

7. $-3\pm5i$. **8.** $-a+ib$. **9.** $+i(a-b)$.

10. $-3, \frac{2}{3}, \frac{1}{2}$. **11.** $\frac{a}{2}, 0, -\frac{2}{a}$. **12.** $2\pm\sqrt{3}, 4$.

13. Prove that the roots of the following equations are real:

(1) $x^2-2ax+a^2-b^2-c^2=0$,

(2) $(a-b+c)x^2+4(a-b)x+(a-b-c)=0$.

14. If the equation $x^2-15-m(2x-8)=0$ has equal roots, find the values of m.

15. For what values of m will the equation

$$x^2-2x(1+3m)+7(3+2m)=0$$

have equal roots?

16. For what value of m will the equation

$$\frac{x^2-bx}{ax-c}=\frac{m-1}{m+1}$$

have roots equal in magnitude but opposite in sign?

17. Prove that the roots of the following equations are rational:

(1) $(a+c-b)x^2+2cx+(b+c-a)=0$,

(2) $abc^2x^2+3a^2cx+b^2cx-6a^2-ab+2b^2=0$.

If α, β are the roots of the equation $ax^2+bx+c=0$, find the values of

18. $\frac{1}{\alpha^2}+\frac{1}{\beta^2}$. **19.** $\alpha^4\beta^7+\alpha^7\beta^4$. **20.** $\left(\frac{\alpha}{\beta}-\frac{\beta}{\alpha}\right)^2$.

Find the value of

21. x^3+x^2-x+22 when $x=1+2i$.

22. $x^3-3x^2-8x+15$ when $x=3+i$.

23. $x^3-ax^2+2a^2x+4a^3$ when $\frac{x}{a}=1-\sqrt{-3}$.

24. If α and β are the roots of $x^2+px+q=0$, form the equation whose roots are $(\alpha-\beta)^2$ and $(\alpha+\beta)^2$.

25. Prove that the roots of $(x-a)(x-b)=h^2$ are always real.

26. If x_1, x_2 are the roots of $ax^2+bx+c=0$, find the value of

(1) $(ax_1+b)^{-2}+(ax_2+b)^{-2}$,

(2) $(ax_1+b)^{-3}+(ax_2+b)^{-3}$.

27. Find the condition that one root of $ax^2+bx+c=0$ shall be n times the other.

28. If α, β are the roots of $ax^2+bx+c=0$, form the equation whose roots are $\alpha^2+\beta^2$ and $\alpha^{-2}+\beta^{-2}$.

29. Form the equation whose roots are the squares of the sum and of the difference of the roots of

$$2x^2+2(m+n)x+m^2+n^2=0.$$

30. Discuss the signs of the roots of the equation

$$px^2+qx+r=0.$$

119. The following example illustrates a useful application of the results proved in Art. 113.

Example. If x is a real quantity, prove that the expression $\dfrac{x^2+2x-11}{2(x-3)}$ can have all numerical values except such as lie between 2 and 6.

Let the given expression be represented by y, so that

$$\frac{x^2+2x-11}{2(x-3)}=y;$$

then multiplying up and transposing, we have

$$x^2+2x(1-y)+6y-11=0.$$

This is a quadratic equation, and in order that x may have real values $4(1-y)^2-4(6y-11)$ must be positive; or dividing by 4 and simplifying, $y^2-8y+12$ must be positive; that is, $(y-6)(y-2)$ must be positive. Hence the factors of this product must be both positive, or both negative. In the former case y is greater than 6; in the latter y is less than 2. Therefore y cannot lie between 2 and 6, but may have any other value.

In this example it will be noticed that the *quadratic expression* $y^2-8y+12$ is positive so long as y does not lie between the roots of the corresponding *quadratic equation* $y^2-8y+12=0$.

This is a particular case of the general proposition investigated in the next article.

120. *For all real values of* x *the expression* ax^2+bx+c *has the same sign as* a, *except when the roots of the equation* $ax^2+bx+c=0$ *are real and unequal, and* x *has a value lying between them*

Case I. Suppose that the roots of the equation

$$ax^2+bx+c=0$$

are real; denote them by α and β, and let α be the greater.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Example. Find the limits between which a must lie in order that

$$\frac{ax^2-7x+5}{5x^2-7x+a}$$

may be capable of all values, x being any real quantity.

Put $$\frac{ax^2-7x+5}{5x^2-7x+a}=y;$$

then $$(a-5y)\,x^2-7x\,(1-y)+(5-ay)=0.$$

In order that the values of x found from this quadratic may be real, the expression

$49\,(1-y)^2-4\,(a-5y)\,(5-ay)$ must be positive,

that is, $(49-20a)\,y^2+2\,(2a^2+1)\,y+(49-20a)$ must be positive;

hence $(2a^2+1)^2-(49-20a)^2$ must be negative or zero, and $49-20a$ must be positive.

Now $(2a^2+1)^2-(49-20a)^2$ is negative or zero, according as

$2\,(a^2-10a+25)\times 2\,(a^2+10a-24)$ is negative or zero;

that is, according as $4\,(a-5)^2\,(a+12)\,(a-2)$ is negative or zero.

This expression is negative as long as a lies between 2 and -12, and for such values $49-20a$ is positive; the expression is zero when $a=5$, -12, or 2, but $49-20a$ is negative when $a=5$. Hence the limiting values are 2 and -12, and a may have any intermediate value.

EXAMPLES. IX. b.

1. Determine the limits between which n must lie in order that the equation

$$2ax\,(ax+nc)+(n^2-2)\,c^2=0$$

may have real roots.

2. If x be real, prove that $\dfrac{x}{x^2-5x+9}$ must lie between 1 and $\dfrac{1}{11}$.

3. Shew that $\dfrac{x^2-x+1}{x^2+x+1}$ lies between 3 and $\dfrac{1}{3}$ for all real values of x.

4. If x be real, prove that $\dfrac{x^2+34x-71}{x^2+2x-7}$ can have no value between 5 and 9.

5. Find the equation whose roots are $\dfrac{\sqrt{a}}{\sqrt{a}\pm\sqrt{a-b}}$.

6. If α, β are roots of the equation $x^2-px+q=0$, find the value of

(1) $\alpha^2\,(\alpha^2\beta^{-1}-\beta)+\beta^2\,(\beta^2\alpha^{-1}-\alpha)$,

(2) $(\alpha-p)^{-4}+(\beta-p)^{-4}$.

7. If the roots of $lx^2+nx+n=0$ be in the ratio of $p:q$, prove that

$$\sqrt{\frac{p}{q}}+\sqrt{\frac{q}{p}}+\sqrt{\frac{n}{l}}=0.$$

8. If x be real, the expression $\dfrac{(x+m)^2-4mn}{2(x-n)}$ admits of all values except such as lie between $2n$ and $2m$.

9. If the roots of the equation $ax^2+2bx+c=0$ be α and β, and those of the equation $Ax^2+2Bx+C=0$ be $\alpha+\delta$ and $\beta+\delta$, prove that

$$\frac{b^2-ac}{a^2}=\frac{B^2-AC}{A^2}.$$

10. Shew that the expression $\dfrac{px^2+3x-4}{p+3x-4x^2}$ will be capable of all values when x is real, provided that p has any value between 1 and 7.

11. Find the greatest value of $\dfrac{x+2}{2x^2+3x+6}$ for real values of x.

12. Shew that if x is real, the expression

$$(x^2-bc)(2x-b-c)^{-1}$$

has no real values between b and c.

13. If the roots of $ax^2+2bx+c=0$ be possible and different, then the roots of

$$(a+c)(ax^2+2bx+c)=2(ac-b^2)(x^2+1)$$

will be impossible, and *vice versâ*.

14. Shew that the expression $\dfrac{(ax-b)(dx-c)}{(bx-a)(cx-d)}$ will be capable of all values when x is real, if a^2-b^2 and c^2-d^2 have the same sign.

*122. We shall conclude this chapter with some miscellaneous theorems and examples. It will be convenient here to introduce a phraseology and notation which the student will frequently meet with in his mathematical reading.

DEFINITION. Any expression which involves x, and whose value is dependent on that of x, is called a **function of x**. Functions of x are usually denoted by symbols of the form $f(x)$, $F(x)$, $\phi(x)$.

Thus the equation $y=f(x)$ may be considered as equivalent to a statement that any change made in the value of x will produce a consequent change in y, and *vice versâ*. The quantities x and y are called **variables**, and are further distinguished as the **independent variable** and the **dependent variable**.

An *independent variable* is a quantity which may have any value we choose to assign to it, and the corresponding *dependent variable* has its value determined as soon as the value of the independent variable is known.

*123. An expression of the form

$$p_0x^n + p_1x^{n-1} + p_2x^{n-2} + \ldots + p_{n-1}x + p_n$$

where n is a positive integer, and the coefficients p_0, p_1, p_2,...p_n do not involve x, is called a **rational and integral algebraical function of x.** In the present chapter we shall confine our attention to functions of this kind.

*124. A function is said to be **linear** when it contains no higher power of the variable than the first; thus $ax + b$ is a linear function of x. A function is said to be **quadratic** when it contains no higher power of the variable than the second; thus $ax^2 + bx + c$ is a quadratic function of x. Functions of the *third*, *fourth*,... degrees are those in which the highest power of the variable is respectively the *third*, *fourth*,.... Thus in the last article the expression is a function of x of the n^{th} degree.

*125. The symbol $f(x, y)$ is used to denote a function of two variables x and y; thus $ax + by + c$, and $ax^2 + bxy + cy^2 + dx + ey + f$ are respectively linear and quadratic functions of x, y.

The *equations* $f(x) = 0$, $f(x, y) = 0$ are said to be linear, quadratic,... according as the *functions* $f(x)$, $f(x, y)$ are linear, quadratic,.

*126. We have proved in Art. 120 that the *expression* $ax^2 + bx + c$ admits of being put in the form $a(x - \alpha)(x - \beta)$, where α and β are the roots of the *equation* $ax^2 + bx + c = 0$.

Thus a quadratic expression $ax^2 + bx + c$ is capable of being resolved into two rational factors of the first degree, whenever the equation $ax^2 + bx + c = 0$ has rational roots; that is, when $b^2 - 4ac$ is a perfect square.

*127. *To find the condition that a quadratic function of* x, y *may be resolved into two linear factors.*

Denote the function by $f(x, y)$ where

$$f(x, y) = ax^2 + 2hxy + by^2 + 2gx + 2fy + c.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

*EXAMPLES. IX. c.

1. For what values of m will the expression

$$y^2+2xy+2x+my-3$$

be capable of resolution into two rational factors?

2. Find the values of m which will make $2x^2+mxy+3y^2-5y-2$ equivalent to the product of two linear factors.

3. Shew that the expression

$$A(x^2-y^2)-xy(B-C)$$

always admits of two real linear factors.

4. If the equations

$$x^2+px+q=0, \qquad x^2+p'x+q'=0$$

have a common root, shew that it must be either

$$\frac{pq'-p'q}{q-q'} \text{ or } \frac{q-q'}{p'-p}.$$

5. Find the condition that the expressions

$$lx^2+mxy+ny^2, \quad l'x^2+m'xy+n'y^2$$

may have a common linear factor.

6. If the expression

$$3x^2+2Pxy+2y^2+2ax-4y+1$$

can be resolved into linear factors, prove that P must be one of the roots of the equation $P^2+4aP+2a^2+6=0$.

7. Find the condition that the expressions

$$ax^2+2hxy+by^2, \quad a'x^2+2h'xy+b'y^2$$

may be respectively divisible by factors of the form $y-mx$, $my+x$.

8. Shew that in the equation

$$x^2-3xy+2y^2-2x-3y-35=0,$$

for every real value of x there is a real value of y, and for every real value of y there is a real value of x.

9. If x and y are two real quantities connected by the equation

$$9x^2+2xy+y^2-92x-20y+244=0,$$

then will x lie between 3 and 6, and y between 1 and 10.

10. If $(ax^2+bx+c)y+a'x^2+b'x+c'=0$, find the condition that x may be a rational function of y.

CHAPTER X.

MISCELLANEOUS EQUATIONS.

129. In this chapter we propose to consider some miscellaneous equations; it will be seen that many of these can be solved by the ordinary rules for quadratic equations, but others require some special artifice for their solution.

Example I. Solve $8x^{\frac{3}{2n}} - 8x^{-\frac{3}{2n}} = 63.$

Multiply by $x^{\frac{3}{2n}}$ and transpose; thus

$$8x^{\frac{3}{n}} - 63x^{\frac{3}{2n}} - 8 = 0;$$

$$(x^{\frac{3}{2n}} - 8)\,(8x^{\frac{3}{2n}} + 1) = 0;$$

$$x^{\frac{3}{2n}} = 8, \text{ or } -\frac{1}{8};$$

$$x = (2^3)^{\frac{2n}{3}}, \text{ or } \left(-\frac{1}{2^3}\right)^{\frac{2n}{3}};$$

$$\therefore\ x = 2^{2n}, \text{ or } \frac{1}{2^{2n}}.$$

Example 2. Solve $2\sqrt{\frac{x}{a}} + 3\sqrt{\frac{a}{x}} = \frac{b}{a} + \frac{6a}{b}.$

Let $\sqrt{\frac{x}{a}} = y$; then $\sqrt{\frac{a}{x}} = \frac{1}{y}$,

$$2y + \frac{3}{y} = \frac{b}{a} + \frac{6a}{b};$$

$$2aby^2 - 6a^2y - b^2y + 3ab = 0;$$

$$(2ay - b)\,(by - 3a) = 0;$$

$$y = \frac{b}{2a}, \text{ or } \frac{3a}{b};$$

$$\frac{x}{a} = \frac{b^2}{4a^2}, \text{ or } \frac{9a^2}{b^2};$$

that is, $$x = \frac{b^2}{4a}, \text{ or } \frac{9a^3}{b^2}.$$

H. H. A.

Example 3. Solve $(x-5)(x-7)(x+6)(x+4)=504$.

We have $(x^2-x-20)(x^2-x-42)=504$;

which, being arranged as a quadratic in x^2-x, gives

$$(x^2-x)^2-62(x^2-x)+336=0;$$

$$\therefore\ (x^2-x-6)(x^2-x-56)=0;$$

$$x^2-x-6=0,\ \text{or}\ x^2-x-56=0;$$

whence $$x=3,\ -2,\ 8,\ -7.$$

130. Any equation which can be thrown into the form

$$ax^2+bx+c+p\sqrt{ax^2+bx+c}=q$$

may be solved as follows. Putting $y=\sqrt{ax^2+bx+c}$, we obtain

$$y^2+py-q=0.$$

Let α and β be the roots of this equation, so that

$$\sqrt{ax^2+bx+c}=\alpha,\quad \sqrt{ax^2+bx+c}=\beta;$$

from these equations we shall obtain *four* values of x.

When no sign is prefixed to a radical it is usually understood that it is to be taken as positive; hence, if α and β are both positive, all the four values of x satisfy the *original* equation. If however α or β is negative, the roots found from the resulting quadratic will satisfy the equation

$$ax^2+bx+c-p\sqrt{ax^2+bx+c}=q,$$

but not the original equation.

Example. Solve $x^2-5x+2\sqrt{x^2-5x+3}=12$.

Add 3 to each side; then

$$x^2-5x+3+2\sqrt{x^2-5x+3}=15.$$

Putting $\sqrt{x^2-5x+3}=y$, we obtain $y^2+2y-15=0$; whence $y=3$ or -5.

Thus $\sqrt{x^2-5x+3}=+3$, or $\sqrt{x^2-5x+3}=-5$.

Squaring, and solving the resulting quadratics, we obtain from the first $x=6$ or -1; and from the second $x=\dfrac{5\pm\sqrt{113}}{2}$. The first pair of values satisfies the given equation, but the second pair satisfies the equation

$$x^2-5x-2\sqrt{x^2-5x+3}=12.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

133. The solution of an equation of the form

$$ax^4 \pm bx^3 \pm cx^2 \pm bx + a = 0,$$

in which the coefficients of terms equidistant from the beginning and end are equal, can be made to depend on the solution of a quadratic. Equations of this type are known as *reciprocal equations*, and are so named because they are not altered when x is changed into its reciprocal $\frac{1}{x}$.

For a more complete discussion of reciprocal equations the student is referred to Arts. 568—570.

Example. Solve $12x^4 - 56x^3 + 89x^2 - 56x + 12 = 0.$

Dividing by x^2 and rearranging,

$$12\left(x^2 + \frac{1}{x^2}\right) - 56\left(x + \frac{1}{x}\right) + 89 = 0.$$

Put $x + \frac{1}{x} = z$; then $x^2 + \frac{1}{x^2} = z^2 - 2$;

$$\therefore\ 12(z^2 - 2) - 56z + 89 = 0;$$

whence we obtain $z = \frac{5}{2}$, or $\frac{13}{6}$.

$$\therefore\ x + \frac{1}{x} = \frac{5}{2}, \text{ or } \frac{13}{6}.$$

By solving these equations we find that $x = 2, \frac{1}{2}, \frac{3}{2}, \frac{2}{3}$.

134. The following equation though not *reciprocal* may be solved in a similar manner.

Example. Solve $6x^4 - 25x^3 + 12x^2 + 25x + 6 = 0.$

We have $$6\left(x^2 + \frac{1}{x^2}\right) - 25\left(x - \frac{1}{x}\right) + 12 = 0;$$

whence $$6\left(x - \frac{1}{x}\right)^2 - 25\left(x - \frac{1}{x}\right) + 24 = 0;$$

$$2\left(x - \frac{1}{x}\right) - 3 = 0, \text{ or } 3\left(x - \frac{1}{x}\right) - 8 = 0;$$

whence we obtain $$x = 2, -\frac{1}{2}, 3, -\frac{1}{3}.$$

135. When one root of a quadratic equation is obvious by inspection, the other root may often be readily obtained by making use of the properties of the roots of quadratic equations proved in Art. 114.

Example. Solve $(1-a^2)(x+a)-2a(1-x^2)=0$.

This is a quadratic, one of whose roots is clearly a.

Also, since the equation may be written

$$2ax^2+(1-a^2)x-a(1+a^2)=0,$$

the product of the roots is $-\frac{1+a^2}{2}$; and therefore the other root is $\frac{1+a^2}{2a}$

EXAMPLES. X. a.

Solve the following equations.

1. $x^{-2}-2x^{-1}=8.$
2. $9+x^{-4}=10x^{-2}$
3. $2\sqrt{x}+2x^{-\frac{1}{2}}=5.$
4. $6x^{\frac{3}{4}}=7x^{\frac{1}{4}}-2x^{\frac{1}{4}}.$
5. $x^{\frac{2}{n}}+6=5x^{\frac{1}{n}}.$
6. $3x^{\frac{1}{2n}}-x^{\frac{1}{n}}-2=0.$
7. $5\sqrt{\frac{3}{x}}+7\sqrt{\frac{x}{3}}=22\frac{2}{3}.$
8. $\sqrt{\frac{x}{1-x}}+\sqrt{\frac{1-x}{x}}=2\frac{1}{6}.$
9. $6\sqrt{x}=5x^{\frac{1}{2}}-13.$
10. $1+8x^{\frac{6}{5}}+9\sqrt[5]{x^3}=0.$
11. $3^{2x}+9=10\,.\,3^x.$
12. $5(5^x+5^{-x})=26.$
13. $2^{2x+8}+1=32\,.\,2^x$
14. $2^{2x+3}-57=65(2^x-1).$
15. $\sqrt{2^x}+\frac{1}{\sqrt{2^x}}=2$
16. $\frac{3}{\sqrt{2x}}-\frac{\sqrt{2x}}{5}=5\frac{9}{10}.$
17. $(x-7)(x-3)(x+5)(x+1)=1680.$
18. $(x+9)(x-3)(x-7)(x+5)=385.$
19. $x(2x+1)(x-2)(2x-3)=63.$
20. $(2x-7)(x^2-9)(2x+5)=91.$
21. $x^2+2\sqrt{x^2+6x}=24-6x.$
22. $3x^2-4x+\sqrt{3x^2-4x-6}=18.$
23. $3x^2-7+3\sqrt{3x^2-16x+21}=16x.$
24. $8+9\sqrt{(3x-1)(x-2)}=3x^2-7x.$
25. $\frac{3x-2}{2}+\sqrt{2x^2-5x+3}=\frac{(x+1)^2}{3}.$

26. $7x-\frac{\sqrt{3x^2-8x+1}}{x}=\left(\frac{8}{\sqrt{x}}+\sqrt{x}\right)^2.$

27. $\sqrt{4x^2-7x-15}-\sqrt{x^2-3x}=\sqrt{x^2-9}.$

28. $\sqrt{2x^2-9x+4}+3\sqrt{2x-1}=\sqrt{2x^2+21x-11}.$

29. $\sqrt{2x^2+5x-7}+\sqrt{3(x^2-7x+6)}-\sqrt{7x^2-6x-1}=0.$

30. $\sqrt{a^2+2ax-3x^2}-\sqrt{a^2+ax-6x^2}=\sqrt{2a^2+3ax-9x^2}.$

31. $\sqrt{2x^2+5x-2}-\sqrt{2x^2+5x-9}=1.$

32. $\sqrt{3x^2-2x+9}+\sqrt{3x^2-2x-4}=13.$

33. $\sqrt{2x^2-7x+1}-\sqrt{2x^2-9x+4}=1.$

34. $\sqrt{3x^2-7x-30}-\sqrt{2x^2-7x-5}=x-5.$

35. $x^4+x^3-4x^2+x+1=0.$

36. $x^4+\frac{8}{9}x^2+1=3x^3+3x.$

37. $x^4+1-3(x^3+x)=2x^2$

38. $10(x^4+1)-63x(x^2-1)+52x^2=0.$

39. $\frac{x+\sqrt{12a-x}}{x-\sqrt{12a-x}}=\frac{\sqrt{a}+1}{\sqrt{a}-1}.$

40. $\frac{a+2x+\sqrt{a^2-4x^2}}{a+2x-\sqrt{a^2-4x^2}}=\frac{5x}{a}.$

41. $\frac{x+\sqrt{x^2-1}}{x-\sqrt{x^2-1}}-\frac{x-\sqrt{x^2-1}}{x+\sqrt{x^2-1}}=8x\sqrt{x^2-3x+2}.$

42. $\sqrt{x^2+x}+\frac{\sqrt{x-1}}{\sqrt{x^3-x}}=\frac{5}{2}.$

43. $\frac{x^3+1}{x^2-1}=x+\sqrt{\frac{6}{x}}.$

44. $2^{x^2}:2^{2x}=8:1.$

45. $a^{2x}(a^2+1)=(a^{3x}+a^x)a.$

46. $\frac{8\sqrt{x-5}}{3x-7}=\frac{\sqrt{3x-7}}{x-5}.$

47. $\frac{18(7x-3)}{2x+1}=\frac{250\sqrt{2x+1}}{3\sqrt{7x-3}}.$

48. $(a+x)^{\frac{2}{3}}+4(a-x)^{\frac{2}{3}}=5(a^2-x^2)^{\frac{1}{3}}.$

49. $\sqrt{x^2+ax-1}-\sqrt{x^2+bx-1}=\sqrt{a}-\sqrt{b}.$

50. $\frac{x+\sqrt{x^2-1}}{x-\sqrt{x^2-1}}+\frac{x-\sqrt{x^2-1}}{x+\sqrt{x^2-1}}=98.$

51. $x^4-2x^3+x=380.$

52. $27x^3+21x+8=0$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

From (3), $$\frac{x}{2}=\frac{y}{3}=\frac{7x+5y}{29}$$

$$=1, \text{ by equation (2).}$$

$$\therefore\ x=2,\ y=3.$$

Again, from (4), $$\frac{x}{19}-\frac{y}{-43}=\frac{7x+5y}{-82}$$

$$=-\frac{29}{82}, \text{ by equation (2),}$$

$$\therefore\ x=-\frac{551}{82},\ y=\frac{1247}{82}.$$

Hence $$x=2,\ y=3;\ \text{or } x=-\frac{551}{82},\ y=\frac{1247}{82}.$$

Example 4. Solve $$4x^3+3x^2y+y^3=8,$$
$$2x^3-2x^2y+xy^2=1.$$

Put $y=mx$, and substitute in both equations. Thus

$$x^3(4+3m+m^3)=8 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

$$x^3(2-2m+m^2)=1 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$$

$$\therefore\ \frac{4+3m+m^3}{2-2m+m^2}=8;$$

$$m^3-8m^2+19m-12=0;$$

that is, $$(m-1)(m-3)(m-4)=0;$$

$$\therefore\ m=1, \text{ or } 3, \text{ or } 4.$$

(i) Take $m=1$, and substitute in either (1) or (2).

From (2), $$x^3=1;\ \therefore\ x=1;$$

and $$y=mx=x=1.$$

(ii) Take $m=3$, and substitute in (2);

thus $$5x^3=1;\ \therefore\ x=\sqrt[3]{\frac{1}{5}};$$

and $$y=mx=3x=3\sqrt[3]{\frac{1}{5}}.$$

(iii) Take $m=4$; we obtain

$$10x^3=1;\ \therefore\ x=\sqrt[3]{\frac{1}{10}};$$

and $$y=mx=4x=4\sqrt[3]{\frac{1}{10}}.$$

Hence the complete solution is

$$x=1,\ \sqrt[3]{\frac{1}{5}},\ \sqrt[3]{\frac{1}{10}}.$$

$$y=1,\ 3\sqrt[3]{\frac{1}{5}},\ 4\sqrt[3]{\frac{1}{10}}.$$

NOTE. The above method of solution may always be used when the equations are *of the same degree and homogeneous.*

Example 5. Solve $31x^2y^2-7y^4-112xy+64=0$ .....(1),

$$x^2-7xy+4y^2+8=0 \text{ .....(2).}$$

From (2) we have $-8=x^2-7xy+4y^2$; and, substituting in (1),

$$31x^2y^2-7y^4+14xy\,(x^2-7xy+4y^2)+(x^2-7xy+4y^2)^2=0;$$

$$\cdot\ 31x^2y^2-7y^4+(x^2-7xy+4y^2)\,(14xy+x^2-7xy+4y^2)=0;$$

$$\cdot\ 31x^2y^2-7y^4+(x^2+4y^2)^2-(7xy)^2=0;$$

that is,

$$x^4-10x^2y^2+9y^4=0 \text{ .....(3).}$$

$$\therefore\ (x^2-y^2)\,(x^2-9y^2)=0;$$

hence

$$x=\pm y,\ \text{or } x=\pm 3y.$$

Taking these cases in succession and substituting in (2), we obtain

$$x=y=\pm 2;$$

$$x=-y=\pm\sqrt{-\frac{2}{3}};$$

$$x=\pm 3,\ y=\pm 1;$$

$$x=\pm 3\sqrt{-\frac{4}{17}},\ y=\mp\sqrt{-\frac{4}{17}}$$

NOTE. It should be observed that equation (3) is *homogeneous.* The method here employed by which one equation is made homogeneous by a suitable combination with the other is a valuable artifice. It is especially useful in Analytical Geometry.

Example 6. Solve $(x+y)^{\frac{2}{3}}+2\,(x-y)^{\frac{2}{3}}=3\,(x^2-y^2)^{\frac{1}{3}}$ .....(1).

$$3x-2y=13 \text{ .....(2).}$$

Divide each term of (1) by $(x^2-y^2)^{\frac{1}{3}}$, or $(x+y)^{\frac{1}{3}}\,(x-y)^{\frac{1}{3}}$;

$$\cdot\ \left(\frac{x+y}{x-y}\right)^{\frac{1}{3}}+2\left(\frac{x-y}{x+y}\right)^{\frac{1}{3}}=3.$$

This equation is a quadratic in $\left(\frac{x+y}{x-y}\right)^{\frac{1}{3}}$, from which we easily find,

$$\left(\frac{x+y}{x-y}\right)^{\frac{1}{3}}=2 \text{ or } 1; \quad \text{whence } \frac{x+y}{x-y}=8 \text{ or } 1;$$

$$\therefore \quad 7x=9y, \text{ or } y=0.$$

Combining these equations with (2), we obtain

$$x=9,\ y=7; \quad \text{or } x=\frac{13}{3},\ y=0.$$

EXAMPLES. X. b.

Solve the following equations:

1. $3x-2y=7,$
$xy=20.$

2. $5x-y=3,$
$y^2-6x^2=25.$

3. $4x \quad 3y=1,$
$12xy+13y^2=25.$

4. $x^4+x^2y^2+y^4=931,$
$x^2- \ xy \ +y^2=19.$

5. $x^2+ \ xy \ +y^2=84,$
$x-\sqrt{xy}+y \ =6.$

6. $x+\sqrt{xy}+y \ =65,$
$x^2+ \ xy \ +y^2=2275.$

7. $x+y \ =7+\sqrt{xy},$
$x^2+y^2=133-xy.$

8. $3x^2-5y^2=7,$
$3xy-4y^2=2.$

9. $5y^2-7x^2=17,$
$5xy-6x^2=6.$

10. $3x^2+165=16xy,$
$7xy+3y^2=132.$

11. $3x^2+xy+y^2=15,$
$31xy-3x^2-5y^2=45.$

12. $x^2+y^2-3=3xy,$
$2x^2-6+y^2=0.$

13. $x^4+y^4=706,$
$x+y=8.$

14. $x^4+y^4=272,$
$x-y=2.$

15. $x^5-y^5=992,$
$x-y=2.$

16. $x+\frac{4}{y}=1,$
$y+\frac{4}{x}=25.$

17. $\frac{x^2}{y}+\frac{y^2}{x}=\frac{9}{2},$
$\frac{3}{x+y}=1.$

18. $\frac{x}{2}+\frac{y}{5}=5.$
$\frac{2}{x}+\frac{5}{y}=\frac{5}{6}.$

19. $x+y=1072,$
$x^{\frac{1}{3}}+y^{\frac{1}{3}}=16.$

20. $xy^{\frac{1}{2}}+yx^{\frac{1}{2}}=20,$
$x^{\frac{3}{2}}+y^{\frac{3}{2}}=65.$

21. $x^{\frac{1}{2}}+y^{\frac{1}{2}}=5,$
$6\,(x^{-\frac{1}{2}}+y^{-\frac{1}{2}})=5.$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Also from (1), $u+z=13$;

whence we obtain $u=7$ or 6; $z=6$ or 7.

Thus we have $\left.\begin{matrix} x+y=7, \\ xy=10 \end{matrix}\right\}$ and $\left.\begin{matrix} x+y=6, \\ xy=10 \end{matrix}\right\}$

Hence the solutions are

$$\left.\begin{matrix} x=5, \text{ or } 2, \\ y=2, \text{ or } 5, \\ z=6; \end{matrix}\right\} \text{ or } \left.\begin{matrix} x=3\pm\sqrt{-1}, \\ y=3\mp\sqrt{-1}, \\ z=7. \end{matrix}\right\}$$

Example 2. Solve $(x+y)(x+z)=30,$

$$(y+z)(y+x)=15,$$

$$(z+x)(z+y)=18.$$

Write u, v, w for $y+z$, $z+x$, $x+y$ respectively; thus

$$vw=30,\ wu=15,\ uv=18 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

Multiplying these equations together, we have

$$u^2v^2w^2=30\times15\times18=15^2\times6^2;$$

$$uvw=\pm90.$$

Combining this result with each of the equations in (1), we have

$$u=3,\ v=6,\ w=5;\ \text{or}\ u=-3,\ v=-6,\ w=-5;$$

$$\therefore\ \left.\begin{matrix} y+z=3, \\ z+x=6, \\ x+y=5; \end{matrix}\right\} \text{ or } \left.\begin{matrix} y+z=-3, \\ z+x=-6, \\ x+y=-5, \end{matrix}\right\}$$

whence $x=4,\ y=1,\ z=2;$ or $x=-4,\ y=-1,\ z=-2.$

Example 3. Solve $y^2+yz+z^2=49$ ..... (1),

$$z^2+zx+x^2=19 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2),$$

$$x^2+xy+y^2=39 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(3).$$

Subtracting (2) from (1)

$$y^2-x^2+z(y-x)=30;$$

that is, $$(y-x)(x+y+z)=30 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(4).$$

Similarly from (1) and (3)

$$(z-x)(x+y+z)=10 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(5).$$

Hence from (4) and (5), by division

$$\frac{y-x}{z-x}=3;$$

whence $$y=3z-2x.$$

Substituting in equation (3), we obtain

$$x^2 - 3xz + 3z^2 = 13.$$

From (2), $$x^2 + xz + z^2 = 19.$$

Solving these homogeneous equations as in Example 4, Art. 136, we obtain

$$x = \pm 2,\ z = \pm 3;\ \text{and therefore } y = \pm 5;$$

or $$x = \pm \frac{11}{\sqrt{7}},\ z = \pm \frac{1}{\sqrt{7}};\ \text{and therefore } y = \mp \frac{19}{\sqrt{7}}.$$

Example 4. Solve $x^2 - yz = a^2,\ y^2 - zx = b^2,\ z^2 - xy = c^2.$

Multiply the equations by y, z, x respectively and add; then

$$c^2x + a^2y + b^2z = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Multiply the equations by z, x, y respectively and add; then

$$b^2x + c^2y + a^2z = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

From (1) and (2), by cross multiplication,

$$\frac{x}{a^4 - b^2c^2} = \frac{y}{b^4 - c^2a^2} = \frac{z}{c^4 - a^2b^2} = k \text{ suppose.}$$

Substitute in any one of the given equations; then

$$k^2 (a^6 + b^6 + c^6 - 3a^2b^2c^2) = 1;$$

$$\therefore\ \frac{x}{a^4 - b^2c^2} = \frac{y}{b^4 - c^2a^2} = \frac{z}{c^4 - a^2b^2} = \pm \frac{1}{\sqrt{a^6 + b^6 + c^6 - 3a^2b^2c^2}}.$$

EXAMPLES. X. c.

Solve the following equations:

1. $9x + y - 8z = 0,$
$4x - 8y + 7z = 0,$
$yz + zx + xy = 47.$

2. $3x + y - 2z = 0,$
$4x - y - 3z = 0,$
$x^3 + y^3 + z^3 = 467.$

3. $x - y - z = 2,$
$x^2 + y^2 - z^2 = 22,$
$xy = 5.$

4. $x + 2y - z = 11,$
$x^2 - 4y^2 + z^2 = 37,$
$xz = 24.$

5. $x^2 + y^2 - z^2 = 21,$
$3xz + 3yz - 2xy = 18,$
$x + y - z = 5.$

6. $x^2 + xy + xz = 18,$
$y^2 + yz + yx + 12 = 0,$
$z^2 + zx + zy = 30.$

7. $x^2 + 2xy + 3xz = 50,$
$2y^2 + 3yz + yx = 10,$
$3z^2 + zx + 2zy = 10.$

8. $(y - z)(z + x) = 22,$
$(z + x)(x - y) = 33,$
$(x - y)(y - z) = 6.$

9. $x^2y^2z^2u=12,\ x^2y^2zu^2=8,\ x^2yz^2u^2=1,\ 3xy^2z^2u^2=4.$

10. $x^3y^2z=12,\ x^3yz^3=54,\ x^7y^3z^2=72.$

11.
$$xy+x+y=23,$$
$$xz+x+z=41,$$
$$yz+y+z=27.$$

12.
$$2xy-4x+y=17,$$
$$3yz+y-6z=52,$$
$$6xz+3z+2x=29.$$

13. $xz+y=7z,\ yz+x=8z,\ x+y+z=12.$

14. $x^3+y^3+z^3=a^3,\ x^2+y^2+z^2=a^2,\ x+y+z=a.$

15. $x^2+y^2+z^2=yz+zx+xy=a^2,\ 3x-y+z=a\sqrt{3}.$

16. $x^2+y^2+z^2=21a^2,\ yz+zx-xy=6a^2,\ 3x+y-2z=3a.$

Indeterminate Equations.

138. Suppose the following problem were proposed for solution:

A person spends £461 in buying horses and cows; if each horse costs £23 and each cow £16, how many of each does he buy?

Let x, y be the number of horses and cows respectively; then

$$23x+16y=461.$$

Here we have *one* equation involving *two* unknown quantities, and it is clear that by ascribing any value we please to x, we can obtain a corresponding value for y; thus it would appear at first sight that the problem admits of an infinite number of solutions. But it is clear from the nature of the question that x and y must be positive integers; and with this restriction, as we shall see later, the number of solutions is limited.

If the number of unknown quantities is greater than the number of independent equations, there will be an unlimited number of solutions, and the equations are said to be **indeterminate.** In the present section we shall only discuss the simplest kinds of indeterminate equations, confining our attention to *positive integral values* of the unknown quantities; it will be seen that this restriction enables us to express the solutions in a very simple form.

The general theory of indeterminate equations will be found in Chap. XXVI.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

hence $$\frac{12x-28}{11}=\text{integer};$$

that is, $$x-2+\frac{x-6}{11}=\text{integer};$$

$$\therefore\ \frac{x-6}{11}=\text{integer}=p \text{ suppose};$$

and, from (1), $$\left.\begin{aligned} x&=11p+6\\ y&=14p+5 \end{aligned}\right\}.$$

This is called the *general solution* of the equation, and by giving to p any positive integral value or zero, we obtain positive integral values of x and y; thus we have

$$\left.\begin{aligned} p&=0,\quad 1,\quad 2,\quad 3,\ldots\ldots\\ x&=6,\ 17,\ 28,\ 39,\ldots\ldots\\ y&=5,\ 19,\ 33,\ 47,\ldots\ldots \end{aligned}\right\},$$

the number of solutions being infinite.

Example 3. In how many ways can £5 be paid in half-crowns and florins?

Let x be the number of half-crowns, y the number of florins; then

$$5x+4y=200;$$

$$\therefore\ x+y+\frac{x}{4}=50;$$

$$\cdot\ \frac{x}{4}=\text{integer}=p \text{ suppose};$$

$$\cdot\ x=4p,$$

and $$y=50-5p.$$

Solutions are obtained by ascribing to p the values 1, 2, 3, ...9; and therefore the number of ways is 9. If, however, the sum may be paid *either* in half-crowns *or* florins, p may also have the values 0 and 10. If $p=0$, then $x=0$, and the sum is paid entirely in florins; if $p=10$, then $y=0$, and the sum is paid entirely in half-crowns. Thus if zero values of x and y are admissible the number of ways is 11.

Example 4. The expenses of a party numbering 43 were £5. 14*s*. 6*d*.; if each man paid 5*s*., each woman 2*s*. 6*d*., and each child 1*s*., how many were there of each?

Let x, y, z denote the number of men, women, and children, respectively; then we have

$$x+y+z=43 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1),$$

$$10x+5y+2z=229.$$

Eliminating z, we obtain $$8x+3y=143.$$

The general solution of this equation is

$$x=3p+1,$$

$$y=45-8p;$$

Hence by substituting in (1), we obtain

$$z = 5p - 3.$$

Here p cannot be negative or zero, but may have positive integral values from 1 to 5. Thus

$$\begin{aligned} p &= 1, \quad 2, \quad 3, \quad 4, \quad 5; \\ x &= 4, \quad 7, 10, 13, 16; \\ y &= 37, 29, 21, 13, \quad 5; \\ z &= 2, \quad 7, 12, 17, 22. \end{aligned}$$

EXAMPLES. X. d.

Solve in positive integers:

1. $3x + 8y = 103$. **2.** $5x + 2y = 53$. **3.** $7x + 12y = 152$.

4. $13x + 11y = 414$. **5.** $23x + 25y = 915$. **6.** $41x + 47y = 2191$.

Find the general solution in positive integers, and the least values of x and y which satisfy the equations:

7. $5x - 7y = 3$. **8.** $6x - 13y = 1$. **9.** $8x - 21y = 33$.

10. $17y - 13x = 0$. **11.** $19y - 23x = 7$. **12.** $77y - 30x = 295$.

13. A farmer spends £752 in buying horses and cows; if each horse costs £37 and each cow £23, how many of each does he buy?

14. In how many ways can £5 be paid in shillings and sixpences, including zero solutions?

15. Divide 81 into two parts so that one may be a multiple of 8 and the other of 5.

16. What is the simplest way for a person who has only guineas to pay 10*s.* 6*d.* to another who has only half-crowns?

17. Find a number which being divided by 39 gives a remainder 16, and by 56 a remainder 27. How many such numbers are there?

18. What is the smallest number of florins that must be given to discharge a debt of £1. 6*s.* 6*d.*, if the change is to be paid in half-crowns only?

19. Divide 136 into two parts one of which when divided by 5 leaves remainder 2, and the other divided by 8 leaves remainder 3.

20. I buy 40 animals consisting of rams at £4, pigs at £2, and oxen at £17: if I spend £301, how many of each do I buy?

21. In my pocket I have 27 coins, which are sovereigns, half-crowns or shillings, and the amount I have is £5. 0*s.* 6*d.*; how many coins of each sort have I?

CHAPTER XI.

Permutations and Combinations.

139. Each of the *arrangements* which can be made by taking some or all of a number of things is called a **permutation.**

Each of the *groups* or *selections* which can be made by taking some or all of a number of things is called a **combination.**

Thus the *permutations* which can be made by taking the letters *a*, *b*, *c*, *d* two at a time are twelve in number, namely,

$$ab, \quad ac, \quad ad, \quad bc, \quad bd, \quad cd,$$
$$ba, \quad ca, \quad da, \quad cb, \quad db, \quad dc;$$

each of these presenting a different *arrangement* of two letters.

The *combinations* which can be made by taking the letters *a*, *b*, *c*, *d* two at a time are six in number: namely,

$$ab, \quad ac, \quad ad, \quad bc, \quad bd, \quad cd;$$

each of these presenting a different *selection* of two letters.

From this it appears that in forming *combinations* we are only concerned with the number of things each selection contains; whereas in forming *permutations* we have also to consider the order of the things which make up each arrangement; for instance, if from four letters *a*, *b*, *c*, *d* we make a selection of three, such as *abc*, this single combination admits of being arranged in the following ways:

$$abc, \quad acb, \quad bca, \quad bac, \quad cab, \quad cba,$$

and so gives rise to six different permutations.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

these ways, the second place can then be filled up in $n-1$ ways; and since each way of filling up the first place can be associated with each way of filling up the second, the number of ways in which the first two places can be filled up is given by the product $n(n-1)$. And when the first two places have been filled up in any way, the third place can be filled up in $n-2$ ways. And reasoning as before, the number of ways in which three places can be filled up is $n(n-1)(n-2)$.

Proceeding thus, and noticing that a new factor is introduced with each new place filled up, and that at any stage the number of factors is the same as the number of places filled up, we shall have the number of ways in which r places can be filled up equal to

$$n(n-1)(n-2).....\text{to } r \text{ factors};$$

and the r^{th} factor is

$$n-(r-1), \quad \text{or} \quad n-r+1.$$

Therefore the number of permutations of n things taken r at a time is

$$n(n-1)(n-2).....(n-r+1).$$

Cor. The number of permutations of n things taken all at a time is

$$n(n-1)(n-2).....\text{to } n \text{ factors},$$

or

$$n(n-1)(n-2).....3\,.\,2\,.\,1.$$

It is usual to denote this product by the symbol $\lfloor n$, which is read "factorial n." Also $n!$ is sometimes used for $\lfloor n$.

142. We shall in future denote the number of permutations of n things taken r at a time by the symbol ${}^nP_r$, so that

$${}^nP_r = n(n-1)(n-2).....(n-r+1);$$

also

$${}^nP_n = \lfloor n.$$

In working numerical examples it is useful to notice that the suffix in the symbol ${}^nP_r$ always denotes the number of factors in the formula we are using.

143. The number of permutations of n things taken r at a time may also be found in the following manner.

Let ${}^nP_r$ represent the number of permutations of n things taken r at a time.

Suppose we form all the permutations of n things taken $r-1$ at a time; the number of these will be ${}^{n}P_{r-1}$.

With *each of these* put one of the remaining $n-r+1$ things. Each time we do this we shall get one permutation of n things r at a time; and therefore the whole number of the permutations of n things r at a time is ${}^{n}P_{r-1} \times (n-r+1)$; that is,

$$ {}^{n}P_{r} = {}^{n}P_{r-1} \times (n - \mathrm{r} + 1). $$

By writing $r-1$ for r in this formula, we obtain

$$ {}^{n}P_{r-1} - {}^{n}P_{r-2} \times (n-r+2), $$

similarly,

$$ {}^{n}P_{r-2} = {}^{n}P_{r-3} \times (n-r+3), $$

$$ \ldots\ldots\ldots\ldots\ldots\ldots $$

$$ {}^{n}P_{3} = {}^{n}P_{2} \times (n-2), $$

$$ {}^{n}P_{2} = {}^{n}P_{1} \times (n-1), $$

$$ {}^{n}P_{1} = n. $$

Multiply together the vertical columns and cancel like factors from each side, and we obtain

$$ {}^{n}P_{r} = n(n-1)(n-2) \ldots\ldots (n-r+1). $$

Example 1. Four persons enter a railway carriage in which there are six seats; in how many ways can they take their places?

The first person may seat himself in 6 ways; and then the second person in 5; the third in 4; and the fourth in 3; and since each of these ways may be associated with each of the others, the required answer is $6 \times 5 \times 4 \times 3$, or 360.

Example 2. How many different numbers can be formed by using six out of the nine digits 1, 2, 3,...9?

Here we have 9 different things and we have to find the number of permutations of them taken 6 at a time;

$$ \text{the required result} = {}^{9}P_{6} $$
$$ = 9 \times 8 \times 7 \times 6 \times 5 \times 4 $$
$$ = 60480. $$

144. *To find the number of combinations of* n *dissimilar things taken* r *at a time.*

Let ${}^{n}C_{r}$ denote the required number of combinations.

Then each of these combinations consists of a group of r dissimilar things which can be arranged among themselves in $\lfloor r$ ways. [Art. 142.]

Hence ${}^nC_r \times \lfloor r$ is equal to the number of *arrangements* of n things taken r at a time; that is

$$
\begin{aligned}
{}^nC_r \times \lfloor \underline{r} &= {}^nP_r \\
&= n(n-1)(n-2)\ldots(n-r+1); \\
\therefore\ {}^nC_r &= \frac{n(n-1)(n-2)\ldots(n-r+1)}{\lfloor \underline{r}} \quad \ldots\ldots\ldots (1).
\end{aligned}
$$

Cor. This formula for ${}^nC_r$ may also be written in a different form; for if we multiply the numerator and the denominator by $\lfloor \underline{n-r}$ we obtain

$$\frac{n(n-1)(n-2)\ldots(n-r+1) \times \lfloor \underline{n-r}}{\lfloor \underline{r} \ \lfloor \underline{n-r}}.$$

The numerator now consists of the product of all the natural numbers from n to 1;

$${}^nC_r = \frac{\lfloor \underline{n}}{\lfloor \underline{r} \ \lfloor \underline{n-r}} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

It will be convenient to remember both these expressions for ${}^nC_r$, using (1) in all cases where a numerical result is required, and (2) when it is sufficient to leave it in an algebraical shape.

Note. If in formula (2) we put $r=n$, we have

$${}^nC_n = \frac{\lfloor \underline{n}}{\lfloor \underline{n} \ \lfloor \underline{0}} = \frac{1}{\lfloor \underline{0}};$$

but ${}^nC_n = 1$, so that if the formula is to be true for $r=n$, the symbol $\lfloor \underline{0}$ must be considered as equivalent to 1.

Example. From 12 books in how many ways can a selection of 5 be made, (1) when one specified book is always included, (2) when one specified book is always excluded?

(1) Since the specified book is to be included in every selection, we have only to choose 4 out of the remaining 11.

$$
\begin{aligned}
\text{Hence the number of ways} &= {}^{11}C_4 \\
&= \frac{11 \times 10 \times 9 \times 8}{1 \times 2 \times 3 \times 4} \\
&= 330.
\end{aligned}
$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

146. *To find the number of ways in which* m + n *things can be divided into two groups containing* m *and* n *things respectively.*

This is clearly equivalent to finding the number of combinations of $m+n$ things m at a time, for every time we select one group of m things we leave a group of n things behind.

Thus the required number $= \dfrac{\lfloor m+n}{\lfloor m \ \lfloor n}$.

NOTE. If $n=m$, the groups are equal, and in this case the number of *different* ways of subdivision is $\dfrac{\lfloor 2m}{\lfloor m \ \lfloor m \ \lfloor 2}$; for in any one way it is possible to interchange the two groups without obtaining a new distribution.

147. *To find the number of ways in which* m + n + p *things can be divided into three groups containing* m, n, p *things severally.*

First divide $m+n+p$ things into two groups containing m and $n+p$ things respectively: the number of ways in which this can be done is $\dfrac{\lfloor m+n+p}{\lfloor m \ \lfloor n+p}$.

Then the number of ways in which the group of $n+p$ things can be divided into two groups containing n and p things respectively is $\dfrac{\lfloor n+p}{\lfloor n \ \lfloor p}$.

Hence the number of ways in which the subdivision into three groups containing m, n, p things can be made is

$$\frac{\lfloor m+n+p}{\lfloor m \ \lfloor n+p} \times \frac{\lfloor n+p}{\lfloor n \ \lfloor p}, \text{ or } \frac{\lfloor m+n+p}{\lfloor m \ \lfloor n \ \lfloor p}.$$

NOTE. If we put $n=p=m$, we obtain $\dfrac{\lfloor 3m}{\lfloor m \ \lfloor m \ \lfloor m}$; but this formula regards as different all the possible orders in which the three groups can occur in any one mode of subdivision. And since there are $\lfloor 3$ such orders corresponding to each mode of subdivision, the number of *different* ways in which subdivision into three *equal* groups can be made is $\dfrac{\lfloor 3m}{\lfloor m \ \lfloor m \ \lfloor m \ \lfloor 3}$.

Example. The number of ways in which 15 recruits can be divided into three equal groups is $\dfrac{\lfloor 15}{\lfloor 5 \ \lfloor 5 \ \lfloor 5 \ \lfloor 3}$; and the number of ways in which they can be drafted into three different regiments, five into each, is $\dfrac{\lfloor 15}{\lfloor 5 \ \lfloor 5 \ \lfloor 5}$.

148. In the examples which follow it is important to notice that the formula for *permutations* should not be used until the suitable *selections* required by the question have been made.

Example 1. From 7 Englishmen and 4 Americans a committee of 6 is to be formed; in how many ways can this be done, (1) when the committee contains exactly 2 Americans, (2) at least 2 Americans?

(1) We have to choose 2 Americans and 4 Englishmen.

The number of ways in which the Americans can be chosen is ${}^4C_2$; and the number of ways in which the Englishmen can be chosen is ${}^7C_4$. Each of the first groups can be associated with each of the second; hence

$$\text{the required number of ways} = {}^4C_2 \times {}^7C_4$$
$$= \frac{\lfloor 4}{\lfloor 2 \lfloor 2} \times \frac{\lfloor 7}{\lfloor 4 \lfloor 3}$$
$$= \frac{\lfloor 7}{\lfloor 2 \lfloor 2 \lfloor 3} = 210.$$

(2) The committee may contain 2, 3, or 4 Americans.

We shall exhaust all the suitable combinations by forming all the groups containing 2 Americans and 4 Englishmen; then 3 Americans and 3 Englishmen; and lastly 4 Americans and 2 Englishmen.

The *sum* of the three results will give the answer. Hence the required

$$\text{number of ways} = {}^4C_2 \times {}^7C_4 + {}^4C_3 \times {}^7C_3 + {}^4C_4 \times {}^7C_2$$
$$= \frac{\lfloor 4}{\lfloor 2 \lfloor 2} \times \frac{\lfloor 7}{\lfloor 4 \lfloor 3} + \frac{\lfloor 4}{\lfloor 3} \times \frac{\lfloor 7}{\lfloor 3 \lfloor 4} + 1 \times \frac{\lfloor 7}{\lfloor 2 \lfloor 5}$$
$$= 210 + 140 + 21 = 371.$$

In this Example we have only to make use of the suitable formulæ for *combinations*, for we are not concerned with the possible arrangements of the members of the committee among themselves.

Example 2. Out of 7 consonants and 4 vowels, how many words can be made each containing 3 consonants and 2 vowels?

The number of ways of choosing the three consonants is ${}^7C_3$, and the number of ways of choosing the 2 vowels is ${}^4C_2$; and since each of the first groups can be associated with each of the second, the number of combined groups, each containing 3 consonants and 2 vowels, is ${}^7C_3 \times {}^4C_2$.

Further, each of these groups contains 5 letters, which may be arranged among themselves in $\lfloor 5$ ways. Hence

$$\text{the required number of words} = {}^7C_3 \times {}^4C_2 \times \lfloor 5$$
$$= \frac{\lfloor 7}{\lfloor 3 \lfloor 4} \times \frac{\lfloor 4}{\lfloor 2 \lfloor 2} \times \lfloor 5$$
$$= 5 \times \lfloor 7$$
$$= 25200.$$

Example 3. How many words can be formed out of the letters *article*, so that the vowels occupy the even places?

Here we have to put the 3 vowels in 3 specified places, and the 4 consonants in the 4 remaining places; the first operation can be done in $\lfloor\underline{3}$ ways, and the second in $\lfloor\underline{4}$. Hence

the required number of words $= \lfloor\underline{3} \times \lfloor\underline{4}$

$= 144.$

In this Example the formula for permutations is immediately applicable, because by the statement of the question there is but one way of choosing the vowels, and one way of choosing the consonants.

EXAMPLES XI. a.

1. In how many ways can a consonant and a vowel be chosen out of the letters of the word *courage?*

2. There are 8 candidates for a Classical, 7 for a Mathematical, and 4 for a Natural Science Scholarship. In how many ways can the Scholarships be awarded?

3. Find the value of ${}^{8}P_{7}$, ${}^{25}P_{5}$, ${}^{24}C_{4}$, ${}^{19}C_{14}$.

4. How many different arrangements can be made by taking 5 of the letters of the word *equation?*

5. If four times the number of permutations of n things 3 together is equal to five times the number of permutations of $n-1$ things 3 together, find n.

6. How many permutations can be made out of the letters of the word *triangle?* How many of these will begin with *t* and end with *e?*

7. How many different selections can be made by taking four of the digits 3, 4, 7, 5, 8, 1? How many different numbers can be formed with four of these digits?

8. If ${}^{2n}C_{3} : {}^{n}C_{2} = 44 : 3$, find n.

9. How many changes can be rung with a peal of 5 bells?

10. How many changes can be rung with a peal of 7 bells, the tenor always being last?

11. On how many nights may a watch of 4 men be drafted from a crew of 24, so that no two watches are identical? On how many of these would any one man be taken?

12. How many arrangements can be made out of the letters of the word *draught*, the vowels never being separated?

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

30. An eight-oared boat is to be manned by a crew chosen from 11 men, of whom 3 can steer but cannot row, and the rest can row but cannot steer. In how many ways can the crew be arranged, if two of the men can only row on bow side?

31. Prove that the number of ways in which p positive and n negative signs may be placed in a row so that no two negative signs shall be together is ${}^{p+1}C_n$.

32. If ${}^{56}P_{r+6} : {}^{54}P_{r+3} = 30800 : 1$, find r.

33. How many different signals can be made by hoisting 6 differently coloured flags one above the other, when any number of them may be hoisted at once?

34. If ${}^{28}C_{2r} : {}^{24}C_{2r-4} = 225 : 11$, find r.

149. Hitherto, in the formulæ we have proved, the things have been regarded as *unlike*. Before considering cases in which some one or more sets of things may be *like*, it is necessary to point out exactly in what sense the words *like* and *unlike* are used. When we speak of things being *dissimilar*, *different*, *unlike*, we imply that the things are *visibly unlike*, so as to be easily distinguishable from each other. On the other hand we shall always use the term *like* things to denote such as are alike to the eye and cannot be distinguished from each other. For instance, in Ex. 2, Art. 148, the consonants and the vowels may be said each to consist of a group of things united by a common characteristic, and thus in a certain sense to be of the same kind; but they cannot be regarded as like things, because there is an individuality existing among the things of each group which makes them easily distinguishable from each other. Hence, in the final stage of the example we considered each group to consist of five *dissimilar* things and therefore capable of $\lfloor 5$ arrangements among themselves. [Art. 141 Cor.]

150. Suppose we have to find all the possible ways of arranging 12 books on a shelf, 5 of them being Latin, 4 English, and the remainder in different languages.

The books in each language may be regarded as belonging to one class, united by a common characteristic; but if they were distinguishable from each other, the number of permutations would be $\underline{\lfloor 12}$, since for the purpose of arrangement among themselves they are essentially different.

If, however, the books in the same language are not distinguishable from each other, we should have to find the number of ways in which 12 things can be arranged among themselves, when 5 of them are exactly alike of one kind, and 4 exactly alike of a second kind: a problem which is not directly included in any of the cases we have previously considered.

151. *To find the number of ways in which* n *things may be arranged among themselves, taking them all at a time, when* p *of the things are exactly alike of one kind,* q *of them exactly alike of another kind,* r *of them exactly alike of a third kind, and the* rest *all different.*

Let there be n letters; suppose p of them to be a, q of them to be b, r of them to be c, and the rest to be unlike.

Let x be the required number of permutations; then if in *any one* of these permutations the p letters a were replaced by p unlike letters different from any of the rest, from this single permutation, without altering the position of any of the remaining letters, we could form $\lfloor\underline{p}$ new permutations. Hence if this change were made in each of the x permutations we should obtain $x \times \lfloor\underline{p}$ permutations.

Similarly, if the q letters b were replaced by q unlike letters, the number of permutations would be

$$x \times \lfloor\underline{p} \times \lfloor\underline{q}.$$

In like manner, by replacing the r letters c by r unlike letters, we should finally obtain $x \times \lfloor\underline{p} \times \lfloor\underline{q} \times \lfloor r$ permutations.

But the things are now all different, and therefore admit of $\lfloor n$ permutations among themselves. Hence

$$x \times \lfloor\underline{p} \times \lfloor\underline{q} \times \lfloor\underline{r} = \lfloor n\,;$$

that is,

$$x = \frac{\lfloor\underline{n}}{\lfloor\underline{p}\ \lfloor\underline{q}\ \lfloor\underline{r}}\,;$$

which is the required number of permutations.

Any case in which the things are not all different may be treated similarly.

Example 1. How many different permutations can be made out of the letters of the word *assassination* taken all together?

We have here 13 letters of which 4 are s, 3 are a, 2 are i, and 2 are n. Hence the number of permutations

$$= \frac{\lfloor 13}{\lfloor 4 \lfloor 3 \lfloor 2 \lfloor 2}$$

$$= 13 . 11 . 10 . 9 . 8 . 7 . 3 . 5$$

$$= 1001 \times 10800 = 10810800.$$

Example 2. How many numbers can be formed with the digits 1, 2, 3, 4, 3, 2, 1, so that the odd digits always occupy the odd places?

The odd digits 1, 3, 3, 1 can be arranged in their four places in

$$\frac{\lfloor 4}{\lfloor 2 \lfloor 2} \text{ ways} \ldots\ldots\ldots\

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

the values 1, 2, 3 in succession, ${}^nC_r$ is continually increased until $\frac{n+1}{r} - 1$ becomes equal to 1 or less than 1.

Now $$\frac{n+1}{r} - 1 > 1,$$

so long as $$\frac{n+1}{r} > 2;$$

that is, $$\frac{n+1}{2} > r.$$

We have to choose the greatest value of r consistent with this inequality.

(1) Let n be even, and equal to $2m$; then

$$\frac{n+1}{2} = \frac{2m+1}{2} = m + \frac{1}{2};$$

and for all values of r up to m inclusive this is greater than r. Hence by putting $r = m = \frac{n}{2}$, we find that the greatest number of combinations is ${}^nC_{\frac{n}{2}}$.

(2) Let n be odd, and equal to $2m+1$; then

$$\frac{n+1}{2} = \frac{2m+2}{2} = m + 1;$$

and for all values of r up to m inclusive this is greater than r; but when $r = m+1$ the multiplying factor becomes equal to 1, and

$${}^nC_{m+1} = {}^nC_m; \text{ that is, } {}^nC_{\frac{n+1}{2}} = {}^nC_{\frac{n-1}{2}};$$

and therefore the number of combinations is greatest when the things are taken $\frac{n+1}{2}$, or $\frac{n-1}{2}$ at a time; the result being the same in the two cases.

155. The formula for the number of combinations of n things r at a time may be found without assuming the formula for the number of permutations.

Let ${}^nC_r$ denote the number of combinations of n things taken r at a time; and let the n things be denoted by the letters $a, b, c, d, \ldots\ldots$.

Take away a; then with the remaining letters we can form ${}^{n-1}C_{r-1}$ combinations of $n-1$ letters taken r $-$ 1 at a time. With each of these write a; thus we see that of the combinations of n things r at a time, the number of those which contain a is ${}^{n-1}C_{r-1}$; similarly the number of those which contain b is ${}^{n-1}C_{r-1}$; and so for each of the n letters.

Therefore $n \times {}^{n-1}C_{r-1}$ is equal to the number of combinations r at a time which contain a, together with those that contain b, those that contain c, and so on.

But by forming the combinations in this manner, each particular one will be repeated r times. For instance, if $r=3$, the combination abc will be found among those containing a, among those containing b, and among those containing c. Hence

$$ {}^{n}C_{r} = {}^{n-1}C_{r-1} \times \frac{n}{r} .$$

By writing $n-1$ and $r-1$ instead of n and r respectively,

$$ {}^{n-1}C_{r-1} = {}^{n-2}C_{r-2} \times \frac{n-1}{r-1} .$$

Similarly,
$$ {}^{n-2}C_{r-2} = {}^{n-3}C_{r-3} \times \frac{n-2}{r-2} ,$$

.....

$$ {}^{n-r+2}C_{2} = {}^{n-r+1}C_{1} \times \frac{n-r+2}{2} ;$$

and finally,
$$ {}^{n-r+1}C_{1} = n-r+1.$$

Multiply together the vertical columns and cancel like factors from each side; thus

$$ {}^{n}C_{r} = \frac{n\,(n-1)\,(n-2)\,\ldots\ldots\,(n-r+1)}{r\,(r-1)\,(r-2)\,\ldots\ldots\,1} .$$

156. *To find the total number of ways in which it is possible to make a selection by taking some or all out of* p + q + r + ... *things, whereof* p *are alike of one kind,* q *alike of a second kind,* r *alike of a third kind; and so on.*

The p things may be disposed of in $p+1$ ways; for we may take 0, 1, 2, 3, ... p of them. Similarly the q things may be disposed of in $q+1$ ways; the r things in $r+1$ ways; and so on.

Hence the number of ways in which all the things may be disposed of is $(p+1)(q+1)(r+1)\ldots\ldots$

But this includes the case in which none of the things are taken; therefore, rejecting this case, the total number of ways is

$$(p+1)(q+1)(r+1)\ldots\ldots \quad 1.$$

157. A general formula expressing the number of permutations, or combinations, of n things taken r at a time, when the things are not all different, may be somewhat complicated; but a particular case may be solved in the following manner.

Example. Find the number of ways in which (1) a selection, (2) an arrangement, of four letters can be made from the letters of the word *proportion*.

There are 10 letters of six different sorts, namely $o, o, o; p, p; r$, r; $t; i; n$.

In finding groups of four these may be classified as follows:

(1) Three alike, one different.
(2) Two alike, two others alike.
(3) Two alike, the other two different.
(4) All four different.

(1) The selection can be made in 5 ways; for each of the five letters, p, r, t, i, n, can be taken with the single group of the three like letters o.

(2) The selection can be made in ${}^3C_2$ ways; for we have to choose two out of the three pairs $o, o; p, p; r$, r. This gives 3 selections.

(3) This selection can be made in 3×10 ways; for we select one of the 3 pairs, and then two from the remaining 5 letters. This gives 30 selections.

(4) This selection can be made in ${}^6C_4$ ways, as we have to take 4 different letters to choose from the six $o, p,$ r, t, i, n. This gives 15 selections.

Thus the total number of selections is $5+3+30+15$; that is, 53.

In finding the different arrangements of 4 letters we have to permute in all possible ways each of the foregoing groups.

(1) gives rise to $5 \times \frac{\lfloor 4}{\lfloor 3}$, or 20 arrangements.

(2) gives rise to $3 \times \frac{\lfloor 4}{\lfloor 2 \lfloor 2}$, or 18 arrangements.

(3) gives rise to $30 \times \frac{\lfloor 4}{\lfloor 2}$, or 360 arrangements.

(4) gives rise to $15 \times \lfloor 4$, or 360 arrangements.

Thus the total number of arrangements is $20+18+360+360$; that is, 758.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

17. A telegraph has 5 arms and each arm is capable of 4 distinct positions, including the position of rest; what is the total number of signals that can be made?

18. In how many ways can 7 persons form a ring? In how many ways can 7 Englishmen and 7 Americans sit down at a round table, no two Americans being together?

19. In how many ways is it possible to draw a sum of money from a bag containing a sovereign, a half-sovereign, a crown, a florin, a shilling, a penny, and a farthing?

20. From 3 cocoa nuts, 4 apples, and 2 oranges, how many selections of fruit can be made, taking at least one of each kind?

21. Find the numbér of different ways of dividing mn things into n equal groups.

22. How many signals can be made by hoisting 4 flags of different colours one above the other, when any number of them may be hoisted at once? How many with 5 flags?

23. Find the number of permutations which can be formed out of the letters of the word *series* taken three together?

24. There are p points in a plane, no three of which are in the same straight line with the exception of q, which are all in the same straight line; find the number (1) of straight lines, (2) of triangles which result from joining them.

25. There are p points in space, no four of which are in the same plane with the exception of q, which are all in the same plane; find how many planes there are each containing three of the points.

26. There are n different books, and p copies of each; find the number of ways in which a selection can be made from them.

27. Find the number of selections and of arrangements that can be made by taking 4 letters from the word *expression*.

28. How many permutations of 4 letters can be made out of the letters of the word *examination*?

29. Find the sum of all numbers greater than 10000 formed by using the digits 1, 3, 5, 7, 9, no digit being repeated in any number.

30. Find the sum of all numbers greater than 10000 formed by using the digits 0, 2, 4, 6, 8, no digit being repeated in any number.

31. If of $p+q+r$ things p be alike, and q be alike, and the rest different, shew that the total number of combinations is

$$(p+1)(q+1)2^r-1.$$

32. Shew that the number of permutations which can be formed from $2n$ letters which are either a's or b's is greatest when the number of a's is equal to the number of b's.

33. If the $n+1$ numbers $a, b, c, d, \ldots$ be all different, and each of them a prime number, prove that the number of different factors of the expression $a^m bcd\ldots\ldots$ is $(m+1)2^n-1$.

CHAPTER XII.

Mathematical Induction.

158. Many important mathematical formulæ are not easily demonstrated by a direct mode of proof; in such cases we frequently find it convenient to employ a method of proof known as **mathematical induction**, which we shall now illustrate.

Example **1.** Suppose it is required to prove that the sum of the cubes of the first n natural numbers is equal to $\left\{\frac{n(n+1)}{2}\right\}^2$.

We can easily see by trial that the statement is true in simple cases, such as when $n=1$, or 2, or 3; and from this we might be led to *conjecture* that the formula was true in all cases. Assume that it is true when n terms are taken; that is, suppose

$$1^3+2^3+3^3+\ldots\ldots \text{ to } n \text{ terms} = \left\{\frac{n(n+1)}{2}\right\}^2.$$

Add the $(n+1)^{\text{th}}$ term, that is, $(n+1)^3$ to each side; then

$$1^3+2^3+3^3+\ldots\ldots \text{ to } n+1 \text{ terms} = \left\{\frac{n(n+1)}{2}\right\}^2+(n+1)^3$$

$$=(n+1)^2\left(\frac{n^2}{4}+n+1\right)$$

$$=\frac{(n+1)^2(n^2+4n+4)}{4}$$

$$=\left\{\frac{(n+1)(n+2)}{2}\right\}^2;$$

which is *of the same form* as the result we assumed to be true for n terms, $n+1$ taking the place of n; in other words, if the result is true when we take a certain number of terms, whatever that number may be, it is true when we increase that number by one; but we see that it is true when 3 terms are taken; therefore it is true when 4 terms are taken; it is therefore true when 5 terms are taken; and so on. Thus the result is true universally.

Example 2. To determine the product of n binomial factors of the form $x+a$.

By actual multiplication we have

$$(x+a)(x+b)(x+c)=x^3+(a+b+c)x^2+(ab+bc+ca)x+abc;$$

$$\begin{aligned}(x+a)(x+b)(x+c)(x+d)=x^4&+(a+b+c+d)x^3\\&+(ab+ac+ad+bc+bd+cd)x^2\\&+(abc+abd+acd+bcd)x+abcd.\end{aligned}$$

In these results we observe that the following laws hold:

1. The number of terms on the right is one more than the number of binomial factors on the left.

2. The index of x in the first term is the same as the number of binomial factors; and in each of the other terms the index is one less than that of the preceding term.

3. The coefficient of the first term is unity; the coefficient of the second term is the sum of the letters a, b, c, ...; the coefficient of the third term is the sum of the products of these letters taken two at a time; the coefficient of the fourth term is the sum of their products taken three at a time; and so on; the last term is the product of all the letters.

Assume that these laws hold in the case of $n-1$ factors; that is, suppose

$$(x+a)(x+b)\ldots(x+h)=x^{n-1}+p_1x^{n-2}+p_2x^{n-3}+p_3x^{n-4}+\ldots+p_{n-1},$$

where

$$\begin{aligned}p_1&=a+b+c+\ldots h;\\p_2&=ab+ac+\ldots+ah+bc+bd+\ldots\ldots;\\p_3&=abc+abd+\ldots\ldots;\\&\ldots\ldots\ldots\ldots\ldots\ldots\\p_{n-1}&=abc\ldots h.\end{aligned}$$

Multiply both sides by another factor $x+k$; thus

$$\begin{aligned}&(x+a)(x+b)\ldots(x+h)(x+k)\\&-x^n+(p_1+k)x^{n-1}+(p_2+p_1k)x^{n-2}+(p_3+p_2k)x^{n-3}+\ldots+p_{n-1}k.\end{aligned}$$

Now

$$\begin{aligned}p_1+k&=(a+b+c+\ldots+h)+k\\&=\text{sum of all the } n \text{ letters } a,\ b,\ c,\ldots k;\end{aligned}$$

$$\begin{aligned}p_2+p_1k&=p_2+k(a+b+\ldots+h)\\&=-\text{sum of the products taken two at a time of all the } n \text{ letters } a,\ b,\ c,\ldots k;\end{aligned}$$

$$\begin{aligned}p_3+p_2k&=p_3+k(ab+ac+\ldots+ah+bc+\ldots)\\&=\text{sum of the products taken three at a time of all the } n \text{ letters } a,\ b,\ c,\ldots k;\end{aligned}$$

$$p_{n-1}k=\text{product of all the } n \text{ letters } a,\ b,\ c,\ldots k.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

CHAPTER XIII.

BINOMIAL THEOREM. POSITIVE INTEGRAL INDEX.

161. IT may be shewn by actual multiplication that

$$(x+a)(x+b)(x+c)(x+d)$$
$$=x^4+(a+b+c+d)x^3+(ab+ac+ad+bc+bd+cd)x^2$$
$$+(abc+abd+acd+bcd)x+abcd \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

We may, however, write down this result by inspection; for the complete product consists of the sum of a number of partial products each of which is formed by multiplying together four letters, *one* being taken from *each* of the four factors. If we examine the way in which the various partial products are formed, we see that

(1) the term x^4 is formed by taking the letter x out of *each* of the factors.

(2) the terms involving x^3 are formed by taking the letter x out of *any three* factors, in every way possible, and *one* of the letters a, b, c, d out of the remaining factor.

(3) the terms involving x^2 are formed by taking the letter x out of *any two* factors, in every way possible, and *two* of the letters a, b, c, d out of the remaining factors.

(4) the terms involving x are formed by taking the letter x out of *any one* factor, and *three* of the letters a, b, c, d out of the remaining factors.

(5) the term independent of x is the product of all the letters a, b, c, d.

Example 1. $(x-2)(x+3)(x-5)(x+9)$

$$=x^4+(-2+3-5+9)x^3+(-6+10-18-15+27-45)x^2$$
$$+(30-54+90-135)x+270$$
$$=x^4+5x^3-47x^2-69x+270.$$

Example 2. Find the coefficient of x^3 in the product

$$(x-3)(x+5)(x-1)(x+2)(x-8).$$

The terms involving x^3 are formed by multiplying together the x in *any three* of the factors, and *two* of the numerical quantities out of the two remaining factors; hence the coefficient is equal to the sum of the products of the quantities $-3, 5, -1, 2, -8$ taken two at a time.

Thus the required coefficient

$$= -15+3-6+24-5+10-40-2+8-16$$
$$= -39.$$

162. If in equation (1) of the preceding article we suppose $b=c=d=a$, we obtain

$$(x+a)^4 = x^4 + 4ax^3 + 6a^2x^2 + 4a^3x + a^4.$$

The method here exemplified of deducing a particular case from a more general result is one of frequent occurrence in Mathematics; for it often happens that it is more easy to prove a general proposition than it is to prove a particular case of it.

We shall in the next article employ the same method to prove a formula known as the **Binomial Theorem**, by which any binomial of the form $x+a$ can be raised to any assigned positive integral power.

163. *To find the expansion of* $(x+a)^n$ *when* n *is a positive integer.*

Consider the expression

$$(x+a)(x+b)(x+c) \qquad (x+k),$$

the number of factors being n.

The expansion of this expression is the continued product of the n factors, $x+a$, $x+b$, $x+c$, ... $x+k$, and every term in the expansion is of n dimensions, being a product formed by multiplying together n letters, *one* taken from each of these n factors.

The highest power of x is x^n, and is formed by taking the letter x from *each* of the n factors.

The terms involving x^{n-1} are formed by taking the letter x from *any* $n-1$ of the factors, and *one* of the letters $a, b, c, \ldots k$ from the remaining factor; thus the coefficient of x^{n-1} in the final product is the sum of the letters $a, b, c, \ldots\ldots k$; denote it by S_1.

The terms involving x^{n-2} are formed by taking the letter x from *any* $n-2$ of the factors, and *two* of the letters $a, b, c, \ldots k$ from the two remaining factors; thus the coefficient of x^{n-2} in the final product is the sum of the products of the letters $a, b, c, \ldots k$ taken two at a time; denote it by S_2.

And, generally, the terms involving x^{n-r} are formed by taking the letter x from *any* $n-r$ of the factors, and r of the letters $a, b, c, \ldots k$ from the r remaining factors; thus the coefficient of x^{n-r} in the final product is the sum of the products of the letters $a, b, c, \ldots k$ taken r at a time; denote it by S_r.

The last term in the product is $abc \ldots k$; denote it by S_n.

Hence $$(x+a)(x+b)(x+c)\ldots(x+k)$$
$$= x^n + S_1 x^{n-1} + S_2 x^{n-2} + \ldots + S_r x^{n-r} + \ldots + S_{n-1} x + S_n.$$

In S_1 the *number of terms* is n; in S_2 *the number of terms* is the same as the number of combinations of n things 2 at a time; that is, ${}^nC_2$; in S_3 *the number of terms* is ${}^nC_3$; and so on.

Now suppose $b, c, \ldots k$, each equal to a; then S_1 becomes ${}^nC_1 a$; S_2 becomes ${}^nC_2 a_2$; S_3 becomes ${}^nC_3 a^3$; and so on; thus

$$(x+a)^n = x^n + {}^nC_1 a x^{n-1} + {}^nC_2 a^2 x^{n-2} + {}^nC_3 a^3 x^{n-3} + \ldots + {}^nC_n a^n;$$

substituting for ${}^nC_1, {}^nC_2, \ldots$ we obtain

$$(x+a)^n = x^n + nax^{n-1} + \frac{n(n-1)}{1.2} a^2 x^{n-2} + \frac{n(n-1)(n-2)}{1.2.3} a^3 x^{n-3} + \ldots + a^n,$$

the series containing $n+1$ terms.

This is the *Binomial Theorem*, and the expression on the right is said to be **the expansion** of $(x+a)^n$.

164. The Binomial Theorem may also be proved as follows.

By induction we can find the product of the n factors $x+a, x+b, x+c, \ldots x+k$ as explained in Art. 158, Ex. 2; we can then deduce the expansion of $(x+a)^n$ as in Art. 163.

165. The coefficients in the expansion of $(x+a)^n$ are very conveniently expressed by the symbols ${}^nC_1, {}^nC_2, {}^nC_3, \ldots {}^nC_n$. We shall, however, sometimes further abbreviate them by omitting n, and writing $C_1, C_2, C_3, \ldots C_n$. With this notation we have

$$(x+a)^n = x^n + C_1 a x^{n-1} + C_2 a^2 x^{n-2} + C_3 a^3 x^{n-3} + \ldots + C_n a^n.$$

If we write $-a$ in the place of a, we obtain

$$(x-a)^n = x^n + C_1(-a)x^{n-1} + C_2(-a)^2 x^{n-2} + C_3(-a)^3 x^{n-3} + \ldots + C_n(-a)^n$$
$$= x^n - C_1 a x^{n-1} + C_2 a^2 x^{n-2} - C_3 a^3 x^{n-3} + \ldots + (-1)^n C_n a^n.$$

Thus the terms in the expansion of $(x+a)^n$ and $(x-a)^n$ are *numerically* the same, but in $(x-a)^n$ they are alternately positive and negative, and the last term is positive or negative according as n is even or odd.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Example 1. Find the fifth term of $(a+2x^3)^{17}$.

The required term $= {}^{17}C_4\, a^{13}\,(2x^3)^4$

$$= \frac{17\,.\,16\,.\,15\,.\,14}{1\,.\,2\,.\,3\,.\,4} \times 16a^{13}\,x^{12}$$

$$= 38080a^{13}\,x^{12}.$$

Example 2. Find the fourteenth term of $(3-a)^{15}$

The required term $= {}^{15}C_{13}\,(3)^2\,(-a)^{13}$

$= {}^{15}C_2 \times (-9a^{13})$ [Art. 145.]

$$= -945a^{13}.$$

167. The simplest form of the binomial theorem is the expansion of $(1+x)^n$. This is obtained from the general formula of Art. 163, by writing 1 in the place of x, and x in the place of a. Thus

$$(1+x)^n = 1 + {}^nC_1x + {}^nC_2x^2 + \ldots + {}^nC_rx^r + \ldots + {}^nC_nx^n$$

$$-1 + nx + \frac{n\,(n-1)}{1\,.\,2}\,x^2 + \ldots\ldots + x^n\,;$$

the general term being

$$\frac{n\,(n-1)\,(n-2)\,\ldots\ldots\,(n-r+1)}{\lfloor r}\,x^r.$$

The expansion of a binomial may always be made to depend upon the case in which the first term is unity; thus

$$(x+y)^n = \left\{x\left(1+\frac{y}{x}\right)\right\}^n$$

$$= x^n(1+z)^n, \text{ where } z-\frac{y}{x}$$

Example 1. Find the coefficient of x^{16} in the expansion of $(x^2-2x)^{10}$.

We have $(x^2-2x)^{10} = x^{20}\left(1-\frac{2}{x}\right)^{10}$;

and, since x^{20} multiplies every term in the expansion of $\left(1-\frac{2}{x}\right)^{10}$, we have in this expansion to seek the coefficient of the term which contains $\frac{1}{x^4}$.

Hence the required coefficient $= {}^{10}C_4\,(-2)^4$

$$= \frac{10\,.\,9\,.\,8\,.\,7}{1\,.\,2\,.\,3\,.\,4} \times 16$$

$$= 3360.$$

In some cases the following method is simpler.

Example 2. Find the coefficient of x^r in the expansion of $\left(x^2+\frac{1}{x^3}\right)^n$

Suppose that x^r occurs in the $(p+1)^{\text{th}}$ term.

The $(p+1)^{\text{th}}$ term $= {}^nC_p\,(x^2)^{n-p}\left(\frac{1}{x^3}\right)^p$

$= {}^nC_p\,x^{2n-5p}$.

But this term contains x^r, and therefore $2n-5p=r$, or $p=\frac{2n-r}{5}$

Thus the required coefficient $= {}^nC_p = {}^nC_{\frac{2n-r}{5}}$

$$= \frac{\lfloor n}{\left\lfloor\frac{1}{5}(2n-r)\right\rfloor\left\lfloor\frac{1}{5}(3n+r)\right.}.$$

Unless $\frac{2n-r}{5}$ is a positive integer there will be no term containing x^r in the expansion.

168. In Art. 163 we deduced the expansion of $(x+a)^n$ from the product of n factors $(x+a)(x+b)\ \ldots(x+k)$, and the method of proof there given is valuable in consequence of the wide generality of the results obtained. But the following shorter proof of the Binomial Theorem should be noticed.

It will be seen in Chap. xv. that a similar method is used to obtain the general term of the expansion of

$$(a+b+c+\ldots\ldots)^n.$$

169. *To prove the Binomial Theorem.*

The expansion of $(x+a)^n$ is the product of n factors, each equal to $x+a$, and every term in the expansion is of n dimensions, being a product formed by multiplying together n letters, *one* taken from each of the n factors. Thus each term involving $x^{n-r}a^r$ is obtained by taking a out of *any* r of the factors, and x out of the remaining $n-r$ factors. Therefore the number of terms which involve $x^{n-r}a^r$ must be equal to the number of ways in which r things can be selected out of n; that is, the coefficient of $x^{n-r}a^r$ is ${}^nC_r$, and by giving to r the values 0, 1, 2, 3, ... n in succession we obtain the coefficients of all the terms. Hence

$$(x+a)^n = x^n + {}^nC_1x^{n-1}a + {}^nC_2x^{n-2}a^2 + \ldots + {}^nC_rx^{n-r}a^r + \ldots + a^n,$$

since ${}^nC_0$ and ${}^nC_n$ are each equal to unity.

EXAMPLES. XIII. a.

Expand the following binomials:

1. $(x-3)^5$. **2.** $(3x+2y)^4$. **3.** $(2x-y)^5$.

4. $(1-3a^2)^6$. **5.** $(x^2+x)^5$. **6.** $(1-xy)^7$.

7. $\left(2-\frac{3x^2}{2}\right)^4$. **8.** $\left(3a-\frac{2}{3}\right)^6$. **9.** $\left(1+\frac{x}{2}\right)^7$.

10. $\left(\frac{2}{3}x-\frac{3}{2x}\right)^6$. **11.** $\left(\frac{1}{2}+a\right)^8$. **12.** $\left(1-\frac{1}{x}\right)^{10}$.

Write down and simplify:

13. The 4^{th} term of $(x-5)^{13}$ **14.** The 10^{th} term of $(1-2x)^{12}$.

15. The 12^{th} term of $(2x-1)^{13}$. **16.** The 28^{th} term of $(5x+8y)^{30}$

17. The 4^{th} term of $\left(\frac{a}{3}+9b\right)^{10}$.

18. The 5^{th} term of $\left(2a-\frac{b}{3}\right)^8$.

19. The 7^{th} term of $\left(\frac{4x}{5}-\frac{5}{2x}\right)^9$.

20. The 5^{th} term of $\left(\frac{x^{\frac{3}{2}}}{a^{\frac{1}{2}}}-\frac{y^{\frac{5}{2}}}{b^{\frac{3}{2}}}\right)^8$.

Find the value of

21. $(x+\sqrt{2})^4+(x-\sqrt{2})^4$ **22.** $(\sqrt{x^2-a^2}+x)^5-(\sqrt{x^2-a^2}-x)^5$

23. $(\sqrt{2}+1)^6-(\sqrt{2}-1)^6$ **24.** $(2-\sqrt{1-x})^6+(2+\sqrt{1-x})^6$.

25. Find the middle term of $\left(\frac{a}{x}+\frac{x}{a}\right)^{10}$.

26. Find the middle term of $\left(1-\frac{x^2}{2}\right)^{14}$.

27. Find the coefficient of x^{18} in $\left(x^2+\frac{3a}{x}\right)^{15}$.

28. Find the coefficient of x^{18} in $(ax^4-bx)^9$.

29. Find the coefficients of x^{32} and x^{-17} in $\left(x^4-\frac{1}{x^3}\right)^{15}$.

30. Find the two middle terms of $\left(3a-\frac{a^3}{6}\right)^9$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Let the r^{th} and $(r+1)^{\text{th}}$ be any two consecutive terms. The $(r+1)^{\text{th}}$ term is obtained by multiplying the r^{th} term by $\frac{n-r+1}{r} \cdot \frac{a}{x}$; that is, by $\left(\frac{n+1}{r} - 1\right)\frac{a}{x}$. [Art. 166.]

The factor $\frac{n+1}{r} - 1$ decreases as r increases; hence the $(r+1)^{\text{th}}$ term is not always greater than the r^{th} term, but only until $\left(\frac{n+1}{r} - 1\right)\frac{a}{x}$ becomes equal to 1, or less than 1.

Now $$\left(\frac{n+1}{r} - 1\right)\frac{a}{x} > 1,$$

so long as $$\frac{n+1}{r} - 1 > \frac{x}{a};$$

that is, $$\frac{n+1}{r} > \frac{x}{a} + 1,$$

or $$\frac{n+1}{\frac{x}{a}+1} > r \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

If $\frac{n+1}{\frac{x}{a}+1}$ be an integer, denote it by p; then if $r = p$ the multiplying factor becomes 1, and the $(p+1)^{\text{th}}$ term is equal to the p^{th}; and these are greater than any other term.

If $\frac{n+1}{\frac{x}{a}+1}$ be not an integer, denote its integral part by q; then the greatest value of r consistent with (1) is q; hence the $(q+1)^{\text{th}}$ term is the greatest.

Since we are only concerned with the *numerically greatest term*, the investigation will be the same for $(x-a)^n$; therefore in any numerical example it is unnecessary to consider the sign of the second term of the binomial. Also it will be found best to work each example independently of the general formula.

Example 1. If $x=\frac{1}{3}$, find the greatest term in the expansion of $(1+4x)^8$

Denote the r^{th} and $(r+1)^{\text{th}}$ terms by T_r and T_{r+1} respectively; then

$$T_{r+1}=\frac{8-r+1}{r}\cdot 4x\times T_r$$

$$=\frac{9-r}{r}\times\frac{4}{3}\times T_r;$$

hence $T_{r+1}>T_r$,

so long as $\frac{9-r}{r}\times\frac{4}{3}>1$;

that is $36-4r>3r$,

or $36>7r$.

The greatest value of r consistent with this is 5; hence the greatest term is the sixth, and its value

$$={}^8C_5\times\left(\frac{4}{3}\right)^5={}^8C_3\times\left(\frac{4}{3}\right)^5=\frac{57344}{243}.$$

Example 2. Find the greatest term in the expansion of (3 $2x)^9$ when $x=1$.

$$(3-2x)^9=3^9\left(1-\frac{2x}{3}\right)^9;$$

thus it will be sufficient to consider the expansion of $\left(1-\frac{2x}{3}\right)^9$

Here $T_{r+1}=\frac{9-r+1}{r}\cdot\frac{2x}{3}\times T_r$, *numerically*,

$$=\frac{10-\mathrm{r}}{r}\times\frac{2}{3}\times T_r;$$

hence $T_{r+1}>T_r$,

so long as $\frac{10-r}{r}\times\frac{2}{3}>1$;

that is, $20>5r$.

Hence for all values of r up to 3, we have $T_{r+1}>T_r$; but if $r=4$, then $T_{r+1}=T_r$, and these are the greatest terms. Thus the 4^{th} and 5^{th} terms are numerically equal and greater than any other term, and their value

$$=3^9\times{}^9C_3\times\left(\frac{2}{3}\right)^3=3^6\times 84\times 8=489888.$$

173. *To find the sum of the coefficients in the expansion of* $(1+x)^n$.

In the identity $(1+x)^n = 1 + C_1x + C_2x^2 + C_3x^3 + \ldots + C_nx^n$, put $x = 1$; thus

$$2^n = 1 + C_1 + C_2 + C_3 + \ldots + C_n$$
$$= \text{sum of the coefficients.}$$

Cor. $C_1 + C_2 + C_3 + \ldots + C_n = 2^n - 1$;

that is "the total number of combinations of n things" is $2^n - 1$. [Art. 153.]

174. *To prove that in the expansion of* $(1+x)^n$, *the sum of the coefficients of the odd terms is equal to the sum of the coefficients of the even terms.*

In the identity $(1+x)^n = 1 + C_1x + C_2x^2 + C_3x^3 + \ldots + C_nx^n$, put $x = -1$; thus

$$0 = 1 - C_1 + C_2 - C_3 + C_4 - C_5 + \ldots\ldots;$$
$$\therefore \quad 1 + C_2 + C_4 + \ldots\ldots = C_1 + C_3 + C_5 + \ldots\ldots$$
$$= \frac{1}{2}(\text{sum of all the coefficients})$$
$$= 2^{n-1}.$$

175. The Binomial Theorem may also be applied to expand expressions which contain more than two terms.

Example. Find the expansion of $(x^2+2x-1)^3$.

Regarding $2x-1$ as a single term, the expansion
$$= (x^2)^3 + 3(x^2)^2(2x-1) + 3x^2(2x-1)^2 + (2x-1)^3$$
$$= x^6 + 6x^5 + 9x^4 - 4x^3 - 9x^2 + 6x - 1, \text{ on reduction.}$$

176. The following example is instructive.

Example. If $(1+x)^n = c_0 + c_1x + c_2x^2 + \ldots\ldots + c_nx^n$,

find the value of $c_0 + 2c_1 + 3c_2 + 4c_3 + \ldots\ldots + (n+1)c_n$ .....(1),

and $c_1^2 + 2c_2^2 + 3c_3^2 + \ldots\ldots + nc_n^2$ .....(?).

The series (1) $= (c_0 + c_1 + c_2 + \ldots\ldots + c_n) + (c_1 + 2c_2 + 3c_3 + \ldots\ldots + nc_n)$
$$= 2^n + n\left\{1 + (n-1) + \frac{(n-1)(n-2)}{1.2} + \ldots\ldots + 1\right\}$$
$$- 2^n + n(1+1)^{n-1}$$
$$- 2^n + n \cdot 2^{n-1}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

7. Shew that the coefficient of the middle term of $(1+x)^{2n}$ is equal to the sum of the coefficients of the two middle terms of $(1+x)^{2n-1}$.

8. If A be the sum of the odd terms and B the sum of the even terms in the expansion of $(x+a)^n$, prove that $A^2-B^2=(x^2-a^2)^n$.

9. The 2^{nd}, 3^{rd}, 4^{th} terms in the expansion of $(x+y)^n$ are 240, 720, 1080 respectively; find x, y, n.

10. Find the expansion of $(1+2x-x^2)^4$

11. Find the expansion of $(3x^2-2ax+3a^2)^3$.

12. Find the r^{th} term from the end in $(x+a)^n$.

13. Find the $(p+2)^{th}$ term from the end in $\left(x-\frac{1}{x}\right)^{2n+1}$.

14. In the expansion of $(1+x)^{43}$ the coefficients of the $(2r+1)^{th}$ and the $(r+2)^{th}$ terms are equal; find r.

15. Find the relation between r and n in order that the coefficients of the $3r^{th}$ and $(r+2)^{th}$ terms of $(1+x)^{2n}$ may be equal.

16. Shew that the middle term in the expansion of $(1+x)^{2n}$ is

$$\frac{1\,.\,3\,.\,5\,\ldots\,(2n-1)}{\lfloor n}\,2^n x^n.$$

If $c_0, c_1, c_2, \ldots c_n$ denote the coefficients in the expansion of $(1+x)^n$, prove that

17. $c_1+2c_2+3c_3+\ldots\ldots+nc_n=n\,.\,2^{n-1}$.

18. $c_0+\frac{c_1}{2}+\frac{c_2}{3}+\ldots\ldots+\frac{c_n}{n+1}=\frac{2^{n+1}-1}{n+1}$.

19. $\frac{c_1}{c_0}+\frac{2c_2}{c_1}+\frac{3c_3}{c_2}+\ldots\ldots+\frac{nc_n}{c_{n-1}}=\frac{n\,(n+1)}{2}$.

20. $(c_0+c_1)\,(c_1+c_2)\ldots\ldots(c_{n-1}+c_n)=\frac{c_1c_2\ldots\ldots c_n\,(n+1)^n}{\lfloor n}$.

21. $2c_0+\frac{2^2c_1}{2}+\frac{2^3c_2}{3}+\frac{2^4c_3}{4}+\ldots\ldots+\frac{2^{n+1}c_n}{n+1}=\frac{3^{n+1}-1}{n+1}$.

22. $c_0{}^2+c_1{}^2+c_2{}^2+\ldots\ldots+c_n{}^2=\frac{\lfloor 2n}{\lfloor n\,\lfloor n}$.

23. $c_0c_r+c_1c_{r+1}+c_2c_{r+2}+\ldots\ldots+c_{n-r}c_n=\frac{\lfloor 2n}{\lfloor n-r\,\lfloor n+r}$.

CHAPTER XIV

Binomial Theorem. Any Index.

177. In the last chapter we investigated the Binomial Theorem when the index was any positive integer; we shall now consider whether the formulæ there obtained hold in the case of negative and fractional values of the index.

Since, by Art. 167, every binomial may be reduced to one common type, it will be sufficient to confine our attention to binomials of the form $(1+x)^n$.

By actual evolution, we have

$$(1+x)^{\frac{1}{2}} = \sqrt{1+x} = 1 + \frac{1}{2}x - \frac{1}{8}x^2 + \frac{1}{16}x^3$$

and by actual division,

$$(1-x)^{-2} = \frac{1}{(1-x)^2} = 1 + 2x + 3x^2 + 4x^3 + \quad ;$$

[Compare Ex. 1, Art. 60.]

and in each of these series the number of terms is unlimited.

In these cases we have by independent processes obtained an expansion for each of the expressions $(1+x)^{\frac{1}{2}}$ and $(1+x)^{-2}$ We shall presently prove that they are only particular cases of the general formula for the expansion of $(1+x)^n$, where n is any rational quantity.

This formula was discovered by Newton.

178. Suppose we have two expressions arranged in ascending powers of x, such as

$$1 + mx + \frac{m(m-1)}{1.2}x^2 + \frac{m(m-1)(m-2)}{1.2.3}x^3 + \ldots\ldots\ldots (1),$$

and $$1 + nx + \frac{n(n-1)}{1.2}x^2 + \frac{n(n-1)(n-2)}{1.2.3}x^3 + \ldots\ldots\ldots\ldots (2).$$

The product of these two expressions will be a series in ascending powers of x; denote it by

$$1 + Ax + Bx^2 + Cx^3 + Dx^4 +$$

then it is clear that A, B, C, ... are functions of m and n, and therefore the actual values of A, B, C, ... in any particular case will depend upon the values of m and n in that case. But the way in which the coefficients of the powers of x in (1) and (2) combine to give A, B, C, ... is quite independent of m and n; in other words, *whatever values* m *and* n *may have*, A, B, C, ... *preserve the same invariable form.* If therefore we can determine the form of A, B, C, ... for any value of m and n, we conclude that A, B, C, ... will have the same form *for all values* of m and n.

The principle here explained is often referred to as an example of "the permanence of equivalent forms;" in the present case we have only to recognise the fact that *in any algebraical product* the *form* of the result will be the same whether the quantities involved are whole numbers, or fractions; positive, or negative.

We shall make use of this principle in the general proof of the Binomial Theorem for any index. The proof which we give is due to Euler.

179. *To prove the Binomial Theorem when the index is a positive fraction.*

Whatever be the value of m, *positive or negative, integral or fractional,* let the symbol $f(m)$ stand for the series

$$1 + mx + \frac{m(m-1)}{1.2}x^2 + \frac{m(m-1)(m-2)}{1.2.3}x^3 + \ldots;$$

then $f(n)$ will stand for the series

$$1 + nx + \frac{n(n-1)}{1.2}x^2 + \frac{n(n-1)(n-2)}{1.2.3}x^3 + \ldots.$$

If we multiply these two series together the product will be another series in ascending powers of x, whose *coefficients will be unaltered in form whatever* m *and* n *may be.*

To determine this *invariable form of the product* we may give to m and n any values that are most convenient; for this purpose suppose that m and n are positive integers. In this case $f(m)$ is the expanded form of $(1+x)^m$, and $f(n)$ is the expanded form of $(1+x)^n$; and therefore

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

180. *To prove the Binomial Theorem when the index is any negative quantity.*

It has been proved that

$$f(m) \times f(n) = f(m+n)$$

for all values of m and n. Replacing m by n (where n is positive), we have

$$f(-n) \times f(n) = f(-n+n)$$
$$= f(0)$$
$$= 1,$$

since all terms of the series except the first vanish;

$$\therefore \quad \frac{1}{f(n)} = f(-n);$$

but $f(n) = (1+x)^n$, for *any positive* value of n;

$$\therefore \quad \frac{1}{(1+x)^n} = f(-n),$$

or
$$(1+x)^{-n} = f(-n).$$

But $f(-n)$ stands for the series

$$1 + (-n)x + \frac{(-n)(-n-1)}{1 \cdot 2} x^2 + \ldots\ldots;$$

$$\therefore \quad (1+x)^{-n} = 1 + (-n)x + \frac{(-n)(-n-1)}{1 \cdot 2} x^2 + \ldots\ldots;$$

which proves the Binomial Theorem for any negative index. Hence the theorem is completely established.

181. The proof contained in the two preceding articles may not appear wholly satisfactory, and will probably present some difficulties to the student. There is only one point to which we shall now refer.

In the expression for $f(m)$ the number of terms is finite when m is a positive integer, and unlimited in all other cases. See Art. 182. It is therefore necessary to enquire in what sense we

are to regard the statement that $f(m) \times f(n) = f(m+n)$. It will be seen in Chapter XXI., that when $x<1$, each of the series $f(m)$, $f(n)$, $f(m+n)$ is *convergent*, and $f(m+n)$ is the true arithmetical equivalent of $f(m) \times f(n)$. But when $x>1$, all these series are *divergent*, and we can only assert that if we multiply the series denoted by $f(m)$ by the series denoted by $f(n)$, the first r terms of the product will agree with the first r terms of $f(m+n)$, whatever finite value r may have. [See Art. 308.]

3

Example 1. Expand $(1-x)^{\frac{3}{2}}$ to four terms.

$$(1-x)^{\frac{3}{2}} = 1 + \frac{3}{2}(-x) + \frac{\frac{3}{2}\left(\frac{3}{2}-1\right)}{1.2}(-x)^2 + \frac{\frac{3}{2}\left(\frac{3}{2}-1\right)\left(\frac{3}{2}-2\right)}{1.2.3}(-x)^3 +$$

$$-1 - \frac{3}{2}x + \frac{3}{8}x^2 + \frac{1}{16}x^3 + \ldots\ldots$$

Example 2. Expand $(2+3x)^{-4}$ to four terms.

$$(2+3x)^{-4} = 2^{-4}\left(1+\frac{3x}{2}\right)^{-4}$$

$$= \frac{1}{2^4}\left[1 + (-4)\left(\frac{3x}{2}\right) + \frac{(-4)(-5)}{1.2}\left(\frac{3x}{2}\right)^2 + \frac{(-4)(-5)(-6)}{1.2.3}\left(\frac{3x}{2}\right)^3 + \quad\right]$$

$$= \frac{1}{16}\left(1 - 6x + \frac{45}{2}x^2 - \frac{135}{2}x^3 + \ldots\ldots\right).$$

182. In finding the general term we must now use the formula

$$\frac{n(n-1)(n-2)\ldots\ldots(n-r+1)}{\lfloor r}x^r$$

written in full; for the symbol ${}^nC_r$ can no longer be employed when n is fractional or negative.

Also the coefficient of the general term can never vanish unless one of the factors of its numerator is zero; the series will therefore stop at the r^{th} term, when $n-r+1$ is zero; that is, when $r=n+1$; but since r is a positive integer this equality can never hold except when the index n is positive and integral. Thus the expansion by the Binomial Theorem extends to $n+1$ terms when n is a positive integer, and to an infinite number of terms in all other cases.

Example 1. Find the general term in the expansion of $(1+x)^{\frac{1}{2}}$

$$\text{The } (r+1)^{\text{th}} \text{ term} = \frac{\frac{1}{2}\left(\frac{1}{2}-1\right)\left(\frac{1}{2}-2\right)\ldots\ldots\left(\frac{1}{2}-r+1\right)}{\lfloor r} x^r$$

$$= \frac{1\,(-1)\,(-3)\,(-5)\ldots\ldots(-2r+3)}{2^r \lfloor r} x^r.$$

The number of factors in the numerator is r, and $r-1$ of these are negative; therefore, by taking -1 out of each of these negative factors, we may write the above expression

$$(-1)^{r-1}\frac{1\,.\,3\,.\,5\ldots\ldots(2r-3)}{2^r \lfloor r} x^r.$$

Example 2. Find the general term in the expansion of $(1-nx)^{\frac{1}{n}}$

$$\text{The } (r+1)^{\text{th}} \text{ term} = \frac{\frac{1}{n}\left(\frac{1}{n}-1\right)\left(\frac{1}{n}-2\right)\ldots\ldots\left(\frac{1}{n}-r+1\right)}{\lfloor r} (-nx)^r$$

$$= \frac{1\,(1-n)\,(1-2n)\ldots\ldots(1-\overline{r-1}\cdot n)}{n^r \lfloor r} (-1)^r n^r x^r$$

$$= (-1)^r \frac{1\,(1-n)\,(1-2n)\ldots\ldots\ (1-\overline{r-1}\cdot n)}{\lfloor r} x^r$$

$$= (-1)^r\,(-1)^{r-1}\frac{(n-1)\,(2n-1)\ldots\ldots(\overline{r-1}\cdot n-1)}{\lfloor r} x^r$$

$$= -\frac{(n-1)\,(2n-1)\ldots\ldots(\overline{r-1}\cdot n-1)}{\lfloor r} x^r,$$

since $$(-1)^r\,(-1)^{r-1} = (-1)^{2r-1} = -1.$$

Example 3. Find the general term in the expansion of $(1\quad x)^{\ 3}$

$$\text{The } (r+1)^{\text{th}} \text{ term} = \frac{(-3)\,(-4)\,(-5)\ldots\ldots(-3-r+1)}{\lfloor r} (-x)^r$$

$$= (-1)^r \frac{3\,.\,4\,.\,5\ldots\ldots(r+2)}{\lfloor r} (-1)^r x^r$$

$$= (-1)^{2r}\frac{3\,.\,4\,.\,5\ldots\ldots(r+2)}{1\,.\,2\,.\,3\ldots\ldots r} x^r$$

$$= \frac{(r+1)\,(r+2)}{1\,.\,2} x^r,$$

by removing like factors from the numerator and denominator.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

and, if not, under what conditions the expansion of $(1+x)^n$ may be used as its true equivalent.

Suppose, for instance, that $n=-1$; then we have

$$(1-x)^{-1} = 1 + x + x^2 + x^3 + x^4 + \ldots\ldots\ldots\ldots (1);$$

in this equation put $x=2$; we then obtain

$$(-1)^{-1} = 1 + 2 + 2^2 + 2^3 + 2^4 + \ldots\ldots .$$

This contradictory result is sufficient to shew that we cannot take

$$1 + nx + \frac{n(n-1)}{1\,.\,2}\, x^2 + \ldots\ldots$$

as the true arithmetical equivalent of $(1+x)^n$ in all cases.

Now from the formula for the sum of a geometrical progression, we know that the sum of the first r terms of the series (1)

$$= \frac{1-x^r}{1-x}$$

$$= \frac{1}{1-x} - \frac{x^r}{1-x};$$

and, when x is numerically less than 1, by taking r sufficiently large we can make $\frac{x^r}{1-x}$ as small as we please; that is, by taking a sufficient number of terms the sum can be made to differ as little as we please from $\frac{1}{1-x}$. But when x is numerically greater than 1, the value of $\frac{x^r}{1-x}$ increases with r, and therefore no such approximation to the value of $\frac{1}{1-x}$ is obtained by taking any number of terms of the series

$$1 + x + x^2 + x^3 + \ldots\ldots .$$

It will be seen in the chapter on Convergency and Divergency of Series that the expansion by the Binomial Theorem of $(1+x)^n$ in ascending powers of x is always arithmetically intelligible when x is less than 1.

But if x is greater than 1, then since the general term of the series

$$1 + nx + \frac{n(n-1)}{1\,.\,2}\, x^2 + \ldots\ldots$$

contains x^r, it can be made greater than any finite quantity by taking r sufficiently large; in which case there is no limit to the value of the above series; and therefore the expansion of $(1+x)^n$ as an infinite series in ascending powers of x has no meaning arithmetically intelligible when x is greater than 1.

184. We may remark that we can always expand $(x+y)^n$ by the Binomial Theorem; for we may write the expression in either of the two following forms:

$$x^n\left(1+\frac{y}{x}\right)^n, \qquad y^n\left(1+\frac{x}{y}\right)^n;$$

and we obtain the expansion from the first or second of these according as x is greater or less than y.

185. *To find in its simplest form the general term in the expansion of* $(1-x)^{-n}$

The $(r+1)^{th}$ term

$$= \frac{(-n)(-n-1)(-n-2)\ldots(-n-r+1)}{\lfloor r}(-x)^r$$

$$= (-1)^r \frac{n(n+1)(n+2)\ldots(n+r-1)}{\lfloor r}(-1)^r x^r$$

$$= (-1)^{2r} \frac{n(n+1)(n+2)\ldots(n+r-1)}{\lfloor r} x^r$$

$$= \frac{n(n+1)(n+2)\ldots(n+r-1)}{\lfloor r} x^r.$$

From this it appears that every term in the expansion of $(1-x)^{-n}$ is positive.

Although the general term in the expansion of any binomial may always be found as explained in Art. 182, it will be found more expeditious in practice to use the above form of the general term in all cases where the index is negative, retaining the form

$$\frac{n(n-1)(n-2)\ldots(n-r+1)}{\lfloor r} x^r$$

only in the case of positive indices.

Example. Find the general term in the expansion of $\frac{1}{\sqrt[3]{1-3x}}$.

$$\frac{1}{\sqrt[3]{1-3x}} = (1-3x)^{\frac{1}{3}}.$$

The $(r+1)^{\text{th}}$ term

$$= \frac{\frac{1}{3}\left(\frac{1}{3}+1\right)\left(\frac{1}{3}+2\right)\ldots\ldots\left(\frac{1}{3}+r-1\right)}{\lfloor r} (3x)^r$$

$$= \frac{1\,.\,4\,.\,7\,\ldots\ldots\,(3r-2)}{3^r\,\lfloor r}\, 3^r x^r$$

$$= \frac{1\,.\,4\,.\,7\,\ldots\ldots\,(3r-2)}{\lfloor r}\, x^r.$$

If the given expression had been $(1+3x)^{-\frac{1}{3}}$ we should have used the same formula for the general term, replacing $3x$ by $-3x$.

186. The following expansions should be remembered:

$$(1-x)^{-1} = 1 + x + x^2 + x^3 + \ldots\ldots + x^r + .$$

$$(1-x)^{-2} = 1 + 2x + 3x^2 + 4x^3 + \ldots\ldots + (r+1)\,x^r +$$

$$(1-x)^{-3} = 1 + 3x + 6x^2 + 10x^3 + \ldots\ldots + \frac{(r+1)\,(r+2)}{1\,.\,2}\, x^r + \ldots\ldots$$

187. The general investigation of the greatest term in the expansion of $(1+x)^n$, when n is unrestricted in value, will be found in Art. 189; but the student will have no difficulty in applying to any numerical example the method explained in Art. 172.

Example. Find the greatest term in the expansion of $(1+x)^{-n}$ when $x=\frac{2}{3}$, and $n=20$.

We have $$T_{r+1} = \frac{n+r-1}{r}\,.\,x \times T_r, \text{ numerically,}$$

$$= \frac{19+r}{r} \times \frac{2}{3} \times T_r;$$

$$\therefore\ T_{r+1} > T_r,$$

so long as $$\frac{2\,(19+r)}{3r} > 1;$$

that is, $$38 > r.$$

Hence for all values of r up to 37, we have $T_{r+1} > T_r$; but if $r=38$, then $T_{r+1} = T_r$, and these are the greatest terms. Thus the 38^{th} and 39^{th} terms are equal numerically and greater than any other term.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Example 3. Find the value of $\frac{1}{\sqrt{47}}$ to four places of decimals.

$$\frac{1}{\sqrt{47}} = (47)^{\frac{1}{2}} = (7^2 - 2)^{\frac{1}{2}} = \frac{1}{7}\left(1 - \frac{2}{7^2}\right)^{\frac{1}{2}}$$

$$-\frac{1}{7}\left(1 + \frac{1}{7^2} + \frac{3}{2}\cdot\frac{1}{7^4} + \frac{5}{2}\cdot\frac{1}{7^6} + \dots\right)$$

$$= \frac{1}{7} + \frac{1}{7^3} + \frac{3}{2}\cdot\frac{1}{7^5} + \frac{5}{2}\cdot\frac{1}{7^7} + \dots$$

To obtain the values of the several terms we proceed as follows:

$$\begin{array}{l} 7\,)\,1 \\ \underline{} \\ 7\,)\,\cdot142857 \dots\dots\dots\dots\dots\dots - \frac{1}{7}, \\ \underline{} \\ 7\,)\,\cdot020408 \\ \underline{} \\ 7\,)\,\cdot002915 \dots\dots\dots\dots\dots\dots = \frac{1}{7^3}, \\ \underline{} \\ 7\,)\,\cdot000416 \\ \underline{} \\ \cdot000059 \dots\dots\dots\dots\dots\dots = \frac{1}{7^5}; \end{array}$$

and we can see that the term $\frac{5}{2}\cdot\frac{1}{7^7}$ is a decimal fraction beginning with 5 ciphers.

$$\frac{1}{\sqrt{47}} = \cdot142857 + \cdot002915 + \cdot000088$$

$$- 14586,$$

and this result is correct to at least four places of decimals.

Example 4. Find the cube root of 126 to 5 places of decimals.

$$(126)^{\frac{1}{3}} = (5^3 + 1)^{\frac{1}{3}}$$

$$-5\left(1 + \frac{1}{5^3}\right)^{\frac{1}{3}}$$

$$-5\left(1 + \frac{1}{3}\cdot\frac{1}{5^3} - \frac{1}{9}\cdot\frac{1}{5^6} + \frac{5}{81}\cdot\frac{1}{5^9} - \dots\right)$$

$$= 5 + \frac{1}{3}\cdot\frac{1}{5^2} - \frac{1}{9}\cdot\frac{1}{5^5} + \frac{1}{81}\cdot\frac{1}{5^7} \quad \dots$$

$$= 5 + \frac{1}{3}\cdot\frac{2^2}{10^2} - \frac{1}{9}\cdot\frac{2^5}{10^5} + \frac{1}{81}\cdot\frac{2^7}{10^7} - \dots$$

$$= 5 + \frac{\cdot04}{3} - \frac{\cdot00032}{9} + \frac{\cdot0000128}{81} - \dots$$

$$-5 + \cdot013333\ldots - \cdot000035\ldots + \ldots$$

$-5\cdot01329$, to five places of decimals.

EXAMPLES. XIV. b.

Find the $(r+1)^{th}$ term in each of the following expansions:

1. $(1+x)^{-\frac{1}{2}}$. **2.** $(1-x)^{-5}$. **3.** $(1+3x)^{\frac{1}{3}}$.

4. $(1+x)^{-\frac{2}{3}}$. **5.** $(1+x^2)^{-3}$. **6.** $(1-2x)^{-\frac{3}{2}}$.

7. $(a+bx)^{-1}$. **8.** $(2-x)^{-2}$ **9.** $\sqrt[3]{(a^3-x^3)^2}$.

10. $\dfrac{1}{\sqrt{1+2x}}$. **11.** $\dfrac{1}{\sqrt[3]{(1-3x)^2}}$. **12.** $\dfrac{1}{\sqrt[n]{a^n-nx}}$.

Find the greatest term in each of the following expansions:

13. $(1+x)^{-7}$ when $x=\frac{4}{15}$.

14. $(1+x)^{21}_{2}$ when $x=\frac{2}{3}$.

15. $(1-7x)^{11}_{4}$ when $x=\frac{1}{8}$.

16. $(2x+5y)^{12}$ when $x=8$ and $y=3$.

17. $(5-4x)^{-7}$ when $x=\frac{1}{2}$.

18. $(3x^2+4y^3)^{-n}$ when $x=9$, $y=2$, $n=15$.

Find to five places of decimals the value of

19. $\sqrt{98}$. **20.** $\sqrt[3]{998}$. **21.** $\sqrt[3]{1003}$. **22.** $\sqrt[4]{2400}$.

23. $\dfrac{1}{\sqrt[3]{128}}$. **24.** $(1\frac{1}{250})^{\frac{1}{3}}$. **25.** $(630)^{-\frac{3}{4}}$. **26.** $\sqrt[5]{3128}$.

If x be so small that its square and higher powers may be neglected, find the value of

27. $(1-7x)^{\frac{1}{3}}(1+2x)^{-\frac{3}{4}}$ **28.** $\sqrt{4-x}\,.\left(3-\frac{x}{2}\right)$

29. $\dfrac{(8+3x)^{\frac{2}{3}}}{(2+3x)\sqrt{4-5x}}$. **30.** $\dfrac{\left(1+\frac{2}{3}x\right)^{-5}\times(4+3x)^{\frac{1}{2}}}{(4+x)^{\frac{3}{2}}}$.

31. $\dfrac{\sqrt[4]{1-\frac{3}{5}x}+\left(1+\frac{5}{6}x\right)^{-6}}{\sqrt[3]{1+2x}+\sqrt[5]{1-\frac{x}{2}}}$. **32.** $\dfrac{\sqrt[3]{8+3x}-\sqrt[5]{1-x}}{(1+5x)^{\frac{3}{5}}+\left(4+\frac{x}{2}\right)^{\frac{1}{2}}}$.

33. Prove that the coefficient of x^r in the expansion of $(1-4x)^{\frac{1}{2}}$ is $\dfrac{\lfloor 2r}{(\lfloor r)^2}$.

34. Prove that $(1+x)^n=2^n\left\{1-n\dfrac{1-x}{1+x}+\dfrac{n(n+1)}{1.2}\left(\dfrac{1-x}{1+x}\right)^2\ldots\ldots\right\}$.

35. Find the first three terms in the expansion of

$$\frac{1}{(1+x)^2\sqrt{1+4x}}.$$

36. Find the first three terms in the expansion of

$$\frac{(1+x)^{\frac{3}{4}}+\sqrt{1+5x}}{(1-x)^2}.$$

37. Shew that the n^{th} coefficient in the expansion of $(1-x)^{-n}$ is double of the $(n-1)^{\text{th}}$.

189. *To find the numerically greatest term in the expansion of* $(1+x)^n$, *for any rational value of* n.

Since we are only concerned with the *numerical* value of the greatest term, we shall consider x throughout as positive.

Case I. Let n be a positive integer.

The $(r+1)^{\text{th}}$ term is obtained by multiplying the r^{th} term by $\dfrac{n-r+1}{r}.x$; that is, by $\left(\dfrac{n+1}{r}-1\right)x$; and therefore the terms continue to increase so long as

$$\left(\frac{n+1}{r}-1\right)x>1;$$

that is,

$$\frac{(n+1)x}{r}>1+x,$$

or

$$\frac{(n+1)x}{1+x}>r.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

(1) If x be greater than unity we may shew, as in Case II., that there is no greatest term.

(2) If x be less than unity, the multiplying factor will be greater than 1, so long as

$$\left(\frac{m-1}{r}+1\right)x>1\,;$$

that is,
$$\frac{(m-1)\,x}{r}>1-x,$$

or
$$\frac{(m-1)\,x}{1-x}>r.$$

If $\frac{(m-1)\,x}{1-x}$ be a positive integer, denote it by p; then the $(p+1)^{\text{th}}$ term is equal to the p^{th} term, and these are greater than any other term.

If $\frac{(m-1)\,x}{1-x}$ be positive but not an integer, let q be its integral part; then the $(q+1)^{\text{th}}$ term is the greatest.

If $\frac{(m-1)\,x}{1-x}$ be negative, then m is less than unity; and by writing the multiplying factor in the form $\left(1-\frac{1-m}{r}\right)x$, we see that it is always less than 1: hence each term is less than the preceding, and consequently the first term is the greatest.

190. *To find the number of homogeneous products of* r *dimensions that can be formed out of the* n *letters* a, b, c, ... *and their powers.*

By division, or by the Binomial Theorem, we have

$$\frac{1}{1-ax}=1+ax+a^2x^2+a^3x^3+\quad,$$

$$\frac{1}{1-bx}=1+bx+b^2x^2+b^3x^3+\quad,$$

$$\frac{1}{1-cx}=1+cx+c^2x^2+c^3x^3+\ldots\ldots,$$

Hence, by multiplication,

$$\frac{1}{1-ax} \cdot \frac{1}{1-bx} \cdot \frac{1}{1-cx} \cdot \ldots\ldots$$

$$-(1+ax+a^2x^2+\ldots)(1+bx+b^2x^2+\ldots)(1+cx+c^2x^2+\quad)$$

$$=1+x(a+b+c+\ldots)+x^2(a^2+ab+ac+b^2+bc+c^2+\ldots)+$$

$$=1+S_1x+S_2x^2+S_3x^3+\ldots\ldots \text{ suppose;}$$

where S_1, S_2, S_3, . are the *sums* of the homogeneous products of *one*, *two*, *three*, ... dimensions that can be formed of a, b, c, and their powers.

To obtain the *number* of these products, put a, b, c, ... each equal to 1; each term in S_1, S_2, S_3, ... now becomes 1, and the values of S_1, S_2, S_3, ... so obtained give the *number* of the homogeneous products of *one*, *two*, *three*, ... dimensions.

Also $$\frac{1}{1-ax} \cdot \frac{1}{1-bx} \cdot \frac{1}{1-cx} \ldots\ldots$$

becomes $$\frac{1}{(1-x)^n} \text{ or } (1-x)^{-n}$$

Hence $S_r =$ coefficient of x^r in the expansion of $(1-x)^{-n}$

$$= \frac{n(n+1)(n+2)\ldots\ldots(n+r-1)}{\lfloor r}$$

$$= \frac{\lfloor n+r-1}{\lfloor r \ \lfloor n-1}.$$

191. *To find the number of terms in the expansion of any multinomial when the index is a positive integer.*

In the expansion of

$$(a_1+a_2+a_3+\ldots\ldots+a_r)^n,$$

every term is of n dimensions; therefore the number of terms is the same as the number of homogeneous products of n dimensions that can be formed out of the r quantities a_1, a_2, ... a_r, and their powers; and therefore by the preceding article is equal to

$$\frac{\lfloor r+n-1}{\lfloor n \ \lfloor r-1}.$$

192. From the result of Art. 190 we may deduce a theorem relating to the number of combinations of n things.

Consider n letters $a, b, c, d, \ldots\ldots$; then if we were to write down all the homogeneous products of r dimensions which can be formed of these letters and their powers, every such product would represent one of the combinations, r at a time, of the n letters, when any one of the letters might occur once, twice, thrice, ... up to r times.

Therefore the number of combinations of n things r at a time when repetitions are allowed is equal to the number of homogeneous products of r dimensions which can be formed out of n letters, and therefore equal to $\frac{\lfloor n+r-1}{\lfloor r \; \lfloor n-1}$, or ${}^{n+r-1}C_r$.

That is, the number of combinations of n things r at a time when repetitions are allowed is equal to the number of combinations of $n+r-1$ things r at a time when repetitions are excluded.

193. We shall conclude this chapter with a few miscellaneous examples.

Example 1. Find the coefficient of x^r in the expansion of $\frac{(1-2x)^2}{(1+x)^3}$.

The expression $= (1-4x+4x^2)\,(1+p_1x+p_2x^2+\ldots+p_rx^r+\ldots)$ suppose.

The coefficient of x^r will be obtained by multiplying p_r, p_{r-1}, p_{r-2} by 1, 4, 4 respectively, and adding the results; hence

$$\text{the required coefficient} = p_r - 4p_{r-1} + 4p_{r-2}.$$

But $$p_r = (-1)^r \frac{(r+1)\,(r+2)}{2}. \qquad \text{[Ex. 3, Art. 182.]}$$

Hence the required coefficient

$$= (-1)^r \frac{(r+1)\,(r+2)}{2} - 4\,(-1)^{r-1} \frac{r\,(r+1)}{2} + 4\,(-1)^{r-2} \frac{(r-1)\,r}{2}$$

$$= \frac{(-1)^r}{2}[(r+1)\,(r+2) + 4r\,(r+1) + 4r\,(r-1)]$$

$$= \frac{(-1)^r}{2}\,(9r^2+3r+2).$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

4. Find the coefficient of x^n in the expansion of $\dfrac{2+x+x^2}{(1+x)^3}$.

5. Prove that

$$1-\frac{1}{2}\cdot\frac{1}{2}+\frac{1.3}{2.4}\cdot\frac{1}{2^2}-\frac{1.3.5}{2.4.6}\cdot\frac{1}{2^3}+\frac{1.3.5.7}{2.4.6.8}\cdot\frac{1}{2^4}-\ldots=\sqrt{\frac{2}{3}}.$$

6. Prove that

$$\sqrt{8}=1+\frac{3}{4}+\frac{3.5}{4.8}+\frac{3.5.7}{4.8.12}+\ldots\ldots$$

7. Prove that

$$1+\frac{2n}{3}+\frac{2n(2n+2)}{3.6}+\frac{2n(2n+2)(2n+4)}{3.6.9}+\ldots\ldots$$

$$=2^n\left\{1+\frac{n}{3}+\frac{n(n+1)}{3.6}+\frac{n(n+1)(n+2)}{3.6.9}+\ldots\ldots\right\}.$$

8. Prove that

$$7^n\left\{1+\frac{n}{7}+\frac{n(n-1)}{7.14}+\frac{n(n-1)(n-2)}{7.14.21}+\ldots\ldots\right\}$$

$$=4^n\left\{1+\frac{n}{2}+\frac{n(n+1)}{2.4}+\frac{n(n+1)(n+2)}{2.4.6}+\ldots\ldots\right\}.$$

9. Prove that approximately, when x is very small,

$$\frac{3\left(x+\frac{4}{9}\right)^{\frac{1}{2}}\left(1-\frac{3}{4}x^2\right)^{\frac{1}{3}}}{2\left(1+\frac{9}{16}x\right)^2}=1-\frac{307}{256}x^2.$$

10. Shew that the integral part of $(5+2\sqrt{6})^n$ is odd, if n be a positive integer.

11. Shew that the integral part of $(8+3\sqrt{7})^n$ is odd, if n be a positive integer.

12. Find the coefficient of x^n in the expansion of

$$(1-2x+3x^2-4x^3+\ldots\ldots)^{-n}.$$

13. Shew that the middle term of $\left(x+\dfrac{1}{x}\right)^{4n}$ is equal to the coefficient of x^n in the expansion of $(1-4x)^{-\left(n+\frac{1}{2}\right)}$

14. Prove that the expansion of $(1-x^3)^n$ may be put into the form

$$(1-x)^{3n}+3nx(1-x)^{3n-2}+\frac{3n(3n-3)}{1.2}x^2(1-x)^{3n-4}+\ldots\ldots$$

15. Prove that the coefficient of x^n in the expansion $\frac{1}{1+x+x^2}$ is $1, 0, -1$ according as n is of the form $3m$, $3m-1$, or $3m+1$.

16. In the expansion of $(a+b+c)^8$ find (1) the number of terms, (2) the sum of the coefficients of the terms.

17. Prove that if n be an even integer,

$$\frac{1}{\lfloor 1 \lfloor n-1} + \frac{1}{\lfloor 3 \lfloor n-3} + \frac{1}{\lfloor 5 \lfloor n-5} + \ldots\ldots + \frac{1}{\lfloor n-1 \lfloor 1} = \frac{2^{n-1}}{\lfloor n}.$$

18. If $c_0, c_1, c_2, \ldots\ldots c_n$ are the coefficients in the expansion of $(1+x)^n$, when n is a positive integer, prove that

(1) $$c_0 - c_1 + c_2 - c_3 + \ldots\ldots + (-1)^r c_r = (-1)^r \frac{\lfloor n-1}{\lfloor r \lfloor n-r-1}.$$

(2) $$c_0 - 2c_1 + 3c_2 - 4c_3 + \ldots\ldots + (-1)^n (n+1) c_n = 0.$$

(3) $${c_0}^2 - {c_1}^2 + {c_2}^2 - {c_3}^2 + \ldots\ldots + (-1)^n {c_n}^2 = 0, \text{ or } (-1)^{\frac{n}{2}} c_{\frac{n}{2}},$$

according as n is odd or even.

19. If s_n denote the sum of the first n natural numbers, prove that

(1) $$(1-x)^{-3} = s_1 + s_2 x + s_3 x^2 + \ldots\ldots + s_n x^{n-1} + .$$

(2) $$2(s_1 s_{2n} + s_2 s_{2n-1} + \ldots\ldots + s_n s_{n+1}) = \frac{\lfloor 2n+4}{\lfloor 5 \lfloor 2n-1}.$$

20. If $q_n = \frac{1 \cdot 3 \cdot 5 \cdot 7 \ldots\ldots (2n-1)}{2 \cdot 4 \cdot 6 \cdot 8 \ldots\ldots 2n}$, prove that

(1) $$q_{2n+1} + q_1 q_{2n} + q_2 q_{2n-1} + \ldots\ldots + q_{n-1} q_{n+2} + q_n q_{n+1} - \frac{1}{2}.$$

(2) $$2\{q_{2n} - q_1 q_{2n-1} + q_2 q_{2n-2} + \ldots\ldots + (-1)^{n-1} q_{n-1} q_{n+1}\} = q_n + (-1)^{n-1} {q_n}^2.$$

21. Find the sum of the products, two at a time, of the coefficients in the expansion of $(1+x)^n$, when n is a positive integer.

22. If $(7+4\sqrt{3})^n = p+\beta$, where n and p are positive integers, and β a proper fraction, shew that $(1-\beta)(p+\beta) = 1$.

23. If $c_0, c_1, c_2, \ldots\ldots c_n$ are the coefficients in the expansion of $(1+x)^n$, where n is a positive integer, shew that

$$c_1 - \frac{c_2}{2} + \frac{c_3}{3} - \ldots\ldots + \frac{(-1)^{n-1} c_n}{n} = 1 + \frac{1}{2} + \frac{1}{3} + \ldots\ldots + \frac{1}{n}$$

CHAPTER XV.

MULTINOMIAL THEOREM.

194. WE have already seen in Art. 175, how we may apply the Binomial Theorem to obtain the expansion of a multinomial expression. In the present chapter our object is not so much to obtain the complete expansion of a multinomial as to find the coefficient of any assigned term.

Example. Find the coefficient of $a^4b^2c^3d^5$ in the expansion of

$$(a+b+c+d)^{14}$$

The expansion is the product of 14 factors each equal to $a+b+c+d$, and every term in the expansion is of 14 dimensions, being a product formed by taking one letter out of each of these factors. Thus to form the term $a^4b^2c^3d^5$, we take a out of any *four* of the fourteen factors, b out of any *two* of the remaining ten, c out of any *three* of the remaining eight. But the number of ways in which this can be done is clearly equal to the number of ways of arranging 14 letters when four of them must be a, two b, three c, and five d; that is, equal to

$$\frac{\lfloor 14}{\lfloor 4 \lfloor 2 \lfloor 3 \lfloor 5}. \qquad \text{[Art. 151.]}$$

This is therefore the number of times in which the term $a^4b^2c^3d^5$ appears in the final product, and consequently the coefficient required is 2522520.

195. *To find the coefficient of any assigned term in the expansion* of $(a+b+c+d+\ldots)^p$, *where* p *is a positive integer.*

The expansion is the product of p factors each equal to $a+b+c+d+\ldots$, and every term in the expansion is formed by taking one letter out of each of these p factors; and therefore the number of ways in which any term $a^\alpha b^\beta c^\gamma d^\delta \ldots$ will appear in the final product is equal to the number of ways of arranging p letters when α of them must be a, β must be b, γ must be c; and so on. That is,

the coefficient of $a^\alpha b^\beta c^\gamma d^\delta \ldots$ is $\dfrac{\lfloor p}{\lfloor \alpha \lfloor \beta \lfloor \gamma \lfloor \delta \ldots}$,

where $\alpha + \beta + \gamma + \delta + \ldots = p$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

And, by Art. 195, the general term of the expansion of

$$(bx + cx^2 + dx^3 + \ldots)^p$$

is $$\frac{\lfloor p}{\lfloor\beta \lfloor\gamma \lfloor\delta \ldots} b^\beta c^\gamma d^\delta \ldots x^{\beta+2\gamma+3\delta+\ldots},$$

where β, γ, δ ... are positive integers whose sum is p.

Hence the general term in the expansion of the given expression is

$$\frac{n(n-1)(n-2)\ldots(n-p+1)}{\lfloor\beta \lfloor\gamma \lfloor\delta \ldots} a^{n-p} b^\beta c^\gamma d^\delta \ldots x^{\beta+2\gamma+3\delta+\ldots},$$

where $$\beta + \gamma + \delta + \ldots = p.$$

197. Since $(a + bx + cx^2 + dx^3 + \ldots)^n$ may be written in the form

$$a^n \left(1 + \frac{b}{a}x + \frac{c}{a}x^2 + \frac{d}{a}x^3 + \ldots\right)^n,$$

it will be sufficient to consider the case in which the first term of the multinomial is unity.

Thus the general term of

$$(1 + bx + cx^2 + dx^3 + \ldots)^n$$

is $$\frac{n(n-1)(n-2)\ldots(n-p+1)}{\lfloor\beta \lfloor\gamma \lfloor\delta} b^\beta c^\gamma d^\delta \ldots x^{\beta+2\gamma+3\delta+} \quad ,$$

where $$\beta + \gamma + \delta + \ldots = p.$$

Example. Find the coefficient of x^3 in the expansion of

$$(1 - 3x - 2x^2 + 6x^3)^{\frac{2}{3}}.$$

The general term is

$$\frac{\frac{2}{3}\left(\frac{2}{3}-1\right)\left(\frac{2}{3}-2\right)\ldots\left(\frac{2}{3}-p+1\right)}{\lfloor\beta \lfloor\gamma \lfloor\delta} (-3)^\beta (-2)^\gamma (6)^\delta x^{\beta+2\gamma+3\delta} \qquad (1).$$

We have to obtain by trial all the positive integral values of β, γ, δ which satisfy the equation $\beta + 2\gamma + 3\delta = 3$; and then p is found from the equation $p = \beta + \gamma + \delta$. The required coefficient will be the sum of the corresponding values of the expression (1).

In finding β, γ, δ, ... it will be best to commence by giving to δ successive integral values beginning with the greatest admissible. In the present case the values are found to be

$$\delta=1, \quad \gamma=0, \quad \beta=0, \quad p=1;$$
$$\delta=0, \quad \gamma=1, \quad \beta=1, \quad p=2;$$
$$\delta=0, \quad \gamma=0, \quad \beta=3, \quad p=3.$$

Substituting these values in (1) the required coefficient

$$= \binom{2}{3}(6) + \binom{2}{3}\binom{-1}{3}(-3)(-2) + \frac{\frac{2}{3}\left(-\frac{1}{3}\right)\left(-\frac{4}{3}\right)}{\underline{|3}}(-3)^3$$
$$= 4 - \frac{4}{3} - \frac{4}{3} = \frac{4}{3}.$$

198. Sometimes it is more expeditious to use the Binomial Theorem.

Example. Find the coefficient of x^4 in the expansion of $(1-2x+3x^2)^{-3}$.

The required coefficient is found by picking out the coefficient of x^4 from the first few terms of the expansion of $(1-2x-3x^2)^{-3}$ by the Binomial Theorem; that is, from

$$1+3(2x-3x^2)+6(2x-3x^2)^2+10(2x-3x^2)^3+15(2x-3x^2)^4;$$

we stop at this term for all the other terms involve powers of x higher than x^4.

The required coefficient $= 6 \,.\, 9 + 10 \,.\, 3\,(2)^2(-3) + 15\,(2)^4$
$$= -66.$$

EXAMPLES. XV.

Find the coefficient of

1. $a^2b^3c^4d$ in the expansion of $(a-b-c+d)^{10}$
2. a^2b^5d in the expansion of $(a+b-c-d)^8$.
3. a^3b^3c in the expansion of $(2a+b+3c)^7$.
4. $x^2y^3z^4$ in the expansion of $(ax-by+cz)^9$
5. x^3 in the expansion of $(1+3x-2x^2)^3$.
6. x^4 in the expansion of $(1+2x+3x^2)^{10}$.
7. x^6 in the expansion of $(1+2x-x^2)^5$.
8. x^8 in the expansion of $(1-2x+3x^2-4x^3)^4$.

Find the coefficient of

9. x^{23} in the expansion of $(1-2x+3x^2-x^4-x^5)^5$

10. x^5 in the expansion of $(1-2x+3x^2)^{-\frac{1}{2}}$

11. x^3 in the expansion of $(1-2x+3x^2-4x^3)^{\frac{1}{2}}$

12. x^8 in the expansion of $\left(1-\frac{x^2}{3}+\frac{x^4}{9}\right)^{-2}$.

13. x^4 in the expansion of $(2-4x+3x^2)^{-2}$

14. x^6 in the expansion of $(1+4x^2+10x^4+20x^6)^{\frac{3}{4}}$

15. x^{12} in the expansion of $(3-15x^3+18x^6)^{-1}$

16. Expand $(1-2x-2x^2)^{\frac{1}{4}}$ as far as x^2.

17. Expand $(1+3x^2-6x^3)^{-\frac{2}{3}}$ as far as x^5.

18. Expand $(8-9x^3+18x^4)^{\frac{4}{3}}$ as far as x^8.

19. If $(1+x+x^2+\ldots\ldots+x^p)^n=a_0+a_1x+a_2x^2+\quad a_{np}x^{np}$,

prove that

(1) $a_0+a_1+a_2+\ldots\ldots+a_{np}=(p+1)^n$.

(2) $a_1+2a_2+3a_3+\ldots\ldots+np\,.\,a_{np}=\frac{1}{2}np\,(p+1)^n$.

20. If a_0, a_1, a_2, a_3 ... are the coefficients in order of the expansion of $(1+x+x^2)^n$, prove that

$$a_0^2-a_1^2+a_2^2-a_3^2+\ldots\ldots+(-1)^{n-1}a_{n-1}^2=\frac{1}{2}a_n\{1-(-1)^n a_n\}.$$

21. If the expansion of $(1+x+x^2)^n$

be $\qquad a_0+a_1x+a_2x^2+\ldots+a_rx^r+\ldots+a_{2n}x^{2n}$,

shew that

$$a_0+a_3+a_6+\ldots-a_1+a_4+a_7+\ldots-a_2+a_5+a_8+\ldots-3^{n-1}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

201. When it is understood that a particular system of logarithms is in use, the suffix denoting the base is omitted. Thus in arithmetical calculations in which 10 is the base, we usually write $\log 2$, $\log 3$,..... instead of $\log_{10} 2$, $\log_{10} 3$,.....

Any number might be taken as the base of logarithms, and corresponding to any such base a system of logarithms of all numbers could be found. But before discussing the logarithmic systems commonly used, we shall prove some general propositions which are true for all logarithms independently of any particular base.

202. *The logarithm of* 1 *is* 0.

For $a^0 = 1$ for all values of a; therefore $\log 1 = 0$, whatever the base may be.

203. *The logarithm of the base itself is* 1.

For $a^1 = a$; therefore $\log_a a = 1$.

204. *To find the logarithm of a product.*

Let MN be the product; let a be the base of the system, and suppose

$$x = \log_a M, \qquad y = \log_a N;$$

so that $$a^x = M, \qquad a^y = N.$$

Thus the product $$MN = a^x \times a^y$$

$$= a^{x+y};$$

whence, by definition, $$\log_a MN = x + y$$

$$= \log_a M + \log_a N.$$

Similarly, $\log_a MNP = \log_a M + \log_a N + \log_a P$;

and so on for any number of factors.

Example. $$\log 42 = \log (2 \times 3 \times 7)$$

$$= \log 2 + \log 3 + \log 7.$$

205. *To find the logarithm of a fraction.*

Let $\frac{M}{N}$ be the fraction, and suppose

$$x = \log_a M, \qquad y = \log_a N;$$

so that $$a^x = M, \qquad a^y = N.$$

Thus the fraction $$\frac{M}{N} = \frac{a^x}{a^y}$$

$$= a^{x-y};$$

whence, by definition, $$\log_a \frac{M}{N} = x - y$$

$$= \log_a M - \log_a N.$$

Example. $$\log\left(4\tfrac{2}{7}\right) = \log \frac{30}{7}$$

$$= \log 30 - \log 7$$

$$= \log (2 \times 3 \times 5) - \log 7$$

$$= \log 2 + \log 3 + \log 5 - \log 7.$$

206. *To find the logarithm of a number raised to any power, integral or fractional.*

Let $\log_a(M^p)$ be required, and suppose

$$x = \log_a M, \text{ so that } a^x = M;$$

then $$M^p = (a^x)^p$$

$$= a^{px};$$

whence, by definition, $$\log_a(M^p) = px;$$

that is, $$\log_a(M^p) = p \log_a M.$$

Similarly, $$\log_a(M^{\frac{1}{r}}) = \frac{1}{r} \log_a M.$$

207. It follows from the results we have proved that

(1) the logarithm of a product is equal to the sum of the logarithms of its factors;

(2) the logarithm of a fraction is equal to the logarithm of the numerator diminished by the logarithm of the denominator;

(3) the logarithm of the p^{th} power of a number is p times the logarithm of the number;

(4) the logarithm of the r^{th} root of a number is equal to $\frac{1}{r}$-th of the logarithm of the number.

Also we see that by the use of logarithms the operations of multiplication and division may be replaced by those of addition and subtraction; and the operations of involution and evolution by those of multiplication and division.

Example 1. Express the logarithm of $\frac{\sqrt{a^3}}{c^5b^2}$ in terms of $\log a$, $\log b$ and $\log c$.

$$\log \frac{\sqrt{a^3}}{c^5b^2} - \log \frac{a^{\frac{3}{2}}}{c^5b^2}$$

$$= -\log a^{\frac{3}{2}} - \log (c^5b^2)$$

$$= \frac{3}{2}\log a - (\log c^5 + \log b^2)$$

$$= \frac{3}{2}\log a - 5\log c - 2\log b.$$

Example 2. Find x from the equation $a^x \cdot c^{-2x} = b^{3x+1}$

Taking logarithms of both sides, we have

$$x\log a - 2x\log c = (3x+1)\log b;$$

$$\therefore\ x(\log a - 2\log c - 3\log b) = \log b;$$

$$\therefore\ x = \frac{\log b}{\log a - 2\log c - 3\log b}.$$

EXAMPLES. XVI. a.

Find the logarithms of

1. 16 to base $\sqrt{2}$, and 1728 to base $2\sqrt{3}$.
2. 125 to base $5\sqrt{5}$, and $\cdot 25$ to base 4.
3. $\frac{1}{256}$ to base $2\sqrt{2}$, and $\cdot\dot{3}$ to base 9.
4. $\cdot 0625$ to base 2, and 1000 to base $\cdot 01$.
5. $\cdot 0001$ to base $\cdot 001$, and $\cdot\dot{1}$ to base $9\sqrt{3}$.
6. $\sqrt[4]{a^{\frac{8}{5}}}$, $\frac{1}{a^{\frac{1}{2}}}$, $\sqrt[3]{a^{-\frac{15}{2}}}$ to base a.
7. Find the value of

$$\log_8 128,\quad \log_6 \frac{1}{216},\quad \log_{27} \frac{1}{81},\quad \log_{343} 49.$$

Express the following seven logarithms in terms of $\log a$, $\log b$, and $\log c$.

8. $\log(\sqrt{a^2b^3})^6$.
9. $\log(\sqrt[3]{a^2} \times \sqrt[2]{b^3})$.
10. $\log(\sqrt[9]{a^{-4}b^3})$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Again, $$\cdot 06 > 10^{-2} \text{ and } < 10^{-1};$$

$$\therefore \log \cdot 06 = -2 + \text{a fraction}.$$

209. DEFINITION. The integral part of a logarithm is called the **characteristic**, and the decimal part is called the **mantissa.**

The characteristic of the logarithm of any number to the base 10 can be written down by inspection, as we shall now shew.

210. *To determine the characteristic of the logarithm of any number greater than unity.*

Since $$10^1 = 10,$$

$$10^2 = 100,$$

$$10^3 = 1000,$$

it follows that a number with two digits in its integral part lies between 10^1 and 10^2; a number with three digits in its integral part lies between 10^2 and 10^3; and so on. Hence a number with n digits in its integral part lies between 10^{n-1} and 10^n

Let N be a number whose integral part contains n digits; then

$$N = 10^{(n-1)+\text{a fraction}};$$

$$\therefore \log N = (n-1) + \text{a fraction}.$$

Hence the characteristic is $n-1$; that is, *the characteristic of the logarithm of a number greater than unity is less by one than the number of digits in its integral part, and is positive.*

211. *To determine the characteristic of the logarithm of a decimal fraction.*

Since $$10^0 = 1,$$

$$10^{-1} = \frac{1}{10} = \cdot 1,$$

$$10^{-2} = \frac{1}{100} = \cdot 01,$$

$$10^{-3} = \frac{1}{1000} = \cdot 001,$$

it follows that a decimal with one cipher immediately after the decimal point, such as ·0324, being greater than ·01 and less than ·1, lies between 10^{-2} and 10^{-1}; a number with two ciphers after the decimal point lies between 10^{-3} and 10^{-2}; and so on. Hence a decimal fraction with n ciphers immediatelv after the decimal point lies between $10^{-(n+1)}$ and 10^{-n}

Let D be a decimal beginning with n ciphers; then

$$D = 10^{-(n+1)\,+\,\text{a fraction}};$$

$$\therefore\ \log D = -(n+1) + \text{a fraction}.$$

Hence the characteristic is $-(n+1)$; that is, *the characteristic of the logarithm of a decimal fraction is greater by unity than the number of ciphers immediately after the decimal point, and is negative.*

212. The logarithms to base 10 of all integers from 1 to 200000 have been found and tabulated; in most Tables they are given to seven places of decimals. This is the system in practical use, and it has two great advantages:

(1) From the results already proved it is evident that the characteristics can be written down by inspection, so that only the mantissæ have to be registered in the Tables.

(2) The mantissæ are the same for the logarithms of all numbers which have the same significant digits; so that it is sufficient to tabulate the mantissæ of the logarithms of *integers*.

This proposition we proceed to prove.

213. Let N be any number, then since multiplying or dividing by a power of 10 merely alters the position of the decimal point without changing the sequence of figures, it follows that $N \times 10^p$, and $N \div 10^q$, where p and q are any integers, are numbers whose significant digits are the same as those of N.

$$\text{Now} \qquad \log(N \times 10^p) = \log N + p \log 10$$
$$= \log N + p \qquad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

$$\text{Again,} \quad \log(N \div 10^q) = \log N - q \log 10$$
$$- \log N - q \qquad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

In (1) an integer is added to $\log N$, and in (2) an integer is subtracted from $\log N$; that is, the mantissa or decimal portion of the logarithm remains unaltered.

In this and the three preceding articles the mantissæ have been supposed positive. In order to secure the advantages of Briggs' system, we arrange our work so as *always to keep the mantissa positive*, so that when the mantissa of any logarithm has been taken from the Tables the characteristic is prefixed with its appropriate sign according to the rules already given.

214. In the case of a negative logarithm the minus sign is written *over the characteristic*, and not before it, to indicate that the characteristic alone is negative, and not the whole expression. Thus $4\cdot30103$, the logarithm of $\cdot0002$, is equivalent to $-4+\cdot30103$, and must be distinguished from $-4\cdot30103$, an expression in which both the integer and the decimal are negative. In working with negative logarithms an arithmetical artifice will sometimes be necessary in order to make the mantissa positive. For instance, a result such as $-3\cdot69897$, in which the whole expression is negative, may be transformed by subtracting 1 from the characteristic and adding 1 to the mantissa. Thus

$$3\cdot69897 = -4+(1-\cdot69897) = 4\cdot30103.$$

Other cases will be noticed in the Examples.

Example 1. Required the logarithm of $\cdot0002432$.

In the Tables we find that 3859636 is the mantissa of $\log 2432$ (the decimal point as well as the characteristic being omitted); and, by Art. 211, the characteristic of the logarithm of the given number is -4;

$$\therefore\ \log \cdot0002432 = \bar{4}\cdot3859636.$$

Example 2. Find the value of $\sqrt[5]{\cdot00000165}$, given

$$\log 165 = 2\cdot2174839,\ \log 697424 = 5\cdot8434968.$$

Let x denote the value required; then

$$\log x = \log (\cdot00000165)^{\frac{1}{5}} = \frac{1}{5}\log (\cdot00000165)$$

$$-\frac{1}{5}(6\cdot2174839);$$

the *mantissa* of $\log \cdot00000165$ being the same as that of $\log 165$, and the *characteristic* being prefixed by the rule.

Now
$$\frac{1}{5}(\overline{6}\cdot2174839) = \frac{1}{5}(\overline{10}+4\cdot2174839)$$

$$= 2\cdot8434968$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

This result may also be proved directly as follows:

Let $$x = \log_a b, \text{ so that } a^x = b;$$

then by taking logarithms to base b, we have

$$x \log_b a = \log_b b$$

$$= 1;$$

$$\log_a b \times \log_b a = 1.$$

218. The following examples will illustrate the utility of logarithms in facilitating arithmetical calculation; but for information as to the use of Logarithmic Tables the reader is referred to works on Trigonometry.

Example 1. Given $\log 3 = \cdot 4771213$, find $\log \{(2\cdot7)^3 \times (\cdot81)^{\frac{4}{5}} \div (90)^{\frac{5}{4}}\}$.

$$\text{The required value} = 3 \log \frac{27}{10} + \frac{4}{5} \log \frac{81}{100} - \frac{5}{4} \log 90$$

$$= 3 (\log 3^3 - 1) + \frac{4}{5} (\log 3^4 - 2) - \frac{5}{4} (\log 3^2 + 1)$$

$$- \left(9 + \frac{16}{5} - \frac{5}{2}\right) \log 3 - \left(3 + \frac{8}{5} + \frac{5}{4}\right)$$

$$= \frac{97}{10} \log 3 - 5\tfrac{17}{20}$$

$$- 4\cdot6280766 - 5\cdot85$$

$$= \bar{2}\cdot7780766.$$

The student should notice that the logarithm of 5 and its powers can always be obtained from $\log 2$; thus

$$\log 5 = \log \frac{10}{2} - \log 10 - \log 2 = 1 - \log 2.$$

Example 2. Find the number of digits in 875^{16}, given

$$\log 2 = \cdot3010300, \log 7 = \cdot8450980.$$

$$\log (875^{16}) = 16 \log (7 \times 125)$$

$$= 16 (\log 7 + 3 \log 5)$$

$$- 16 (\log 7 + 3 - 3 \log 2)$$

$$- 16 \times 2\cdot9420080$$

$$- 47\cdot072128;$$

hence the number of digits is 48. [Art. 210.]

Example 3. Given $\log 2$ and $\log 3$, find to two places of decimals the value of x from the equation

$$6^{3-4x} \cdot 4^{x+5} = 8.$$

Taking logarithms of both sides, we have

$$(3-4x)\log 6 + (x+5)\log 4 = \log 8;$$

$$\therefore\ (3-4x)(\log 2 + \log 3) + (x+5)\,2\log 2 = 3\log 2;$$

$$x(-4\log 2 - 4\log 3 + 2\log 2) = 3\log 2 - 3\log 2 - 3\log 3 \quad 10\log 2;$$

$$\therefore\ x = \frac{10\log 2 + 3\log 3}{2\log 2 + 4\log 3}$$

$$= \frac{4{\cdot}4416639}{2{\cdot}5105452}$$

$$-1{\cdot}77$$

EXAMPLES. XVI. b.

1. Find, by inspection, the characteristics of the logarithms of 21735, 23·8, 350, ·035, ·2, ·87, ·875.

2. The mantissa of $\log 7623$ is ·8821259; write down the logarithms of 7·623, 762·3, ·007623, 762300, ·000007623.

3. How many digits are there in the integral part of the numbers whose logarithms are respectively

4·30103, 1·4771213, 3·69897, ·56515?

4. Give the position of the first significant figure in the numbers whose logarithms are

2·7781513, ·6910815, 5·4871384.

Given $\log 2 = {\cdot}3010300$, $\log 3 = {\cdot}4771213$, $\log 7 = {\cdot}8450980$, find the value of

5. $\log 64$. **6.** $\log 84$. **7.** $\log {\cdot}128$.

8. $\log {\cdot}0125$. **9.** $\log 14{\cdot}4$. **10.** $\log 4\frac{2}{3}$.

11. $\log \sqrt[3]{12}$. **12.** $\log \sqrt{\frac{35}{27}}$. **13.** $\log \sqrt[4]{{\cdot}0105}$.

14. Find the seventh root of ·00324, having given that

$$\log 44092388 = 7{\cdot}6443636.$$

15. Given $\log 194{\cdot}8445 = 2{\cdot}2896883$, find the eleventh root of $(39{\cdot}2)^2$.

16. Find the product of 37·203, 3·7203, ·0037203, 372030, having given that

$$\log 37{\cdot}203 = 1{\cdot}5705780, \text{ and } \log 1915631 = 6{\cdot}2823120.$$

17. Given $\log 2$ and $\log 3$, find $\log \sqrt[3]{\left(\frac{3^2 5^4}{\sqrt{2}}\right)}$.

18. Given $\log 2$ and $\log 3$, find $\log (\sqrt[3]{48} \times 108^{\frac{1}{4}} \div \sqrt[12]{6})$.

19. Calculate to six decimal places the value of

$$\sqrt[3]{\left(\frac{294 \times 125}{42 \times 32}\right)^2};$$

given $\log 2$, $\log 3$, $\log 7$; also $\log 9076{\cdot}226 = 3{\cdot}9579053$.

20. Calculate to six places of decimals the value of

$$(330 \div 49)^4 \div \sqrt[3]{22 \times 70};$$

given $\log 2$, $\log 3$, $\log 7$; also

$$\log 11 = 1{\cdot}0413927, \text{ and } \log 17814{\cdot}1516 = 4{\cdot}2507651.$$

21. Find the number of digits in $3^{12} \times 2^8$.

22. Shew that $\left(\frac{21}{20}\right)^{100}$ is greater than 100.

23. Determine how many ciphers there are between the decimal point and the first significant digit in $\left(\frac{1}{2}\right)^{1000}$

Solve the following equations, having given $\log 2$, $\log 3$, and $\log 7$.

24. $3^{x-2} = 5$.

25. $5^x = 10^3$.

26. $5^{5-3x} - 2^{x+2}$

27. $21^x = 2^{2x+1} \cdot 5^x$.

28. $2^x \cdot 6^{x-2} = 5^{2x} \cdot 7^{1-x}$

29.
$$\left.\begin{aligned} 2^{x+y} &= 6^y \\ 3^x &= 3 \cdot 2^{y+1} \end{aligned}\right\}.$$

30.
$$\left.\begin{aligned} 3^{1-x-y} &= 4^{-y} \\ 2^{2x-1} &= 3^{3y-x} \end{aligned}\right\}.$$

31. Given $\log_{10} 2 = {\cdot}30103$, find $\log_{25} 200$.

32. Given $\log_{10} 2 = {\cdot}30103$, $\log_{10} 7 = {\cdot}84509$, find $\log_7 \sqrt{2}$ and $\log_{\sqrt{2}} 7$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

hence the series (1) is the x^{th} power of the series (2); that is,

$$1+x+\frac{x\left(x-\frac{1}{n}\right)}{\lfloor 2}+\frac{x\left(x-\frac{1}{n}\right)\left(x-\frac{2}{n}\right)}{\lfloor 3}+\ldots\ldots$$
$$=\left\{1+1+\frac{1-\frac{1}{n}}{\lfloor 2}+\frac{\left(1-\frac{1}{n}\right)\left(1-\frac{2}{n}\right)}{\lfloor 3}+\ldots\right\}^{x};$$

and this is true however great n may be. If therefore n be indefinitely increased we have

$$1+x+\frac{x^2}{\lfloor 2}+\frac{x^3}{\lfloor 3}+\frac{x^4}{\lfloor 4}+\quad\ldots=\left(1+1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 3}+\frac{1}{\lfloor 4}+\quad\ldots\right)^{x}.$$

The series $\quad 1+1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 3}+\frac{1}{\lfloor 4}+\ldots$

is usually denoted by e; hence

$$e^x=1+x+\frac{x^2}{\lfloor 2}+\frac{x^3}{\lfloor 3}+\frac{x^4}{\lfloor 4}+$$

Write cx for x, then

$$e^{cx}=1+cx+\frac{c^2x^2}{\lfloor 2}+\frac{c^3x^3}{\lfloor 3}+\ldots\ldots.$$

Now let $e^c=a$, so that $c=\log_e a$; by substituting for c we obtain

$$a^x=1+x\log_e a+\frac{x^2(\log_e a)^2}{\lfloor 2}+\frac{x^3(\log_e a)^3}{\lfloor 3}+\ldots\ldots.$$

This is the *Exponential Theorem.*

Cor. When n is infinite, the *limit* of $\left(1+\frac{1}{n}\right)^n=e$.

[See Art. 266.]

Also as in the preceding investigation, it may be shewn that when n is indefinitely increased,

$$\left(1+\frac{x}{n}\right)^n=1+x+\frac{x^2}{\lfloor 2}+\frac{x^3}{\lfloor 3}+\frac{x^4}{\lfloor 4}+\quad;$$

that is, when n is infinite, the limit of $\left(1+\frac{x}{n}\right)^n = e^x$.

By putting $\frac{x}{n} = -\frac{1}{m}$, we have

$$\left(1-\frac{x}{n}\right)^n = \left(1+\frac{1}{m}\right)^{-mx} = \left\{\left(1+\frac{1}{m}\right)^m\right\}^{-x}.$$

Now m is infinite when n is infinite;

thus the limit of $\left(1-\frac{x}{n}\right)^n = e^{-x}$.

Hence the limit of $\left(1-\frac{1}{n}\right)^n = e^{-1}$.

221. In the preceding article no restriction is placed upon the value of x; also since $\frac{1}{n}$ is less than unity, the expansions we have used give results arithmetically intelligible. [Art. 183.]

But there is another point in the foregoing proof which deserves notice. We have assumed that when n is infinite

the limit of $\dfrac{x\left(x-\frac{1}{n}\right)\left(x-\frac{2}{n}\right)\ldots\left(x-\frac{r-1}{n}\right)}{\lfloor r}$ is $\frac{x^r}{\lfloor r}$

for all values of r.

Let us denote the value of

$$\frac{x\left(x-\frac{1}{n}\right)\left(x-\frac{2}{n}\right)\ldots\left(x-\frac{r-1}{n}\right)}{\lfloor r}$$ by u_r.

Then $$\frac{u_r}{u_{r-1}} = \frac{1}{r}\left(x-\frac{r-1}{n}\right) = \frac{x}{r} - \frac{1}{n} + \frac{1}{nr}.$$

Since n is infinite, we have

$$\frac{u_r}{u_{r-1}} = \frac{x}{r};\ \text{that is, } u_r = \frac{x}{r}u_{r-1}.$$

It is clear that the limit of u_2 is $\frac{x^2}{\lfloor 2}$; hence the limit of u_3 is $\frac{x^3}{\lfloor 3}$; that of u_4 is $\frac{x^4}{\lfloor 4}$; and generally that of u_r is $\frac{x^r}{\lfloor r}$.

222. The series

$$1+1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 3}+\frac{1}{\lfloor 4}+\quad ,$$

which we have denoted by e, is very important as it is the base to which logarithms are first calculated. Logarithms to this base are known as the Napierian system, so named after Napier their inventor. They are also called *natural* logarithms from the fact that they are the first logarithms which naturally come into consideration in algebraical investigations.

When logarithms are used in theoretical work it is to be remembered that the base e is always understood, just as in arithmetical work the base 10 is invariably employed.

From the series the approximate value of e can be determined to any required degree of accuracy; to 10 places of decimals it is found to be 2·7182818284.

Example 1. Find the sum of the infinite series

$$1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 4}+\frac{1}{\lfloor 6}+\ldots\ldots$$

We have $$e=1+1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 3}+\frac{1}{\lfloor 4}+\ldots\ldots;$$

and by putting $x=-1$ in the series for e^x,

$$e^{-1}=1-1+\frac{1}{\lfloor 2}-\frac{1}{\lfloor 3}+\frac{1}{\lfloor 4}-\ldots\ldots.$$

$$\therefore\quad e+e^{-1}=2\left(1+\frac{1}{\lfloor 2}+\frac{1}{\lfloor 4}+\frac{1}{\lfloor 6}+\ldots\ldots\right);$$

hence the sum of the series is $\frac{1}{2}(e+e^{-1})$.

Example 2. Find the coefficient of x^r in the expansion of $\frac{1-ax-x^2}{e^x}$.

$$\frac{1-ax-x^2}{e^x}=(1-ax-x^2)\,e^{-x}$$

$$=(1-ax-x^2)\left\{1-x+\frac{x^2}{\lfloor 2}-\frac{x^3}{\lfloor 3}+\ldots+\frac{(-1)^r x^r}{\lfloor r}+\ldots\ldots\right\}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

224. Except when x is very small the series for $\log_e(1+x)$ is of little use for numerical calculations. We can, however, deduce from it other series by the aid of which Tables of Logarithms may be constructed.

By writing $\frac{1}{n}$ for x we obtain $\log_e \frac{n+1}{n}$; hence

$$\log_e(n+1) - \log_e n = \frac{1}{n} - \frac{1}{2n^2} + \frac{1}{3n^3} - \ldots\ldots\ldots\ldots(1).$$

By writing $-\frac{1}{n}$ for x we obtain $\log_e \frac{n-1}{n}$; hence, by changing signs on both sides of the equation,

$$\log_e n - \log_e(n-1) = \frac{1}{n} + \frac{1}{2n^2} + \frac{1}{3n^3} + \ldots\ldots\ldots\ldots (2).$$

From (1) and (2) by addition,

$$\log_e(n+1) - \log_e(n-1) = 2\left(\frac{1}{n} + \frac{1}{3n^3} + \frac{1}{5n^5} + \ldots\right) \ldots\ldots(3).$$

From this formula by putting $n=3$ we obtain $\log_e 4 - \log_e 2$, that is $\log_e 2$; and by effecting the calculation we find that the value of $\log_e 2 = \cdot 69314718\ldots$; whence $\log_e 8$ is known.

Again by putting $n=9$ we obtain $\log_e 10 - \log_e 8$; whence we find $\log_e 10 = 2\cdot 30258509\ldots.$

To convert Napierian logarithms into logarithms to base 10 we multiply by $\frac{1}{\log_e 10}$, which is the *modulus* [Art. 216] of the common system, and its value is $\frac{1}{2\cdot 30258509\ldots}$, or $\cdot 43429448\ldots$; we shall denote this modulus by μ.

In the *Proceedings of the Royal Society of London*, Vol. XXVII. page 88, Professor J. C. Adams has given the values of e, μ, $\log_e 2$, $\log_e 3$, $\log_e 5$ to more than 260 places of decimals.

225. If we multiply the above series throughout by μ, we obtain formulæ adapted to the calculation of *common logarithms*.

Thus from (1), $\mu \log_e(n+1) - \mu \log_e n = \frac{\mu}{n} - \frac{\mu}{2n^2} + \frac{\mu}{3n^3} - \ldots;$

that is,

$$\log_{10}(n+1) - \log_{10} n = \frac{\mu}{n} - \frac{\mu}{2n^2} + \frac{\mu}{3n^3} - \ldots\ldots\ldots (1).$$

Similarly from (2),

$$\log_{10} n - \log_{10}(n-1) = \frac{\mu}{n} + \frac{\mu}{2n^2} + \frac{\mu}{3n^3} + \ldots\ldots\ldots (2).$$

From either of the above results we see that if the logarithm of one of two consecutive numbers be known, the logarithm of the other may be found, and thus a table of logarithms can be constructed.

It should be remarked that the above formulæ are only needed to calculate the logarithms of *prime* numbers, for the logarithm of a *composite* number may be obtained by adding together the logarithms of its component factors.

In order to calculate the logarithm of any one of the smaller prime numbers, we do not usually substitute the number in either of the formulæ (1) or (2), but we endeavour to find some value of n by which division may be easily performed, and such that either $n+1$ or $n-1$ contains the given number as a factor. We then find $\log(n+1)$ or $\log(n-1)$ and deduce the logarithm of the given number.

Example. Calculate $\log 2$ and $\log 3$, given $\mu = \cdot 43429448$.

By putting $n = 10$ in (2), we have the value of $\log 10 - \log 9$; thus

$$1 - 2\log 3 = \cdot 043429448 + \cdot 002171472 + \cdot 000144765 + \cdot 000010857 + \cdot 000000868 + \cdot 000000072 + \cdot 000000006;$$

$$1 - 2\log 3 = \cdot 045757488,$$

$$\log 3 = \cdot 477121256.$$

Putting $n = 80$ in (1), we obtain $\log 81 - \log 80$; thus

$$4\log 3 - 3\log 2 - 1 = \cdot 005428681 - \cdot 000033929 + \cdot 000000283 \quad \cdot 000000003;$$

$$3\log 2 = \cdot 908485024 - \cdot 005395032,$$

$$\log 2 = \cdot 301029997.$$

In the next article we shall give another series for $\log_e(n+1) - \log_e n$ which is often useful in the construction of Logarithmic Tables. For further information on the subject the reader is referred to Mr Glaisher's article on *Logarithms* in the *Encyclopædia Britannica*.

226. In Art. 223 we have proved that

$$\log_e(1+x) = x - \frac{x^2}{2} + \frac{x^3}{3} \quad \ldots$$

changing x into $-x$, we have

$$\log_e(1-x) = -x - \frac{x^2}{2} - \frac{x^3}{3} - \ldots$$

By subtraction,

$$\log_e \frac{1+x}{1-x} = 2\left(x + \frac{x^3}{3} + \frac{x^5}{5} + \ldots\right).$$

Put $\dfrac{1+x}{1-x} = \dfrac{n+1}{n}$, so that $x = \dfrac{1}{2n+1}$; we thus obtain

$$\log_e(n+1) - \log_e n = 2\left\{\frac{1}{2n+1} + \frac{1}{3(2n+1)^3} + \frac{1}{5(2n+1)^5} + \ldots\right\}.$$

NOTE. This series converges very rapidly, but in practice is not always so convenient as the series in Art. 224.

227. The following examples illustrate the subject of the chapter.

Example 1. If α, β are the roots of the equation $ax^2+bx+c=0$, shew that $\log(a-bx+cx^2) = \log a + (\alpha+\beta)x - \dfrac{\alpha^2+\beta^2}{2}x^2 + \dfrac{\alpha^3+\beta^3}{3}x^3 - \ldots$

Since $\alpha+\beta = \dfrac{b}{a}$, $\alpha\beta = \dfrac{c}{a}$, we have

$$a - bx + cx^2 = a\{1 + (\alpha+\beta)x + \alpha\beta x^2\}$$
$$= a(1+\alpha x)(1+\beta x).$$
$$\therefore \log(a-bx+cx^2) = \log a + \log(1+\alpha x) + \log(1+\beta x)$$
$$= \log a + \alpha x - \frac{\alpha^2x^2}{2} + \frac{\alpha^3x^3}{3} - \ldots + \beta x - \frac{\beta^2x^2}{2} + \frac{\beta^3x^3}{3} - \ldots$$
$$= \log a + (\alpha+\beta)x - \frac{\alpha^2+\beta^2}{2}x^2 + \frac{\alpha^3+\beta^3}{3}x^3 - \ldots$$

Example 2. Prove that the coefficient of x^n in the expansion of $\log(1+x+x^2)$ is $-\dfrac{2}{n}$ or $\dfrac{1}{n}$ according as n is or is not a multiple of 3.

$$\log(1+x+x^2) = \log\frac{1-x^3}{1-x} = \log(1-x^3) - \log(1-x)$$
$$= -x^3 - \frac{x^6}{2} - \frac{x^9}{3} - \ldots - \frac{x^{3r}}{r} - \ldots + \left(x + \frac{x^2}{2} + \frac{x^3}{3} + \ldots + \frac{x^r}{r} + \quad\right).$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

3. Shew that

$$\log_e(n+a)-\log_e(n-a)=2\left(\frac{a}{n}+\frac{a^3}{3n^3}+\frac{a^5}{5n^5}+\ldots.\right).$$

4. If $$y=x-\frac{x^2}{2}+\frac{x^3}{3}\quad\frac{x^4}{4}+\ldots,$$

shew that $$x=y+\frac{y^2}{\lfloor 2}+\frac{y^3}{\lfloor 3}+\ldots.$$

5. Shew that

$$\frac{a-b}{a}+\frac{1}{2}\left(\frac{a-b}{a}\right)^2+\frac{1}{3}\left(\frac{a-b}{a}\right)^3+\ldots=\log_e a-\log_e b.$$

6. Find the Napierian logarithm of $\frac{1001}{999}$ correct to sixteen places of decimals.

7. Prove that $$e^{-1}=2\left(\frac{1}{\lfloor 3}+\frac{2}{\lfloor 5}+\frac{3}{\lfloor 7}+\ldots.\right).$$

8. Prove that

$$\log_e(1+x)^{1+x}(1-x)^{1-x}=2\left(\frac{x^2}{1.2}+\frac{x^4}{3.4}+\frac{x^6}{5.6}+\ldots.\right).$$

9. Find the value of

$$x^2-y^2+\frac{1}{\lfloor 2}(x^4-y^4)+\frac{1}{\lfloor 3}(x^6-y^6)+\ldots.$$

10. Find the numerical values of the common logarithms of **7, 11** and **13**; given $\mu=\cdot 43429448$, $\log 2=\cdot 30103000$.

11. Shew that if ax^2 and $\frac{a}{x^2}$ are each less unity

$$a\left(x^2+\frac{1}{x^2}\right)-\frac{a^2}{2}\left(x^4+\frac{1}{x^4}\right)+\frac{a^3}{3}\left(x^6+\frac{1}{x^6}\right)-\ldots=\log_e\left(1+ax^2+a^2+\frac{a}{x^2}\right).$$

12. Prove that

$$\log_e(1+3x+2x^2)=3x-\frac{5x^2}{2}+\frac{9x^3}{3}-\frac{17x^4}{4}+\ldots;$$

and find the general term of the series.

13. Prove that

$$\log_e\frac{1+3x}{1-2x}=5x-\frac{5x^2}{2}+\frac{35x^3}{3}-\frac{65x^4}{4}+\ldots;$$

and find the general term of the series.

14. Expand $\frac{e^{5x}+e^x}{e^{3x}}$ in a series of ascending powers of x.

15. Express $\frac{1}{2}(e^{ix}+e^{-ix})$ in ascending powers of x, where $i=\sqrt{-1}$.

16. Shew that

$$\log_e(x+2h)=2\log_e(x+h)-\log_e x-\left\{\frac{h^2}{(x+h)^2}+\frac{h^4}{2(x+h)^4}+\frac{h^6}{3(x+h)^6}+\ldots\right\}.$$

17. If α and β be the roots of $x^2-px+q=0$, shew that

$$\log_e(1+px+qx^2)=(\alpha+\beta)x-\frac{\alpha^2+\beta^2}{2}x^2+\frac{\alpha^3+\beta^3}{3}x^3-\ldots.$$

18. If $x<1$, find the sum of the series

$$\frac{1}{2}x^2+\frac{2}{3}x^3+\frac{3}{4}x^4+\frac{4}{5}x^5+\ldots.$$

19. Shew that

$$\log_e\left(1+\frac{1}{n}\right)^n=1-\frac{1}{2(n+1)}-\frac{1}{2.3(n+1)^2}-\frac{1}{3.4(n+1)^3}-\ldots.$$

20. If $\log_e\frac{1}{1+x+x^2+x^3}$ be expanded in a series of ascending powers of x, shew that the coefficient of x^n is $-\frac{1}{n}$ if n be odd, or of the form $4m+2$, and $\frac{3}{n}$ if n be of the form $4m$.

21. Shew that

$$1+\frac{2^3}{\lfloor 2}+\frac{3^3}{\lfloor 3}+\frac{4^3}{\lfloor 4}+\ldots=5e.$$

22. Prove that

$$2\log_e n-\log_e(n+1)-\log_e(n-1)=\frac{1}{n^2}+\frac{1}{2n^4}+\frac{1}{3n^6}+$$

23. Shew that

$$\frac{1}{n+1}+\frac{1}{2(n+1)^2}+\frac{1}{3(n+1)^3}+\ldots$$
$$=\frac{1}{n}-\frac{1}{2n^2}+\frac{1}{3n^3}-\ldots.$$

24. If $\log_e\frac{9}{10}=-a$, $\log_e\frac{24}{25}=-b$, $\log_e\frac{81}{80}=c$, shew that

$\log_e 2=7a-2b+3c$, $\log_e 3=11a-3b+5c$, $\log_e 5=16a-4b+7c$;

and calculate $\log_e 2$, $\log_e 3$, $\log_e 5$ to 8 places of decimals.

CHAPTER XVIII.

INTEREST AND ANNUITIES.

229. In this chapter we shall explain how the solution of questions connected with Interest and Discount may be simplified by the use of algebraical formulæ.

We shall use the terms *Interest*, *Discount*, *Present Value* in their ordinary arithmetical sense; but instead of taking as the rate of interest the interest on £100 for one year, we shall find it more convenient to take the interest on £1 for one year.

230. *To find the interest and amount of a given sum in a given time at simple interest.*

Let P be the principal in pounds, r the interest of £1 for one year, n the number of years, I the interest, and M the amount.

The interest of P for one year is Pr, and therefore for n years is Pnr; that is,

$$I = Pnr \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

Also $M = P + I$;

that is, $M = P(1 + nr) \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$

From (1) and (2) we see that if of the quantities P, n, r, I, or P, n, r, M, any three be given the fourth may be found.

231. *To find the present value and discount of a given sum due in a given time, allowing simple interest.*

Let P be the given sum, V the present value, D the discount, r the interest of £1 for one year, n the number of years.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

The amount of P at the end of the first year is PR; and, since this is the principal for the second year, the amount at the end of the second year is $PR \times R$ or PR^2. Similarly the amount at the end of the third year is PR^3, and so on; hence the amount in n years is PR^n; that is,

$$M = PR^n;$$

$$I = P(R^n - 1).$$

NOTE. If r denote the interest on £1 for one year, we have

$$R = 1 + r.$$

233. In business transactions when the time contains a fraction of a year it is usual to allow *simple* interest for the fraction of the year. Thus the amount of £1 in $\frac{1}{2}$ year is reckoned $1 + \frac{r}{2}$; and the amount of P in $4\frac{2}{3}$ years at compound interest is $PR^4\left(1 + \frac{2}{3}r\right)$. Similarly the amount of P in $n + \frac{1}{m}$ years is $PR^n\left(1 + \frac{r}{m}\right)$.

If the interest is payable more than once a year there is a distinction between the *nominal annual rate* of interest and that actually received, which may be called the *true annual rate*; thus if the interest is payable twice a year, and if r is the *nominal* annual rate of interest, the amount of £1 in half a year is $1 + \frac{r}{2}$, and therefore in the whole year the amount of £1 is $\left(1 + \frac{r}{2}\right)^2$, or $1 + r + \frac{r^2}{4}$; so that the *true* annual rate of interest is $r + \frac{r^2}{4}$.

234. If the interest is payable q times a year, and if r is the nominal annual rate, the interest on £1 for each interval is $\frac{r}{q}$, and therefore the amount of P in n years, or qn intervals, is $P\left(1 + \frac{r}{q}\right)^{qn}$.

In this case the interest is said to be "converted into principal" q times a year.

If the interest is convertible into principal every moment, then q becomes infinitely great. To find the value of the amount, put $\frac{r}{q} = \frac{1}{x}$, so that $q = rx$; thus

$$\text{the amount} = P\left(1+\frac{r}{q}\right)^{qn} = P\left(1+\frac{1}{x}\right)^{xnr} = P\left\{\left(1+\frac{1}{x}\right)^{x}\right\}$$
$$= Pe^{nr}, \text{ [Art. 220, Cor.,]}$$

since x is infinite when q is infinite.

235. *To find the present value and discount of a given sum due in a given time, allowing compound interest.*

Let P be the given sum, V the present value, D the discount, R the amount of £1 for one year, n the number of years.

Since V is the sum which, put out to interest at the present time, will in n years amount to P, we have

$$P = VR^n;$$

$$\therefore \quad V = \frac{P}{R^n} = PR^{-n},$$

and
$$D = P\left(1 - R^{-n}\right).$$

Example. The present value of £672 due in a certain time is £126; if compound interest at $4\frac{1}{6}$ per cent. be allowed, find the time; having given

$$\log 2 = \cdot 30103, \ \log 3 = \cdot 47712.$$

Here
$$r = \frac{4\frac{1}{6}}{100} = \frac{1}{24}, \text{ and } R = \frac{25}{24}.$$

Let n be the number of years; then

$$672 = 126\left(\frac{25}{24}\right)^n;$$

$$\therefore \ n \log \frac{25}{24} = \log \frac{672}{126},$$

or
$$n \log \frac{100}{96} = \log \frac{16}{3};$$

$$\therefore \ n\left(\log 100 - \log 96\right) = \log 16 - \log 3,$$

$$n = \frac{4 \log 2 - \log 3}{2 - 5 \log 2 - \log 3}$$

$$n = \frac{\cdot 72700}{\cdot 01773} = 41, \text{ very nearly;}$$

thus the time is very nearly 41 years.

EXAMPLES. XVIII. a.

When required the following logarithms may be used.

$$\log 2 = \cdot 3010300, \quad \log 3 = \cdot 4771213,$$
$$\log 7 = \cdot 8450980, \quad \log 11 = 1\cdot 0413927.$$

1. Find the amount of £100 in 50 years, at 5 per cent. compound interest; given $\log 114\cdot 674 = 2\cdot 0594650$.

2. At simple interest the interest on a certain sum of money is £90, and the discount on the same sum for the same time and at the same rate is £80; find the sum.

3. In how many years will a sum of money double itself at 5 per cent. compound interest?

4. Find, correct to a farthing, the present value of £10000 due 8 years hence at 5 per cent. compound interest; given

$$\log 67683\cdot 94 = 4\cdot 8304856.$$

5. In how many years will £1000 become £2500 at 10 per cent. compound interest?

6. Shew that at simple interest the discount is half the harmonic mean between the sum due and the interest on it.

7. Shew that money will increase more than a hundredfold in a century at 5 per cent. compound interest.

8. What sum of money at 6 per cent. compound interest will amount to £1000 in 12 years? Given

$$\log 106 = 2\cdot 0253059, \quad \log 49697 = 4\cdot 6963292.$$

9. A man borrows £600 from a money-lender, and the bill is renewed every half-year at an increase of 18 per cent.: what time will elapse before it reaches £6000? Given $\log 118 = 2\cdot 071882$.

10. What is the amount of a farthing in 200 years at 6 per cent. compound interest? Given $\log 106 = 2\cdot 0253059$, $\log 115\cdot 0270 = 2\cdot 0611800$.

Annuities.

236. An **annuity** is a fixed sum paid periodically under certain stated conditions; the payment may be made either once a year or at more frequent intervals. Unless it is otherwise stated we shall suppose the payments annual.

An **annuity certain** is an annuity payable for a fixed term of years independent of any contingency; a **life annuity** is an annuity which is payable during the lifetime of a person, or of the survivor of a number of persons.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

239. In finding the present value of annuities it is always customary to reckon compound interest; the results obtained when simple interest is reckoned being contradictory and untrustworthy. On this point and for further information on the subject of annuities the reader may consult Jones on the *Value of Annuities and Reversionary Payments*, and the article *Annuities* in the *Encyclopædia Britannica*.

240. *To find the present value of an annuity to continue for a given number of years, allowing compound interest.*

Let A be the annuity, R the amount of £1 in one year, n the number of years, V the required present value.

The present value of A due in 1 year is AR^{-1};

the present value of A due in 2 years is AR^{-2};

the present value of A due in 3 years is AR^{-3};

and so on. [Art. 235.]

Now V is the sum of the present values of the different payments;

$$V = AR^{-1} + AR^{-2} + AR^{-3} + \quad \text{to } n \text{ terms}$$

$$= AR^{-1}\frac{1-R^{-n}}{1-R^{-1}}$$

$$= A\frac{1-R^{-n}}{R-1}.$$

NOTE. This result may also be obtained by dividing the value of M, given in Art. 238, by R^n. [Art. 232.]

COR. If we make n infinite we obtain for the present value of a *perpetuity*

$$V = \frac{A}{R-1} = \frac{A}{r}.$$

241. If mA is the present value of an annuity A, the annuity is said to be worth m **years' purchase.**

In the case of a perpetual annuity $mA = \frac{A}{r}$; hence

$$m = \frac{1}{r} = \frac{100}{\text{rate per cent.}};$$

that is, the number of years' purchase of a perpetual annuity is obtained by dividing 100 by the rate per cent.

As instances of perpetual annuities we may mention the income arising from investments in irredeemable Stocks such as many Government Securities, Corporation Stocks, and Railway Debentures. A good test of the credit of a Government is furnished by the number of years' purchase of its Stocks; thus the $2\frac{3}{4}$ p. c. Consols at $96\frac{1}{4}$ are worth 35 years' purchase; Egyptian 4 p. c. Stock at 96 is worth 24 years' purchase; while Austrian 5 p. c. Stock at 80 is only worth 16 years' purchase.

242. *To find the present value of a deferred annuity to commence at the end of* p *years and to continue for* n *years, allowing compound interest.*

Let A be the annuity, R the amount of £1 in one year, V the present value.

The first payment is made at the end of $(p+1)$ years. [Art. 236.]

Hence the present values of the first, second, third ... payments are respectively

$$AR^{-(p+1)},\ AR^{-(p+2)},\ AR^{-(p+3)},\ \ldots$$

$$\therefore\quad V = AR^{-(p+1)} + AR^{-(p+2)} + AR^{-(p+3)} + \qquad \text{to } n \text{ terms}$$

$$= AR^{-(p+1)}\,\frac{1-R^{-n}}{1-R^{-1}}$$

$$= \frac{AR^{-p}}{R-1} - \frac{AR^{-p-n}}{R-1}.$$

Cor. The present value of a *deferred perpetuity* to commence after p years is given by the formula

$$V = \frac{AR^{-p}}{R-1}.$$

243. **A freehold estate** is an estate which yields a perpetual annuity called the *rent*; and thus the value of the estate is equal to the present value of a perpetuity equal to the rent.

It follows from Art. 241 that if we know the number of years' purchase that a tenant pays in order to buy his farm, we obtain the rate per cent. at which interest is reckoned by dividing 100 by the number of years' purchase.

Example. The reversion after 6 years of a freehold estate is bought for £20000; what rent ought the purchaser to receive, reckoning compound interest at 5 per cent.? Given $\log 1{\cdot}05 = {\cdot}0211893$, $\log 1{\cdot}340096 = {\cdot}1271358$.

The rent is equal to the annual value of the perpetuity, deferred for 6 years, which may be purchased for £20000.

Let £A be the value of the annuity; then since $R = 1{\cdot}05$, we have

$$20000 = \frac{A \times (1{\cdot}05)^{-6}}{{\cdot}05};$$

$$\therefore\ A \times (1{\cdot}05)^{-6} = 1000;$$

$$\therefore\ \log A - 6 \log 1{\cdot}05 = 3,$$

$$\log A = 3{\cdot}1271358 = \log 1340{\cdot}096.$$

$$\therefore\ A = 1340{\cdot}096,$$ and the rent is £1340. 1*s*. 11*d*.

244. Suppose that a tenant by paying down a certain sum has obtained a lease of an estate for $p+q$ years, and that when q years have elapsed he wishes to renew the lease for a term $p+n$ years; the sum that he must pay is called the **fine** for renewing n years of the lease.

Let A be the annual value of the estate; then since the tenant has paid for p of the $p+n$ years, the fine must be equal to the present value of a deferred annuity A, to commence after p years and to continue for n years; that is,

$$\text{the fine} = \frac{AR^{-p}}{R-1} - \frac{AR^{-p-n}}{R-1}. \qquad \text{[Art. 242.]}$$

EXAMPLES. XVIII. b.

The interest is supposed compound unless the contrary is stated.

1. A person borrows £672 to be repaid in 5 years by annual instalments of £120; find the rate of interest, reckoning simple interest.

2. Find the amount of an annuity of £100 in 20 years, allowing compound interest at $4\frac{1}{2}$ per cent. Given

$$\log 1{\cdot}045 = {\cdot}0191163, \quad \log 24{\cdot}117 = 1{\cdot}3823260.$$

3. A freehold estate is bought for £2750; at what rent should it be let so that the owner may receive 4 per cent. on the purchase money?

4. A freehold estate worth £120 a year is sold for £4000; find the rate of interest.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

CHAPTER XIX.

INEQUALITIES.

245. ANY quantity a is said to be greater than another quantity b when $a-b$ is positive; thus 2 is greater than -3, because $2-(-3)$, or 5 is positive. Also b is said to be less than a when $b-a$ is negative; thus -5 is less than -2, because $-5-(-2)$, or -3 is negative.

In accordance with this definition, zero must be regarded as greater than any negative quantity.

In the present chapter we shall suppose (unless the contrary is directly stated) that the letters always denote real and positive quantities.

246. If $a > b$, then it is evident that

$$a+c > b+c;$$

$$a-c > b-c;$$

$$ac > bc;$$

$$\frac{a}{c} > \frac{b}{c};$$

that is, *an inequality will still hold after each side has been increased, diminished, multiplied, or divided by the same* positive *quantity.*

247. If $$a-c > b,$$

by adding c to each side,

$$a > b+c;$$

which shews that *in an inequality any term may be transposed from one side to the other if its sign be changed.*

If $a > b$, then evidently $b < a$;

that is, *if the sides of an inequality be transposed, the sign of inequality must be reversed.*

If $a > b$, then $a - b$ is positive, and $b - a$ is negative; that is, $-a-(-b)$ is negative, and therefore

$$a < -b;$$

hence, *if the signs of all the terms of an inequality be changed, the sign of inequality must be reversed.*

Again, if $a > b$, then $-a < -b$, and therefore

$$-ac < -bc;$$

that is, *if the sides of an inequality be multiplied by the same negative quantity, the sign of inequality must be reversed.*

248. If $a_1 > b_1$, $a_2 > b_2$, $a_3 > b_3$, ... $a_m > b_m$, it is clear that

$$a_1 + a_2 + a_3 + \ldots + a_m > b_1 + b_2 + b_3 + \ldots + b_m;$$

and

$$a_1 a_2 a_3 \ldots a_m > b_1 b_2 b_3 \ldots b_m.$$

249. If $a > b$, and if p, q are positive integers, then $\sqrt[q]{a} > \sqrt[q]{b}$, or $a^{\frac{1}{q}} > b^{\frac{1}{q}}$; and therefore $a^{\frac{p}{q}} > b^{\frac{p}{q}}$; that is, $a^n > b^n$, where n is any positive quantity.

Further, $\dfrac{1}{a^n} < \dfrac{1}{b^n}$; that is $a^{-n} < b^{-n}$.

250. The square of every real quantity is positive, and therefore greater than zero. Thus $(a-b)^2$ is positive;

$$a^2 - 2ab + b^2 > 0;$$

$$\therefore \quad a^2 + b^2 > 2ab.$$

Similarly

$$\frac{x+y}{2} > \sqrt{xy};$$

that is, *the arithmetic mean of two positive quantities is greater than their geometric mean.*

The inequality becomes an equality when the quantities are equal.

251. The results of the preceding article will be found very useful, especially in the case of inequalities in which the letters are involved symmetrically.

Example 1. If a, b, c denote positive quantities, prove that

$$a^2+b^2+c^2>bc+ca+ab;$$

and
$$2(a^3+b^3+c^3)>bc(b+c)+ca(c+a)+ab(a+b).$$

For
$$b^2+c^2>2bc \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1);$$
$$c^2+a^2>2ca;$$
$$a^2+b^2>2ab;$$

whence by addition
$$a^2+b^2+c^2>bc+ca+ab.$$

It may be noticed that this result is true for *any* real values of a, b, c.

Again, from (1)
$$b^2-bc+c^2>bc \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2);$$
$$\therefore\ b^3+c^3>bc(b+c) \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots (3).$$

By writing down the two similar inequalities and adding, we obtain

$$2(a^3+b^3+c^3)>bc(b+c)+ca(c+a)+ab(a+b).$$

It should be observed that (3) is obtained from (2) by introducing the factor $b+c$, and that if this factor be negative the inequality (3) will no longer hold.

Example 2. If x may have any real value find which is the greater, x^3+1 or x^2+x.

$$\begin{aligned} x^3+1-(x^2+x) &= x^3-x^2-(x-1) \\ &= (x^2-1)(x-1) \\ &= (x-1)^2(x+1). \end{aligned}$$

Now $(x-1)^2$ is positive, hence

$$x^3+1 > \text{ or } < x^2+x$$

according as $x+1$ is positive or negative; that is, according as $x >$ or < -1.

If $x=-1$, the inequality becomes an equality.

252. Let a and b be two positive quantities, S their sum and P their product; then from the identity

$$4ab=(a+b)^2-(a-b)^2,$$

we have

$$4P=S^2-(a-b)^2, \text{ and } S^2=4P+(a-b)^2.$$

Hence, if S is given, P is greatest when $a=b$; and if P is given, S is least when

$$a=b;$$

that is, *if the sum of two positive quantities is given, their product is greatest when they are equal;* and *if the product of two positive quantities is given, their sum is least when they are equal.*

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

254. *To find the greatest value of* $a^m b^n c^p \ldots$ *when* $a + b + c +$ *is constant;* m, n, p,... *being positive integers.*

Since m, n, p,... are constants, the expression $a^m b^n c^p \ldots$ will be greatest when $\left(\frac{a}{m}\right)^m \left(\frac{b}{n}\right)^n \left(\frac{c}{p}\right)^p \ldots$ is greatest. But this last expression is the product of $m+n+p+\ldots$ factors whose sum is $m\left(\frac{a}{m}\right) + n\left(\frac{b}{n}\right) + p\left(\frac{c}{p}\right) + \ldots$, or $a+b+c+\ldots$, and therefore constant. Hence $a^m b^n c^p \ldots$ will be greatest when the factors

$$\frac{a}{m}, \quad \frac{b}{n}, \quad \frac{c}{p}, \ldots$$

are all equal, that is, when

$$\frac{a}{m} = \frac{b}{n} = \frac{c}{p} = \ldots = \frac{a+b+c+\ldots}{m+n+p+\ldots}.$$

Thus the greatest value is

$$m^m n^n p^p \ldots \left(\frac{a+b+c+\ldots}{m+n+p+\ldots}\right)^{m+n+p+\ldots}$$

Example. Find the greatest value of $(a+x)^3 (a-x)^4$ for any real value of x numerically less than a.

The given expression is greatest when $\left(\frac{a+x}{3}\right)^3 \left(\frac{a-x}{4}\right)^4$ is greatest; but the sum of the factors of this expression is $3\left(\frac{a+x}{3}\right) + 4\left(\frac{a-x}{4}\right)$, or $2a$; hence $(a+x)^3 (a-x)^4$ is greatest when $\frac{a+x}{3} = \frac{a-x}{4}$, or $x = -\frac{a}{7}$.

Thus the greatest value is $\frac{6^3 \cdot 8^4}{7^7} a^7$.

255. The determination of *maximum* and *minimum* values may often be more simply effected by the solution of a quadratic equation than by the foregoing methods. Instances of this have already occurred in Chap. IX.; we add a further illustration.

Example. Divide an odd integer into two integral parts whose product is a maximum.

Denote the integer by $2n+1$; the two parts by x and $2n+1-x$; and the product by y; then $(2n+1)x - x^2 = y$; whence

$$2x = (2n+1) \pm \sqrt{(2n+1)^2 - 4y};$$

but the quantity under the radical must be positive, and therefore y cannot be greater than $\frac{1}{4}(2n+1)^2$, or $n^2+n+\frac{1}{4}$; and since y is integral its greatest value must be n^2+n; in which case $x=n+1$, or n; thus the two parts are n and $n+1$.

256. Sometimes we may use the following method.

Example. Find the minimum value of $\dfrac{(a+x)(b+x)}{c+x}$.

Put $c+x=y$; then

the expression $$=\frac{(a-c+y)(b-c+y)}{y}$$

$$=\frac{(a-c)(b-c)}{y}+y+a-c+b-c$$

$$=\left(\frac{\sqrt{(a-c)(b-c)}}{\sqrt{y}}-\sqrt{y}\right)^2+a-c+b-c+2\sqrt{(a-c)(b-c)}.$$

Hence the expression is a minimum when the square term is zero; that is when $y=\sqrt{(a-c)(b-c)}$.

Thus the minimum value is

$$a-c+b-c+2\sqrt{(a-c)(b-c)};$$

and the corresponding value of x is $\sqrt{(a-c)(b-c)}-c$.

EXAMPLES. XIX. a.

1. Prove that $(ab+xy)(ax+by)>4abxy$.

2. Prove that $(b+c)(c+a)(a+b)>8abc$.

3. Shew that the sum of any real positive quantity and its reciprocal is never less than 2.

4. If $a^2+b^2=1$, and $x^2+y^2=1$, shew that $ax+by<1$.

5. If $a^2+b^2+c^2=1$, and $x^2+y^2+z^2=1$, shew that
$$ax+by+cz<1.$$

6. If $a>b$, shew that $a^ab^b>a^bb^a$, and $\log\frac{b}{a}<\log\frac{1+b}{1+a}$.

7. Shew that $(x^2y+y^2z+z^2x)(xy^2+yz^2+zx^2)>9x^2y^2z^2$

8. Find which is the greater $3ab^2$ or a^3+2b^3.

9. Prove that $a^3b+ab^3<a^4+b^4$.

10. Prove that $6abc<bc(b+c)+ca(c+a)+ab(a+b)$.

11. Shew that $b^2c^2+c^2a^2+a^2b^2>abc(a+b+c)$.

12. Which is the greater x^3 or x^2+x+2 for positive values of x?

13. Shew that $x^3+13a^2x > 5ax^2+9a^3$, if $x > a$.

14. Find the greatest value of x in order that $7x^2+11$ may be greater than x^3+17x.

15. Find the minimum value of $x^2-12x+40$, and the maximum value of $24x-8-9x^2$.

16. Shew that $(\lfloor\underline{n})^2 > n^n$, and $2.4.6...2n < (n+1)^n$.

17. Shew that $(x+y+z)^3 > 27xyz$.

18. Shew that $n^n > 1.3.5...(2n-1)$.

19. If n be a positive integer greater than 2, shew that

$$2^n > 1+n\sqrt{2^{n-1}}$$

20. Shew that $(\lfloor\underline{n})^3 < n^n\left(\frac{n+1}{2}\right)^{2n}$.

21. Shew that

(1) $(x+y+z)^3 > 27(y+z-x)(z+x-y)(x+y-z)$.

(2) $xyz > (y+z-x)(z+x-y)(x+y-z)$.

22. Find the maximum value of $(7-x)^4(2+x)^5$ when x lies between 7 and -2.

23. Find the minimum value of $\frac{(5+x)(2+x)}{1+x}$.

*257. *To prove that if* a *and* b *are positive and unequal,* $\frac{a^m+b^m}{2} > \left(\frac{a+b}{2}\right)^m$, *except when* m *is a positive proper fraction.*

We have $a^m+b^m = \left(\frac{a+b}{2}+\frac{a-b}{2}\right)^m + \left(\frac{a+b}{2}-\frac{a-b}{2}\right)^m$; and since $\frac{a-b}{2}$ is less than $\frac{a+b}{2}$, we may expand each of these expressions in ascending powers of $\frac{a-b}{2}$. [Art. 184.]

$$\therefore \frac{a^m+b^m}{2} = \left(\frac{a+b}{2}\right)^m + \frac{m(m-1)}{1.2}\left(\frac{a+b}{2}\right)^{m-2}\left(\frac{a-b}{2}\right)^2 + \frac{m(m-1)(m-2)(m-3)}{1.2.3.4}\left(\frac{a+b}{2}\right)^{m-4}\left(\frac{a-b}{2}\right)^4 + \ldots.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Hence so long as any two of the quantities $a, b, c, \ldots k$ are unequal the expression $a^m + b^m + c^m + \ldots + k^m$ can be diminished without altering the value of $a + b + c + \ldots + k$; and therefore the value of $a^m + b^m + c^m + \ldots + k^m$ will be least when all the quantities $a, b, c, \ldots k$ are equal. In this case each of the quantities is equal

to $$\frac{a + b + c + \ldots + k}{n};$$

and the value of $a^m + b^m + c^m + \ldots + k^m$ then becomes

$$n\left(\frac{a + b + c + \ldots + k}{n}\right)^m.$$

Hence when $a, b, c, \ldots k$ are unequal,

$$\frac{a^m + b^m + c^m + \ldots + k^m}{n} > \left(\frac{a + b + c + \ldots + k}{n}\right)^m.$$

If m lies between 0 and 1 we may in a similar manner prove that the sign of inequality in the above result must be reversed.

The proposition may be stated verbally as follows:

The arithmetic mean of the m^{th} *powers of* n *positive quantities is greater than the* m^{th} *power of their arithmetic mean in all cases except when* m *lies between* 0 *and* 1.

*259. *If* a *and* b *are positive integers, and* $\mathrm{a} > \mathrm{b}$, *and if* x *be a positive quantity,* $$\left(1 + \frac{\mathrm{x}}{\mathrm{a}}\right)^{\mathrm{a}} > \left(1 + \frac{\mathrm{x}}{\mathrm{b}}\right)^{\mathrm{b}}.$$

For

$$\left(1 + \frac{x}{a}\right)^a = 1 + x + \left(1 - \frac{1}{a}\right)\frac{x^2}{\lfloor 2} + \left(1 - \frac{1}{a}\right)\left(1 - \frac{2}{a}\right)\frac{x^3}{\lfloor 3} + \ldots (1),$$

the series consisting of $a + 1$ terms; and

$$\left(1 + \frac{x}{b}\right)^b = 1 + x + \left(1 - \frac{1}{b}\right)\frac{x^2}{\lfloor 2} + \left(1 - \frac{1}{b}\right)\left(1 - \frac{2}{b}\right)\frac{x^3}{\lfloor 3} + \ldots (2),$$

the series consisting of $b + 1$ terms.

After the second term, each term of (1) is greater than the corresponding term of (2); moreover the number of terms in (1) is greater than the number of terms in (2); hence the proposition is established.

*260. *To prove that* $\sqrt[x]{\frac{1+x}{1-x}} > \sqrt[y]{\frac{1+y}{1-y}}$,

if x *and* y *are proper fractions and positive, and* $x > y$.

For $$\sqrt[x]{\frac{1+x}{1-x}} > \text{ or } < \sqrt[y]{\frac{1+y}{1-y}},$$

according as $$\frac{1}{x}\log\frac{1+x}{1-x} > \text{ or } < \frac{1}{y}\log\frac{1+y}{1-y}.$$

But $$\frac{1}{x}\log\frac{1+x}{1-x} = 2\left(1+\frac{x^2}{3}+\frac{x^4}{5}+\ldots\right), \text{ [Art. 226]};$$

and $$\frac{1}{y}\log\frac{1+y}{1-y} = 2\left(1+\frac{y^2}{3}+\frac{y^4}{5}+\ldots\right).$$

$$\therefore \quad \frac{1}{x}\log\frac{1+x}{1-x} > \frac{1}{y}\log\frac{1+y}{1-y},$$

and thus the proposition is proved.

*261. *To prove that* $(1+x)^{1+x}(1-x)^{1-x} > 1$, *if* $x < 1$, *and to deduce that* $$a^a b^b > \left(\frac{a+b}{2}\right)^{a+b}.$$

Denote $(1+x)^{1+x}(1-x)^{1-x}$ by P; then

$$\log P = (1+x)\log(1+x) + (1-x)\log(1-x)$$

$$= -x\{\log(1+x) - \log(1-x)\} + \log(1+x) + \log(1 \quad x)$$

$$= -2x\left(x+\frac{x^3}{3}+\frac{x^5}{5}+\ldots\right) - 2\left(\frac{x^2}{2}+\frac{x^4}{4}+\frac{x^6}{6}+\ldots\right)$$

$$= 2\left(\frac{x^2}{1.2}+\frac{x^4}{3.4}+\frac{x^6}{5.6}+\ldots\right).$$

Hence $\log P$ is positive, and therefore $P > 1$;

that is, $$(1+x)^{1+x}(1-x)^{1-x} > 1.$$

In this result put $x = \frac{z}{u}$, where $u > z$; then

$$\left(1 + \frac{z}{u}\right)^{1+\frac{z}{u}} \left(1 - \frac{z}{u}\right)^{1-\frac{z}{u}} > 1;$$

$$\therefore \quad \left(\frac{u+z}{u}\right)^{u+z} \left(\frac{u-z}{u}\right)^{u-z} > 1^u, \text{ or } 1;$$

$$\therefore \quad (u+z)^{u+z} (u-z)^{u-z} > u^{2u}$$

Now put $u + z = a$, $u - z = b$, so that $u = \frac{a+b}{2}$;

$$\therefore \quad a^a b^b > \left(\frac{a+b}{2}\right)^{a+b}.$$

*EXAMPLES. XIX. b.

1. Shew that $27(a^4 + b^4 + c^4) > (a+b+c)^4$.

2. Shew that $n(n+1)^3 < 8(1^3 + 2^3 + 3^3 + \ldots + n^3)$.

3. Shew that the sum of the m^{th} powers of the first n even numbers is greater than $n(n+1)^m$, if $m > 1$.

4. If α and β are positive quantities, and $\alpha > \beta$, shew that

$$\left(1 + \frac{1}{\alpha}\right)^{\alpha} > \left(1 + \frac{1}{\beta}\right)^{\beta}.$$

Hence shew that if $n > 1$ the value of $\left(1 + \frac{1}{n}\right)^n$ lies between 2 and 2·718...

5. If a, b, c are in descending order of magnitude, shew that

$$\left(\frac{a+c}{a-c}\right)^a < \left(\frac{b+c}{b-c}\right)^b.$$

6. Shew that $\left(\frac{a+b+c+\ldots+k}{n}\right)^{a+b+c+\ldots+k} < a^a b^b c^c \ldots k^k$

7. Prove that $\frac{1}{m}\log(1+\alpha^m) < \frac{1}{n}\log(1+\alpha^n)$, if $m > n$.

8. If n is a positive integer and $x < 1$, shew that

$$\frac{1-x^{n+1}}{n+1} < \frac{1-x^n}{n}$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

CHAPTER XX.

LIMITING VALUES AND VANISHING FRACTIONS.

262. If a be a constant finite quantity, the fraction $\frac{a}{x}$ can be made as small as we please by sufficiently increasing x; that is, we can make $\frac{a}{x}$ approximate to zero as nearly as we please by taking x large enough; this is usually abbreviated by saying, "when x is infinite the limit of $\frac{a}{x}$ is zero."

Again, the fraction $\frac{a}{x}$ increases as x decreases, and by making x as small as we please we can make $\frac{a}{x}$ as large as we please; thus when x is zero $\frac{a}{x}$ has no finite limit; this is usually expressed by saying, "when x is zero the limit of $\frac{a}{x}$ is infinite."

263. When we say that a quantity *increases without limit* or *is infinite*, we mean that we can suppose the quantity to become greater than any quantity we can name.

Similarly when we say that a quantity *decreases without limit*, we mean that we can suppose the quantity to become smaller than any quantity we can name.

The symbol ∞ is used to denote the value of any quantity which is indefinitely increased, and the symbol 0 is used to denote the value of any quantity which is indefinitely diminished.

264. The two statements of Art. 262 may now be written symbolically as follows·

$$\text{if } x \text{ is } \infty, \text{ then } \frac{a}{x} \text{ is } 0;$$

$$\text{if } x \text{ is } 0, \text{ then } \frac{a}{x} \text{ is } \infty.$$

But in making use of such concise modes of expression, it must be remembered that they are only convenient abbreviations of fuller verbal statements.

265. The student will have had no difficulty in understanding the use of the word *limit*, wherever we have already employed it; but as a clear conception of the ideas conveyed by the words *limit* and *limiting value* is necessary in the higher branches of Mathematics we proceed to explain more precisely their use and meaning.

266. DEFINITION. If $y = f(x)$, and if when x approaches a value a, the function $f(x)$ can be made to differ by as little as we please from a fixed quantity b, then b is called the **limit** of y when $x = a$.

For instance, if S denote the sum of n terms of the series $1 + \frac{1}{2} + \frac{1}{2^2} + \frac{1}{2^3} + \ldots$; then $S = 2 - \frac{1}{2^{n-1}}$. [Art. 56.]

Here S is a function of n, and $\frac{1}{2^{n-1}}$ can be made as small as we please by increasing n; that is, the limit of S is 2 when n is infinite.

267. We shall often have occasion to deal with expressions consisting of a series of terms arranged according to powers of some common letter, such as

$$a_0 + a_1 x + a_2 x^2 + a_3 x^3 + \ldots\ldots$$

where the coefficients a_0, a_1, a_2, a_3, ... are finite quantities independent of x, and the number of terms may be limited or unlimited.

It will therefore be convenient to discuss some propositions connected with the limiting values of such expressions under certain conditions.

268. *The limit of the series*

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots\ldots$$

when x *is indefinitely diminished is* a_0.

Suppose that the series consists of an *infinite* number of terms.

Let b be the greatest of the coefficients a_1, a_2, a_3, ; and let us denote the given series by $a_0 + S$; then

$$S < bx + bx^2 + bx^3 + \quad ;$$

and if $x < 1$, we have $$S < \frac{bx}{1-x}.$$

Thus when x is indefinitely diminished, S can be made as small as we please; hence the limit of the given series is a_0.

If the series consists of a *finite* number of terms, S is less than in the case we have considered, hence *a fortiori* the proposition is true.

269. *In the series*

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots,$$

by taking x *small enough we may make any term as large as we please compared with the sum of all that follow it; and by taking* x *large enough we may make any term as large as we please compared with the sum of all that precede it.*

The ratio of the term a_nx^n to the sum of all that follow it is

$$\frac{a_nx^n}{a_{n+1}x^{n+1} + a_{n+2}x^{n+2} + \ldots}, \text{ or } \frac{a_n}{a_{n+1}x + a_{n+2}x^2 + \ldots}$$

When x is indefinitely small the denominator can be made as small as we please; that is, the fraction can be made as large as we please.

Again, the ratio of the term a_nx^n to the sum of all that precede it is

$$\frac{a_nx^n}{a_{n-1}x^{n-1} + a_{n-2}x^{n-2} + \ldots}, \text{ or } \frac{a_n}{a_{n-1}y + a_{n-2}y^2 + \ldots};$$

where $y = \frac{1}{x}$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

VANISHING FRACTIONS.

271. Suppose it is required to find the limit of

$$\frac{x^2+ax-2a^2}{x^2-a^2}$$

when $x=a$.

If we put $x=a+h$, then h will approach the value zero as x approaches the value a.

Substituting $a+h$ for x,

$$\frac{x^2+ax-2a^2}{x^2-a^2}=\frac{3ah+h^2}{2ah+h^2}=\frac{3a+h}{2a+h};$$

and when h is indefinitely small the limit of this expression is $\frac{3}{2}$.

There is however another way of regarding the question; for

$$\frac{x^2+ax-2a^2}{x^2-a^2}=\frac{(x-a)(x+2a)}{(x-a)(x+a)}=\frac{x+2a}{x+a},$$

and if we *now* put $x=a$ the value of the expression is $\frac{3}{2}$, as before.

If in the given expression $\frac{x^2+ax-2a^2}{x^2-a^2}$ we put $x=a$ *before* simplification it will be found that it assumes the form $\frac{0}{0}$, the value of which is indeterminate; also we see that it has this form in consequence of the factor $x-a$ appearing in both numerator and denominator. Now we cannot divide by a *zero factor*, but as long as x is not absolutely equal to a the factor $x-a$ may be removed, and we then find that the nearer x approaches to the value a, the nearer does the value of the fraction approximate to $\frac{3}{2}$, or in accordance with the definition of Art. 266,

when $x=a$, the limit of $\frac{x^2+ax-2a^2}{x^2-a^2}$ is $\frac{3}{2}$.

272. If $f(x)$ and $\phi(x)$ are two functions of x, each of which becomes equal to zero for some particular value a of x, the fraction $\frac{f(a)}{\phi(a)}$ takes the form $\frac{0}{0}$, and is called a **Vanishing Fraction.**

Example 1. If $x=3$, find the limit of

$$\frac{x^3-5x^2+7x-3}{x^3-x^2-5x-3}.$$

When $x=3$, the expression reduces to the indeterminate form $\frac{0}{0}$; but by removing the factor $x-3$ from numerator and denominator, the fraction becomes $\frac{x^2-2x+1}{x^2+2x+1}$. When $x=3$ this reduces to $\frac{1}{4}$, which is therefore the required limit.

Example 2. The fraction $\frac{\sqrt{3x-a}-\sqrt{x+a}}{x-a}$ becomes $\frac{0}{0}$ when $x=a$.

To find its limit, multiply numerator and denominator by the surd conjugate to $\sqrt{3x-a}-\sqrt{x+a}$; the fraction then becomes

$$\frac{(3x-a)-(x+a)}{(x-a)(\sqrt{3x-a}+\sqrt{x+a})}, \text{ or } \frac{2}{\sqrt{3x-a}+\sqrt{x+a}};$$

whence by putting $x=a$ we find that the limit is $\frac{1}{\sqrt{2a}}$.

Example 3. The fraction $\frac{1-\sqrt[3]{x}}{1-\sqrt[5]{x}}$ becomes $\frac{0}{0}$ when $x=1$.

To find its limit, put $x=1+h$ and expand by the Binomial Theorem. Thus the fraction

$$=\frac{1-(1+h)^{\frac{1}{3}}}{1-(1+h)^{\frac{1}{5}}}=\frac{1-\left(1+\frac{1}{3}h-\frac{1}{9}h^2+\ldots\right)}{1-\left(1+\frac{1}{5}h-\frac{2}{25}h^2+\ldots\right)}$$

$$=\frac{-\frac{1}{3}+\frac{1}{9}h-\ldots\ldots}{-\frac{1}{5}+\frac{2}{25}h\quad\ldots\ldots}$$

Now $h=0$ when $x=1$; hence the required limit is $\frac{5}{3}$.

273. Sometimes the roots of an equation assume an indeterminate form in consequence of some relation subsisting between the coefficients of the equation.

For example, if $$ax + b = cx + d,$$

$$(a - c)x = d - b,$$

$$x = \frac{d - b}{a - c}.$$

But if $c = a$, then x becomes $\frac{d - b}{0}$, or ∞; that is, the root of a simple equation is indefinitely great if the coefficient of x is indefinitely small.

274. The solution of the equations

$$ax + by + c = 0, \quad a'x + b'y + c' = 0,$$

is $$x = \frac{bc' - b'c}{ab' - a'b}, \; y = \frac{ca' - c'a}{ab' - a'b}.$$

If $ab' - a'b = 0$, then x and y are both infinite. In this case $\frac{a'}{a} = \frac{b'}{b} = m$ suppose; by substituting for a', b', the second equation becomes $ax + by + \frac{c'}{m} = 0$.

If $\frac{c'}{m}$ is not equal to c, the two equations $ax + by + c = 0$ and $ax + by + \frac{c'}{m} = 0$ differ only in their absolute terms, and being *inconsistent* cannot be satisfied by any finite values of x and y.

If $\frac{c'}{m}$ is equal to c, we have $\frac{a'}{a} - \frac{b'}{b} = \frac{c'}{c}$, and the two equations are now identical.

Here, since $bc' - b'c = 0$ and $ca' - c'a = 0$ the values of x and y each assume the form $\frac{0}{0}$, and the solution is *indeterminate*. In fact, in the present case we have really only *one* equation involving *two* unknowns, and such an equation may be satisfied by an unlimited number of values. [Art. 138.]

The reader who is acquainted with Analytical Geometry will have no difficulty in interpreting these results in connection with the geometry of the straight line.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

EXAMPLES. XX.

Find the limits of the following expressions,

(1) when $x=\infty$,

1. $\dfrac{(2x-3)(3-5x)}{7x^2-6x+4}$.

3. $\dfrac{(3+2x^3)(x-5)}{(4x^3-9)(1+x)}$.

5. $\dfrac{1-x^2}{2x^3-1} \div \dfrac{1-x}{2x^2}$.

(2) when $x=0$.

2. $\dfrac{(3x^2-1)^2}{x^4+9}$.

4. $\dfrac{(x-3)(2-5x)(3x+1)}{(2x-1)^3}$

6. $\dfrac{(3-x)(x+5)(2-7x)}{(7x-1)(x+1)^3}$.

Find the limits of

7. $\dfrac{x^3+1}{x^2-1}$, when $x=-1$.

8. $\dfrac{a^x-b^x}{x}$, when $x=0$.

9. $\dfrac{e^x-e^{-x}}{\log(1+x)}$, when $x=0$.

10. $\dfrac{e^{mx}-e^{ma}}{x-a}$, when $x=a$.

11. $\dfrac{\sqrt{x}-\sqrt{2a}+\sqrt{x-2a}}{\sqrt{x^2-4a^2}}$, when $x=2a$.

12. $\dfrac{\log(1+x^2+x^4)}{3x^2(1-2x)}$, when $x=0$.

13. $\dfrac{1-x+\log x}{1-\sqrt{2x-x^2}}$, when $x=1$.

14. $\dfrac{(a^2-x^2)^{\frac{1}{2}}+(a-x)^{\frac{3}{2}}}{(a^3-x^3)^{\frac{1}{2}}+(a-x)^{\frac{1}{2}}}$, when $x=a$.

15. $\dfrac{\sqrt{a^2+ax+x^2}-\sqrt{a^2-ax+x^2}}{\sqrt{a+x}-\sqrt{a-x}}$, when $x=0$.

16. $\left\{\left(\dfrac{n+1}{n}\right)^n-\dfrac{n+1}{n}\right\}^{-n}$, when $n=\infty$.

17. $n\log\dfrac{e}{\left(1+\dfrac{1}{n}\right)^{n-1}}$, when $n=\infty$

18. $\sqrt[x]{\dfrac{a+x}{a-x}}$, when $x=0$.

CHAPTER XXI.

CONVERGENCY AND DIVERGENCY OF SERIES.

276. An expression in which the successive terms are formed by some regular law is called a **series**; if the series terminate at some assigned term it is called a **finite series**; if the number of terms is unlimited, it is called an **infinite series.**

In the present chapter we shall usually denote a series by an expression of the form

$$u_1 + u_2 + u_3 + \ldots\ldots + u_n + \ldots\ldots$$

277. Suppose that we have a series consisting of n terms. The sum of the series will be a function of n; if n increases indefinitely, the sum either tends to become equal to a certain finite *limit*, or else it becomes infinitely great.

An infinite series is said to be **convergent** when the sum of the first n terms cannot numerically exceed some finite quantity however great n may be.

An infinite series is said to be **divergent** when the sum of the first n terms can be made numerically greater than any finite quantity by taking n sufficiently great.

278. If we can find the sum of the first n terms of a given series, we may ascertain whether it is convergent or divergent by examining whether the series remains finite, or becomes infinite, when n is made indefinitely great.

For example, the sum of the first n terms of the series

$$1 + x + x^2 + x^3 + \ldots \text{ is } \frac{1 - x^n}{1 - x}.$$

If x is numerically less than 1, the sum approaches to the finite limit $\frac{1}{1-x}$, and the series is therefore convergent.

If x is numerically greater than 1, the sum of the first n terms is $\frac{x^n-1}{x-1}$, and by taking n sufficiently great, this can be made greater than any finite quantity; thus the series is divergent.

If $x=1$, the sum of the first n terms is n, and therefore the series is divergent.

If $x=-1$, the series becomes

$$1-1+1-1+1-1+\ldots\ldots$$

The sum of an even number of terms is 0, while the sum of an odd number of terms is 1; and thus the sum oscillates between the values 0 and 1. This series belongs to a class which may be called *oscillating* or *periodic convergent series*.

279. There are many cases in which we have no method of finding the sum of the first n terms of a series. We proceed therefore to investigate rules by which we can test the convergency or divergency of a given series without effecting its summation.

280. *An infinite series in which the terms are alternately positive and negative is convergent if each term is numerically less than the preceding term.*

Let the series be denoted by

$$u_1-u_2+u_3-u_4+u_5-u_6+\ldots\ldots$$

where $$u_1>u_2>u_3>u_4>u_5\ldots\ldots$$

The given series may be written in each of the following forms:

$$(u_1-u_2)+(u_3-u_4)+(u_5-u_6)+\ldots\ldots\ldots\ldots\ (1),$$

$$u_1-(u_2-u_3)-(u_4-u_5)-(u_6-u_7)-\ldots\ldots\ldots\ldots\ (2).$$

From (1) we see that the sum of any number of terms is a positive quantity; and from (2) that the sum of any number of terms is less than u_1; hence the series is convergent.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

284. *An infinite series is convergent if from and after some fixed term the ratio of each term to the preceding term is numerically less than some quantity which is itself numerically less than unity.*

Let the series beginning from the fixed term be denoted by

$$u_1 + u_2 + u_3 + u_4 + \ldots\ldots\ldots;$$

and let $$\frac{u_2}{u_1} < r, \quad \frac{u_3}{u_2} < r, \quad \frac{u_4}{u_3} < r, \ \ldots\ldots,$$

where $r < 1$.

Then
$$\begin{aligned} & u_1 + u_2 + u_3 + u_4 + \ldots \\ &= u_1 \left(1 + \frac{u_2}{u_1} + \frac{u_3}{u_2}.\frac{u_2}{u_1} + \frac{u_4}{u_3}.\frac{u_3}{u_2}.\frac{u_2}{u_1} + \ldots\right) \\ &< u_1 \left(1 + r + r^2 + r^3 + \quad\right); \end{aligned}$$

that is, $< \dfrac{u_1}{1-r}$, since $r < 1$.

Hence the given series is convergent.

285. In the enunciation of the preceding article the student should notice the significance of the words "from and after a fixed term."

Consider the series

$$1 + 2x + 3x^2 + 4x^3 + \ldots\ldots + nx^{n-1} +$$

Here $$\frac{u_n}{u_{n-1}} = \frac{nx}{n-1} = \left(1 + \frac{1}{n-1}\right)x;$$

and by taking n sufficiently large we can make this ratio approximate to x as nearly as we please, and the ratio of each term to the preceding term will ultimately be x. Hence if $x < 1$ the series is convergent.

But the ratio $\dfrac{u_n}{u_{n-1}}$ will not be less than 1, until $\dfrac{nx}{n-1} < 1$; that is, until $n > \dfrac{1}{1-x}$.

Here we have a case of a convergent series in which the terms may increase up to a certain point and then begin to decrease. For example, if $x = \dfrac{99}{100}$, then $\dfrac{1}{1-x} = 100$, and the terms do not begin to decrease until after the 100^{th} term.

286. *An infinite series in which all the terms are of the same sign is divergent if from and after some fixed term the ratio of each term to the preceding term is greater than unity, or equal to unity.*

Let the fixed term be denoted by u_1. If the ratio is equal to unity, each of the succeeding terms is equal to u_1, and the sum of n terms is equal to nu_1; hence the series is divergent.

If the ratio is greater than unity, each of the terms after the fixed term is greater than u_1, and the sum of n terms is greater than nu_1; hence the series is divergent.

287. In the practical application of these tests, to avoid having to ascertain the particular term after which each term is greater or less than the preceding term, it is convenient to find the limit of $\frac{u_n}{u_{n-1}}$ when n is indefinitely increased; let this limit be denoted by λ.

If $\lambda < 1$, the series is convergent. [Art. 284.]

If $\lambda > 1$, the series is divergent. [Art. 286.]

If $\lambda = 1$, the series may be either convergent or divergent, and a further test will be required; for it may happen that $\frac{u_n}{u_{n-1}} < 1$ *but continually approaching to* 1 *as its limit when* n *is indefinitely increased.* In this case we cannot name any finite quantity r which is itself less than 1 and yet greater than λ. Hence the test of Art. 284 fails. If, however, $\frac{u_n}{u_{n-1}} > 1$ but continually approaching to 1 as its limit, the series is divergent by Art. 286.

We shall use "$Lim \frac{u_n}{u_{n-1}}$" as an abbreviation of the words "the limit of $\frac{u_n}{u_{n-1}}$ when n is infinite."

Example 1. Find whether the series whose n^{th} term is $\frac{(n+1)\,x^n}{n^2}$ is convergent or divergent.

Here $$\frac{u_n}{u_{n-1}} = \frac{(n+1)\,x^n}{n^2} \div \frac{n x^{n-1}}{(n-1)^2} = \frac{(n+1)\,(n-1)^2}{n^3} \cdot x\,,$$

$$Lim \frac{u_n}{u_{n-1}} = x\,;$$

hence if $x<1$ the series is convergent;

if $x>1$ the series is divergent.

If $x=1$, then $Lim\ \frac{u_n}{u_{n-1}}-1$, and a further test is required.

Example 2. Is the series

$$1^2+2^2x+3^2x^2+4^2x^3+\ldots\ldots$$

convergent or divergent?

Here $$Lim\ \frac{u_n}{u_{n-1}}=Lim\ \frac{n^2x^{n-1}}{(n-1)^2x^{n-2}}=x.$$

Hence if $x<1$ the series is convergent;

if $x>1$ the series is divergent.

If $x=1$ the series becomes $1^2+2^2+3^2+4^2+\ldots$, and is obviously divergent.

Example 3. In the series

$$a+(a+d)\,r+(a+2d)\,r^2+\ldots+(a+\overline{n-1}\,.\,d)\,r^{n-1}+\ldots,$$

$$Lim\ \frac{u_n}{u_{n-1}}=Lim\ \frac{a+(n-1)\,d}{a+(n-2)\,d}\,.\,r=r;$$

thus if $r<1$ the series is convergent, and the sum is finite. [See Art. 60, Cor.]

288. *If there are two infinite series in each of which all the terms are positive, and if the ratio of the corresponding terms in the two series is always finite, the two series are both convergent, or both divergent.*

Let the two infinite series be denoted by

$$u_1+u_2+u_3+u_4+\ldots\ldots\ldots,$$

and $$v_1+v_2+v_3+v_4+\ldots\ldots\ldots$$

The value of the fraction

$$\frac{u_1+u_2+u_3+\ldots\ldots\ldots+u_n}{v_1+v_2+v_3+\ldots\ldots\ldots+v_n}$$

lies between the greatest and least of the fractions

$$\frac{u_1}{v_1},\ \frac{u_2}{v_2},\ \ldots\ldots\ \frac{u_n}{v_n},\qquad\text{[Art. 14.]}$$

and is therefore a *finite* quantity, L say;

$$\therefore\ u_1+u_2+u_3+\ldots+u_n=L(v_1+v_2+v_3+\ldots+v_n).$$

Hence if one series is finite in value, so is the other; if one series is infinite in value, so is the other; which proves the proposition.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Example. Prove that the series

$$\frac{2}{1}+\frac{3}{4}+\frac{4}{9}+\ldots+\frac{n+1}{n^2}+$$

is divergent.

Compare the given series with $1+\frac{1}{2}+\frac{1}{3}+\ldots+\frac{1}{n}+\ldots.$

Thus if u_n and v_n denote the n^{th} terms of the given series and the auxiliary series respectively, we have

$$\frac{u_n}{v_n}=\frac{n+1}{n^2}\div\frac{1}{n}=\frac{n+1}{n};$$

hence $Lim\ \frac{u_n}{v_n}=1$, and therefore the two series are both convergent or both divergent. But the auxiliary series is divergent, therefore also the given series is divergent.

This completes the solution of Example 1. Art. 287.

291. In the application of Art. 288 it is necessary that the limit of $\frac{u_n}{v_n}$ should be finite; this will be the case if we find our auxiliary series in the following way:

Take u_n, the n^{th} term of the given series and retain only the highest powers of n. Denote the result by v_n; then the limit of $\frac{u_n}{v_n}$ is finite by Art. 270, and v_n may be taken as the n^{th} term of the auxiliary series.

Example 1. Shew that the series whose n^{th} term is $\frac{\sqrt[3]{2n^2-1}}{\sqrt[4]{3n^3+2n+5}}$ is divergent.

As n increases, u_n approximates to the value

$$\frac{\sqrt[3]{2n^2}}{\sqrt[4]{3n^3}},\ \text{or}\ \frac{\sqrt[3]{2}}{\sqrt[4]{3}}\cdot\frac{1}{n^{\frac{1}{12}}}$$

Hence, if $v_n=\frac{1}{n^{\frac{1}{12}}}$, we have $Lim\frac{u_n}{v_n}=\frac{\sqrt[3]{2}}{\sqrt[4]{3}}$, which is a finite quantity; therefore the series whose n^{th} term is $\frac{1}{n^{12}}$ may be taken as the auxiliary series. But this series is divergent [Art. 290]; therefore the given series is divergent.

Example 2. Find whether the series in which

$$u_n = \sqrt[3]{n^3+1} - n$$

is convergent or divergent.

Here
$$u_n = n\left(\sqrt[3]{1+\frac{1}{n^3}} - 1\right)$$

$$-n\left(1+\frac{1}{3n^3} - \frac{1}{9n^6} + \quad -1\right)$$

$$= \frac{1}{3n^2} - \frac{1}{9n^5} + \cdots$$

If we take $v_n - \frac{1}{n^2}$, we have

$$\frac{u_n}{v_n} = \frac{1}{3} - \frac{1}{9n^3} + \cdots$$

$$\therefore \; Lim\, \frac{u_n}{v_n} = \frac{1}{3}.$$

But the auxiliary series

$$\frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \cdots \frac{1}{n^2} + \cdots$$

is convergent, therefore the given series is convergent.

292. *To shew that the expansion of* $(1+x)^n$ *by the Binomial Theorem is convergent when* $x < 1$.

Let u_r, u_{r+1} represent the r^{th} and $(r+1)^{\text{th}}$ terms of the expansion; then

$$\frac{u_{r+1}}{u_r} = \frac{n-r+1}{r} x.$$

When $r > n+1$, this ratio is negative; that is, from this point the terms are alternately positive and negative when x is positive, and always of the same sign when x is negative.

Now when r is infinite, $Lim\, \frac{u_{r+1}}{u_r} = x$ numerically; therefore since $x < 1$ the series is convergent if all the terms are of the same sign; and therefore *a fortiori* it is convergent when some of the terms are positive and some negative. [Art. 283.]

293. *To shew that the expansion of* a^x *in ascending powers of* x *is convergent for every value of* x.

Here $\frac{u_n}{u_{n-1}} = \frac{x \log_e a}{n-1}$; and therefore $Lim\, \frac{u_n}{u_{n-1}} < 1$ whatever be the value of x; hence the series is convergent.

294. *To shew that the expansion of* $\log(1+x)$ *in ascending powers of* x *is convergent when* x *is numerically less than* 1.

Here the numerical value of $\frac{u_n}{u_{n-1}} = \frac{n-1}{n}x$, which in the limit is equal to x; hence the series is convergent when x is less than 1.

If $x=1$, the series becomes $1-\frac{1}{2}+\frac{1}{3}-\frac{1}{4}+\ldots$, and is convergent. [Art. 280.]

If $x=-1$, the series becomes $-1-\frac{1}{2}-\frac{1}{3}-\frac{1}{4}-\ldots$, and is divergent. [Art. 290.] This shews that the logarithm of zero is infinite and negative, as is otherwise evident from the equation $e^{-\infty}=0$.

295. The results of the two following examples are important, and will be required in the course of the present chapter.

Example 1. Find the limit of $\frac{\log x}{x}$ when x is infinite.

Put $x=e^y$; then

$$\frac{\log x}{x}=\frac{y}{e^y}=\frac{y}{1+y+\frac{y^2}{\lfloor 2}+\frac{y^3}{\lfloor 3}+\ldots}$$

$$=\frac{1}{\frac{1}{y}+1+\frac{y}{\lfloor 2}+\frac{y^2}{\lfloor 3}+\ldots};$$

also when x is infinite y is infinite; hence the value of the fraction is zero.

Example 2. Shew that when n is infinite the limit of $nx^n=0$, when $x<1$.

Let $x=\frac{1}{y}$, so that $y>1$;

also let $y^n=z$, so that $n\log y=\log z$; then

$$nx^n=\frac{n}{y^n}=\frac{1}{z}\cdot\frac{\log z}{\log y}=\frac{1}{\log y}\cdot\frac{\log z}{z}.$$

Now when n is infinite z is infinite, and $\frac{\log z}{z}=0$; also $\log y$ is finite; therefore

$$Lim\, nx^n=0.$$

296. It is sometimes necessary to determine whether the product of an infinite number of factors is finite or not.

Suppose the product to consist of n factors and to be denoted by

$$u_1u_2u_3\ldots\ldots u_n;$$

then if as n increases indefinitely $u_n<1$, the product will ultimately be zero, and if $u_n>1$ the product will be infinite; hence in order that the product may be finite, u_n must tend to the limit 1.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

For example, if we expand $(1-x)^{-2}$ by the Binomial Theorem, we find

$$(1-x)^{-2} = 1 + 2x + 3x^2 + 4x^3 +$$

But if we obtain the sum of n terms of this series as explained in Art. 60, it appears that

$$1 + 2x + 3x^2 + \quad + nx^{n-1} = \frac{1-x^n}{(1-x)^2} - \frac{nx^n}{1-x};$$

whence

$$\frac{1}{(1-x)^2} = 1 + 2x + 3x^2 + \quad .. + nx^{n-1} + \frac{x^n}{(1-x)^2} + \frac{nx^n}{1-x}.$$

By making n infinite, we see that $\frac{1}{(1-x)^2}$ can only be regarded as the true equivalent of the infinite series

$$1 + 2x + 3x^2 + 4x^3 + ...$$

when $\frac{x^n}{(1-x)^2} + \frac{nx^n}{1-x}$ vanishes.

If n is infinite, this quantity becomes infinite when $x = 1$, or $x > 1$, and diminishes indefinitely when $x < 1$, [Art. 295], so that it is only when $x < 1$ that we can assert that

$$\frac{1}{(1-x)^2} = 1 + 2x + 3x^2 + 4x^3 + ...\text{to inf.};$$

and we should be led to erroneous conclusions if we were to use the expansion of $(1-x)^{-2}$ by the Binomial Theorem as if it were true for all values of x. In other words, we can introduce the infinite series $1 + 2x + 3x^2 + \ldots$ into our reasoning without error if the series is convergent, but we cannot do so when the series is divergent.

The difficulties of divergent series have compelled a distinction to be made between a series and its *algebraical equivalent.* For example, if we divide 1 by $(1-x)^2$, we can always obtain as many terms as we please of the series

$$1 + 2x + 3x^2 + 4x^3 + ...$$

whatever x may be, and so in a certain sense $\frac{1}{(1-x)^2}$ may be called its *algebraical equuvalent;* yet, as we have seen, the equivalence does not really exist except when the series is con-

vergent. It is therefore more appropriate to speak of $\frac{1}{(1-x)^2}$ as the *generating function* of the series

$$1 + 2x + 3x^2 + \ldots\ldots$$

being that function which when developed by ordinary algebraical rules will give the series in question.

The use of the term *generating function* will be more fully explained in the chapter on Recurring Series.

EXAMPLES. XXI. a.

Find whether the following series are convergent or divergent:

1. $\frac{1}{x} - \frac{1}{x+a} + \frac{1}{x+2a} - \frac{1}{x+3a} + \ldots\ldots,$

x and a being positive quantities.

2. $\frac{1}{1.2} + \frac{1}{2.3} + \frac{1}{3.4} + \frac{1}{4.5} + \ldots\ldots$

3. $\frac{1}{xy} - \frac{1}{(x+1)(y+1)} + \frac{1}{(x+2)(y+2)} - \frac{1}{(x+3)(y+3)} + \ldots\ldots,$

x and y being positive quantities.

4. $\frac{x}{1.2} + \frac{x^2}{2.3} + \frac{x^3}{3.4} + \frac{x^4}{4.5} + \ldots\ldots$

5. $\frac{x}{1.2} + \frac{x^2}{3.4} + \frac{x^3}{5.6} + \frac{x^4}{7.8} + \ldots\ldots$

6. $1 + \frac{2^2}{\lfloor 2} + \frac{3^2}{\lfloor 3} + \frac{4^2}{\lfloor 4} + \ldots\ldots$

7. $\sqrt{\frac{1}{2}} + \sqrt{\frac{2}{3}} + \sqrt{\frac{3}{4}} + \sqrt{\frac{4}{5}} + \ldots\ldots$

8. $1 + 3x + 5x^2 + 7x^3 + 9x^4 + \ldots\ldots$

9. $\frac{2}{1^p} + \frac{3}{2^p} + \frac{4}{3^p} + \frac{5}{4^p} + \ldots\ldots$

10. $1 + \frac{x}{2} + \frac{x^2}{5} + \frac{x^3}{10} + \ldots + \frac{x^n}{n^2+1} + \ldots\ldots$

11. $x + \frac{3}{5}x^2 + \frac{8}{10}x^3 + \frac{15}{17}x^4 + \ldots + \frac{n^2-1}{n^2+1}x^n + \ldots\ldots$

12. $1+\frac{2}{5}x+\frac{6}{9}x^2+\frac{14}{17}x^3+\ldots+\frac{2^n-2}{2^n+1}x^{n-1}+\ldots\ldots$

13. $\frac{1}{1^p}+\frac{1}{3^p}+\frac{1}{5^p}+\frac{1}{7^p}+\ldots\ldots$

14. $2x+\frac{3x^2}{8}+\frac{4x^3}{27}+\ldots+\frac{(n+1)\,x^n}{n^3}+\ldots\ldots$

15. $\left(\frac{2^2}{1^2}-\frac{2}{1}\right)^{-1}+\left(\frac{3^3}{2^3}-\frac{3}{2}\right)^{-2}+\left(\frac{4^4}{3^4}-\frac{4}{3}\right)^{-3}+\ldots\ldots$

16. $1+\frac{1}{2^2}+\frac{2^2}{3^3}+\frac{3^3}{4^4}+\frac{4^4}{5^5}+\ldots\ldots$

17. Test the series whose general terms are

(1) $\sqrt{n^2+1}-n.$ (2) $\sqrt{n^4+1}-\sqrt{n^4-1}.$

18. Test the series

(1) $\frac{1}{x}+\frac{1}{x+1}+\frac{1}{x+2}+\frac{1}{x+3}+\ldots\ldots,$

(2) $\frac{1}{x}+\frac{1}{x-1}+\frac{1}{x+1}+\frac{1}{x-2}+\frac{1}{x+2}+\ldots\ldots$

x being a positive fraction.

19. Shew that the series

$$1+\frac{2^p}{\lfloor 2}+\frac{3^p}{\lfloor 3}+\frac{4^p}{\lfloor 4}+\ldots.$$

is convergent for all values of p.

20. Shew that the infinite series

$$u_1+u_2+u_3+u_4+\ldots\ldots$$

is convergent or divergent according as $Lim\sqrt[n]{u_n}$ is <1, or >1.

21. Shew that the product

$$\frac{2}{1}\cdot\frac{2}{3}\cdot\frac{4}{3}\cdot\frac{4}{5}\cdot\frac{6}{5}\ldots\ldots\frac{2n-2}{2n-3}\cdot\frac{2n-2}{2n-1}\cdot\frac{2n}{2n-1}$$

is finite when n is infinite.

22. Shew that when $x=1$, no term in the expansion of $(1+x)^n$ is infinite, except when n is negative and numerically greater than unity.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

that is, $$> \frac{u_1}{v_1}(v_1 + v_2 + v_3 + \ldots).$$

Hence, if the v-series is divergent the u-series is also divergent.

*300. We have seen in Art. 287 that a series is convergent or divergent according as the limit of the ratio of the n^{th} term to the *preceding* term is less than 1, or greater than 1. In the remainder of the chapter we shall find it more convenient to use this test in the equivalent form:

A series is convergent or divergent according as the limit of the ratio of the n^{th} term to the *succeeding* term is greater than 1, or less than 1; that is, according as $Lim \frac{u_n}{u_{n+1}} > 1$, or < 1.

Similarly the theorem of the preceding article may be enunciated:

The u-series will be convergent when the v-series is convergent provided that $Lim \frac{u_n}{u_{n+1}} > Lim \frac{v_n}{v_{n+1}}$; and the u-series will be divergent when the v-series is divergent provided that

$$Lim \frac{u_n}{u_{n+1}} < Lim \frac{v_n}{v_{n+1}}.$$

*301. *The series whose general term is* u_n *is convergent or divergent according as* $Lim \left\{ n \left(\frac{u_n}{u_{n+1}} - 1 \right) \right\} > 1$, or < 1.

Let us compare the given series with the auxiliary series whose general term v_n is $\frac{1}{n^p}$.

When $p > 1$ the auxiliary series is convergent, and in this case the given series is convergent if

$$\frac{u_n}{u_{n+1}} > \frac{(n+1)^p}{n^p}, \text{ or } \left(1 + \frac{1}{n}\right)^p;$$

that is, if $$\frac{u_n}{u_{n+1}} > 1 + \frac{p}{n} + \frac{p(p-1)}{2n^2} + \ldots;$$

or $$n\left(\frac{u_n}{u_{n+1}} - 1\right) > p + \frac{p(p-1)}{2n} + \ldots:$$

that is, if $$Lim \left\{ n \left(\frac{u_n}{u_{n+1}} - 1 \right) \right\} > p.$$

But the auxiliary series is convergent if p is greater than 1 by a finite quantity however small; hence the first part of the proposition is established.

When $p<1$ the auxiliary series is divergent, and by proceeding as before we may prove the second part of the proposition.

Example. Find whether the series

$$\frac{x}{1}+\frac{1}{2}\cdot\frac{x^3}{3}+\frac{1.3}{2.4}\cdot\frac{x^5}{5}+\frac{1.3.5}{2.4.6}\cdot\frac{x^7}{7}+\dots$$

is convergent or divergent.

Here $Lim\ \frac{u_n}{u_{n+1}}=\frac{1}{x^2}$; hence if $x<1$ the series is convergent, and if $x>1$ the series is divergent.

If $x=1$, $Lim\ \frac{u_n}{u_{n+1}}=1$. In this case

$$u_n=\frac{1.3.5\dots\dots(2n-3)}{2.4.6\dots\dots(2n-2)}\cdot\frac{1}{2n-1},$$

and

$$\frac{u_n}{u_{n+1}}=\frac{2n(2n+1)}{(2n-1)(2n-1)};$$

$$n\left(\frac{u_n}{u_{n+1}}-1\right)=\frac{n(6n-1)}{(2n-1)^2};$$

$$\therefore\ Lim\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)\right\}=\frac{3}{2};$$

hence when $x=1$ the series is convergent.

*302. *The series whose general term is* u_n *is convergent or divergent, according as* $Lim\left(n\log\frac{u_n}{u_{n+1}}\right)>1$, *or* <1.

Let us compare the given series with the series whose general term is $\frac{1}{n^p}$.

When $p>1$ the auxiliary series is convergent, and in this case the given series is convergent if

$$\frac{u_n}{u_{n+1}}>\left(1+\frac{1}{n}\right)^r;$$ [Art. 300.]

that is, if

$$\log\frac{u_n}{u_{n+1}}>p\log\left(1+\frac{1}{n}\right);$$

or if

$$\log\frac{u_n}{u_{n+1}}>\frac{p}{n}-\frac{P}{2n^2}+\dots;$$

that is, if $$Lim\left(n\log\frac{u_n}{u_{n+1}}\right)>p.$$

Hence the first part of the proposition is established.

When $p<1$ we proceed in a similar manner; in this case the auxiliary series is divergent.

Example. Find whether the series

$$x+\frac{2^2x^2}{\lfloor\underline{2}}+\frac{3^3x^3}{\lfloor\underline{3}}+\frac{4^4x^4}{\lfloor\underline{4}}+\frac{5^5x^5}{\lfloor\underline{5}}+\dots$$

is convergent or divergent.

Here $$\frac{u_n}{u_{n+1}}=\frac{n^nx^n}{\lfloor\underline{n}}\div\frac{(n+1)^{n+1}x^{n+1}}{\lfloor\underline{n+1}}=\frac{n^n}{(n+1)^nx}=\frac{1}{\left(1+\frac{1}{n}\right)^nx};$$

$$\therefore\ Lim\frac{u_n}{u_{n+1}}=\frac{1}{ex}.$$ [Art. 220 Cor.].

Hence if $x<\frac{1}{e}$ the series is convergent, if $x>\frac{1}{e}$ the series is divergent.

If $x=\frac{1}{e}$, then $$\frac{u_n}{u_{n+1}}=\frac{e}{\left(1+\frac{1}{n}\right)^n};$$

$$\therefore\ \log\frac{u_n}{u_{n+1}}=\log e-n\log\left(1+\frac{1}{n}\right)$$

$$=1-n\left(\frac{1}{n}-\frac{1}{2n^2}+\frac{1}{3n^3}-\dots\right)$$

$$=\frac{1}{2n}-\frac{1}{3n^2}+\dots;$$

$$\therefore\ n\log\frac{u_n}{u_{n+1}}-\frac{1}{2}\quad\frac{1}{3n}+\dots;$$

$$\therefore\ Lim\left(n\log\frac{u_n}{u_{n+1}}\right)=\frac{1}{2};$$

hence when $x=\frac{1}{e}$ the series is divergent.

*303. If $Lim\frac{u_n}{u_{n+1}}-1$, and also $Lim\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)\right\}=1$, the tests given in Arts. 300, 301 are not applicable.

To discover a further test we shall make use of the auxiliary series whose general term is $\frac{1}{n(\log n)^p}$. In order to establish the convergency or divergency of this series we need the theorem proved in the next article.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

*305. *The series whose general term is* $\frac{1}{n\,(\log n)^p}$ *is convergent if* $p > 1$, *and divergent if* $p = 1$, *or* $p < 1$.

By the preceding article the series will be convergent or divergent for the same values of p as the series whose general term is

$$a^n \times \frac{1}{a^n\,(\log a^n)^p}, \text{ or } \frac{1}{(n \log a)^p}, \text{ or } \frac{1}{(\log a)^p} \times \frac{1}{n^p}.$$

The constant factor $\frac{1}{(\log a)^p}$ is common to every term; therefore the given series will be convergent or divergent for the same values of p as the series whose general term is $\frac{1}{n^p}$. Hence the required result follows. [Art. 290.]

*306. *The series whose general term is* u_n *is convergent or divergent according as* $Lim \left[\left\{n\left(\frac{u_n}{u_{n+1}} - 1\right) - 1\right\} \log n\right] > 1$, or < 1.

Let us compare the given series with the series whose general term is $\frac{1}{n(\log n)^p}$.

When $p > 1$ the auxiliary series is convergent, and in this case the given series is convergent by Art. 299, if

$$\frac{u_n}{u_{n+1}} > \frac{(n+1)\{\log(n+1)\}^p}{n\,(\log n)^p} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots(1).$$

Now when n is very large,

$$\log(n+1) = \log n + \log\left(1 + \frac{1}{n}\right) = \log n + \frac{1}{n}, \text{ nearly;}$$

Hence the condition (1) becomes

$$\frac{u_n}{u_{n+1}} > \left(1 + \frac{1}{n}\right)\left(1 + \frac{1}{n \log n}\right)^p;$$

that is,
$$\frac{u_n}{u_{n+1}} > \left(1 + \frac{1}{n}\right)\left(1 + \frac{p}{n \log n}\right);$$

that is,
$$\frac{u_n}{u_{n+1}} > 1 + \frac{1}{n} + \frac{p}{n \log n};$$

or $$n\left(\frac{u_n}{u_{n+1}}-1\right)>1+\frac{p}{\log n};$$

or $$\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)-1\right\}\log n>p.$$

Hence the first part of the proposition is established. The second part may be proved in the manner indicated in Art. 301.

Example. Is the series

$$1+\frac{2^2}{3^2}+\frac{2^2\,.\,4^2}{3^2\,.\,5^2}+\frac{2^2\,.\,4^2\,.\,6^2}{3^2\,.\,5^2\,.\,7^2}+\ldots\ldots$$

convergent or divergent?

Here $$\frac{u_n}{u_{n+1}}=\frac{(2n+1)^2}{(2n)^2}=1+\frac{1}{n}+\frac{1}{4n^2} \quad \ldots\ldots\ldots\ldots\ldots\ldots (1).$$

$Lim\ \frac{u_n}{u_{n+1}}-1$, and we proceed to the next test.

From (1), $$n\left(\frac{u_n}{u_{n+1}}-1\right)=1+\frac{1}{4n} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

$Lim\ \left\{n\left(\frac{u_n}{u_{n+1}}-1\right)\right\}=1$, and we pass to the next test.

From (2), $$\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)-1\right\}\log n=\frac{\log n}{4n};$$

$$Lim\left[\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)-1\right\}\log n\right]=0,$$

since $Lim\ \frac{\log n}{n}=0$ [Art. 295]; hence the given series is divergent.

*307. We have shewn in Art. 183 that the use of divergent series in mathematical reasoning may lead to erroneous results. But even when the infinite series are convergent it is necessary to exercise caution in using them.

For instance, the series

$$1-x+\frac{x^2}{\sqrt[4]{2}}-\frac{x^3}{\sqrt[4]{3}}+\frac{x^4}{\sqrt[4]{4}}-\frac{x^5}{\sqrt[4]{5}}+\ \ldots$$

is convergent when $x=1$. [Art. 280.] But if we multiply the series by itself, the coefficient of x^{2n} in the product is

$$\frac{1}{\sqrt[4]{2n}}+\frac{1}{\sqrt[4]{2n-1}}+\frac{1}{\sqrt[4]{2}\,.\sqrt[4]{2n-2}}+\ldots+\frac{1}{\sqrt[4]{r}\,.\ \sqrt[4]{2n-r}}+\ldots+\frac{1}{\sqrt[4]{2n}}.$$

Denote this by a_{2n}; then since

$$\frac{1}{\sqrt[4]{r}\,.\,\sqrt[4]{2n-r}} > \frac{1}{(\sqrt[4]{n})^2}, \text{ or } > \frac{1}{\sqrt{n}},$$

$a_{2n} > \dfrac{2n+1}{\sqrt{n}}$, and is therefore infinite when n is infinite.

If $x=1$, the product becomes

$$a_0 - a_1 + a_2 - a_3 + \ldots + a_{2n} - a_{2n+1} + a_{2n+2} - \ldots,$$

and since the terms a_{2n}, a_{2n+1}, a_{2n+2} are infinite, the series has no arithmetical meaning.

This leads us to enquire under what conditions the product of two infinite convergent series is also convergent.

*308. Let us denote the two infinite series

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots + a_{2n}x^{2n} + \ldots$$
$$b_0 + b_1x + b_2x^2 + b_3x^3 + \ldots + b_{2n}x^{2n} + \ldots$$

by A and B respectively.

If we multiply these series together we obtain a result of the form

$$a_0b_0 + (a_1b_0 + a_0b_1)\,x + (a_2b_0 + a_1b_1 + a_0b_2)\,x^2 + \ldots$$

Suppose this series to be *continued to infinity* and let us denote it by C; then we have to examine under what conditions C may be regarded as the true arithmetical equivalent of the product AB.

First suppose that all the terms in A and B are positive.

Let A_{2n}, B_{2n}, C_{2n} denote the series formed by taking the first $2n+1$ terms of A, B, C respectively.

If we multiply together the two series A_{2n}, B_{2n}, the coefficient of each power of x in their product is equal to the coefficient of the like power of x in C as far as the term x^{2n}; but in $A_{2n}B_{2n}$ there are terms containing powers of x higher than x^{2n}, whilst x^{2n} is the highest power of x in C_{2n}; hence

$$A_{2n}B_{2n} > C_{2n}.$$

If we form the product A_nB_n the last term is $a_nb_nx^{2n}$; but C_{2n} includes all the terms in the product and some other terms besides; hence

$$C_{2n} > A_nB_n.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

*EXAMPLES. XXI. b.

Find whether the following series are convergent or divergent:

1. $1+\frac{1}{2}\cdot\frac{x^2}{4}+\frac{1.3.5}{2.4.6}\cdot\frac{x^4}{8}+\frac{1.3.5.7.9}{2.4.6.8.10}\cdot\frac{x^6}{12}+\ldots\ldots$

2. $1+\frac{3}{7}x+\frac{3.6}{7.10}x^2+\frac{3.6.9}{7.10.13}x^3+\frac{3.6.9.12}{7.10.13.16}x^4+\ldots\ldots$

3. $x^2+\frac{2^2}{3.4}x^4+\frac{2^2.4^2}{3.4.5.6}x^6+\frac{2^2.4^2.6^2}{3.4.5.6.7.8}x^8+\ldots\ldots$

4. $1+\frac{2x}{\lfloor\underline{2}}+\frac{3^2x^2}{\lfloor\underline{3}}+\frac{4^3x^3}{\lfloor\underline{4}}+\frac{5^4x^4}{\lfloor\underline{5}}+\ldots\ldots$

5. $1+\frac{1}{2}x+\frac{\lfloor\underline{2}}{3^2}x^2+\frac{\lfloor\underline{3}}{4^3}x^3+\frac{\lfloor\underline{4}}{5^4}x^4+\ldots\ldots$

6. $\frac{1^2}{2^2}+\frac{1^2.3^2}{2^2.4^2}x+\frac{1^2.3^2.5^2}{2^2.4^2.6^2}x^2+\ldots\ldots$

7. $1+\frac{\alpha(1-\alpha)}{1^2}+\frac{(1+\alpha)\alpha(1-\alpha)(2-\alpha)}{1^2.2^2}$
$+\frac{(2+\alpha)(1+\alpha)\alpha(1-\alpha)(2-\alpha)(3-\alpha)}{1^2.2^2.3^2}+\ldots\ldots$

α being a proper fraction.

8. $\frac{a+x}{1}+\frac{(a+2x)^2}{\lfloor\underline{2}}+\frac{(a+3x)^3}{\lfloor\underline{3}}+\ldots\ldots$

9. $1+\frac{a.\beta}{1.\gamma}x+\frac{a(a+1)\beta(\beta+1)}{1.2.\gamma(\gamma+1)}x^2$
$+\frac{a(a+1)(a+2)\beta(\beta+1)(\beta+2)}{1.2.3.\gamma(\gamma+1)(\gamma+2)}x^3+\ldots\ldots$

10. $x^2(\log 2)^q+x^3(\log 3)^q+x^4(\log 4)^q+\ldots\ldots$

11. $1+\alpha+\frac{\alpha(\alpha+1)}{1.2}+\frac{\alpha(\alpha+1)(\alpha+2)}{1.2.3}+\ldots\ldots$

12. If $\frac{u_n}{u_{n+1}}=\frac{n^k+An^{k-1}+Bn^{k-2}+Cn^{k-3}+\ldots}{n^k+an^{k-1}+bn^{k-2}+cn^{k-3}+\ldots}$, where k is a positive integer, shew that the series $u_1+u_2+u_3+.$ is convergent if $A-\alpha-1$ is positive, and divergent if $A-\alpha-1$ is negative or zero.

CHAPTER XXII.

UNDETERMINED COEFFICIENTS.

309. In Art. 230 of the *Elementary Algebra*, it was proved that if any rational integral function of x vanishes when $x=a$, it is divisible by $x-a$. [See also Art. 514. Cor.]

Let $f \quad -p_0x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_n$

be a rational integral function of x of n dimensions, which vanishes when x is equal to each of the unequal quantities

$$a_1,\ a_2,\ a_3,\ \ldots\ldots\ a_n.$$

Denote the function by $f(x)$; then since $f(x)$ is divisible by $x-a_1$, we have

$$f(x)=(x-a_1)\,(p_0x^{n-1}+\ldots\ldots),$$

the quotient being of $n-1$ dimensions.

Similarly, since $f(x)$ is divisible by $x-a_2$, we have

$$p_0x^{n-1}+\ldots\ldots-(x-a_2)\,(p_0x^{n-2}+\quad\ ),$$

the quotient being of $n-2$ dimensions; and

$$p_0x^{n-2}+\ldots\ldots-(x-a_3)\,(p_0x^{n-3}+\ldots\ldots).$$

$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$

Proceeding in this way, we shall finally obtain after n divisions

$$f(x)=p_0\,(x-a_1)\,(x-a_2)\,(x-a_3)\ \ldots\ldots\ (x-a_n).$$

310. *If a rational integral function of* n *dimensions vanishes for more than* n *values of the variable, the coefficient of each power of the variable must be zero.*

Let the function be denoted by $f(x)$, where

$$f(x)=p_0x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_n;$$

and suppose that $f(x)$ vanishes when x is equal to each of the unequal values $a_1, a_2, a_3 \ldots\ldots a_n$; then

$$f(x) = p_0 (x-a_1)(x-a_2)(x-a_3) \ldots\ldots (x-a_n).$$

Let c be another value of x which makes $f(x)$ vanish; then since $f(c) = 0$, we have

$$p_0 (c-a_1)(c-a_2)(c-a_3) \ldots\ldots (c-a_n) = 0;$$

and therefore $p_0 = 0$, since, by hypothesis, none of the other factors is equal to zero. Hence $f(x)$ reduces to

$$p_1 x^{n-1} + p_2 x^{n-2} + p_3 x^{n-3} + \ldots\ldots + p_n$$

By hypothesis this expression vanishes for more than n values of x, and therefore $p_1 = 0$.

In a similar manner we may shew that each of the coefficients $p_2, p_3, \ldots\ldots p_n$ must be equal to zero.

This result may also be enunciated as follows:

If a rational integral function of n *dimensions vanishes for more than* n *values of the variable, it must vanish for every value of the variable.*

Cor. If the function $f(x)$ vanishes for more than n values of x, the *equation* $f(x) = 0$ has more than n roots.

Hence also, *if an equation of* n *dimensions has more than* n *roots it is an identity.*

Example. Prove that

$$\frac{(x-b)(x-c)}{(a-b)(a-c)} + \frac{(x-c)(x-a)}{(b-c)(b-a)} + \frac{(x-a)(x-b)}{(c-a)(c-b)} = 1.$$

This equation is of *two* dimensions, and it is evidently satisfied by each of the *three* values a, b, c; hence it is an identity.

311. *If two rational integral functions of* n *dimensions are equal for more than* n *values of the variable, they are equal for every value of the variable.*

Suppose that the two functions

$$p_0 x^n + p_1 x^{n-1} + p_2 x^{n-2} + \ldots\ldots + p_n,$$

$$q_0 x^n + q_1 x^{n-1} + q_2 x^{n-2} + \ldots\ldots + q_n,$$

are equal for more than n values of x; then the expression

$$(p_0 - q_0) x^n + (p_1 - q_1) x^{n-1} + (p_2 - q_2) x^{n-2} + \ldots\ldots + (p_n - q_n)$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Hence the sum $= A + \frac{2n}{3} + n^2 + \frac{1}{3}n^3$

To find A, put $n=1$; the series then reduces to its first term, and

$$2 = A + 2, \text{ or } A = 0.$$

Hence $1.2+2.3+3.4+\ldots+n(n+1)=\frac{1}{3}n(n+1)(n+2)$.

NOTE. It will be seen from this example that when the n^{th} term is a rational integral function of n, it is sufficient to assume for the sum a function of n which is of one dimension higher than the n^{th} term of the series.

Example 2. Find the conditions that x^3+px^2+qx+r may be divisible by x^2+ax+b.

Assume $x^3+px^2+qx+r=(x+k)(x^2+ax+b)$.

Equating the coefficients of the like powers of x, we have

$$k+a=p,\ ak+b=q,\ kb=r.$$

From the last equation $k=\frac{r}{b}$; hence by substitution we obtain

$$\frac{r}{b}+a=p, \text{ and } \frac{ar}{b}+b=q;$$

that is, $r=b(p-a)$, and $ar=b(q-b)$;

which are the conditions required.

EXAMPLES. XXII. a.

Find by the method of Undetermined Coefficients the sum of

1. $1^2+3^2+5^2+7^2+\ldots$to n terms.
2. $1.2.3+2.3.4+3.4.5+\ldots$to n terms.
3. $1.2^2+2.3^2+3.4^2+4.5^2+\ldots$to n terms.
4. $1^3+3^3+5^3+7^3+\ldots$to n terms.
5. $1^4+2^4+3^4+4^4+\ldots$to n terms.
6. Find the condition that $x^3-3px+2q$ may be divisible by a factor of the form $x^2+2ax+a^2$.
7. Find the conditions that ax^3+bx^2+cx+d may be a perfect cube.
8. Find the conditions that $a^2x^4+bx^3+cx^2+dx+f^2$ may be a perfect square.
9. Prove that $ax^2+2bxy+cy^2+2dx+2ey+f$ is a perfect square, if $b^2=ac$, $d^2=af$, $e^2=cf$.

10. If ax^3+bx^2+cx+d is divisible by x^2+h^2, prove that $ad=bc$.

11. If $x^5-5qx+4r$ is divisible by $(x-c)^2$, shew that $q^5=r^4$

12. Prove the identities:

(1) $$\frac{a^2(x-b)(x-c)}{(a-b)(a-c)}+\frac{b^2(x-c)(x-a)}{(b-c)(b-a)}+\frac{c^2(x-a)(x-b)}{(c-a)(c-b)}=x^2.$$

(2) $$\frac{(x-b)(x-c)(x-d)}{(a-b)(a-c)(a-d)}+\frac{(x-c)(x-d)(x-a)}{(b-c)(b-d)(b-a)}$$
$$+\frac{(x-d)(x-a)(x-b)}{(c-d)(c-a)(c-b)}+\frac{(x-a)(x-b)(x-c)}{(d-a)(d-b)(d-c)}=1.$$

13. Find the condition that

$$ax^2+2hxy+by^2+2gx+2fy+c$$

may be the product of two factors of the form

$$px+qy+r, \quad p'x+q'y+r'.$$

14. If $\xi=lx+my+nz$, $\eta=nx+ly+mz$, $\zeta=mx+ny+lz$, and if the same equations are true for all values of x, y, z when ξ, η, ζ are interchanged with x, y, z respectively, shew that

$$l^2+2mn=1, \quad m^2+2ln=0, \quad n^2+2lm=0.$$

15. Shew that the sum of the products $n-r$ together of the n quantities a, a^2, a^3, ... a^n is

$$\frac{(a^{r+1}-1)(a^{r+2}-1)\ldots(a^n-1)}{(a-1)(a^2-1)\ldots(a^{n-r}-1)}\,a^{\frac{1}{2}(n-r)(n-r+1)}.$$

313. *If the infinite series* $a_0+a_1x+a_2x^2+a_3x^3+\ldots\ldots$ *is equal to zero for every finite value of* x *for which the series is convergent, then each coefficient must be equal to zero identically.*

Let the series be denoted by S, and let S_1 stand for the expression $a_1+a_2x+a_3x^2+\ldots\ldots$; then $S=a_0+xS_1$, and therefore, by hypothesis, $a_0+xS_1=0$ for all finite values of x. But since S is convergent, S_1 cannot exceed some finite limit; therefore by taking x small enough xS_1 may be made as small as we please. In this case the limit of S is a_0; but S is *always* zero, therefore a_0 must be equal to zero identically.

Removing the term a_0, we have $xS_1=0$ for all finite values of x; that is, $a_1+a_2x+a_3x^2+$ vanishes for all finite values of x.

Similarly, we may prove in succession that each of the coefficients a_1, a_2, a_3,..... is equal to zero identically.

314. *If two infinite series are equal to one another for every finite value of the variable for which both series are convergent, the coefficients of like powers of the variable in the two series are equal.*

Suppose that the two series are denoted by

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots\ldots$$

and

$$A_0 + A_1x + A_2x^2 + A_3x^3 + \ldots\ldots ;$$

then the expression

$$a_0 - A_0 + (a_1 - A_1)\,x + (a_2 - A_2)\,x^2 + (a_3 - A_3)\,x^3 +$$

vanishes for all values of x within the assigned limits; therefore by the last article

$$a_0 - A_0 = 0,\ \ a_1 - A_1 = 0,\ \ a_2 - A_2 = 0,\ \ a_3 - A_3 = 0, \ldots\ldots$$

that is,

$$a_0 = A_0,\ \ a_1 = A_1,\ \ a_2 = A_2,\ \ a_3 = A_3, \ldots\ldots ;$$

which proves the proposition.

Example 1. Expand $\dfrac{2+x^2}{1+x-x^2}$ in a series of ascending powers of x as far as the term involving x^5.

Let

$$\frac{2+x^2}{1+x-x^2} = a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots,$$

where $a_0, a_1, a_2, a_3, \ldots$ are constants whose values are to be determined; then

$$2 + x^2 = (1 + x - x^2)\,(a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots).$$

In this equation we may equate the coefficients of like powers of x on each side. On the right-hand side the coefficient of x^n is $a_n + a_{n-1} - a_{n-2}$, and therefore, since x^2 is the highest power of x on the left, for all values of $n > 2$ we have

$$a_n + a_{n-1} - a_{n-2} = 0 ;$$

this will suffice to find the successive coefficients after the first three have been obtained. To determine these we have the equations

$$a_0 = 2,\ \ a_1 + a_0 = 0,\ \ a_2 + a_1 - a_0 = 1 ;$$

whence

$$a_0 = 2,\ \ a_1 = -2,\ \ a_2 = 5.$$

Also

$$a_3 + a_2 - a_1 = 0, \text{ whence } a_3 = -7 ;$$

$$a_4 + a_3 - a_2 = 0, \text{ whence } a_4 = 12 ;$$

and

$$a_5 + a_4 - a_3 = 0, \text{ whence } a_5 = -19 ;$$

thus

$$\frac{2+x^2}{1+x-x^2} = 2 - 2x + 5x^2 - 7x^3 + 12x^4 - 19x^5 + \ldots$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

EXAMPLES. XXII. b.

Expand the following expressions in ascending powers of x as far as x^3.

1. $\dfrac{1+2x}{1-x-x^2}$.

2. $\dfrac{1-8x}{1-x-6x^2}$.

3. $\dfrac{1+x}{2+x+x^2}$.

4. $\dfrac{3+x}{2-x-x^2}$.

5. $\dfrac{1}{1+ax-ax^2-x^3}$.

6. Find a and b so that the n^{th} term in the expansion of $\dfrac{a+bx}{(1-x)^2}$ may be $(3n-2)x^{n-1}$

7. Find a, b, c so that the coefficient of x^n in the expansion of $\dfrac{a+bx+cx^2}{(1-x)^3}$ may be n^2+1.

8. If $y^2+2y=x(y+1)$, shew that one value of y is

$$\tfrac{1}{2}x+\tfrac{1}{8}x^2-\tfrac{1}{128}x^4+$$

9. If $cx^3+ax-y=0$, shew that one value of x is

$$\frac{y}{a}-\frac{cy^3}{a^4}+\frac{3c^2y^5}{a^7}-\frac{12c^3y^7}{a^{10}}\ldots\ldots$$

Hence shew that $x=\cdot00999999$ is an approximate solution of the equation $x^3+100x-1=0$. To how many places of decimals is the result correct?

10. In the expansion of $(1+x)(1+ax)(1+a^2x)(1+a^3x)\ldots\ldots$, the number of factors being infinite, and $a<1$, shew that the coefficient of x^r is $\dfrac{1}{(1-a)(1-a^2)(1-a^3)\ldots\ldots(1-a^r)}a^{\frac{1}{2}r(r-1)}$

11. When $a<1$, find the coefficient of x^n in the expansion of

$$\frac{1}{(1-ax)(1-a^2x)(1-a^3x)\ldots\ldots\text{to inf.}}.$$

12. If n is a positive integer, shew that

(1) $n^{n+1}-n(n-1)^{n+1}+\dfrac{n(n-1)}{\lfloor\underline{2}}(n-2)^{n+1}-\ldots\ldots-\tfrac{1}{2}n\,\lfloor\underline{n+1}$;

(2) $n^n-(n+1)(n-1)^n+\dfrac{(n+1)n}{\lfloor\underline{2}}(n-2)^n-\qquad\qquad-1$.

the series in each case being extended to n terms; and

(3) $1^n-n2^n+\dfrac{n(n-1)}{1\,.\,2}3^n-\ldots\ldots=(-1)^n\,\lfloor\underline{n}$;

(4) $(n+p)^n-n(n+p-1)^n+\dfrac{n(n-1)}{\lfloor\underline{2}}(n+p-2)^n-\ldots\ldots-\lfloor\underline{n}$;

the series in the last two cases being extended to $n+1$ terms.

CHAPTER XXIII.

Partial Fractions.

315. In elementary Algebra, a group of fractions connected by the signs of addition and subtraction is reduced to a more simple form by being collected into one single fraction whose denominator is the lowest common denominator of the given fractions. But the converse process of separating a fraction into a group of simpler, or *partial*, fractions is often required. For example, if we wish to expand $\frac{3-5x}{1-4x+3x^2}$ in a series of ascending powers of x, we might use the method of Art. 314, Ex. 1, and so obtain as many terms as we please. But if we wish to find the general term of the series this method is inapplicable, and it is simpler to express the given fraction in the equivalent form $\frac{1}{1-x}+\frac{2}{1-3x}$. Each of the expressions $(1-x)^{-1}$ and $(1-3x)^{-1}$ can now be expanded by the Binomial Theorem, and the general term obtained.

316. In the present chapter we shall give some examples illustrating the decomposition of a rational fraction into partial fractions. For a fuller discussion of the subject the reader is referred to Serret's *Cours d'Algèbre Supérieure*, or to treatises on the Integral Calculus. In these works it is proved that any rational fraction may be resolved into a series of partial fractions; and that to any linear factor $x-a$ in the denominator there corresponds a partial fraction of the form $\frac{A}{x-a}$; to any linear factor $x-b$ occurring *twice* in the denominator there correspond *two* partial fractions, $\frac{B_1}{x-b}$ and $\frac{B_2}{(x-b)^2}$. If $x-b$ occurs *three* times, there is an additional fraction $\frac{B_3}{(x-b)^3}$; and so on. To

any quadratic factor x^2+px+q there corresponds a partial fraction of the form $\dfrac{Px+Q}{x^2+px+q}$; if the factor x^2+px+q occurs twice, there is a second partial fraction $\dfrac{P_1x+Q_1}{(x^2+px+q)^2}$; and so on.

Here the quantities A_1, B_1, B_2, B_3,.....P, Q, P_1, Q_1 are all independent of x.

We shall make use of these results in the examples that follow.

Example 1. Separate $\dfrac{5x-11}{2x^2+x-6}$ into partial fractions.

Since the denominator $2x^2+x-6=(x+2)(2x-3)$, we assume

$$\frac{5x-11}{2x^2+x-6}=\frac{A}{x+2}+\frac{B}{2x-3},$$

where A and B are quantities independent of x whose values have to be determined.

Clearing of fractions,

$$5x-11=A(2x-3)+B(x+2).$$

Since this equation is identically true, we may equate coefficients of like powers of x; thus

$$2A+B=5, \quad -3A+2B=-11;$$

whence

$$A=3, \quad B=-1.$$

$$\therefore \quad \frac{5x-11}{2x^2+x-6}=\frac{3}{x+2}-\frac{1}{2x-3}.$$

Example 2. Resolve $\dfrac{mx+n}{(x-a)(x+b)}$ into partial fractions.

Assume

$$\frac{mx+n}{(x-a)(x+b)}=\frac{A}{x-a}+\frac{B}{x+b}.$$

$$\therefore \quad mx+n=A(x+b)+B(x-a).....(1).$$

We might now equate coefficients and find the values of A and B, but it is simpler to proceed in the following manner.

Since A and B are independent of x, we may give to x any value we please.

In (1) put $x-a=0$, or $x=a$; then

$$A=\frac{ma+n}{a+b};$$

putting $x+b=0$, or $x=-b$, $\quad B=\dfrac{mb-n}{a+b}$.

$$\therefore \quad \frac{mx+n}{(x-a)(x+b)}=\frac{1}{a+b}\left(\frac{ma+n}{x-a}+\frac{mb-n}{x+b}\right).$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Example. Resolve $\dfrac{9x^3-24x^2+48x}{(x-2)^4(x+1)}$ into partial fractions.

Assume $$\frac{9x^3-24x^2+48x}{(x-2)^4(x+1)}=\frac{A}{x+1}+\frac{f(x)}{(x-2)^4},$$

where A is some constant, and $f(x)$ a function of x whose value remains to be determined.

$$\therefore\quad 9x^3-24x^2+48x=A(x-2)^4+(x+1)f(x).$$

Let $x=-1$, then $A=-1$.

Substituting for A and transposing,

$$(x+1)f(x)=(x-2)^4+9x^3-24x^2+48x=x^4+x^3+16x+16;$$

$$f(x)=x^3+16.$$

To determine the partial fractions corresponding to $\dfrac{x^3+16}{(x-2)^4}$, put $x-2=z$;

then $$\frac{x^3+16}{(x-2)^4}=\frac{(z+2)^3+16}{z^4}=\frac{z^3+6z^2+12z+24}{z^4}$$

$$=\frac{1}{z}+\frac{6}{z^2}+\frac{12}{z^3}+\frac{24}{z^4}$$

$$=\frac{1}{x-2}+\frac{6}{(x-2)^2}+\frac{12}{(x-2)^3}+\frac{24}{(x-2)^4}.$$

$$\therefore\quad \frac{9x^3-24x^2+48x}{(x-2)^4(x+1)}=-\frac{1}{x+1}+\frac{1}{x-2}+\frac{6}{(x-2)^2}+\frac{12}{(x-2)^3}+\frac{24}{(x-2)^4}.$$

318. In all the preceding examples the numerator has been of lower dimensions than the denominator; if this is not the case, we divide the numerator by the denominator until a remainder is obtained which is of lower dimensions than the denominator.

Example. Resolve $\dfrac{6x^3+5x^2-7}{3x^2-2x-1}$ into partial fractions.

By division,

$$\frac{6x^3+5x^2-7}{3x^2-2x-1}=2x+3+\frac{8x-4}{3x^2-2x-1};$$

and $$\frac{8x-4}{3x^2-2x-1}=\frac{5}{3x+1}+\frac{1}{x-1};$$

$$\therefore\quad \frac{6x^3+5x^2-7}{3x^2-2x-1}=2x+3+\frac{5}{3x+1}+\frac{1}{x-1}.$$

319. We shall now explain how resolution into partial fractions may be used to facilitate the expansion of a rational fraction in ascending powers of x.

Example 1. Find the general term of $\dfrac{3x^2+x-2}{(x-2)^2(1-2x)}$ when expanded in a series of ascending powers of x.

By Ex. 4, Art. 316, we have

$$\frac{3x^2+x-2}{(x-2)^2(1-2x)} = -\frac{1}{3(1-2x)} - \frac{5}{3(x-2)} - \frac{4}{(x-2)^2}$$

$$= -\frac{1}{3(1-2x)} + \frac{5}{3(2-x)} - \frac{4}{(2-x)^2}$$

$$= -\frac{1}{3}(1-2x)^{-1} + \frac{5}{6}\left(1-\frac{x}{2}\right)^{-1} - \left(1-\frac{x}{2}\right)^{-2}$$

Hence the general term of the expansion is

$$\left(-\frac{2^r}{3} + \frac{5}{6}\cdot\frac{1}{2^r} - \frac{r+1}{2^r}\right)x^r.$$

Example 2. Expand $\dfrac{7+x}{(1+x)(1+x^2)}$ in ascending powers of x and find the general term.

Assume $$\frac{7+x}{(1+x)(1+x^2)} = \frac{A}{1+x} + \frac{Bx+C}{1+x^2};$$

$$\therefore \quad 7+x = A(1+x^2) + (Bx+C)(1+x).$$

Let $1+x=0$, then $A=3$;

equating the absolute terms, $7 = A+C$, whence $C=4$;

equating the coefficients of x^2, $0 = A+B$, whence $B=-3$.

$$\therefore \quad \frac{7+x}{(1+x)(1+x^2)} = \frac{3}{1+x} + \frac{4-3x}{1+x^2}$$

$$= 3(1+x)^{-1} + (4-3x)(1+x^2)^{-1}$$

$$= 3\{1 - x + x^2 - \qquad + (-1)^p x^p + \ldots\}$$

$$+ (4-3x)\{1 - x^2 + x^4 - \ldots\ldots + (-1)^p x^{2p} + \ldots\}.$$

To find the coefficient of x^r:

(1) If r is even, the coefficient of x^r in the second series is $4(-1)^{\frac{r}{2}}$; therefore in the expansion the coefficient of x^r is $3 + 4(-1)^{\frac{r}{2}}$.

(2) If r is odd, the coefficient of x^r in the second series is $-3(-1)^{\frac{r-1}{2}}$, and the required coefficient is $3(-1)^{\frac{r+1}{2}} - 3$.

EXAMPLES. XXIII.

Resolve into partial fractions:

1. $\dfrac{7x-1}{1-5x+6x^2}$.

2. $\dfrac{46+13x}{12x^2-11x-15}$.

3. $\dfrac{1+3x+2x^2}{(1-2x)(1-x^2)}$.

4. $\dfrac{x^2-10x+13}{(x-1)(x^2-5x+6)}$.

5. $\dfrac{2x^3+x^2-x-3}{x(x-1)(2x+3)}$.

6. $\dfrac{9}{(x-1)(x+2)^2}$.

7. $\dfrac{x^4-3x^3-3x^2+10}{(x+1)^2(x-3)}$.

8. $\dfrac{26x^2+208x}{(x^2+1)(x+5)}$.

9. $\dfrac{2x^2-11x+5}{(x-3)(x^2+2x-5)}$.

10. $\dfrac{3x^3-8x^2+10}{(x-1)^4}$.

11. $\dfrac{5x^3+6x^2+5x}{(x^2-1)(x+1)^3}$.

Find the general term of the following expressions when expanded in ascending powers of x.

12. $\dfrac{1+3x}{1+11x+28x^2}$.

13. $\dfrac{5x+6}{(2+x)(1-x)}$.

14. $\dfrac{x^2+7x+3}{x^2+7x+10}$.

15. $\dfrac{2x-4}{(1-x^2)(1-2x)}$.

16. $\dfrac{4+3x+2x^2}{(1-x)(1+x-2x^2)}$.

17. $\dfrac{3+2x-x^2}{(1+x)(1-4x)^2}$.

18. $\dfrac{4+7x}{(2+3x)(1+x)^2}$.

19. $\dfrac{2x+1}{(x-1)(x^2+1)}$.

20. $\dfrac{1-x+2x^2}{(1-x)^3}$.

21. $\dfrac{1}{(1-ax)(1-bx)(1-cx)}$.

22. $\dfrac{3-2x^2}{(2-3x+x^2)^2}$.

23. Find the sum of n terms of the series

(1) $\dfrac{1}{(1+x)(1+x^2)}+\dfrac{x}{(1+x^2)(1+x^3)}+\dfrac{x^2}{(1+x^3)(1+x^4)}+\ldots\ldots$

(2) $\dfrac{x(1-ax)}{(1+x)(1+ax)(1+a^2x)}+\dfrac{ax(1-a^2x)}{(1+ax)(1+a^2x)(1+a^3x)}+\ldots\ldots$

24. When $x<1$, find the sum of the infinite series

$$\frac{1}{(1-x)(1-x^3)}+\frac{x^2}{(1-x^3)(1-x^5)}+\frac{x^4}{(1-x^5)(1-x^7)}+\ldots\ldots$$

25. Sum to n terms the series whose p^{th} term is

$$\frac{x^p(1+x^{p+1})}{(1-x^p)(1-x^{p+1})(1-x^{p+2})}.$$

26. Prove that the sum of the homogeneous products of n dimensions which can be formed of the letters a, b, c and their powers is

$$\frac{a^{n+2}(b-c)+b^{n+2}(c-a)+c^{n+2}(a-b)}{a^2(b-c)+b^2(c-a)+c^2(a-b)}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

terms are known. As the method of procedure is the same however many terms the scale of relation may consist of, the following illustration will be sufficient.

If $$1 - px - qx^2 - rx^3$$

is the scale of relation of the series

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots$$

we have

$$a_nx^n = px \cdot a_{n-1}x^{n-1} + qx^2 \cdot a_{n-2}x^{n-2} + rx^3 \cdot a_{n-3}x^{n-3},$$

or $$a_n = pa_{n-1} + qa_{n-2} + ra_{n-3};$$

thus any coefficient can be found when the coefficients of the three preceding terms are known.

323. Conversely, if a sufficient number of the terms of a series be given, the scale of relation may be found.

Example. Find the scale of relation of the recurring series

$$2 + 5x + 13x^2 + 35x^3 + \ldots\ldots$$

Let the scale of relation be $1 - px - qx^2$; then to obtain p and q we have the equations $13 - 5p - 2q = 0$, and $35 - 13p - 5q = 0$;

whence $p = 5$, and $q = -6$, thus the scale of relation is

$$1 - 5x + 6x^2$$

324. If the scale of relation consists of 3 terms it involves 2 constants, p and q; and we must have 2 equations to determine p and q. To obtain the first of these we must know at least 3 terms of the series, and to obtain the second we must have one more term given. Thus to obtain a scale of relation involving two constants we must have at least 4 terms given.

If the scale of relation be $1 - px - qx^2 - rx^3$, to find the 3 constants we must have 3 equations. To obtain the first of these we must know at least 4 terms of the series, and to obtain the other two we must have two more terms given; hence to find a scale of relation involving 3 constants, at least 6 terms of the series must be given.

Generally, to find a scale of relation involving m constants, we must know at least $2m$ consecutive terms.

Conversely, if $2m$ consecutive terms are given, we may assume for the scale of relation

$$1 - p_1x - p_2x^2 - p_3x^3 - \ldots\ldots - p_mx^m.$$

325. *To find the sum of* n *terms of a recurring series.*

The method of finding the sum is the same whatever be the scale of relation; for simplicity we shall suppose it to contain only two constants.

Let the series be

$$a_0 + a_1x + a_2x^2 + a_3x^3 + \ldots\ldots\ldots\ldots\ldots\ldots (1)$$

and let the sum be S; let the scale of relation be $1 - px - qx^2$; so that for every value of n greater than 1, we have

$$a_n - pa_{n-1} - qa_{n-2} = 0.$$

$$\text{Now } S = a_0 + a_1x + a_2x^2 + \ldots + a_{n-1}x^{n-1},$$

$$px\,S = \quad -pa_0x - pa_1x^2 - \ldots - pa_{n-2}x^{n-1} - pa_{n-1}x^n,$$

$$qx^2\,S = \quad\quad -qa_0x^2 - \ldots - qa_{n-3}x^{n-1} - qa_{n-2}x^n - qa_{n-1}x^{n+1}.$$

$$\therefore (1 - px - qx^2)\,S = a_0 + (a_1 - pa_0)\,x - (pa_{n-1} + qa_{n-2})\,x^n - qa_{n-1}x^{n+1},$$

for the coefficient of every other power of x is zero in consequence of the relation

$$a_n - pa_{n-1} - qa_{n-2} = 0.$$

$$\therefore S = \frac{a_0 + (a_1 - pa_0)\,x}{1 - px - qx^2} - \frac{(pa_{n-1} + qa_{n-2})\,x^n + qa_{n-1}x^{n+1}}{1 - px - qx^2}.$$

Thus the sum of a recurring series is a fraction whose denominator is the scale of relation.

326. If the second fraction in the result of the last article decreases indefinitely as n increases indefinitely, the sum of an infinite number of terms reduces to $\dfrac{a_0 + (a_1 - pa_0)\,x}{1 - px - qx^2}$.

If we develop this fraction in ascending powers of x as explained in Art. 314, we shall obtain as many terms of the original series as we please; for this reason the expression

$$\frac{a_0 + (a_1 - pa_0)\,x}{1 - px - qx^2}$$

is called the *generating function* of the series.

327. From the result of Art. 325, we obtain

$$\frac{a_0 + (a_1 - pa_0)\,x}{1 - px - qx^2} = a_0 + a_1x + a_2x^2 + \ldots + a_{n-1}x^{n+1} + \frac{(pa_{n-1} + qa_{n-2})\,x^n + qa_{n-1}x^{n+1}}{1 - px - qx^2};$$

from which we see that although the generating function

$$\frac{a_0 + (a_1 - pa_0)\,x}{1 - px - qx^2}$$

may be used to obtain as many terms of the series as we please, it can be regarded as the true equivalent of the infinite series

$$a_0 + a_1x + a_2x^2 + \ldots.$$

only if the remainder

$$\frac{(pa_{n-1} + qa_{n-2})\,x^n + qa_{n-1}x^{n+1}}{1 - px - qx^2}$$

vanishes when n is indefinitely increased; in other words only when the series is convergent.

328. When the *generating function* can be expressed as a group of partial fractions the general term of a recurring series may be easily found. Thus, suppose the generating function can be decomposed into the partial fractions

$$\frac{A}{1-ax} + \frac{B}{1+bx} + \frac{C}{(1-cx)^2}.$$

Then the general term is

$$\{Aa^r + (-1)^r Bb^r + (r+1)\,Cc^r\}\,x^r.$$

In this case the sum of n terms may be found without using the method of Art. 325.

Example. Find the generating function, the general term, and the sum to n terms of the recurring series

$$1 - 7x - x^2 - 43x^3 - \ldots\ldots$$

Let the scale of relation be $1 - px - qx^2$; then

$$-1 + 7p - q = 0,\ -43 + p + 7q = 0;$$

whence $p = 1$, $q = 6$; and the scale of relation is

$$1 - x - 6x^2.$$

Let S denote the sum of the series; then

$$\begin{aligned} S &= 1 - 7x - x^2 - 43x^3 \ldots\ldots \\ xS &= -x + 7x^2 + x^3 + \ldots\ldots \\ -6x^2S &= -6x^2 + 42x^3 + \end{aligned}$$

$$(1 - x - 6x^2)\,S = 1 - 8x,$$

$$S = \frac{1 - 8x}{1 - x - 6x^2};$$

which is the generating function.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

EXAMPLES. XXIV.

Find the generating function and the general term of the following series:

1. $1+5x+9x^2+13x^3+\ldots\ldots$ **2.** $2-x+5x^2-7x^3+\ldots\ldots$

3. $2+3x+5x^2+9x^3+\ldots\ldots$ **4.** $7-6x+9x^2+27x^4+\ldots\ldots$

5. $3+6x+14x^2+36x^3+98x^4+276x^5+$

Find the n^{th} term and the sum to n terms of the following series:

6. $2+5+13+35+.$ **7.** $-1+6x^2+30x^3+$

8. $2+7x+25x^2+91x^3+\ldots\ldots$

9. $1+2x+6x^2+20x^3+66x^4+212x^5+$

10. $\frac{3}{2}+2+0+8+$

11. Shew that the series

$$1^2+2^2+3^2+4^2+\ldots\ldots+n^2,$$

$$1^3+2^3+3^3+4^3+\ldots\ldots+n^3,$$

are recurring series, and find their scales of relation.

12. Shew how to deduce the sum of the first n terms of the recurring series

$$a_0+a_1x+a_2x^2+a_3x^3+\ldots\ldots$$

from the sum to infinity.

13. Find the sum of $2n+1$ terms of the series

$$3-1+13-9+41-53+\ldots\ldots$$

14. The scales of the recurring series

$$a_0+a_1x+a_2x^2+a_3x^3+\ldots\ldots,$$

$$b_0+b_1x+b_2x^2+b_3x^3+\ldots\ldots,$$

are $1+px+qx^2$, $1+rx+sx^2$, respectively; shew that the series whose general term is $(a_n+b_n)\,x^n$ is a recurring series whose scale is

$$1+(p+r)\,x+(q+s+pr)\,x^2+(qr+ps)\,x^3+qsx^4.$$

15. If a series be formed having for its n^{th} term the sum of n terms of a given recurring series, shew that it will also form a recurring series whose scale of relation will consist of one more term than that of the given series.

CHAPTER XXV.

CONTINUED FRACTIONS.

331. An expression of the form $a + \cfrac{b}{c + \cfrac{d}{e + \ldots}}$ is called a **continued fraction**; here the letters a, b, c, may denote any quantities whatever, but for the present we shall only consider the simpler form $a_1 + \cfrac{1}{a_2 + \cfrac{1}{a_3 + \ldots}}$, where a_1, a_2, a_3,... are positive integers. This will be usually written in the more compact form

$$a_1 + \frac{1}{a_2 +}\ \frac{1}{a_3 +}\ \ldots\ldots$$

332. When the number of *quotients* a_1, a_2, a_3,... is finite the continued fraction is said to be *terminating*; if the number of quotients is unlimited the fraction is called an *infinite continued fraction.*

It is possible to reduce every terminating continued fraction to an ordinary fraction by simplifying the fractions in succession beginning from the lowest.

333. *To convert a given fraction into a continued fraction.*

Let $\frac{m}{n}$ be the given fraction; divide m by n, let a_1 be the quotient and p the remainder; thus

$$\frac{m}{n} = a_1 + \frac{p}{n} = a_1 + \frac{1}{\frac{n}{p}};$$

divide n by p, let a_2 be the quotient and q the remainder; thus

$$\frac{n}{p} - a_2 + \frac{q}{p} = a_2 + \frac{1}{\frac{p}{q}};$$

divide p by q, let a_3 be the quotient and r the remainder; and so on. Thus

$$\frac{m}{n} - a_1 + \cfrac{1}{a_2 + \cfrac{1}{a_3 + \dots}} = a_1 + \frac{1}{a_2 +}\ \frac{1}{a_3 +}\ \dots\dots$$

If m is less than n, the first quotient is zero, and we put

$$\frac{m}{n} = \frac{1}{\frac{n}{m}}$$

and proceed as before.

It will be observed that the above process is the same as that of finding the greatest common measure of m and n; hence if m and n are *commensurable* we shall at length arrive at a stage where the division is exact and the process terminates. Thus every fraction whose numerator and denominator are positive integers can be converted into a terminating continued fraction.

Example. Reduce $\frac{251}{802}$ to a continued fraction.

Finding the greatest common measure of 251 and 802 by the usual process, we have

5	251	802	3
6	6	49	8
		1	

and the successive quotients are 3, 5, 8, 6; hence

$$\frac{251}{802} = \frac{1}{3+}\ \frac{1}{5+}\ \frac{1}{8+}\ \frac{1}{6}.$$

334. The fractions obtained by stopping at the first, second, third,..... quotients of a continued fraction are called the first, second, third,. .... **convergents**, because, as will be shewn in Art. 339, each successive convergent is a nearer approximation to the true value of the continued fraction than any of the preceding convergents.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

The $(n+1)^{\text{th}}$ convergent differs from the n^{th} only in having the quotient $a_n + \dfrac{1}{a_{n+1}}$ in the place of a_n; hence the $(n+1)^{\text{th}}$ convergent

$$= \frac{\left(a_n + \dfrac{1}{a_{n+1}}\right) p_{n-1} + p_{n-2}}{\left(a_n + \dfrac{1}{a_{n+1}}\right) q_{n-1} + q_{n-2}} = \frac{a_{n+1}(a_n p_{n-1} + p_{n-2}) + p_{n-1}}{a_{n+1}(a_n q_{n-1} + q_{n-2}) + q_{n-1}}$$

$$= \frac{a_{n+1} p_n + p_{n-1}}{a_{n+1} q_n + q_{n-1}}, \text{ by supposition.}$$

If therefore we put

$$p_{n+1} = a_{n+1} p_n + p_{n-1}, \quad q_{n+1} = a_{n+1} q_n + q_{n-1},$$

we see that the numerator and denominator of the $(n+1)^{\text{th}}$ convergent follow the law which was supposed to hold in the case of the n^{th}. But the law does hold in the case of the third convergent, hence it holds for the fourth, and so on; therefore it holds universally.

337. It will be convenient to call a_n the n^{th} *partial* quotient; the *complete* quotient at this stage being $a_n + \dfrac{1}{a_{n+1}+} \dfrac{1}{a_{n+2}+} \cdots$. We shall usually denote the complete quotient at any stage by k.

We have seen that

$$\frac{p_n}{q_n} = \frac{a_n p_{n-1} + p_{n-2}}{a_n q_{n-1} + q_{n-2}};$$

let the continued fraction be denoted by x; then x differs from $\dfrac{p_n}{q_n}$ only in taking the complete quotient k instead of the partial quotient a_n; thus

$$x = \frac{k p_{n-1} + p_{n-2}}{k q_{n-1} + q_{n-2}}.$$

338. *If* $\dfrac{p_n}{q_n}$ *be the* n^{th} *convergent to a continued fraction, then*

$$p_n q_{n-1} - p_{n-1} q_n = (-1)^n.$$

Let the continued fraction be denoted by

$$a_1 + \frac{1}{a_2+} \frac{1}{a_3+} \frac{1}{a_4+} \cdots,$$

then

$$p_n q_{n-1} \quad p_{n-1} q_n = (a_n p_{n-1} + p_{n-2}) q_{n-1} - p_{n-1} (a_n q_{n-1} + q_{n-2})$$
$$= -(-1)(p_{n-1} q_{n-2} - p_{n-2} q_{n-1})$$
$$= (-1)^2 (p_{n-2} q_{n-3} - p_{n-3} q_{n-2}), \text{ similarly,}$$
$$= \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$
$$= (-1)^{n-2} (p_2 q_1 - p_1 q_2).$$

But $p_2 q_1 - p_1 q_2 = (a_1 a_2 + 1) - a_1 . a_2 = 1 = (-1)^2$;

hence $$p_n q_{n-1} - p_{n-1} q_n = (-1)^n.$$

When the continued fraction is *less* than unity, this result will still hold if we suppose that $a_1 = 0$, and that the first convergent is zero.

NOTE. When we are calculating the numerical value of the successive convergents, the above theorem furnishes an easy test of the accuracy of the work.

COR. 1. Each convergent is in its lowest terms; for if p_n and q_n had a common divisor it would divide $p_n q_{n-1} - p_{n-1} q_n$, or unity; which is impossible.

COR. 2. The difference between two successive convergents is a fraction whose numerator is unity; for

$$\frac{p_n}{q_n} \sim \frac{p_{n-1}}{q_{n-1}} = \frac{p_n q_{n-1} \sim p_{n-1} q_n}{q_n q_{n-1}} = \frac{1}{q_n q_{n-1}}.$$

EXAMPLES. XXV. a.

Calculate the successive convergents to

1. $2 + \cfrac{1}{6+} \cfrac{1}{1+} \cfrac{1}{1+} \cfrac{1}{11+} \cfrac{1}{2}$.

2. $\cfrac{1}{2+} \cfrac{1}{2+} \cfrac{1}{3+} \cfrac{1}{1+} \cfrac{1}{4+} \cfrac{1}{2+} \cfrac{1}{6}$.

3. $3 + \cfrac{1}{3+} \cfrac{1}{1+} \cfrac{1}{2+} \cfrac{1}{2+} \cfrac{1}{1+} \cfrac{1}{9}$.

Express the following quantities as continued fractions and find the fourth convergent to each.

4. $\frac{253}{179}$.

5. $\frac{832}{159}$.

6. $\frac{1189}{3927}$.

7. $\frac{729}{2318}$.

8. ·37·

9. 1·139.

10. ·3029·

11. 4·316̇.

12. A metre is 39·37079 inches, shew by the theory of continued fractions that 32 metres is nearly equal to 35 yards.

13. Find a series of fractions converging to ·24226, the excess in days of the true tropical year over 365 days.

14. A kilometre is very nearly equal to ·62138 miles; shew that the fractions $\frac{5}{8}, \frac{18}{29}, \frac{23}{37}, \frac{64}{103}$ are successive approximations to the ratio of a kilometre to a mile.

15. Two scales of equal length are divided into 162 and 209 equal parts respectively; if their zero points be coincident shew that the 31st division of one nearly coincides with the 40th division of the other.

16. If $\frac{n^4+n^2-1}{n^3+n^2+n+1}$ is converted into a continued fraction, shew that the quotients are $n-1$ and $n+1$ alternately, and find the successive convergents.

17. Shew that

$$(1)\quad \frac{p_{n+1}-p_{n-1}}{q_{n+1}-q_{n-1}}=\frac{p_n}{q_n},$$

$$(2)\quad \left(\frac{p_{n+2}}{p_n}-1\right)\left(1-\frac{p_{n-1}}{p_{n+1}}\right)=\left(\frac{q_{n+2}}{q_n}-1\right)\left(1-\frac{q_{n-1}}{q_{n+1}}\right).$$

18. If $\frac{p_n}{q_n}$ is the n^{th} convergent to a continued fraction, and a_n the corresponding quotient, shew that

$$p_{n+2}q_{n-2}\sim p_{n-2}q_{n+2}=a_{n+2}\cdot a_{n+1}\cdot a_n+a_{n+2}+a_n.$$

339. *Each convergent is nearer to the continued fraction than any of the preceding convergents.*

Let x denote the continued fraction, and $\frac{p_n}{q_n}, \frac{p_{n+1}}{q_{n+1}}, \frac{p_{n+2}}{q_{n+2}}$ three consecutive convergents; then x differs from $\frac{p_{n+2}}{q_{n+2}}$ only in taking the *complete* $(n+2)^{\text{th}}$ quotient in the place of a_{n+2}; denote this by k; thus $x=\frac{kp_{n+1}+p_n}{kq_{n+1}+q_n}$;

$$x\sim\frac{p_n}{q_n}=\frac{k\,(p_{n+1}q_n\sim p_nq_{n+1})}{q_n\,(kq_{n+1}+q_n)}=\frac{k}{q_n\,(kq_{n+1}+q_n)},$$

and

$$\frac{p_{n+1}}{q_{n+1}}\sim x=\frac{p_{n+1}\,q_n\sim p_n\,q_{n+1}}{q_{n+1}\,(kq_{n+1}+q_n)}=\frac{1}{q_{n+1}\,(kq_{n+1}+q_n)}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

therefore, *any convergent which immediately precedes a large quotient is a near approximation to the continued fraction.*

Again, since the error is less than $\frac{1}{q_n^2}$, it follows that in order to find a convergent which will differ from the continued fraction by less than a given quantity $\frac{1}{a}$, we have only to calculate the successive convergents up to $\frac{p_n}{q_n}$, where q_n^2 is greater than a.

342. The properties of continued fractions enable us to find two small integers whose ratio closely approximates to that of two incommensurable quantities, or to that of two quantities whose exact ratio can only be expressed by large integers.

Example. Find a series of fractions approximating to 3·14159.

In the process of finding the greatest common measure of 14159 and 100000, the successive quotients are 7, 15, 1, 25, 1, 7, 4. Thus

$$3{\cdot}14159 = 3 + \frac{1}{7+}\ \frac{1}{15+}\ \frac{1}{1+}\ \frac{1}{25+}\ \frac{1}{1+}\ \frac{1}{7+}\ \frac{1}{4}.$$

The successive convergents are

$$\frac{3}{1}, \frac{22}{7}, \frac{333}{106}, \frac{355}{113}, \ldots\ldots,$$

this last convergent which precedes the large quotient 25 is a very near approximation, the error being less than $\frac{1}{25\times(113)^2}$, and therefore less than $\frac{1}{25\times(100)^2}$, or ·000004.

343. *Any convergent is nearer to the continued fraction than any other fraction whose denominator is less than that of the convergent.*

Let x be the continued fraction, $\frac{p_n}{q_n}$, $\frac{p_{n-1}}{q_{n-1}}$ two consecutive convergents, $\frac{r}{s}$ a fraction whose denominator s is less than q_n.

If possible, let $\frac{r}{s}$ be nearer to x than $\frac{p_n}{q_n}$, then $\frac{r}{s}$ must be nearer to x than $\frac{p_{n-1}}{q_{n-1}}$ [Art. 339]; and since x lies between $\frac{p_n}{q_n}$ and $\frac{p_{n-1}}{q_{n-1}}$, it follows that $\frac{r}{s}$ must lie between $\frac{p_n}{q_n}$ and $\frac{p_{n-1}}{q_{n-1}}$.

Hence

$$\frac{r}{s} \sim \frac{p_{n-1}}{q_{n-1}} < \frac{p_n}{q_n} \sim \frac{p_{n-1}}{q_{n-1}}, \text{ that is } < \frac{1}{q_n q_{n-1}};$$

$$\therefore\ rq_{n-1} \sim sp_{n-1} < \frac{s}{q_n};$$

that is, an integer less than a fraction; which is impossible Therefore $\frac{p_n}{q_n}$ must be nearer to the continued fraction than $\frac{r}{s}$.

344. *If* $\frac{p}{q}$, $\frac{p'}{q'}$ *be two consecutive convergents to a continued fraction* x, *then* $\frac{pp'}{qq'}$ *is greater or less than* x^2, *according as* $\frac{p}{q}$ *is greater or less than* $\frac{p'}{q'}$.

Let k be the complete quotient corresponding to the convergent immediately succeeding $\frac{p'}{q'}$; then $x = \frac{kp' + p}{kq' + q}$,

$$\therefore\ \frac{pp'}{qq'} - x^2 = \frac{1}{qq'(kq'+q)^2}\{pp'(kq'+q)^2 - qq'(kp'+p)^2\}$$

$$= \frac{(k^2p'q' - pq)(pq' - p'q)}{qq'(kq'+q)^2}.$$

The factor $k^2p'q' - pq$ is positive, since $p' > p$, $q' > q$, and $k > 1$; hence $\frac{pp'}{qq'} >$ or $< x^2$, according as $pq' - p'q$ is positive or negative; that is, according as $\frac{p}{q} >$ or $< \frac{p'}{q'}$.

Cor. It follows from the above investigation that the expressions $pq' - p'q$, $pp' - qq'x^2$, $p^2 - q^2x^2$, $q'^2x^2 - p'^2$ have the same sign.

EXAMPLES. XXV. b.

1. Find limits to the error in taking $\frac{222}{203}$ yards as equivalent to a metre, given that a metre is equal to 1·0936 yards.

2. Find an approximation to

$$\cdot 1+\frac{1}{3+}\ \frac{1}{5+}\ \frac{1}{7+}\ \frac{1}{9+}\ \frac{1}{11+}\ \ldots\ldots$$

which differs from the true value by less than $\cdot 0001$.

3. Shew by the theory of continued fractions that $\frac{99}{70}$ differs from $1\cdot 41421$ by a quantity less than $\frac{1}{11830}$.

4. Express $\frac{a^3+6a^2+13a+10}{a^4+6a^3+14a^2+15a+7}$ as a continued fraction, and find the third convergent.

5. Shew that the difference between the first and n^{th} convergents is numerically equal to

$$\frac{1}{q_1q_2}-\frac{1}{q_2q_3}+\frac{1}{q_3q_4}-\ldots+\frac{(-1)^n}{q_{n-1}q_n}.$$

6. Shew that if a_n is the quotient corresponding to $\frac{p_n}{q_n}$,

(1) $$\frac{p_n}{p_{n-1}}=a_n+\frac{1}{a_{n-1}+}\ \frac{1}{a_{n-2}+}\ \frac{1}{a_{n-3}+}\ \cdots\ \frac{1}{a_3+}\ \frac{1}{a_2+}\ \frac{1}{a_1},$$

(2) $$\frac{q_n}{q_{n-1}}=a_n+\frac{1}{a_{n-1}+}\ \frac{1}{a_{n-2}+}\ \frac{1}{a_{n-3}+}\ \cdots\ \frac{1}{a_3+}\ \frac{1}{a_2}.$$

7. In the continued fraction $\frac{1}{a+}\ \frac{1}{a+}\ \frac{1}{a+}\ \frac{1}{a+}\ \ldots\ldots$, shew that

(1) $p_n^2+p^2{}_{n+1}=p_{n-1}p_{n+1}+p_np_{n+2}$,

(2) $p_n=q_{n-1}$.

8. If $\frac{p_n}{q_n}$ is the n^{th} convergent to the continued fraction

$$\frac{1}{a+}\ \frac{1}{b+}\ \frac{1}{a+}\ \frac{1}{b+}\ \frac{1}{a+}\ \frac{1}{b+}\ \ldots\ldots,$$

shew that $$q_{2n}=p_{2n+1},\quad q_{2n-1}=\frac{a}{b}p_{2n}.$$

9. In the continued fraction

$$\frac{1}{a+}\ \frac{1}{b+}\ \frac{1}{a+}\ \frac{1}{b+}\ \ldots\ldots,$$

shew that

$$p_{n+2}-(ab+2)\,p_n+p_{n-2}=0,\quad q_{n+2}-(ab+2)\,q_n+q_{n-2}=0.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

CHAPTER XXVI.

INDETERMINATE EQUATIONS OF THE FIRST DEGREE.

345. In Chap. X. we have shewn how to obtain the positive integral solutions of indeterminate equations with numerical coefficients; we shall now apply the properties of continued fractions to obtain the general solution of any indeterminate equation of the first degree.

346. Any equation of the first degree involving two unknowns x and y can be reduced to the form $ax \pm by = \pm c$, where a, b, c are positive integers. This equation admits of an unlimited number of solutions; but if the conditions of the problem require x and y to be positive integers, the number of solutions may be limited.

It is clear that the equation $ax + by = -c$ has no positive integral solution; and that the equation $ax - by = -c$ is equivalent to $by - ax = c$; hence it will be sufficient to consider the equations $ax \pm by = c$.

If a and b have a factor m which does not divide c, neither of the equations $ax \pm by = c$ can be satisfied by integral values of x and y; for $ax \pm by$ is divisible by m, whereas c is not.

If a, b, c have a common factor it can be removed by division; so that we shall suppose a, b, c to have no common factor, and that a and b are prime to each other.

347. *To find the general solution in positive integers of the equation*

$$ax - by = c.$$

Let $\frac{a}{b}$ be converted into a continued fraction, and let $\frac{p}{q}$ denote the convergent just preceding $\frac{a}{b}$; then $aq - bp = \pm 1$. [Art. 338.]

I. If $aq - bp = 1$, the given equation may be written

$$ax - by = c\,(aq - bp);$$
$$a\,(x - cq) = b\,(y - cp).$$

Now since a and b have no common factor, $x - cq$ must be divisible by b; hence $x - cq = bt$, where t is an integer,

$$\therefore \quad \frac{x - cq}{b} = t = \frac{y - cp}{a};$$

that is, $$x = bt + cq, \;\; y = at + cp;$$

from which positive integral solutions may be obtained by giving to t any positive integral value, or any negative integral value numerically smaller than the less of the two quantities $\frac{cq}{b}$, $\frac{cp}{a}$; also t may be zero; thus the number of solutions is unlimited.

II. If $aq - bp = -1$, we have

$$ax - by = -c\,(aq - bp);$$
$$a\,(x + cq) = b\,(y + cp);$$
$$\therefore \quad \frac{x + cq}{b} = \frac{y + cp}{a} = t, \text{ an integer};$$

hence $$x = bt - cq, \;\; y = at - cp;$$

from which positive integral solutions may be obtained by giving to t any positive integral value which exceeds the greater of the two quantities $\frac{cq}{b}$, $\frac{cp}{a}$; thus the number of solutions is unlimited.

III. If either a or b is unity, the fraction $\frac{a}{b}$ cannot be converted into a continued fraction with unit numerators, and the investigation fails. In these cases, however, the solutions may be written down by inspection; thus if $b = 1$, the equation becomes $ax - y = c$; whence $y = ax - c$, and the solutions may be found by ascribing to x any positive integral value greater than $\frac{c}{a}$

NOTE. It should be observed that the series of values for x and y form two arithmetical progressions in which the common differences are b and a respectively.

Example. Find the general solution in positive integers of $29x - 42y = 5$.

In converting $\frac{42}{29}$ into a continued fraction the convergent just before $\frac{42}{29}$ is $\frac{13}{9}$; we have therefore

$$29 \times 13 - 42 \times 9 = -1;$$

$$29 \times 65 - 42 \times 45 = -5;$$

combining this with the given equation, we obtain

$$29(x + 65) = 42(y + 45);$$

$$\therefore \frac{x + 65}{42} = \frac{y + 45}{29} = t, \text{ an integer};$$

hence the general solution is

$$x = 42t - 65, \; y = 29t - 45.$$

348. *Given one solution in positive integers of the equation* $ax - by = c$, *to find the general solution.*

Let h, k be a solution of $ax - by = c$; then $ah - bk = c$.

$$\therefore \quad ax - by = ah - bk;$$

$$a(x - h) = b(y - k);$$

$$\therefore \quad \frac{x - h}{b} = \frac{y - k}{a} = t, \text{ an integer};$$

$$x = h + bt, \; y = k + at;$$

which is the general solution.

349. *To find the general solution in positive integers of the equation* $ax + by = c$.

Let $\frac{a}{b}$ be converted into a continued fraction, and let $\frac{p}{q}$ be the convergent just preceding $\frac{a}{b}$; then $aq - bp = \pm 1$.

I. If $aq - bp = 1$, we have

$$ax + by = c(aq - bp);$$

$$a(cq - x) = b(y + cp);$$

$$\therefore \quad \frac{cq - x}{b} = \frac{y + cp}{a} = t, \text{ an integer};$$

$$x = cq - bt, \; y = at - cp;$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

I. Let $aq - bp = 1$; then the general solution is

$$x = cq - bt, \quad y = at - cp. \qquad \text{[Art. 349.]}$$

Positive integral solutions will be obtained by giving to t positive integral values not greater than $\frac{cq}{b}$, and not less than $\frac{cp}{a}$.

(i) Suppose that $\frac{c}{a}$ and $\frac{c}{b}$ are not integers.

Let $$\frac{cp}{a} = m + f, \quad \frac{cq}{b} = n + g,$$

where m, n are positive integers and f, g proper fractions; then the least value t can have is $m + 1$, and the greatest value is n; therefore the number of solutions is

$$n - m = \frac{cq}{b} - \frac{cp}{a} + f - g - \frac{c}{ab} + f - g.$$

Now this is an integer, and may be written $\frac{c}{ab}$ + a fraction, or $\frac{c}{ab}$ − a fraction, according as f is greater or less than g. Thus the number of solutions is the integer nearest to $\frac{c}{ab}$, greater or less according as f or g is the greater.

(ii) Suppose that $\frac{c}{b}$ is an integer.

In this case $g = 0$, and one value of x is zero. If we include this, the number of solutions is $\frac{c}{ab} + f$, which must be an integer. Hence the number of solutions is the greatest integer in $\frac{c}{ab} + 1$ or $\frac{c}{ab}$, according as we include or exclude the zero solution.

(iii) Suppose that $\frac{c}{a}$ is an integer.

In this case $f = 0$, and one value of y is zero. If we include this, the least value of t is m and the greatest is n; hence the number of solutions is $n - m + 1$, or $\frac{c}{ab} - g + 1$. Thus the

number of solutions is the greatest integer in $\frac{c}{ab}+1$ or $\frac{c}{ab}$, according as we include or exclude the zero solution.

(iv) Suppose that $\frac{c}{a}$ and $\frac{c}{b}$ are both integers.

In this case $\gamma f=0$ and $g=0$, and both x and y have a zero value. If we include these, the least value t can have is m, and the greatest is n; hence the number of solutions is $n-m+1$, or $\frac{c}{ab}+1$. If we exclude the zero values the number of solutions is $\frac{c}{ab}-1$.

II. If $aq-bp=-1$, the general solution is

$$x=bt-cq,\ \ y=cp-at,$$

and similar results will be obtained.

352. To find the solutions in positive integers of the equation $ax+by+cz=d$, we may proceed as follows.

By transposition $ax+by=d-cz$; from which by giving to z in succession the values 0, 1, 2, 3,..... we obtain equations of the form $ax+by=c'$, which may be solved as already explained.

353. If we have two simultaneous equations

$$ax+by+cz=d,\ \ a'x+b'y+c'z=d',$$

by eliminating one of the unknowns, z say, we obtain an equation of the form $Ax+By=C$. Suppose that $x=f$, $y=g$ is a solution, then the general solution can be written

$$x=f+Bs,\ \ y=g-As,$$

where s is an integer.

Substituting these values of x and y in either of the given equations, we obtain an equation of the form $Fs+Gz=H$, of which the general solution is

$$s=h+Gt,\ \ z=k-Ft \text{ say.}$$

Substituting for s, we obtain

$$x=f+Bh+BGt,\ \ y=g-Ah-AGt;$$

and the values of x, y, z are obtained by giving to t suitable integral values.

354. If one solution in positive integers of the equations

$$ax + by + cz = d, \quad a'x + b'y + c'z = d',$$

can be found, the general solution may be obtained as follows.

Let f, g, h be the particular solution; then

$$af + bg + ch = d, \quad a'f + b'g + c'h = d'.$$

By subtraction,

$$a(x-f) + b(y-g) + c(z-h) = 0,$$
$$a'(x-f) + b'(y-g) + c'(z-h) = 0;$$

whence

$$\frac{x-f}{bc'-b'c} = \frac{y-g}{ca'-c'a} = \frac{z-h}{ab'-a'b} = \frac{t}{k},$$

where t is an integer and k is the H.C.F. of the denominators $bc'-b'c$, $ca'-c'a$, $ab'-a'b$. Thus the general solution is

$$x = f + (bc'-b'c)\frac{t}{k}, \quad y = g + (ca'-c'a)\frac{t}{k}, \quad z = h + (ab'-a'b)\frac{t}{k}.$$

EXAMPLES. XXVI.

Find the general solution and the least positive integral solution of

1. $775x - 711y = 1$. **2.** $455x - 519y = 1$. **3.** $436x - 393y = 5$.

4. In how many ways can £1. 19*s*. 6*d*. be paid in florins and half-crowns?

5. Find the number of solutions in positive integers of

$$11x + 15y = 1031.$$

6. Find two fractions having 7 and 9 for their denominators, and such that their sum is $1\frac{10}{63}$.

7. Find two proper fractions in their lowest terms having 12 and 8 for their denominators and such that their difference is $\frac{1}{24}$.

8. A certain sum consists of x pounds y shillings, and it is half of y pounds x shillings; find the sum.

Solve in positive integers:

9. $\left.\begin{aligned} 6x + 7y + 4z &= 122 \\ 11x + 8y - 6z &= 145 \end{aligned}\right\}$.

10. $\left.\begin{aligned} 12x - 11y + 4z &= 22 \\ -4x + 5y + z &= 17 \end{aligned}\right\}$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

CHAPTER XXVII.

RECURRING CONTINUED FRACTIONS.

355. We have seen in Chap. XXV. that a *terminating* continued fraction with rational quotients can be reduced to an ordinary fraction with integral numerator and denominator, and therefore cannot be equal to a surd; but we shall prove that a quadratic surd can be expressed as an *infinite* continued fraction whose quotients recur. We shall first consider a numerical example.

Example. Express $\sqrt{19}$ as a continued fraction, and find a series of fractions approximating to its value.

$$\sqrt{19}=4+(\sqrt{19}-4)=4+\frac{3}{\sqrt{19}+4};$$

$$\frac{\sqrt{19}+4}{3}=2+\frac{\sqrt{19}-2}{3}=2+\frac{5}{\sqrt{19}+2};$$

$$\frac{\sqrt{19}+2}{5}=1+\frac{\sqrt{19}-3}{5}=1+\frac{2}{\sqrt{19}+3};$$

$$\frac{\sqrt{19}+3}{2}=3+\frac{\sqrt{19}-3}{2}=3+\frac{5}{\sqrt{19}+3};$$

$$\frac{\sqrt{19}+3}{5}=1+\frac{\sqrt{19}-2}{5}=1+\frac{3}{\sqrt{19}+2};$$

$$\frac{\sqrt{19}+2}{3}=2+\frac{\sqrt{19}-4}{3}=2+\frac{1}{\sqrt{19}+4};$$

$$\sqrt{19}+4=8+(\sqrt{19}-4)=8+$$

after this the quotients 2, 1, 3, 1, 2, 8 recur; hence

$$\sqrt{19}=4+\frac{1}{2+}\,\frac{1}{1+}\,\frac{1}{3+}\,\frac{1}{1+}\,\frac{1}{2+}\,\frac{1}{8+}\,\cdots.$$

It will be noticed that the quotients recur as soon as we come to quotient which is double of the first. In Art. 361 we shall prove that this always the case.

[*Explanation.* In each of the lines above we perform the same series of operations. For example, consider the second line: we first find the greatest integer in $\frac{\sqrt{19}+4}{3}$; this is 2, and the remainder is $\frac{\sqrt{19}+4}{3}-2$, that is $\frac{\sqrt{19}-2}{3}$. We then multiply numerator and denominator by the surd conjugate to $\sqrt{19}-2$, so that after inverting the result $\frac{5}{\sqrt{19}+2}$, we begin a new line with a rational denominator.]

The first seven convergents formed as explained in Art. 336 are

$$\frac{4}{1}, \frac{9}{2}, \frac{13}{3}, \frac{48}{11}, \frac{61}{14}, \frac{170}{39}, \frac{1421}{326}.$$

The error in taking the last of these is less than $\frac{1}{(326)^2}$, and is therefore less than $\frac{1}{(320)^2}$ or $\frac{1}{102400}$, and *a fortiori* less than ·00001. Thus the seventh convergent gives the value to at least four places of decimals.

356. *Every periodic continued fraction is equal to one of the roots of a quadratic equation of which the coefficients are rational.*

Let x denote the continued fraction, and y the periodic part, and suppose that

$$x = a + \frac{1}{b+}\,\frac{1}{c+}\,\cdots\cdots\,\frac{1}{h+}\,\frac{1}{k+}\,\frac{1}{y},$$

and

$$y = m + \frac{1}{n+}\,\cdots\cdots\,\frac{1}{u+}\,\frac{1}{v+}\,\frac{1}{y},$$

where $a, b, c, \ldots h, k, m, n, \ldots u, v$ are positive integers.

Let $\frac{p}{q}, \frac{p'}{q'}$ be the convergents to x corresponding to the quotients h, k respectively; then since y is the complete quotient, we have $x = \frac{p'y+p}{q'y+q}$; whence $y = \frac{p-qx}{q'x-p'}$.

Let $\frac{r}{s}, \frac{r'}{s'}$ be the convergents to y corresponding to the quotients u, v respectively; then $y = \frac{r'y+r}{s'y+s}$.

Substituting for y in terms of x and simplifying we obtain a quadratic of which the coefficients are rational.

The equation $s'y^2+(s-r')y-r=0$, which gives the value of y, has its roots real and of opposite signs; if the positive value of y be substituted in $x=\dfrac{p'y+p}{q'y+q}$, on rationalising the denominator the value of x is of the form $\dfrac{A+\sqrt{B}}{C}$, where A, B, C are integers, B being positive since the value of y is real.

Example. Express $1+\cfrac{1}{2+}\ \cfrac{1}{3+}\ \cfrac{1}{2+}\ \cfrac{1}{3+}\ \ldots$ as a surd.

Let x be the value of the continued fraction; then $x-1=\cfrac{1}{2+}\ \cfrac{1}{3+(x-1)}$; whence $2x^2+2x-7=0$.

The continued fraction is equal to the positive root of this equation, and is therefore equal to $\dfrac{\sqrt{15}-1}{2}$.

EXAMPLES. XXVII. a.

Express the following surds as continued fractions, and find the sixth convergent to each:

1. $\sqrt{3}$. **2.** $\sqrt{5}$. **3.** $\sqrt{6}$. **4.** $\sqrt{8}$.

5. $\sqrt{11}$. **6.** $\sqrt{13}$. **7.** $\sqrt{14}$. **8.** $\sqrt{22}$.

9. $2\sqrt{3}$. **10.** $4\sqrt{2}$. **11.** $3\sqrt{5}$. **12.** $4\sqrt{10}$.

13. $\dfrac{1}{\sqrt{21}}$. **14.** $\dfrac{1}{\sqrt{33}}$. **15.** $\sqrt{\dfrac{6}{5}}$. **16.** $\sqrt{\dfrac{7}{11}}$.

17. Find limits of the error when $\dfrac{268}{65}$ is taken for $\sqrt{17}$.

18. Find limits of the error when $\dfrac{916}{191}$ is taken for $\sqrt{23}$.

19. Find the first convergent to $\sqrt{101}$ that is correct to five places of decimals.

20. Find the first convergent to $\sqrt{15}$ that is correct to five places of decimals.

Express as a continued fraction the positive root of each of the following equations:

21. $x^2+2x-1=0$. **22.** $x^2-4x-3=0$. **23.** $7x^2-8x-3=0$.

24. Express each root of $x^2-5x+3=0$ as a continued fraction.

25. Find the value of $3+\cfrac{1}{6+}\ \cfrac{1}{6+}\ \cfrac{1}{6+}\ \ldots\ldots$

26. Find the value of $\cfrac{1}{1+}\ \cfrac{1}{3+}\ \cfrac{1}{1+}\ \cfrac{1}{3+}\ \ldots\ldots$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

We shall call the series of quotients

$$\sqrt{N},\quad \frac{\sqrt{N}+a_1}{r_1},\quad \frac{\sqrt{N}+a_2}{r_2},\quad \frac{\sqrt{N}+a_3}{r_3},\ldots$$

the first, second, third, fourth.....complete quotients.

*358. From the preceding article it appears that the quantities a_1, r_1, b_1, b_2, b_3..... are positive integers; we shall now prove that the quantities a_2, a_3, a_4, ..., r_2, r_3, r_4,...are also positive integers.

Let $\frac{p}{q}$, $\frac{p'}{q'}$, $\frac{p''}{q''}$ be three consecutive convergents to $\sqrt{N}$, and let $\frac{p''}{q''}$ be the convergent corresponding to the partial quotient b_n.

The complete quotient at this stage is $\frac{\sqrt{N}+a_n}{r_n}$; hence

$$\sqrt{N}=\frac{\frac{\sqrt{N}+a_n}{r_n}p'+p}{\frac{\sqrt{N}+a_n}{r_n}q'+q}=\frac{p'\sqrt{N}+a_np'+r_np}{q'\sqrt{N}+a_nq'+r_nq}.$$

Clearing of fractions and equating rational and irrational parts, we have

$$a_np'+r_np=Nq',\quad a_nq'+r_nq=p';$$

whence $a_n(pq'-p'q)=pp'-qq'N$, $r_n(pq'-p'q)=Nq'^2-p'^2$.

But $pq'-p'q=\pm1$, and $pq'-p'q$, $pp'-qq'N$, $Nq'^2-p'^2$ have the same sign [Art. 344]; hence a_n and r_n are positive integers. Since two convergents precede the complete quotient $\frac{\sqrt{N}+a_2}{r_2}$, this investigation holds for all values of n greater than 1.

*359. *To prove that the complete and partial quotients recur.*

In Art. 357 we have proved that $r_nr_{n-1}=N-a_n^2$. Also r_n and r_{n-1} are positive integers; hence a_n must be less than $\sqrt{N}$, thus a_n cannot be greater than a_1, and therefore it cannot have any values except 1, 2, 3,...a_1; that is, *the number of different values of* a_n *cannot exceed* a_1.

Again, $a_{n+1}=r_nb_n-a_n$, that is $r_nb_n=a_n+a_{n+1}$, and therefore r_nb_n cannot be greater than $2a_1$; also b_n is a positive integer; hence r_n cannot be greater than $2a_1$. Thus r_n cannot have any values except 1, 2, 3,...$2a_1$; that is, *the number of different values of* r_n *cannot exceed* $2a_1$.

Thus the complete quotient $\frac{\sqrt{N}+a_n}{r_n}$ cannot have more than $2a_1^2$ different values; that is, *some one complete quotient, and therefore all subsequent ones, must recur.*

Also b_n is the greatest integer in $\frac{\sqrt{N}+a_n}{r_n}$; hence *the partial quotients must also recur, and the number of partial quotients in each cycle cannot be greater than* $2a_1^2$.

*360. *To prove that* $a_1 < a_n + r_n$.

We have $$a_{n-1} + a_n = b_{n-1} r_{n-1};$$

$$\therefore\ a_{n-1} + a_n = \text{or} > r_{n-1},$$

since b_{n-1} is a positive integer;

$$\sqrt{N} + a_n > r_{n-1}.$$

But $$N - a_n^2 = r_n r_{n-1};$$

$$\therefore\ \sqrt{N} - a_n < r_n;$$

$$\therefore\ a_1 - a_n < r_n,$$

which proves the proposition.

*361. *To shew that the period begins with the second partial quotient and terminates with a partial quotient double of the first.*

Since, as we have seen in Art. 359, a recurrence must take place, let us suppose that the $(n+1)^{\text{th}}$ complete quotient recurs at the $(s+1)^{\text{th}}$; then

$$a_s = a_n,\ r_s = r_n,\ \text{and}\ b_s = b_n;$$

we shall prove that

$$a_{s-1} = a_{n-1},\ r_{s-1} = r_{n-1},\ b_{s-1} = b_{n-1}.$$

We have

$$r_{s-1} r_s = N - a_s^2 = N - a_n^2 = r_{n-1} r_n = r_{n-1} r_s;$$

$$\therefore\ r_{s-1} = r_{n-1}.$$

Again,

$$a_{n-1} + a_n = b_{n-1} r_{n-1},\ a_{s-1} + a_s = b_{s-1} r_{s-1} = b_{s-1} r_{n-1};$$

$$\therefore\ a_{n-1} - a_{s-1} = r_{n-1}(b_{n-1} - b_{s-1});$$

$$\therefore\ \frac{a_{n-1} - a_{s-1}}{r} = b_{n-1} - b_{s-1} = \text{zero, or an integer.}$$

But, by Art. 360, $a_1 - a_{n-1} < r_{n-1}$, and $a_1 - a_{s-1} < r_{s-1}$; that is $a_1 - a_{s-1} < r_{n-1}$; therefore $a_{n-1} - a_{s-1} < r_{n-1}$; hence $\frac{a_{n-1} - a_{s-1}}{r_{n-1}}$ is less than unity, and therefore must be zero.

Thus $a_{s-1} = a_{n-1}$, and also $b_{s-1} = b_{n-1}$.

Hence if the $(n+1)^{\text{th}}$ complete quotient recurs, the n^{th} complete quotient must also recur; therefore the $(n-1)^{\text{th}}$ complete quotient must also recur; and so on.

This proof holds as long as n is not less than 2 [Art. 358], hence the complete quotients recur, beginning with the second quotient $\frac{\sqrt{N} + a_1}{r_1}$. It follows therefore that the recurrence begins with the second partial quotient b_1; we shall now shew that it terminates with a partial quotient $2a_1$.

Let $\frac{\sqrt{N} + a_n}{r_n}$ be the complete quotient which just precedes the second complete quotient $\frac{\sqrt{N} + a_1}{r_1}$ when it recurs; then $\frac{\sqrt{N} + a_n}{r_n}$ and $\frac{\sqrt{N} + a_1}{r_1}$ are two consecutive complete quotients; therefore

$$a_n + a_1 = r_n b_n, \quad r_n r_1 = N - a_1^2;$$

but $N - a_1^2 = r_1$; hence $r_n = 1$.

Again, $a_1 - a_n < r_n$, that is < 1; hence $a_1 - a_n = 0$, that is

$$a_n = a_1.$$

Also $a_n + a_1 = r_n b_n = b_n$; hence $b_n = 2a_1$; which establishes the proposition.

*362. *To shew that in any period the partial quotients equidistant from the beginning and end are equal, the last partial quotient being excluded.*

Let the last complete quotient be denoted by $\frac{\sqrt{N} + a_n}{r_n}$; then

$$r_n = 1, \quad a_n = a_1, \quad b_n = 2a_1.$$

We shall prove that

$$r_{n-1} = r_1, \quad a_{n-1} = a_2, \quad b_{n-1} = b_1;$$
$$r_{n-2} = r_2, \quad a_{n-2} = a_3, \quad b_{n-2} = b_2;$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

and is therefore equal to $a_1 + \sqrt{N}$; hence

$$\sqrt{N} = \frac{(a_1 + \sqrt{N})\, p_n + p_{n-1}}{(a_1 + \sqrt{N})\, q_n + q_{n-1}}.$$

Clearing of fractions and equating rational and irrational parts, we obtain

$$a_1 p_n + p_{n-1} = N q_n, \quad a_1 q_n + q_{n-1} = p_n \ldots\ldots\ldots\ldots (1).$$

Again $\frac{p_{2n}}{q_{2n}}$ can be obtained from $\frac{p_n}{q_n}$ and $\frac{p_{n-1}}{q_{n-1}}$ by taking for the quotient

$$2a_1 + \frac{1}{b_1 +}\,\frac{1}{b_2 +}\,\cdots\cdots\,\frac{1}{b_{n-1}},$$

which is equal to $a_1 + \frac{p_n}{q_n}$. Thus

$$\frac{p_{2n}}{q_{2n}} = \frac{\left(a_1 + \frac{p_n}{q_n}\right) p_n + p_{n-1}}{\left(a_1 + \frac{p_n}{q_n}\right) q_n + q_{n-1}} = \frac{N q_n + \frac{p_n}{q_n} \cdot p_n}{p_n + \frac{p_n}{q_n} \cdot q_n}, \text{ from (1);}$$

$$\therefore \quad \frac{p_{2n}}{q_{2n}} = \frac{1}{2}\left(\frac{p_n}{q_n} + \frac{N q_n}{p_n}\right) \ldots\ldots\ldots\ldots\ldots\ldots (2).$$

In like manner we may prove that if $\frac{p_{cn}}{q_{cn}}$ is the penultimate convergent in the c^{th} recurring period,

$$a_1 p_{cn} + p_{cn-1} = N q_{cn}, \quad a_1 q_{cn} + q_{cn-1} = p_{cn},$$

and by using these equations, we may obtain $\frac{p_{3n}}{q_{3n}}$, $\frac{p_{4n}}{q_{4n}}$, ... successively.

It should be noticed that equation (2) holds for all multiples of n; thus

$$\frac{p_{2cn}}{q_{2cn}} = \frac{1}{2}\left(\frac{p_{cn}}{q_{cn}} + \frac{N q_{cn}}{p_{cn}}\right);$$

the proof being similar to that already given.

*365. In Art. 356, we have seen that a periodic continued fraction can be expressed as the root of a quadratic equation with rational coefficients.

Conversely, we might prove by the method of Art. 357 that an expression of the form $\frac{A+\sqrt{B}}{C}$, where A, B, C are positive integers, and B not a perfect square, can be converted into a recurring continued fraction. In this case the periodic part will not usually begin with the second partial quotient, nor will the last partial quotient be double the first.

For further information on the subject of recurring continued fractions we refer the student to Serret's *Cours d'Algèbre Supérieure*, and to a pamphlet on *The Expression of a Quadratic Surd as a Continued Fraction*, by Thomas Muir, M.A., F.R.S.E.

*EXAMPLES. XXVII. b.

Express the following surds as continued fractions, and find the fourth convergent to each:

1. $\sqrt{a^2+1}$.
2. $\sqrt{a^2-a}$.
3. $\sqrt{a^2-1}$.
4. $\sqrt{1+\frac{1}{a}}$.
5. $\sqrt{a^2+\frac{2a}{b}}$.
6. $\sqrt{a^2-\frac{a}{n}}$.

7. Prove that

$$\sqrt{9a^2+3}=3a+\frac{1}{2a+}\,\frac{1}{6a+}\,\frac{1}{2a+}\,\frac{1}{6a+}\,\cdots\cdots,$$

and find the fifth convergent.

8. Shew that

$$p+\frac{2}{1+}\,\frac{1}{p+}\,\frac{1}{1+}\,\frac{1}{p+}\,\frac{1}{1+}\,\cdots\cdots=\sqrt{p^2+4p}.$$

9. Shew that

$$p\left(a_1+\frac{1}{pqa_2+}\,\frac{1}{a_3+}\,\frac{1}{pqa_4+}\,\cdots\cdots\right)=pa_1+\frac{1}{qa_2+}\,\frac{1}{pa_3+}\,\frac{1}{qa_4+}\,\cdots\cdots$$

10. If $\sqrt{a^2+1}$ be expressed as a continued fraction, shew that

$$2(a^2+1)q_n=p_{n-1}+p_{n+1},\quad 2p_n=q_{n-1}+q_{n+1}.$$

11. If

$$x=\frac{1}{a_1+}\,\frac{1}{a_2+}\,\frac{1}{a_1+}\,\frac{1}{a_2+}\,\cdots$$

$$y=\frac{1}{2a_1+}\,\frac{1}{2a_2+}\,\frac{1}{2a_1+}\,\frac{1}{2a_2+}\,\cdots,$$

$$z=\frac{1}{3a_1+}\,\frac{1}{3a_2+}\,\frac{1}{3a_1+}\,\frac{1}{3a_2+}\,\cdots,$$

shew that $x(y^2-z^2)+2y(z^2-x^2)+3z(x^2-y^2)=0.$

12. Prove that

$$\left(a+\frac{1}{b+}\,\frac{1}{a+}\,\frac{1}{b+}\,\frac{1}{a+}\cdots\right)\left(\frac{1}{b+}\,\frac{1}{a+}\,\frac{1}{b+}\,\frac{1}{a+}\cdots\right)=\frac{a}{b}.$$

13. If

$$x=a+\frac{1}{b+}\,\frac{1}{b+}\,\frac{1}{a+}\,\frac{1}{a+}\cdots,$$

$$y=b+\frac{1}{a+}\,\frac{1}{a+}\,\frac{1}{b+}\,\frac{1}{b+}\cdots,$$

shew that $(ab^2+a+b)\,x-(a^2b+a+b)\,y=a^2-b^2.$

14. If $\frac{p_n}{q_n}$ be the n^{th} convergent to $\sqrt{a^2+1}$, shew that

$$\frac{p_2{}^2+p_3{}^2+\ldots+p^2{}_{n+1}}{q_2{}^2+q_3{}^2+\ldots+q^2{}_{n+1}}=\frac{p_{n+1}p_{n+2}-p_1p_2}{q_{n+1}q_{n+2}-q_1q_2}.$$

15. Shew that

$$\left(\frac{1}{a+}\,\frac{1}{b+}\,\frac{1}{c+}\cdots\right)\left(c+\frac{1}{b+}\,\frac{1}{a+}\,\frac{1}{c+}\cdots\right)=\frac{1+bc}{1+ab}.$$

16. If $\frac{p_r}{q_r}$ denote the r^{th} convergent to $\frac{\sqrt{5}+1}{2}$, shew that

$$p_3+p_5+\ldots+p_{2n-1}=p_{2n}-p_2,\quad q_3+q_5+\ldots+q_{2n-1}=q_{2n}-q_2.$$

17. Prove that the difference of the infinite continued fractions

$$\frac{1}{a+}\,\frac{1}{b+}\,\frac{1}{c+}\cdots,\qquad \frac{1}{b+}\,\frac{1}{a+}\,\frac{1}{c+}\cdots$$

is equal to $\frac{a-b}{1+ab}$.

18. If $\sqrt{N}$ is converted into a continued fraction, and if n is the number of quotients in the period, shew that

$$q_{2n}=2p_nq_n,\qquad p_{2n}=2p_n{}^2+(-1)^{n+1}.$$

19. If $\sqrt{N}$ be converted into a continued fraction, and if the penultimate convergents in the first, second, ...k^{th} recurring periods be denoted by $n_1, n_2, \ldots n_k$ respectively, shew that

$$\frac{n_k+\sqrt{N}}{n_k-\sqrt{N}}=\left(\frac{n_1+\sqrt{N}}{n_1-\sqrt{N}}\right)^k.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Unless this equation can be solved in positive integers, the original equation does not admit of a positive integral solution. We shall return to this point in Art. 374.

If a, b, h are all positive, it is clear that the number of solutions is limited, because for large values of x and y the sign of the expression on the left depends upon that of $ax^2+2hxy+by^2$ [Art. 269], and thus cannot be zero for large positive integral values of x and y.

Again, if h^2-ab is negative, the coefficient of y^2 in (1) is negative, and by similar reasoning we see that the number of solutions is limited.

Example. Solve in positive integers the equation

$$x^2-4xy+6y^2-2x-20y=29.$$

Solving as a quadratic in x, we have

$$x=2y+1\pm\sqrt{30+24y-2y^2}.$$

But $30+24y-2y^2=102-2(y-6)^2$; hence $(y-6)^2$ cannot be greater than 51. By trial we find that the expression under the radical becomes a perfect square when $(y-6)^2=1$ or 49; thus the positive integral values of y are 5, 7, 13.

When $y=5$, $x=21$ or 1; when $y=7$, $x=25$ or 5; when $y=13$, $x=29$ or 25.

*368. We have seen that the solution in positive integers of the equation

$$ax^2+2hxy+by^2+2gx+2fy+c=0$$

can be made to depend upon the solution of an equation of the form

$$x^2\pm Ny^2=\pm a,$$

where N and a are positive integers.

The equation $x^2+Ny^2=-a$ has no real roots, whilst the equation $x^2+Ny^2=a$ has a limited number of solutions, which may be found by trial; we shall therefore confine our attention to equations of the form $x^2-Ny^2=\pm a$.

*369. *To shew that the equation* $x^2-Ny^2=1$ *can always be solved in positive integers.*

Let $\sqrt{N}$ be converted into a continued fraction, and let $\frac{p}{q}$, $\frac{p'}{q'}$, $\frac{p''}{q''}$ be any three consecutive convergents; suppose that

$\frac{\sqrt{N}+a_n}{r_n}$ is the complete quotient corresponding to $\frac{p''}{q''}$; then

$$r_n(pq'-p'q) = Nq'^2 - p'^2 \qquad \text{[Art. 358].}$$

But $r_n = 1$ at the end of any period [Art. 361];

$$\therefore p'^2 - Nq'^2 = p'q - pq';$$

$\frac{p'}{q'}$ being the penultimate convergent of any recurring period.

If the number of quotients in the period is even, $\frac{p'}{q'}$ is an even convergent, and is therefore greater than $\sqrt{N}$, and therefore greater than $\frac{p}{q}$; thus $p'q - pq' = 1$. In this case $p'^2 - Nq'^2 = 1$, and therefore $x = p'$, $y = q'$ is a solution of the equation $x^2 - Ny^2 = 1$.

Since $\frac{p'}{q'}$ is the penultimate convergent of any recurring period, the number of solutions is unlimited.

If the number of quotients in the period is odd, the penultimate convergent in the first period is an *odd* convergent, but the penultimate convergent in the second period is an *even* convergent. Thus integral solutions will be obtained by putting $x = p'$, $y = q'$, where $\frac{p'}{q'}$ is the penultimate convergent in the second, fourth, sixth,.....recurring periods. Hence also in this case the number of solutions is unlimited.

*370. *To obtain a solution in positive integers of the equation* $x^2 - Ny^2 = -1$.

As in the preceding article, we have

$$p'^2 - Nq'^2 = p'q - pq'.$$

If the number of quotients in the period is *odd*, and if $\frac{p'}{q'}$ is an *odd* penultimate convergent in any recurring period, $\frac{p'}{q'} < \frac{p}{q}$, and therefore $p'q - pq' = -1$.

In this case $p'^2 - Nq'^2 = -1$, and integral solutions of the equation $x^2 - Ny^2 = -1$ will be obtained by putting $x = p'$, $y = q'$, where $\frac{p'}{q}$ is the penultimate convergent in the first, third, fifth recurring periods.

happen that we can discover

Example. Solve in positive integers $x^2 - 13y^2 = \pm 1$.

We can shew that

$$\sqrt{13} = 3 + \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{6+}\ \cdots\cdots$$

Here the number of quotients in the period is odd; the penultimate convergent in the first period is $\frac{18}{5}$; hence $x = 18$, $y = 5$ is a solution of

$$x^2 - 13y^2 = -1.$$

By Art. 364, the penultimate convergent in the second recurring period is

$$\frac{1}{2}\left(\frac{18}{5} + \frac{5}{18} \times 13\right), \text{ that is, } \frac{649}{180};$$

hence $x = 649$, $y = 180$ is a solution of $x^2 - 13y^2 = 1$.

By forming the successive penultimate convergents of the recurring periods we can obtain any number of solutions of the equations

$$x^2 - 13y^2 = -1, \text{ and } x^2 - 13y^2 = +1.$$

*371. When one solution in positive integers of $x^2 - Ny^2 = 1$ has been found, we may obtain as many as we please by the following method.

Suppose that $x = h$, $y = k$ is a solution, h and k being positive integers; then $(h^2 - Nk^2)^n = 1$, where n is any positive integer.

Thus
$$x^2 - Ny^2 = (h^2 - Nk^2)^n.$$

$$\therefore\ (x + y\sqrt{N})\,(x - y\sqrt{N}) = (h + k\sqrt{N})^n\,(h - k\sqrt{N})^n.$$

Put $x + y\sqrt{N} = (h + k\sqrt{N})^n$, $\quad x - y\sqrt{N} = (h - k\sqrt{N})^n$;

$$\therefore\ 2x = (h + k\sqrt{N})^n + (h - k\sqrt{N})^n;$$

$$2y\sqrt{N} = (h + k\sqrt{N})^n - (h - k\sqrt{N})^n.$$

The values of x and y so found are positive integers, and by ascribing to n the values 1, 2, 3,..., as many solutions as we please can be obtained.

Similarly if $x = h$, $y = k$ is a solution of the equation $x^2 - Ny^2 = -1$, and if n is any *odd* positive integer,

$$x^2 - Ny^2 = (h^2 - Nk^2)^n.$$

Thus the values of x and y are the same as already found, but n is restricted to the values 1, 3, 5,..

*372. By putting $x = ax'$, $y = ay'$ the equations $x^2 - Ny^2 = \pm a^2$ become $x'^2 - Ny'^2 = \pm 1$, which we have already shewn how to solve.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

positive integral solution of the equations $x^2 - Ny^2 = \pm a$, when a is not one of the above mentioned denominators; thus we easily find that the equation $x^2 - 7y^2 = 53$ is satisfied by $y = 2$, $x = 9$. When one solution in integers has been found, any number of solutions may be obtained as explained in the next article.

*376. Suppose that $x = f$, $y = g$ is a solution of the equation $x^2 - Ny^2 = a$; and let $x = h$, $y = k$ be *any* solution of the equation $x^2 - Ny^2 = 1$; then

$$x^2 - Ny^2 = (f^2 - Ng^2)(h^2 - Nk^2)$$
$$= (fh \pm Ngk)^2 - N(fk \pm gh)^2$$

By putting $x = fh \pm Ngk$, $y = fk \pm gh$,

and ascribing to h, k their values found as explained in Art. 371, we may obtain any number of solutions.

*377. Hitherto it has been supposed that N is not a perfect square; if, however, N is a perfect square the equation takes the form $x^2 - n^2y^2 = a$, which may be readily solved as follows.

Suppose that $a = bc$, where b and c are two positive integers, of which b is the greater; then

$$(x + ny)(x - ny) = bc.$$

Put $x + ny = b$, $x - ny = c$; if the values of x and y found from these equations are integers we have obtained one solution of the equation; the remaining solutions may be obtained by ascribing to b and c all their possible values.

Example. Find two positive integers the difference of whose squares is equal to 60.

Let x, y be the two integers; then $x^2 - y^2 = 60$; that is, $(x+y)(x-y) = 60$.

Now 60 is the product of any of the pair of factors

$$1, 60;\ \ 2, 30;\ \ 3, 20;\ \ 4, 15;\ \ 5, 12;\ \ 6, 10;$$

and the values required are obtained from the equations

$$x + y = 30, \qquad x + y = 10,$$
$$x - y = 2; \qquad x - y = 6;$$

the other equations giving fractional values of x and y.

Thus the numbers are 16, 14; or 8, 2.

Cor. In like manner we may obtain the solution in positive integers of

$$ax^2 + 2hxy + by^2 + 2gx + 2fy + c = k,$$

if the left-hand member can be resolved into two rational linear factors.

*378. If in the general equation a, or b, or both, are zero, instead of employing the method explained in Art. 367 it is simpler to proceed as in the following example.

Example. Solve in positive integers

$$2xy - 4x^2 + 12x - 5y = 11.$$

Expressing y in terms of x, we have

$$y = \frac{4x^2 - 12x + 11}{2x - 5} = 2x - 1 + \frac{6}{2x - 5}.$$

In order that y may be an integer $\frac{6}{2x-5}$ must be an integer; hence $2x - 5$ must be equal to ± 1, or ± 2, or ± 3, or ± 6.

The cases ± 2, ± 6 may clearly be rejected; hence the admissible values of x are obtained from $2x - 5 = \pm 1$, $2x - 5 = \pm 3$;

whence the values of x are 3, 2, 4, 1.

Taking these values in succession we obtain the solutions

$$x = 3,\ y = 11;\ x = 2,\ y = -3;\ x = 4,\ y = 9;\ x = 1,\ y = -1;$$

and therefore the admissible solutions are

$$x = 3,\ y = 11;\ x = 4,\ y = 9.$$

*379. The principles already explained enable us to discover for what values of the variables given linear or quadratic functions of x and y become perfect squares. Problems of this kind are sometimes called *Diophantine Problems* because they were first investigated by the Greek mathematician Diophantus about the middle of the fourth century.

Example 1. Find the general expressions for two positive integers which are such that if their product is taken from the sum of their squares the difference is a perfect square.

Denote the integers by x and y; then

$$x^2 - xy + y^2 = z^2 \text{ suppose};$$

$$x(x - y) = z^2 - y^2.$$

This equation is satisfied by the suppositions

$$mx = n(z + y), \quad n(x - y) = m(z - y),$$

where m and n are positive integers.

Hence $$mx - ny - nz = 0, \quad nx + (m-n)\,y - mz = 0.$$

From these equations we obtain by cross multiplication

$$\frac{x}{2mn - n^2} = \frac{y}{m^2 - n^2} = \frac{z}{m^2 - mn + n^2};$$

and since the given equation is homogeneous we may take for the general solution

$$x = 2mn - n^2, \quad y = m^2 - n^2, \quad z = m^2 - mn + n^2.$$

Here m and n are any two positive integers, m being the greater; thus if $m=7$, $n=4$, we have

$$x = 40, \; y = 33, \; z = 37.$$

Example 2. Find the general expression for three positive integers in arithmetic progression, and such that the sum of every two is a perfect square.

Denote the integers by $x-y$, x, $x+y$; and let

$$2x - y = p^2, \; 2x = q^2, \; 2x + y = r^2;$$

then $$p^2 + r^2 = 2q^2,$$

or $$r^2 - q^2 = q^2 - p^2.$$

This equation is satisfied by the suppositions,

$$m\,(r-q) = n\,(q-p), \; n\,(r+q) = m\,(q+p),$$

where m and n are positive integers.

From these equations we obtain by cross multiplication

$$\frac{p}{n^2 + 2mn - m^2} = \frac{q}{m^2 + n^2} = \frac{r}{m^2 + 2mn - n^2}.$$

Hence we may take for the general solution

$$p = n^2 + 2mn - m^2, \; q = m^2 + n^2, \; r = m^2 + 2mn - n^2;$$

whence $$x = \frac{1}{2}(m^2 + n^2)^2, \; y = 4mn\,(m^2 - n^2),$$

and the three integers can be found.

From the value of x it is clear that m and n are either both even or both odd; also their values must be such that x is greater than y, that is,

$$(m^2 + n^2)^2 > 8mn\,(m^2 - n^2),$$

or $$m^3(m - 8n) + 2m^2n^2 + 8mn^3 + n^4 > 0;$$

which condition is satisfied if $m > 8n$.

If $m=9$, $n=1$, then $x=3362$, $y=2880$, and the numbers are 482, 3362, 6242. The sums of these taken in pairs are 3844, 6724, 9604, which are the squares of 62, 82, 98 respectively.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

CHAPTER XXIX.

SUMMATION OF SERIES.

380. Examples of summation of certain series have occurred in previous chapters; it will be convenient here to give a synopsis of the methods of summation which have already been explained.

(i) Arithmetical Progression, Chap. IV.

(ii) Geometrical Progression, Chap. V.

(iii) Series which are partly arithmetical and partly geometrical, Art. 60.

(iv) Sums of the powers of the Natural Numbers and allied Series, Arts. 68 to 75.

(v) Summation by means of Undetermined Coefficients, Art. 312.

(vi) Recurring Series, Chap. XXIV.

We now proceed to discuss methods of greater generality; but in the course of the present chapter it will be seen that some of the foregoing methods may still be usefully employed.

381. If the r^{th} term of a series can be expressed as the difference of two quantities one of which is the same function of r that the other is of $r-1$, the sum of the series may be readily found.

For let the series be denoted by

$$u_1 + u_2 + u_3 + \ldots + u_n,$$

and its sum by S_n, and suppose that any term u_r can be put in the form $v_r - v_{r-1}$; then

$$\begin{aligned} S_n &= (v_1 - v_0) + (v_2 - v_1) + (v_3 - v_2) + \ldots + (v_{n-1} - v_{n-2}) + (v_n - v_{n-1}) \\ &= v_n - v_0. \end{aligned}$$

Example. Sum to n terms the series

$$\frac{1}{(1+x)(1+2x)}+\frac{1}{(1+2x)(1+3x)}+\frac{1}{(1+3x)(1+4x)}+\ldots\ldots$$

If we denote the series by

$$u_1+u_2+u_3+\ldots\ldots+u_n,$$

we have

$$u_1=\frac{1}{x}\left(\frac{1}{1+x}-\frac{1}{1+2x}\right),$$

$$u_2=\frac{1}{x}\left(\frac{1}{1+2x}-\frac{1}{1+3x}\right)$$

$$u_3=\frac{1}{x}\left(\frac{1}{1+3x}-\frac{1}{1+4x}\right),$$

.....

$$u_n=\frac{1}{x}\left(\frac{1}{1+nx}-\frac{1}{1+\overline{n+1}\,.\,x}\right),$$

$\therefore$ by addition,

$$S_n=\frac{1}{x}\left(\frac{1}{1+x}-\frac{1}{1+\overline{n+1}\,.\,x}\right)$$

$$=\frac{n}{(1+x)(1+\overline{n+1}\,.\,x)}.$$

382. Sometimes a suitable transformation may be obtained by separating u_n into partial fractions by the methods explained in Chap. XXIII.

Example. Find the sum of

$$\frac{1}{(1+x)(1+ax)}+\frac{a}{(1+ax)(1+a^2x)}+\frac{a^2}{(1+a^2x)(1+a^3x)}+\ldots \text{ to } n \text{ terms.}$$

$$\text{The } n^{\text{th}} \text{ term}=\frac{a^{n-1}}{(1+a^{n-1}x)(1+a^nx)}=\frac{A}{1+a^{n-1}x}+\frac{B}{1+a^nx} \text{ suppose;}$$

$$\therefore\ a^{n-1}=A(1+a^nx)+B(1+a^{n-1}x).$$

By putting $1+a^{n-1}x$, $1+a^nx$ equal to zero in succession, we obtain

$$A=\frac{a^{n-1}}{1-a},\ B=-\frac{a^n}{1-a}.$$

Hence

$$u_1=\frac{1}{1-a}\left(\frac{1}{1+x}-\frac{a}{1+ax}\right),$$

similarly,

$$u_2=\frac{1}{1-a}\left(\frac{a}{1+ax}-\frac{a^2}{1+a^2x}\right),$$

.....

$$u_n=\frac{1}{1-a}\left(\frac{a^{n-1}}{1+a^{n-1}x}-\frac{a^n}{1+a^nx}\right),$$

$$\therefore\ S_n=\frac{1}{1-a}\left(\frac{1}{1+x}-\frac{a^n}{1+a^nx}\right).$$

383. *To find the sum of* n *terms of a series each term of which is composed of* r *factors in arithmetical progression, the first factors of the several terms being in the same arithmetical progression.*

Let the series be denoted by $u_1 + u_2 + u_3 + \ldots\ldots + u_n$, where

$$u_n = (a + nb)\,(a + \overline{n+1}\,.\,b)\,(a + \overline{n+2}\,.\,b) \ldots (a + \overline{n+r-1}\,.\,b).$$

Replacing n by $n-1$, we have

$$u_{n-1} = (a + \overline{n-1}\,.\,b)\,(a + nb)\,(a + \overline{n+1}\,.\,b) \ldots (a + \overline{n+r-2}\,.\,b);$$

$$\therefore\ (a + \overline{n-1}\,.\,b)\,u_n = (a + \overline{n+r-1}\,.\,b)\,u_{n-1} = v_n, \text{ say.}$$

Replacing n by $n+1$ we have

$$(a + \overline{n+r}\,.\,b)\,u_n = v_{n+1};$$

therefore, by subtraction,

$$(r+1)\,b\,.\,u_n = v_{n+1} - v_n.$$

Similarly, $(r+1)\,b\,.\,u_{n-1} = v_n - v_{n-1}$,

$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$

$$(r+1)\,b\,.\,u_2 = v_3 - v_2,$$

$$(r+1)\,b\,.\,u_1 = v_2 - v_1.$$

By addition, $(r+1)\,b\,.\,S_n = v_{n+1} - v_1$;

that is,
$$S_n = \frac{v_{n+1} - v_1}{(r+1)\,b}$$

$$= \frac{(a + \overline{n+r}\,.\,b)\,u_n}{(r+1)\,b} + C, \text{ say};$$

where C is a quantity independent of n, which may be found by ascribing to n some particular value.

The above result gives us the following convenient rule:

Write down the n$^{\text{th}}$ *term, affix the next factor at the end, divide by the number of factors thus increased and by the common difference, and add a constant.*

It may be noticed that $C = -\frac{v_1}{(r+1)\,b} = -\frac{a}{(r+1)\,b}\,u_1$; it is however better not to quote this result, but to obtain C as above indicated.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

386. *To find the sum of* n *terms of a series each term of which is composed of the reciprocal of the product of* r *factors in arithmetical progression, the first factors of the several terms being in the same arithmetical progression.*

Let the series be denoted by $u_1 + u_2 + u_3 + \ldots\ldots + u_n$,
where

$$\frac{1}{u_n} = (a+nb)(a+\overline{n+1}\,.\,b)(a+\overline{n+2}\,.\,b)\ldots\ldots(a+\overline{n+r-1}\;\;b).$$

Replacing n by $n-1$,

$$\frac{1}{u_{n-1}} = (a+\overline{n-1}\,.\,b)\,(a+nb)\,(a+\overline{n+1}\,.\,b)\ldots(a+\overline{n+r-2}\,.\,b)\,;$$

$$\therefore\ (a+\overline{n+r-1}\,.\,b)\,u_n = (a+\overline{n-1}\,.\,b)\,u_{n-1} = v_n,\ \text{say.}$$

Replacing n by $n+1$, we have

$$(a+nb)\,u_n = v_{n+1}\,;$$

therefore, by subtraction,

$$(r-1)\,b\,.\,u_n = v_n - v_{n+1},$$

Similarly $(r-1)\,b\,.\,u_{n-1} = v_{n-1} - v_n,$

$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$

$$(r-1)\,b\,.\,u_2 = v_2 - v_3,$$

$$(r-1)\,b\,.\,u_1 = v_1 - v_2\,.$$

By addition, $(r-1)\,b\,.\,S_n = v_1 - v_{n+1}\,;$

that is $$S_n = \frac{v_1 - v_{n+1}}{(r-1)\,b} = C - \frac{(a+nb)\,u_n}{(r-1)\,b},$$

where C is a quantity independent of n, which may be found by ascribing to n some particular value.

Thus $S_n = C - \dfrac{1}{(r-1)\,b}\cdot\dfrac{}{(a+\overline{n+1}\,.\,b)\ldots(a+\overline{n+r-1}\,.\,b)}$.

Hence the sum may be found by the following rule:

Write down the n$^{\text{th}}$ *term, strike off a factor from the beginning, divide by the number of factors so diminished and by the common difference, change the sign and add a constant.*

The value of $C = \dfrac{v_1}{(r-1)\,b} = \dfrac{a+rb}{(r-1)\,b}\,u_1$; but it is advisable in each case to determine C by ascribing to n some particular value.

Example 1. Find the sum of n terms of the series

$$\frac{1}{1.2.3.4}+\frac{1}{2.3.4.5}+\frac{1}{3.4.5.6}+\cdots\cdots$$

The n^{th} term is $\dfrac{1}{n(n+1)(n+2)(n+3)}$;

hence, by the rule, we have

$$S_n = C - \frac{1}{3(n+1)(n+2)(n+3)}.$$

Put $n=1$, then $\dfrac{1}{1.2.3.4}=C-\dfrac{1}{3.2.3.4}$; whence $C=\dfrac{1}{18}$;

$$\therefore\ S_n=\frac{1}{18}-\frac{1}{3(n+1)(n+2)(n+3)}.$$

By making n indefinitely great, we obtain $S_\infty=\dfrac{1}{18}$.

Example 2. Find the sum to n terms of the series

$$\frac{3}{1.2.4}+\frac{4}{2.3.5}+\frac{5}{3.4.6}+\cdots\cdots$$

Here the rule is not directly applicable, because although 1, 2, 3, ..., the first factors of the several denominators, are in arithmetical progression, the factors of any one denominator are not. In this example we may proceed as follows:

$$u_n=\frac{n+2}{n(n+1)(n+3)}=\frac{(n+2)^2}{n(n+1)(n+2)(n+3)}$$

$$=\frac{n(n+1)+3n+4}{n(n+1)(n+2)(n+3)}$$

$$=\frac{1}{(n+2)(n+3)}+\frac{3}{(n+1)(n+2)(n+3)}+\frac{4}{n(n+1)(n+2)(n+3)}.$$

Each of these expressions may now be taken as the n^{th} term of a series to which the rule is applicable.

$$\therefore\ S_n=C-\frac{1}{n+3}-\frac{3}{2(n+2)(n+3)}-\frac{4}{3(n+1)(n+2)(n+3)};$$

put $n=1$ then

$$\frac{3}{1.2.4}=C-\frac{1}{4}-\frac{3}{2.3.4}-\frac{4}{3.2.3.4};\ \text{whence}\ C=\frac{29}{36};$$

$$S_n=\frac{29}{36}-\frac{1}{n+3}-\frac{3}{2(n+2)(n+3)}-\frac{4}{3(n+1)(n+2)(n+3)}.$$

387. In cases where the methods of Arts. 383, 386 are *directly* applicable, instead of quoting the rules we may always effect the summation in the following way, which is sometimes called 'the Method of Subtraction.'

Example. Find the sum of n terms of the series

$$2.5+5.8+8.11+11.14+$$

The arithmetical progression in this case is

$$2, 5, 8, 11, 14,.$$

In each term of the given series introduce as a new factor the next term of the arithmetical progression; denote this series by S', and the given series by S; then

$$S'=2.5.8+5.8.11+8.11.14+\ldots\ldots+(3n-1)(3n+2)(3n+5);$$

$$S'-2.5.8=5.8.11+8.11.14+11.14.17+\ldots \text{ to } (n-1) \text{ terms.}$$

By subtraction,

$$2.5.8=9[5.8+8.11+11.14+\ldots \text{to}(n-1)\text{terms}]-(3n-1)(3n+2)(3n+5),$$

$$2.5.8=9[S-2.5]-(3n-1)(3n+2)(3n+5),$$

$$9S=(3n-1)(3n+2)(3n+5)-2.5.8+2.5.9,$$

$$S=n(3n^2+6n+1).$$

388. When the n^{th} term of a series is a rational integral function of n it can be expressed in a form which will enable us readily to apply the method given in Art. 383.

For suppose $\phi(n)$ is a rational integral function of n of p dimensions, and assume

$$\phi(n)=A+Bn+Cn(n+1)+Dn(n+1)(n+2)+\ldots\ldots,$$

where A, B, C, D, are undetermined constants $p+1$ in number.

This identity being true for all values of n, we may equate the coefficients of like powers of n; we thus obtain $p+1$ simple equations to determine the $p+1$ constants.

Example. Find the sum of n terms of the series whose general term is

$$n^4+6n^3+5n^2.$$

Assume

$$n^4+6n^3+5n^2=A+Bn+Cn(n+1)+Dn(n+1)(n+2)+En(n+1)(n+2)(n+3);$$

it is at once obvious that $A=0$, $B=0$, $E=1$; and by putting $n=-2$, $n=-3$ successively, we obtain $C=-6$, $D=0$. Thus

$$n^4+6n^3+5n^2=n(n+1)(n+2)(n+3)-6n(n+1).$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

392. *To find the* n$^{\text{th}}$ *term and the sum of* n *terms of the* r$^{\text{th}}$ *order of figurate numbers.*

The n^{th} term of the first order is 1; the n^{th} term of the second order is n; the n^{th} term of the third order is Σn, that is $\frac{1}{2}n(n+1)$; the n^{th} term of the fourth order is $\Sigma \frac{n(n+1)}{\lfloor 2}$, that is $\frac{n(n+1)(n+2)}{\lfloor 3}$; the n^{th} term of the fifth order is $\Sigma \frac{n(n+1)(n+2)}{\lfloor 4}$, that is $\frac{n(n+1)(n+2)(n+3)}{\lfloor 4}$; and so on.

Thus it is easy to see that the n^{th} term of the r^{th} order is

$$\frac{n(n+1)(n+2)\ldots(n+r-2)}{\lfloor r-1}, \text{ or } \frac{\lfloor n+r-2}{\lfloor n-1 \lfloor r-1}.$$

Again, the sum of n terms of the r^{th} order is

$$\frac{n(n+1)(n+2)\ldots(n+r-1)}{\lfloor r},$$

which is the n^{th} term of the $(r+1)^{\text{th}}$ order.

NOTE. In applying the rule of Art. 383 to find the sum of n terms of any order of figurate numbers, it will be found that the constant is always zero.

393. The properties of *figurate numbers* are historically interesting on account of the use made of them by Pascal in his *Traité du triangle arithmétique*, published in 1665.

The following table exhibits the *Arithmetical Triangle* in its simplest form

1	1	1	1	1	1	1	1	1	1
1	2	3	4	5	6	7	8	9	
1	3	6	10	15	21	28	36		
1	4	10	20	35	56	84			
1	5	15	35	70	126				
1	6	21	56	126					
1	7	28	84						
1	8	36							
1	9								

Pascal constructed the numbers in the triangle by the following rule :

Each number is the sum of that immediately above it and that immediately to the left of it;

thus $15 = 5 + 10,\ 28 = 7 + 21,\ 126 = 56 + 70.$

From the mode of construction, it follows that the numbers in the successive horizontal rows, or vertical columns, are the figurate numbers of the first, second, third, ... orders.

A line drawn so as to cut off an equal number of units from the top row and the left-hand column is called a *base*, and the bases are numbered beginning from the top left-hand corner. Thus the 6th base is a line drawn through the numbers 1, 5, 10, 10, 5, 1 ; and it will be observed that there are six of these numbers, and that they are the coefficients of the terms in the expansion of $(1 + x)^5$.

The properties of these numbers were discussed by Pascal with great skill : in particular he used his *Arithmetical Triangle* to develop the theory of Combinations, and to establish some interesting propositions in Probability. The subject is fully treated in Todhunter's *History of Probability*, Chapter II.

394. Where no ambiguity exists as to the number of terms in a series, we have used the symbol Σ to indicate summation ; but in some cases the following modified notation, which indicates the limits between which the summation is to be effected, will be found more convenient.

Let $\phi(x)$ be any function of x, then $\sum_{x=l}^{x=m} \phi(x)$ denotes the sum of the series of terms obtained from $\phi(x)$ by giving to x all positive integral values from l to m inclusive.

For instance, suppose it is required to find the sum of all the terms of the series obtained from the expression

$$\frac{(p-1)(p-2)\ldots(p-r)}{\lfloor r}$$

by giving to p all integral values from $r+1$ to p inclusive.

Writing the factors of the numerator in ascending order,

$$\text{the required sum} = \sum_{p=r+1}^{p=p} \frac{(p-r)(p-r+1)\dots(p-1)}{\lfloor r}$$

$$= \frac{1}{\lfloor r}\{1.2.3.\dots.r+2.3.4.\dots.(r+1)+\dots+(p-r)(p-r+1)\dots(p-1)\}$$

$$= \frac{1}{\lfloor r}.\frac{(p-r)(p-r+1)\dots(p-1)\,p}{r+1}, \qquad \text{[Art. 383.]}$$

$$= \frac{p\,(-1)(p-2)\dots(p-r)}{\lfloor r+1}.$$

Since the given expression is zero for all values of p from 1 to r inclusive, we may write the result in the form

$$\sum_{p=1}^{p=p} \frac{(p-1)(p-2)\dots(p-r)}{\lfloor r} = \frac{p\,(p-1)(p-2)\dots(p-r)}{\lfloor r+1}.$$

EXAMPLES. XXIX. a.

Sum the following series to n terms:

1. $1.2.3+2.3.4+3.4.5+\dots\dots$

2. $1.2.3.4+2.3.4.5+3.4.5.6+$

3. $1.4.7+4.7.10+7.10.13+\dots\dots$

4. $1.4.7+2.5.8+3.6.9+$

5. $1.5.9+2.6.10+3.7.11+$

Sum the following series to n terms and to infinity:

6. $\frac{1}{1.2}+\frac{1}{2.3}+\frac{1}{3.4}+\dots\dots$

7. $\frac{1}{1.4}+\frac{1}{4.7}+\frac{1}{7.10}+\dots\dots$

8. $\frac{1}{1.3.5}+\frac{1}{3.5.7}+\frac{1}{5.7.9}+\dots\dots$

9. $\frac{1}{1.4.7}+\frac{1}{4.7.10}+\frac{1}{7.10.13}+\dots\dots$

10. $\frac{4}{1.2.3}+\frac{5}{2.3.4}+\frac{6}{3.4.5}+\dots\dots$

11. $\frac{1}{3.4.5}+\frac{2}{4.5.6}+\frac{3}{5.6.7}+\dots\dots$

12. $\frac{1}{1.2.3}+\frac{3}{2.3.4}+\frac{5}{3.4.5}+\frac{7}{4.5.6}+\dots\dots$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

From this series we may proceed to form the *series of the third, fourth, fifth,... orders of differences*, the general terms of these series being $\Delta_3 u_r$, $\Delta_4 u_r$, $\Delta_5 u_r$,... respectively.

From the law of formation of the series

$$u_1, \quad u_2, \quad u_3, \quad u_4, \quad u_5, \quad u_6, \ldots\ldots\ldots$$

$$\Delta u_1, \quad \Delta u_2, \quad \Delta u_3, \quad \Delta u_4, \quad \Delta u_5, \ldots\ldots\ldots$$

$$\Delta_2 u_1, \quad \Delta_2 u_2, \quad \Delta_2 u_3, \quad \Delta_2 u_4, \ldots\ldots\ldots$$

$$\Delta_3 u_1, \quad \Delta_3 u_2, \quad \Delta_3 u_3,$$

$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$

it appears that any term in any series is equal to the term immediately preceding it added to the term below it on the left.

Thus $u_2 = u_1 + \Delta u_1$, and $\Delta u_2 = \Delta u_1 + \Delta_2 u_1$.

By addition, since $u_2 + \Delta u_2 = u_3$ we have

$$u_3 = u_1 + 2\Delta u_1 + \Delta_2 u_1.$$

In an exactly similar manner by using the second, third, and fourth series in place of the first, second, and third, we obtain

$$\Delta u_3 = \Delta u_1 + 2\Delta_2 u_1 + \Delta_3 u_1.$$

By addition, since $u_3 + \Delta u_3 = u_4$, we have

$$u_4 = u_1 + 3\Delta u_1 + 3\Delta_2 u_1 + \Delta_3 u_1.$$

So far as we have proceeded, the numerical coefficients follow the same law as those of the Binomial theorem. We shall now prove by induction that this will always be the case. For suppose that

$$u_{n+1} = u_1 + n\Delta u_1 + \frac{n(n-1)}{1 \cdot 2} \Delta_2 u_1 + \ldots + {}^nC_r \Delta_r u_1 + \ldots\ldots + \Delta_n u_1 ;$$

then by using the second to the $(n+2)^{\text{th}}$ series in the place of the first to the $(n+1)^{\text{th}}$ series, we have

$$\Delta u_{n+1} = \Delta u_1 + n\Delta_2 u_1 + \frac{n(n-1)}{1 \cdot 2} \Delta_3 u_1 + \ldots + {}^nC_{r-1} \Delta_r u_1 + \ldots + \Delta_{n+1} u_1 .$$

By addition, since $u_{n+1} + \Delta u_{n+1} = u_{n+2}$, we obtain

$$u_{n+2} - u_1 + (n+1)\,\Delta u_1 + \ldots + ({}^nC_r + {}^nC_{r-1})\,\Delta_r u_1 + \ldots + \Delta_{n+1} u_1 .$$

$$\text{But} \quad {}^nC_r + {}^nC_{r-1} = \left(\frac{n-r+1}{r} + 1\right) \times {}^nC_{r-1} = \frac{n+1}{r} \times {}^nC_{r-1}$$

$$= \frac{(n+1)\,n\,(n-1)\,\ldots\,(\overline{n+1}-r+1)}{1\,.\,2\,.\,3\,\ldots\,(r-1)\,r} = {}^{n+1}C_r.$$

Hence if the law of formation holds for u_{n+1} it also holds for u_{n+2}, but it is true in the case of u_4, therefore it holds for u_5, and therefore universally. Hence

$$u_n = u_1 + (n-1)\,\Delta u_1 + \frac{(n-1)(n-2)}{1\,.\,2}\,\Delta_2 u_1 + \ldots + \Delta_{n-1} u_1.$$

396. To find the sum of n terms of the series

$$u_1, \quad u_2, \quad u_3, \quad u_4, \ldots\ldots$$

in terms of the differences of u_1.

Suppose the series $u_1, u_2, u_3, \ldots$ is the first order of differences of the series

$$v_1, \quad v_2, \quad v_3, \quad v_4, \ldots,$$

then $v_{n+1} = (v_{n+1} - v_n) + (v_n - v_{n-1}) + \ldots + (v_2 - v_1) + v_1$ identically;

$$\therefore \; v_{n+1} - u_n + u_{n-1} + \ldots + u_2 + u_1 + v_1.$$

Hence in the series

$$0, \quad v_2, \quad v_3, \quad v_4, \quad v_5 \ldots\ldots$$

$$u_1, \quad u_2, \quad u_3, \quad u_4, \ldots\ldots$$

$$\Delta u_1, \quad \Delta u_2, \quad \Delta u_3 \ldots\ldots$$

the law of formation is the same as in the preceding article;

$$\therefore \; v_{n+1} = 0 + nu_1 + \frac{n\,(n-1)}{1\,.\,2}\,\Delta u_1 + \ldots + \Delta_n u_1;$$

that is, $u_1 + u_2 + u_3 + \ldots + u_n$

$$= nu_1 + \frac{n\,(n-1)}{\lfloor 2}\,\Delta u_1 + \frac{n\,(n-1)\,(n-2)}{\lfloor\underline{3}}\,\Delta_2 u_1 + \ldots + \Delta_n u_1.$$

The formulæ of this and the preceding article may be expressed in a slightly different form, as follows: if a is the first term of a given series, d_1, d_2, d_3 the first terms of the successive orders of differences, the n^{th} term of the given series is obtained from the formula

$$a + (n-1)\,d_1 + \frac{(n-1)\,(n-2)}{\lfloor\underline{2}}\,d_2 + \frac{(n-1)\,(n-2)\,(n-3)}{\lfloor\underline{3}}\,d_3 + \ldots$$

and the sum of n terms is

$$na+\frac{n(n-1)}{\lfloor 2}d_1+\frac{n(n-1)(n-2)}{\lfloor 3}d_2+\frac{n(n-1)(n-2)(n-3)}{\lfloor 4}d_3+\ldots.$$

Example. Find the general term and the sum of n terms of the series

12, 40, 90, 168, 280, 432,.....

The successive orders of difference are

28, 50, 78, 112, 152,.....

22, 28, 34, 40,.....

6, 6, 6,.

0, 0,...

Hence the n^{th} term $=12+28(n-1)+\frac{22(n-1)(n-2)}{\lfloor 2}+\frac{6(n-1)(n-2)(n-3)}{\lfloor 3}$

$$-n^3+5n^2+6n.$$

The sum of n terms may now be found by writing down the value of $\Sigma n^3+5\Sigma n^2+6\Sigma n$. Or we may use the formula of the present article and obtain $S_n=12n+\frac{28n(n-1)}{\lfloor 2}+\frac{22n(n-1)(n-2)}{\lfloor 3}+\frac{6n(n-1)(n-2)(n-3)}{\lfloor 4}$

$$-\frac{n}{12}(3n^2+26n+69n+46),$$

$$=\frac{1}{12}n(n+1)(3n^2+23n+46).$$

397. It will be seen that this method of summation will only succeed when the series is such that in forming the orders of differences we eventually come to a series in which all the terms are equal. This will always be the case if the n^{th} term of the series is a rational integral function of n.

For simplicity we will consider a function of three dimensions; the method of proof, however, is perfectly general.

Let the series be

$$u_1+u_2+u_3+\ldots\ldots+u_n+u_{n+1}+u_{n+2}+u_{n+3}+\ldots\ldots$$

where $$u_n=An^3+Bn^2+Cn+D,$$

and let v_n, w_n, z_n denote the n^{th} term of the first, second, third orders of differences;

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Hence it follows that after the successive multiplications by $1-x$, the coefficients of x^n in the first, second, third, ... products are general terms in the first, second, third, ... orders of differences of the coefficients.

By hypothesis a_n is a rational integral function of n of p dimensions; therefore after p multiplications by $1-x$ we shall arrive at a series the terms of which, with the exception of p terms at the beginning, and p terms at the end of the series, form a geometrical progression, each of whose coefficients is the same. [Art. 397.]

Thus $$S(1-x)^p = k(x^p + x^{p+1} + \ldots + x^n) + f(x),$$

where k is a constant, and $f(x)$ stands for the p terms at the beginning and p terms at the end of the product.

$$\therefore\ S(1-x)^p = \frac{k(x^p - x^{n+1})}{1-x} + f(x);$$

that is, $$S = \frac{kx^p(1-x^{n-p+1}) + (1-x)f(x)}{(1-x)^{p+1}};$$

thus the series is a recurring series whose scale of relation is $(1-x)^{p+1}$ [Art. 325.]

If the general term is not given, the dimensions of a_n are readily found by the method explained in Art. 397.

Example. Find the generating function of the series

$$3 + 5x + 9x^2 + 15x^3 + 23x^4 + 33x^5 +$$

Forming the successive orders of differences of the coefficients, we have the series

$$2,\ 4,\ 6,\ 8,\ 10,$$

$$2,\ 2,\ 2,\ 2, \ldots\ldots;$$

thus the terms in the second order of differences are equal; hence a_n is a rational integral function of n of two dimensions; and therefore the scale of relation is $(1-x)^3$. We have

$$\begin{aligned}
S &= 3 + 5x + 9x^2 + 15x^3 + 23x^4 + 33x^5 + \ldots\ldots \\
-3xS &= -9x - 15x^2 - 27x^3 - 45x^4 - 69x^5 \quad \ldots\ldots \\
3x^2S &= 9x^2 + 15x^3 + 27x^4 + 45x^5 + \ldots\ldots \\
-x^3S &= 3x^3 - 5x^4 - 9x^5 - \ldots\ldots
\end{aligned}$$

By addition, $$(1-x)^3 S = 3 - 4x + 3x^2;$$

$$\therefore\ S = \frac{3 - 4x + 3x^2}{(1-x)^3}.$$

399. We have seen in Chap. XXIV. that the generating function of a recurring series is a rational fraction whose denominator is the scale of relation. Suppose that this denominator can be resolved into the factors $(1-ax)(1-bx)(1-cx)\ldots\ldots$; then the generating function can be separated into partial fractions of the form

$$\frac{A}{1-ax}+\frac{B}{1-bx}+\frac{C}{1-cx}+\ldots\ldots$$

Each of these fractions can be expanded by the Binomial Theorem in the form of a geometrical series; hence in this case the recurring series can be expressed as the sum of a number of geometrical series.

If however the scale of relation contains any factor $1-ax$ more than once, corresponding to this repeated factor there will be partial fractions of the form $\frac{A_2}{(1-ax)^2}$, $\frac{A_3}{(1-ax)^3}$,$\ldots\ldots$; which when expanded by the Binomial Theorem do not form geometrical series; hence in this case the recurring series cannot be expressed as the sum of a number of geometrical series.

400. The successive orders of differences of the geometrical progression

$$a,\ ar,\ ar^2,\ ar^3,\ ar^4,\ ar^5,\ \ldots\ldots$$

are

$$a(r-1),\ a(r-1)r,\ a(r-1)r^2,\ a(r-1)r^3,\ldots\ldots$$
$$a(r-1)^2,\ a(r-1)^2r,\ a(r-1)^2r^2,$$
$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$

which are themselves geometrical progressions having the same common ratio r as the original series.

401. Let us consider the series in which

$$u_n=ar^{n-1}+\phi(n),$$

where $\phi(n)$ is a rational integral function of n of p dimensions, and from this series let us form the successive orders of differences. Each term in any of these orders is the sum of two parts, one arising from terms of the form ar^{n-1}, and the other from terms of the form $\phi(n)$ in the original series. Now since $\phi(n)$ is of p dimensions, the part arising from $\phi(n)$ will be zero in the $(p+1)^{\text{th}}$ and succeeding orders of differences, and therefore these series will be geometrical progressions whose common ratio is r.

[Art. 400.]

Hence if the first few terms of a series are given, and if the p^{th} order of differences of these terms form a geometrical progression whose common ratio is r, then we may assume that the general term of the given series is $ar^{n-1}+\phi f(n)$, where $\phi f(n)$ is a rational integral function of n of $p-1$ dimensions.

Example. Find the n^{th} term of the series

10, 23, 60, 169, 494, ...

The successive orders of differences are

13, 37, 109, 335,.....

24, 72, 216,.....

Thus the second order of differences is a geometrical progression in which the common ratio is 3; hence we may assume for the general term

$$u_n = a \cdot 3^{n-1} + bn + c.$$

To determine the constants a, b, c, make n equal to 1, 2, 3 successively;

then $$a+b+c=10,\ 3a+2b+c=23,\ 9a+3b+c=60;$$

whence $$a=6,\ b=1,\ c=3.$$

Thus $$u_n = 6 \cdot 3^{n-1} + n + 3 = 2 \cdot 3^n + n + 3.$$

402. In each of the examples on recurring series that we have just given, on forming the successive orders of differences we have obtained a series the law of which is obvious on inspection, and we have thus been enabled to find a general expression for the n^{th} term of the original series.

If, however, the recurring series is equal to the sum of a number of geometrical progressions whose common ratios are a, b, c, . ., its general term is of the form $Aa^{n-1}+Bb^{n-1}+Cc^{n-1}$, and therefore the general term in the successive orders of differences is of the same form; that is, all the orders of differences follow the same law as the original series. In this case to find the general term of the series we must have recourse to the more general method explained in Chap. XXIV. But when the coefficients are large the scale of relation is not found without considerable arithmetical labour; hence it is generally worth while to write down a few of the orders of differences to see whether we shall arrive at a series the law of whose terms is evident.

403. We add some examples in further illustration of the preceding principles.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Hence $u_n=(n+1)(n+2)\{2n(n+3)+1\}$

$=2n(n+1)(n+2)(n+3)+(n+1)(n+2)$;

$\therefore\ S_n=\frac{2}{5}n(n+1)(n+2)(n+3)(n+4)+\frac{1}{3}(n+1)(n+2)(n+3)-2.$

Example 4. Find the sum of n terms of the series

$2\,.\,2+6\,.\,4+12\,.\,8+20\,.\,16+30\,.\,32+\ldots\ldots$

In the series 2, 6, 12, 20, 30, ... the n^{th} term is n^2+n;

hence $u_n=(n^2+n)\,2^n.$

Assume $(n^2+n)\,2^n=(An^2+Bn+C)\,2^n-\{A(n-1)^2+B(n-1)+C\}\,2^{n-1}$;

dividing out by 2^{n-1} and equating coefficients of like powers of n, we have

$2=A,\ 2=2A+B,\ 0=C-A+B$;

whence $A=2,\ B=-2,\ C=4.$

$\therefore\ u_n=(2n^2-2n+4)\,2^n-\{2(n-1)^2-2(n-1)+4\}\,2^{n-1}$;

and $S_n=(2n^2-2n+4)\,2^n-4=(n^2-n+2)\,2^{n+1}-4.$

EXAMPLES. XXIX. b.

Find the n^{th} term and the sum of n terms of the series:

1. 4, 14, 30, 52, 80, 114, ...

2. 8, 26, 54, 92, 140, 198,

3. 2, 12, 36, 80, 150, 252,

4. 8, 16, 0, -64, -200, -432, ...

5. 30, 144, 420, 960, 1890, 3360, ...

Find the generating functions of the series:

6. $1+3x+7x^2+13x^3+21x^4+31x^5+\ldots\ldots$

7. $1+2x+9x^2+20x^3+35x^4+54x^5+\ldots\ldots$

8. $2+5x+10x^2+17x^3+26x^4+37x^5+\ldots\ldots$

9. $1-3x+5x^2-7x^3+9x^4-11x^5+\ldots\ldots$

10. $1^4+2^4x+3^4x^2+4^4x^3+5^4x^4+$

Find the sum of the infinite series:

11. $\frac{1\,.\,2}{3}+\frac{2\,.\,3}{3^2}+\frac{3\,.\,4}{3^3}+\frac{4\,.\,5}{3^4}+\ldots\ldots$

12. $1^2-\frac{2^2}{5}+\frac{3^2}{5^2}\quad\frac{4^2}{5^3}+\frac{5^2}{5^4}-\frac{6^2}{5^5}+\ldots\ldots$

Find the general term and the sum of n terms of the series:

13. 9, 16, 29, 54, 103,.

14. $-3, -1, 11, 39, 89, 167,\ldots\ldots$

15. 2, 5, 12, 31, 86,

16. 1, 0, 1, 8, 29, 80, 193,.....

17. 4, 13, 35, 94, 262, 755.....

Find the sum of n terms of the series:

18. $1+2x+3x^2+4x^3+5x^4+\ldots\ldots$

19. $1+3x+6x^2+10x^3+15x^4+\ldots\ldots$

20. $\frac{3}{1.2}\cdot\frac{1}{2}+\frac{4}{2.3}\cdot\frac{1}{2^2}+\frac{5}{3.4}\cdot\frac{1}{2^3}+\frac{6}{4.5}\cdot\frac{1}{2^4}+\ldots\ldots$

21. $\frac{1^2}{2.3}\cdot 4+\frac{2^2}{3.4}\cdot 4^2+\frac{3^2}{4.5}\cdot 4^3+\frac{4^2}{5.6}\cdot 4^4+\ldots\ldots$

22. $3.4+8.11+15.20+24.31+35.44+\ldots\ldots$

23. $1.3+4.7+9.13+16.21+25.31+\ldots\ldots$

24. $1.5+2.15+3.31+4.53+5.81+\ldots\ldots$

25. $\frac{1}{1.3}+\frac{2}{1.3.5}+\frac{3}{1.3.5.7}+\frac{4}{1.3.5.7.9}+\ldots\ldots$

26. $\frac{1.2}{\lfloor 3}+\frac{2.2^2}{\lfloor 4}+\frac{3.2^3}{\lfloor 5}+\frac{4.2^4}{\lfloor 6}+\ldots\ldots$

27. $2.2+4.4+7.8+11.16+16.32+\ldots\ldots$

28. $1.3+3.3^2+5.3^3+7.3^4+9.3^5+$

29. $\frac{1}{2.4}+\frac{1.3}{2.4.6}+\frac{1.3.5}{2.4.6.8}+\frac{1.3.5.7}{2.4.6.8.10}+\ldots\ldots$

30. $\frac{2}{1.2}+\frac{5}{2.3}\cdot 2+\frac{10}{3.4}\cdot 2^2+\frac{17}{4.5}\cdot 2^3+\ldots\ldots$

31. $\frac{4}{1.2.3}\cdot\frac{1}{3}+\frac{5}{2.3.4}\cdot\frac{1}{3^2}+\frac{6}{3.4.5}\cdot\frac{1}{3^3}+\ldots\ldots$

32. $\frac{1}{\lfloor 3}+\frac{5}{\lfloor 4}+\frac{11}{\lfloor 5}+\frac{19}{\lfloor 6}+$

33. $\frac{19}{1.2.3}\cdot\frac{1}{4}+\frac{28}{2.3.4}\cdot\frac{1}{8}+\frac{39}{3.4.5}\cdot\frac{1}{16}+\frac{52}{4.5.6}\cdot\frac{1}{32}+\ldots\ldots$

404. There are many series the summation of which can be brought under no general rule. In some cases a skilful modification of the foregoing methods may be necessary; in others it will be found that the summation depends on the properties of certain known expansions, such as those obtained by the Binomial, Logarithmic, and Exponential Theorems.

Example 1. Find the sum of the infinite series

$$\frac{2}{\lfloor 1} + \frac{12}{\lfloor 2} + \frac{28}{\lfloor 3} + \frac{50}{\lfloor 4} + \frac{78}{\lfloor 5} + \ldots\ldots$$

n^{th} term of the series 2, 12, 28, 50, 78..... is $3n^2+n-2$; hence

$$u_n = \frac{3n^2+n-2}{\lfloor n} = \frac{3n(n-1)+4n-2}{\lfloor n}$$

$$= \frac{3}{\lfloor n-2} + \frac{4}{\lfloor n-1} - \frac{2}{\lfloor n}.$$

Put n equal to 1, 2, 3, 4,... in succession; then we have

$$u_1 = 4 \quad \frac{2}{\lfloor 1}; \quad u_2 = 3 + \frac{4}{\lfloor 1} - \frac{2}{\lfloor 2}; \quad u_3 = \frac{3}{\lfloor 1} + \frac{4}{\lfloor 2} - \frac{2}{\lfloor 3};$$

and so on.

Whence $S_\infty = 3e + 4e - 2(e-1) = 5e+2.$

Example 2. If $(1+x)^n = c_0 + c_1x + c_2x^2 + \ldots + c_nx^n$, find the value of

$$1^2c_1 + 2^2c_2 + 3^2c_3 + \ldots + n^2c_n.$$

As in Art. 398 we may easily shew that

$$1^2 + 2^2x + 3^2x^2 + 4^2x^3 + \ldots + n^2x^{n-1} + \ldots = \frac{1+x}{(1-x)^3}.$$

Also $c_n + c_{n-1}x + \ldots c_2x^{n-2} + c_1x^{n-1} + c_0x^n = (1+x)^n$

Multiply together these two results; then the given series is equal to the coefficient of x^{n-1} in $\frac{(1+x)^{n+1}}{(1-x)^3}$, that is, in $\frac{(2-\overline{1-x})^{n+1}}{(1-x)^3}$.

The only terms containing x^{n-1} in this expansion arise from

$$2^{n+1}(1-x)^{-3} - (n+1)\,2^n(1-x)^{-2} + \frac{(n+1)\,n}{\lfloor 2}\,2^{n-1}(1-x)^{-1};$$

$\therefore$ the given series $= \frac{n(n+1)}{\lfloor 2}\,2^{n+1} - n(n+1)\,2^n + \frac{n(n+1)}{\lfloor 2}\,2^{n-1}$

$$= n(n+1)\,2^{n-2}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

405. *To find the sum of the* r^{th} *powers of the first* n *natural numbers.*

Let the sum be denoted by S_n; then

$$S_n = 1^r + 2^r + 3^r + \ldots + n^r.$$

Assume that

$$S_n = A_0 n^{r+1} + A_1 n^r + A_2 n^{r-1} + A_3 n^{r-2} + \ldots + A_r n + A_{r+1} \ldots\ldots\ldots (1),$$

where A_0, A_1, A_2, A_3, ... are quantities whose values have to be determined.

Write $n+1$ in the place of n and subtract; thus

$$(n+1)^r = A_0\{(n+1)^{r+1} - n^{r+1}\} + A_1\{(n+1)^r - n^r\}$$
$$+ A_2\{(n+1)^{r-1} - n^{r-1}\} + A_3\{(n+1)^{r-2} - n^{r-2}\} + \ldots + A_r \ldots (2).$$

Expand $(n+1)^{r+1}$, $(n+1)^r$, $(n+1)^{r-1}$, and equate the coefficients of like powers of n. By equating the coefficients of n^r, we have

$$1 = A_0(r+1), \text{ so that } A_0 = \frac{1}{r+1}.$$

By equating the coefficients of n^{r-1}, we have

$$r = \frac{A_0(r+1)\,r}{2} + A_1 r; \text{ whence } A_1 = \frac{1}{2}.$$

Equate the coefficients of n^{r-p}, substitute for A_0 and A_1, and multiply both sides of the equation by

$$\frac{\lfloor\underline{p}}{r(r-1)(r-2)\ldots(r-p+1)};$$

we thus obtain

$$1 = \frac{1}{p+1} + \frac{1}{2} + A_2\frac{p}{r} + A_3\frac{p(p-1)}{r(r-1)} + A_4\frac{p(p-1)(p-2)}{r(r-1)(r-2)} + \ldots (3).$$

In (1) write $n-1$ in the place of n and subtract; thus

$$n^r = A_0\{n^{r+1} - (n-1)^{r+1}\} + A_1\{n^r - (n-1)^r\} + A_2\{n^{r-1} - (n-1)^{r-1}\} + \ldots$$

Equate the coefficients of n^{r-p}, and substitute for A_0, A_1; thus

$$0 = \frac{1}{p+1} - \frac{1}{2} + A_2\frac{p}{r} - A_3\frac{p(p-1)}{r(r-1)} + A_4\frac{p(p-1)(p-2)}{r(r-1)(r-2)} - \ldots . (4)$$

From (3) and (4), by addition and subtraction,

$$\frac{1}{2} - \frac{1}{p+1} = A_2 \frac{p}{r} + A_4 \frac{p(p-1)(p-2)}{r(r-1)(r-2)} + \ldots\ldots\ldots\ldots\ldots\ldots\ldots (5).$$

$$0 = A_3 \frac{p(p-1)}{r(r-1)} + A_5 \frac{p(p-1)(p-2)(p-3)}{r(r-1)(r-2)(r-3)} + \ldots\ldots (6).$$

By ascribing to p in succession the values 2, 4, 6,..., we see from (6) that each of the coefficients A_3, A_5, A_7,... is equal to zero; and from (5) we obtain

$$A_2 = \frac{1}{6} \cdot \frac{r}{\lfloor 2}, \quad A_4 = -\frac{1}{30} \cdot \frac{r(r-1)(r-2)}{\lfloor 4};$$

$$A_6 = \frac{1}{42} \cdot \frac{r(r-1)(r-2)(r-3)(r-4)}{\lfloor 6} \quad \ldots\ldots$$

By equating the absolute terms in (2), we obtain

$$1 = A_0 + A_1 + A_2 + A_3 + \ldots\ldots + A_r;$$

and by putting $n = 1$ in equation (1), we have

$$1 = A_0 + A_1 + A_2 + A_3 + \ldots\ldots + A_r + A_{r+1};$$

thus $$A_{r+1} = 0.$$

406. The result of the preceding article is most conveniently expressed by the formula,

$$S_n = \frac{n^{r+1}}{r+1} + \frac{1}{2} n^r + B_1 \frac{r}{\lfloor 2} n^{r-1} - B_3 \frac{r(r-1)(r-2)}{\lfloor 4} n^{r-3} + B_5 \frac{r(r-1)(r-2)(r-3)(r-4)}{\lfloor 6} n^{r-5} + \ldots$$

where $B_1 = \frac{1}{6}$, $B_3 = \frac{1}{30}$, $B_5 = \frac{1}{42}$, $B_7 = \frac{1}{30}$, $B_9 = \frac{5}{66}$, .

The quantities $B_1, B_3, B_5, \ldots$ are known as *Bernoulli's Numbers;* for examples of their application to the summation of other series the advanced student may consult Boole's *Finite Differences.*

Example. Find the value of $1^5 + 2^5 + 3^5 + \quad . + n^5$.

We have $$S_n = \frac{n^6}{6} + \frac{n^5}{2} + B_1 \frac{5}{\lfloor 2} n^4 - B_3 \frac{5.4.3}{\lfloor 4} n^2 + C,$$

$$= \frac{n^6}{6} + \frac{n^5}{2} + \frac{5n^4}{12} - \frac{n^2}{12},$$

the constant being zero.

EXAMPLES. XXIX. c.

Find the sum of the following series:

1. $\frac{x^3}{\lfloor 3} + \frac{x^5}{\lfloor 5} + \frac{x^7}{\lfloor 7} + \ldots\ldots$

2. $\frac{x}{1.2} + \frac{x^2}{2.3} + \frac{x^3}{3.4} + \ldots\ldots$

3. $x + \frac{x^5}{\lfloor 5} + \frac{x^9}{\lfloor 9} + \ldots\ldots$

4. $\frac{1}{\lfloor r} + \frac{\lfloor 2}{\lfloor r+1} + \frac{\lfloor 3}{\lfloor r+2} + \ldots\ldots$

5. $1 + 2x + \frac{2^2-1}{\lfloor 2} \cdot \frac{x^2}{1} + \frac{3^2-1}{\lfloor 3} \cdot \frac{x^3}{2} + \frac{4^2-1}{\lfloor 4} \cdot \frac{x^4}{3} + \ldots\ldots$

6. $\frac{p^r}{\lfloor r} + \frac{p^{r-1}}{\lfloor r-1} \cdot \frac{q}{1} + \frac{p^{r-2}}{\lfloor r-2} \cdot \frac{q^2}{\lfloor 2} + \frac{p^{r-3}}{\lfloor r-3} \cdot \frac{q^3}{\lfloor 3} + \ldots\ldots$ to $r+1$ terms.

7. $\frac{n(1+x)}{1+nx} - \frac{n(n-1)}{\lfloor 2} \cdot \frac{1+2x}{(1+nx)^2}$
$+ \frac{n(n-1)(n-2)}{\lfloor 3} \cdot \frac{1+3x}{(1+nx)^3} - \ldots\ldots$ to n terms.

8. $1 + 3\frac{2n+1}{2n-1} + 5\left(\frac{2n+1}{2n-1}\right)^2 + \ldots\ldots$ to n terms.

9. $1 - \frac{n^2}{1^2} + \frac{n^2(n^2-1^2)}{1^2.2^2} - \frac{n^2(n^2-1^2)(n^2-2^2)}{1^2.2^2.3^2} + \ldots\ldots$ to $n+1$ terms.

10. $(1+2)\log_e 2 + \frac{1+2^2}{\lfloor 2}(\log_e 2)^2 + \frac{1+2^3}{\lfloor 3}(\log_e 2)^3 +$

11. $\frac{1}{1.2.3} + \frac{1}{3.4.5} + \frac{1}{5.6.7} + \ldots\ldots$

12. $\frac{2}{\lfloor 1} + \frac{3}{\lfloor 2} + \frac{6}{\lfloor 3} + \frac{11}{\lfloor 4} + \frac{18}{\lfloor 5} + \ldots\ldots$

13. $1 + \frac{2x^2}{\lfloor 2} - \frac{x^3}{\lfloor 3} + \frac{7x^4}{\lfloor 4} - \frac{23x^5}{\lfloor 5} + \frac{121x^6}{\lfloor 6} - \ldots\ldots$

14. Without assuming the formula, find the sum of the series:

(1) $1^6 + 2^6 + 3^6 + \ldots\ldots + n^6$. (2) $1^7 + 2^7 + 3^7 + \ldots + n^7$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

24. If A_r is the coefficient of x^r in the expansion of

$$(1+x)^2\left(1+\frac{x}{2}\right)^2\left(1+\frac{x}{2^2}\right)^2\left(1+\frac{x}{2^3}\right)^2\ldots\ldots,$$

prove that $A_r=\dfrac{2^2}{2^r-1}(A_{r-1}+A_{r-2})$, and $A_4=\dfrac{1072}{315}$.

25. If n is a multiple of 6, shew that each of the series

$$n-\frac{n(n-1)(n-2)}{\lfloor 3}\cdot 3+\frac{n(n-1)(n-2)(n-3)(n-4)}{\lfloor 5}\cdot 3^2-\ldots.$$

$$n-\frac{n(n-1)(n-2)}{\lfloor 3}\cdot\frac{1}{3}+\frac{n(n-1)(n-2)(n-3)(n-4)}{\lfloor 5}\cdot\frac{1}{3^2}-\ldots.$$

is equal to zero.

26. If n is a positive integer, shew that

$$(p+q)^n-(n-1)pq(p+q)^{n-2}+\frac{(n-2)(n-3)}{\lfloor 2}p^2q^2(p+q)^{n-4}$$

is equal to $\dfrac{p^{n+1}-q^{n+1}}{p-q}$.

27. If $P_r=(n-r)(n-r+1)(n-r+2)\ldots\ldots(n-r+p-1)$,

$$Q_r=r(r+1)(r+2)\ldots\ldots(r+q-1),$$

shew that

$$P_1Q_1+P_2Q_2+P_3Q_3+\ldots\ldots+P_{n-1}Q_{n-1}=\frac{\lfloor p\ \lfloor q\ \lfloor n-1+p+q}{\lfloor p+q+1\ \lfloor n-2}.$$

28. If n is a multiple of 3, shew that

$$1-\frac{n-3}{2}+\frac{(n-4)(n-5)}{\lfloor 3}-\frac{(n-5)(n-6)(n-7)}{\lfloor 4}+\ldots.$$

$$+(-1)^{r-1}\frac{(n-r-1)(n-r-2)\ldots(n-2r+1)}{\lfloor r}+\ldots.$$

is equal to $\dfrac{3}{\gamma^r}$ or $-\dfrac{1}{\gamma^r}$, according as n is odd or even.

29. If x is a proper fraction, shew that

$$\frac{x}{1-x^2}-\frac{x^3}{1-x^6}+\frac{x^5}{1-x^{10}}-\ldots\ldots=\frac{x}{1+x^2}+\frac{x^3}{1+x^6}+\frac{x^5}{1+x^{10}}+\ldots\ldots$$

CHAPTER XXX.

THEORY OF NUMBERS.

407. In this chapter we shall use the word *number* as equivalent in meaning to *positive integer*.

A number which is not exactly divisible by any number except itself and unity is called a *prime number*, or a *prime*; a number which is divisible by other numbers besides itself and unity is called a *composite number*; thus 53 is a prime number, and 35 is a composite number. Two numbers which have no common factor except unity are said to be prime to each other; thus 24 is prime to 77.

408. We shall make frequent use of the following elementary propositions, some of which arise so naturally out of the definition of a prime that they may be regarded as axioms.

(i) If a number a divides a product bc and is prime to one factor b, it must divide the other factor c.

For since a divides bc, every factor of a is found in bc; but since a is prime to b, no factor of a is found in b; therefore all the factors of a are found in c; that is, a divides c.

(ii) If a prime number a divides a product $bcd\ldots$, it must divide one of the factors of that product; and therefore if a prime number a divides b^n, where n is any positive integer, it must divide b.

(iii) If a is prime to each of the numbers b and c, it is prime to the product bc. For no factor of a can divide b or c; therefore the product bc is not divisible by any factor of a, that is, a is prime to bc. Conversely if a is prime to bc, it is prime to each of the numbers b and c.

Also if a is prime to each of the numbers b, c, d, ..., it is prime to the product $bcd\ldots$; and conversely if a is prime to any number, it is prime to every factor of that number.

(iv) If a and b are prime to each other, every positive integral power of a is prime to every positive integral power of b. This follows at once from (iii).

(v) If a is prime to b, the fractions $\frac{a}{b}$ and $\frac{a^n}{b^m}$ are in their lowest terms, n and m being any positive integers. Also if $\frac{a}{b}$ and $\frac{c}{d}$ are any two equal fractions, and $\frac{a}{b}$ is in its lowest terms, then c and d must be equimultiples of a and b respectively.

409. *The number of primes is infinite.*

For if not, let p be the greatest prime number; then the product $2.3.5.7.11...p$, in which each factor is a prime number, is divisible by each of the factors $2, 3, 5, ...p$; and therefore the number formed by adding unity to their product is not divisible by any of these factors; hence it is either a prime number itself or is divisible by some prime number greater than p: in either case p is not the *greatest* prime number, and therefore the number of primes is not limited.

410. *No rational algebraical formula can represent prime numbers only.*

If possible, let the formula $a + bx + cx^2 + dx^3 + \ldots$ represent prime numbers only, and suppose that when $x = m$ the value of the expression is p, so that

$$p = a + bm + cm^2 + dm^3 + \ldots\ldots;$$

when $x = m + np$ the expression becomes

$$a + b(m + np) + c(m + np)^2 + d(m + np)^3 + \ldots,$$

that is, $a + bm + cm^2 + dm^3 + \ldots +$ a multiple of p,

or $p +$ a multiple of p,

thus the expression is divisible by p, and is therefore not a prime number.

411. *A number can be resolved into prime factors in only one way.*

Let N denote the number; suppose $N = abcd\ldots$, where $a, b, c, d, \ldots$ are prime numbers. Suppose also that $N = \alpha\beta\gamma\delta$ where $\alpha, \beta, \gamma, \delta, \ldots$ are other prime numbers. Then

$$abcd\ldots = \alpha\beta\gamma\delta\ldots;$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

414. *To find the number of ways in which a composite number can be resolved into two factors which are prime to each other.*

As before, let the number $N = a^p b^q c^r$ Of the two factors one must contain a^p, for otherwise there would be some power of a in one factor and some power of a in the other factor, and thus the two factors would not be prime to each other. Similarly b^q must occur in one of the factors only; and so on. Hence the required number is equal to the number of ways in which the product $abc\ldots$ can be resolved into two factors; that is, the number of ways is $\frac{1}{2}(1+1)(1+1)(1+1)\ldots$ or 2^{n-1}, where n is the number of *different* prime factors in N.

415. *To find the sum of the divisors of a number.*

Let the number be denoted by $a^p b^q c^r \ldots$, as before. Then each term of the product

$$(1 + a + a^2 + \ldots + a^p)(1 + b + b^2 + \ldots + b^q)(1 + c + c^2 + \ldots + c^r)\ldots$$

is a divisor, and therefore the *sum* of the divisors is equal to this product; that is,

$$\text{the sum required} = \frac{a^{p+1}-1}{a-1} \cdot \frac{b^{q+1}-1}{b-1} \cdot \frac{c^{r+1}-1}{c-1} \cdots.$$

Example 1. Consider the number 21600.

Since $21600 = 6^3 \cdot 10^2 = 2^3 \cdot 3^3 \cdot 2^2 \cdot 5^2 = 2^5 \cdot 3^3 \cdot 5^2$,

$$\text{the number of divisors} = (5+1)(3+1)(2+1) = 72;$$

$$\text{the sum of the divisors} = \frac{2^6-1}{2-1} \cdot \frac{3^4-1}{3-1} \cdot \frac{5^3-1}{5-1}$$

$$= 63 \times 40 \times 31$$

$$= 78120.$$

Also 21600 can be resolved into two factors prime to each other in 2^{3-1}, or 4 ways.

Example 2. If n is odd shew that $n(n^2-1)$ is divisible by 24.

We have $$n(n^2-1) = n(n-1)(n+1).$$

Since n is odd, $n-1$ and $n+1$ are two consecutive even numbers; hence one of them is divisible by 2 and the other by 4.

Again $n-1$, n, $n+1$ are three consecutive numbers; hence one of them is divisible by 3. Thus the given expression is divisible by the product of 2, 3, and 4, that is, by 24.

Example 3. Find the highest power of 3 which is contained in $\lfloor\underline{100}$.

Of the first 100 integers, as many are divisible by 3 as the number of times that 3 is contained in 100, that is, 33; and the integers are 3, 6, 9,...99. Of these, some contain the factor 3 again, namely 9, 18, 27,...99, and their number is the quotient of 100 divided by 9. Some again of these last integers contain the factor 3 a third time, namely 27, 54, 81, the number of them being the quotient of 100 by 27. One number only, 81, contains the factor 3 four times.

Hence the highest power required $= 33 + 11 + 3 + 1 = 48$.

This example is a particular case of the theorem investigated in the next article.

416. *To find the highest power of a prime number* a *which is contained in* $\lfloor\underline{\text{n}}$.

Let the greatest integer contained in $\frac{n}{a}$, $\frac{n}{a^2}$, $\frac{n}{a^3}$, ... respectively be denoted by $I\left(\frac{n}{a}\right)$, $I\left(\frac{n}{a^2}\right)$, $I\left(\frac{n}{a^3}\right)$,... Then among the numbers 1, 2, 3, ... n, there are $I\left(\frac{n}{a}\right)$ which contain a at least once, namely the numbers a, $2a$, $3a$, $4a$, ... Similarly there are $I\left(\frac{n}{a^2}\right)$ which contain a^2 at least once, and $I\left(\frac{n}{a^3}\right)$ which contain a^3 at least once; and so on. Hence the highest power of a contained in $\lfloor\underline{n}$ is

$$I\left(\frac{n}{a}\right) + I\left(\frac{n}{a^2}\right) + I\left(\frac{n}{a^3}\right) + \ldots$$

417. In the remainder of this chapter we shall find it convenient to express a multiple of n by the symbol $M(n)$.

418. *To prove that the product of* r *consecutive integers is divisible by* $\lfloor\underline{\text{r}}$.

Let P_n stand for the product of r consecutive integers, the least of which is n; then

$$P_n = n(n+1)(n+2) \ldots (n+r-1),$$

and

$$P_{n+1} = (n+1)(n+2)(n+3) \ldots (n+r);$$

$$nP_{n+1} = (n+r)P_n = nP_n + rP_n;$$

$$\therefore \quad P_{n+1} - P_n = \frac{P_n}{n} \times r$$

$= r$ times the product of $r-1$ consecutive integers.

Hence if the product of $r-1$ consecutive integers is divisible by $\underline{|r-1}$, we have

$$P_{n+1} - P_n = rM(\underline{|r-1}) - M(|r).$$

Now $P_1 = |r$, and therefore P_2 is a multiple of $|r$; therefore also P_3, P_4, are multiples of $\underline{|r}$. We have thus proved that if the product of $r-1$ consecutive integers is divisible by $\underline{|r-1}$, the product of r consecutive integers is divisible by $\underline{|r}$; but the product of every two consecutive integers is divisible by $\underline{|2}$; therefore the product of every three consecutive integers is divisible by $\underline{|3}$; and so on generally.

This proposition may also be proved thus:

By means of Art. 416, we can show that every prime factor is contained in $\underline{|n+r}$ as often *at least* as it is contained in $\underline{|n}\ \underline{|r}$.

This we leave as an exercise to the student.

419. *If* p *is a prime number, the coefficient of every term in the expansion of* $(a+b)^p$, *except the first and last, is divisible by* p.

With the exception of the first and last, every term has a coefficient of the form

$$\frac{p(p-1)(p-2)\ldots(p-r+1)}{\underline{|r}},$$

where r may have any integral value not exceeding $p-1$. Now this expression is an integer; also since p is prime no factor of $\underline{|r}$ is a divisor of it, and since p is greater than r it cannot divide any factor of $\underline{|r}$; that is, $(p-1)(p-2)\ldots(p-r+1)$ must be divisible by $\underline{|r}$. Hence every coefficient except the first and the last is divisible by p.

420. *If* p *is a prime number, to prove that*

$$(a+b+c+d+\ldots)^p = a^p + b^p + c^p + d^p + \ldots + M(p).$$

Write β for $b+c+\ldots$; then by the preceding article

$$(a+\beta)^p = a^p + \beta^p + M(p).$$

Again $\beta^p = (b+c+d+\ldots)^p = (b+\gamma)^p$ suppose;

$$= b^p + \gamma^p + M(p).$$

By proceeding in this way we may establish the required result.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

EXAMPLES. XXX. a.

1. Find the least multipliers of the numbers

3675, 4374, 18375, 74088

respectively, which will make the products perfect squares.

2. Find the least multipliers of the numbers

7623, 109350, 539539

respectively, which will make the products perfect cubes.

3. If x and y are positive integers, and if $x-y$ is even, shew that x^2-y^2 is divisible by 4.

4. Shew that the difference between any number and its square is even.

5. If $4x-y$ is a multiple of 3, shew that $4x^2+7xy-2y^2$ is divisible by 9.

6. Find the number of divisors of 8064.

7. In how many ways can the number 7056 be resolved into two factors?

8. Prove that $2^{4n}-1$ is divisible by 15.

9. Prove that $n(n+1)(n+5)$ is a multiple of 6.

10. Shew that every number and its cube when divided by 6 leave the same remainder.

11. If n is even, shew that $n(n^2+20)$ is divisible by 48.

12. Shew that $n(n^2-1)(3n+2)$ is divisible by 24.

13. If n is greater than 2, shew that n^5-5n^3+4n is divisible by 120.

14. Prove that $3^{2n}+7$ is a multiple of 8.

15. If n is a prime number greater than 3, shew that n^2-1 is a multiple of 24.

16. Shew that n^5-n is divisible by 30 for all values of n, and by 240 if n is odd.

17. Shew that the difference of the squares of any two prime numbers greater than 6 is divisible by 24.

18. Shew that no square number is of the form $3n-1$.

19. Shew that every cube number is of the form $9n$ or $9n\pm1$.

20. Shew that if a cube number is divided by 7, the remainder is 0, 1 or 6.

21. If a number is both square and cube, shew that it is of the form $7n$ or $7n+1$.

22. Shew that no triangular number can be of the form $3n-1$.

23. If $2n+1$ is a prime number, shew that 1^2, 2^2, 3^2,...n^2 when divided by $2n+1$ leave different remainders.

24. Shew that a^x+a and a^x-a are always even, whatever a and x may be.

25. Prove that every even power of every odd number is of the form $8r+1$.

26. Prove that the 12^{th} power of any number is of the form $13n$ or $13n+1$.

27. Prove that the 8^{th} power of any number is of the form $17n$ or $17n \pm 1$.

28. If n is a prime number greater than 5, shew that n^4-1 is divisible by 240

29. If n is any prime number greater than 3, except 7, shew that n^6-1 is divisible by 168.

30. Show that $n^{36}-1$ is divisible by 33744 if n is prime to 2, 3, 19 and 37.

31. When $p+1$ and $2p+1$ are both prime numbers, shew that $x^{2p}-1$ is divisible by $8(p+1)(2p+1)$, if x is prime to 2, $p+1$, and $2p+1$.

32. If p is a prime, and x prime to p, shew that $x^{p^r-p^{r-1}}-1$ is divisible by p^r

33. If m is a prime number, and a, b two numbers less than m, prove that

$$a^{m-2}+a^{m-3}b+a^{m-4}b^2+\ldots\ldots+b^{m-2}$$

is a multiple of m.

423. If a is any number, then any other number N may be expressed in the form $N=aq+r$, where q is the integral quotient when N is divided by a, and r is a remainder less than a. The number a, to which the other is referred, is sometimes called the *modulus*; and to any given modulus a there are a different

forms of a number N, each form corresponding to a different value of r. Thus to modulus 3, we have numbers of the form $3q$, $3q+1$, $3q+2$; or, more simply, $3q$, $3q \pm 1$, since $3q+2$ is equal to $3(q+1)-1$. In like manner to modulus 5 any number will be one of the five forms $5q$, $5q \pm 1$, $5q \pm 2$.

424. If b, c are two integers, which when divided by a leave the same remainder, they are said to be **congruent** with respect to the modulus a. In this case $b-c$ is a multiple of a, and following the notation of Gauss we shall sometimes express this as follows:

$$b \equiv c \text{ (mod. } a\text{)}, \text{ or } b - c \equiv 0 \text{ (mod. } a\text{)}.$$

Either of these formulæ is called a **congruence.**

425. *If* b, c *are congruent with respect to modulus* a, *then* pb *and* pc *are congruent,* p *being any integer.*

For, by supposition, $b - c = na$, where n is some integer; therefore $pb - pc = pna$; which proves the proposition.

426. *If* a *is prime to* b, *and the quantities*

$$\text{a}, \quad 2\text{a}, \quad 3\text{a}, \qquad (\text{b}-1)\,\text{a}$$

are divided by b, *the remainders are all different.*

For if possible, suppose that two of the quantities ma and $m'a$ when divided by b leave the same remainder r, so that

$$ma = qb + r, \quad m'a = q'b + r;$$

then

$$(m - m')\,a = (q - q')\,b;$$

therefore b divides $(m-m')\,a$; hence it must divide $m-m'$, since it is prime to a; but this is impossible since m and m' are each less than b.

Thus the remainders are all different, and since none of the quantities is exactly divisible by b, the remainders must be the terms of the series 1, 2, 3, $\quad b-1$, but not necessarily in this order.

Cor. If a is prime to b, and c is any number, the b terms of the A. P.

$$c, \quad c+a, \quad c+2a, \qquad c+(b-1)\,a,$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

430. *To shew that if the numbers* a, b, c, d, ... *are prime to each other*,

$$\phi(\text{abcd}\ldots) = \phi(\text{a}) \,.\, \phi(\text{b}) \,.\, \phi(\text{c})$$

Consider the product ab; then the first ab numbers can be written in b lines, each line containing a numbers; thus

$$\begin{array}{cccc} 1, & 2, & k, & a, \\ a+1, & a+2, & a+k, & a+a, \\ 2a+1, & 2a+2, & 2a+k, & 2a+a, \\ \ldots\ldots & \ldots\ldots & \ldots\ldots & \ldots\ldots \\ (b-1)a+1, & (b-1)a+2, & (b-1)a+k, & (b-1)a+a. \end{array}$$

Let us consider the vertical column which begins with k; if k is prime to a all the terms of this column will be prime to a; but if k and a have a common divisor, no number in the column will be prime to a. Now the first row contains $\phi(a)$ numbers prime to a; therefore there are $\phi(a)$ vertical columns in each of which every term is prime to a; let us suppose that the vertical column which begins with k is one of these. This column is an A.P., the terms of which when divided by b leave remainders $0, 1, 2, 3, \ldots b-1$ [Art. 426 Cor.]; hence the column contains $\phi(b)$ integers prime to b.

Similarly, each of the $\phi(a)$ vertical columns in which every term is prime to a contain $\phi(b)$ integers prime to b; hence in the table there are $\phi(a) \,.\, \phi(b)$ integers which are prime to a and also to b, and therefore to ab; that is

$$\phi(ab) = \phi(a) \,.\, \phi(b).$$

Therefore $\phi(abcd\ldots) = \phi(a) \,.\, \phi(bcd\ldots)$

$$= \phi(a) \,.\, \phi(b) \,.\, \phi(cd\quad)$$

$$= \phi(a) \,.\, \phi(b) \,.\, \phi(c)\ \ \phi(d)$$

431. *To find the number of positive integers less than a given number, and prime to it.*

Let N denote the number, and suppose that $N = a^p b^q c^r \ldots$, where a, b, c, ... are different prime numbers, and p, q, r ... positive integers. Consider the factor a^p; of the natural numbers 1, 2, 3, ... $a^p - 1$, a^p, the only ones not prime to a are

$$a,\ 2a,\ 3a,\ \ldots (a^{p-1} - 1)\, a,\ (a^{p-1})\, a,$$

and the number of these is a^{p-1}; hence

$$\phi(a^p) = a^p - a^{p-1} = a^p\left(1 - \frac{1}{a}\right).$$

Now all the factors a^p, b^q, c^r, ... are prime to each other;

$$\phi(a^p b^q c^r \ldots) = \phi(a^p) \cdot \phi(b^q) \cdot \phi(c^r) \ldots$$

$$= a^p\left(1 - \frac{1}{a}\right) \cdot b^q\left(1 - \frac{1}{b}\right) \cdot c^r\left(1 - \frac{1}{c}\right) \ldots$$

$$- a^p b^q c^r \ldots \left(1 - \frac{1}{a}\right)\left(1 - \frac{1}{b}\right)\left(1 - \frac{1}{c}\right) \ldots;$$

that is,
$$\phi(N) = N\left(1 - \frac{1}{a}\right)\left(1 - \frac{1}{b}\right)\left(1 - \frac{1}{c}\right) \ldots.$$

Example. Shew that the sum of all the integers which are less than N and prime to it is $\frac{1}{2} N \phi(N)$.

If x is any integer less than N and prime to it, then $N - x$ is also an integer less than N and prime to it.

Denote the integers by 1, p, q, r, ..., and their sum by S; then

$$S = 1 + p + q + r + \ldots + (N-r) + (N-q) + (N-p) + (N-1),$$

the series consisting of $\phi(N)$ terms.

Writing the series in the reverse order,

$$S = (N-1) + (N-p) + (N-q) + (N-r) + \ldots + r + q + p + 1;$$

by addition, $2S = N + N + N + \ldots$ to $\phi(N)$ terms;

$$\therefore\ S = \tfrac{1}{2} N \phi(N).$$

432. From the last article it follows that the number of integers which are less than N and *not* prime to it is

$$N - N\left(1 - \frac{1}{a}\right)\left(1 - \frac{1}{b}\right)\left(1 - \frac{1}{c}\right)\left(1 - \frac{1}{d}\right) \ldots;$$

that is,

$$\frac{N}{a} + \frac{N}{b} + \frac{N}{c} + \ldots - \frac{N}{ab} - \frac{N}{ac} - \frac{N}{bc} - \ldots + \frac{N}{abc} + \ldots.$$

Here the term $\frac{N}{a}$ gives the number of the integers

$$a,\ 2a,\ 3a,\ \ldots\ \frac{N}{a} \cdot a$$

which contain a as a factor; the term $\frac{N}{ab}$ gives the number of

the integers ab, $2ab$, $3ab$, $\frac{N}{ab}ab$, which contain ab as a factor, and so on. Further, every integer is reckoned once, and once only; thus, each multiple of ab will appear once among the multiples of a, once among the multiples of b, and once negatively among the multiples of ab, and is thus reckoned once only. Again, each multiple of abc will appear among the $\frac{N}{a}$, $\frac{N}{b}$, $\frac{N}{c}$ terms which are multiples of a, b, c respectively; among the $\frac{N}{ab}$, $\frac{N}{ac}$, $\frac{N}{bc}$ terms which are multiples of ab, ac, bc respectively; and among the $\frac{N}{abc}$ multiples of abc; that is, since $3-3+1=1$, each multiple of abc occurs once, and once only. Similarly, other cases may be discussed.

433. [Wilson's Theorem.] *If* p *be a prime number,* $1+\lfloor\underline{p-1}$ *is divisible by* p.

By Ex. 2, Art. 314 we have

$$\lfloor\underline{p-1} = (p-1)^{p-1} - (p-1)(p-2)^{p-1} + \frac{(p-1)(p-2)}{1\,.\,2}(p-3)^{p-1}$$

$$- \frac{(p-1)(p-2)(p-3)}{\lfloor\underline{3}}(p-4)^{p-1} + \ldots \text{ to } p-1 \text{ terms};$$

and by Fermat's Theorem each of the expressions $(p-1)^{p-1}$, $(p-2)^{p-1}$, $(p-3)^{p-1}$, ... is of the form $1+M(p)$; thus

$$\lfloor\underline{p-1} = M(p) + \left\{1 - (p-1) + \frac{(p-1)(p-2)}{1\,.\,2} - \ldots \text{ to } p-1 \text{ terms}\right\}$$

$$= M(p) + \{(1-1)^{p-1} - (-1)^{p-1}\}$$

$$= M(p) - 1, \text{ since } p-1 \text{ is even.}$$

Therefore $1+\lfloor\underline{p-1} = M(p)$.

This theorem is only true when p is prime. For suppose p has a factor q; then q is less than p and must divide $\lfloor\underline{p-1}$; hence $1+\lfloor\underline{p-1}$ is not a multiple of q, and therefore not a multiple of p.

Wilson's Theorem may also be proved without using the result quoted from Art. 314, as in the following article.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

435. Many theorems relating to the properties of numbers can be proved by induction.

Example 1. If p is a prime number, $x^p - x$ is divisible by p.

Let $x^p - x$ be denoted by $f(x)$; then

$$f(x+1) - f(x) = (x+1)^p - (x+1) - (x^p - x)$$

$$= px^{p-1} + \frac{p(p-1)}{1.2} x^{p-2} + \ldots + px$$

$$= \text{a multiple of } p, \text{ if } p \text{ is prime [Art. 419.]}$$

$$\therefore \quad f(x+1) = f(x) + \text{a multiple of } p.$$

If therefore $f(x)$ is divisible by p, so also is $f(x+1)$; but

$$f(2) = 2^p - 2 = (1+1)^p - 2,$$

and this is a multiple of p when p is prime [Art. 419]; therefore $f(3)$ is divisible by p, therefore $f(4)$ is divisible by p, and so on; thus the proposition is true universally.

This furnishes another proof of Fermat's theorem, for if x is prime to p, it follows that $x^{p-1} - 1$ is a multiple of p.

Example 2. Prove that $5^{2n+2} - 24n - 25$ is divisible by 576.

Let $5^{2n+2} - 24n - 25$ be denoted by $f(n)$;

then
$$f(n+1) = 5^{2n+4} - 24(n+1) - 25$$

$$= -5^2 . 5^{2n+2} - 24n - 49;$$

$$\therefore \quad f(n+1) - 25 f(n) = 25(24n+25) - 24n - 49$$

$$= -576(n+1).$$

Therefore if $f(n)$ is divisible by 576, so also is $f(n+1)$; but by trial we see that the theorem is true when $n=1$, therefore it is true when $n=2$, therefore it is true when $n=3$, and so on; thus it is true universally.

The above result may also be proved as follows:

$$5^{2n+2} - 24n - 25 = 25^{n+1} - 24n - 25$$

$$= -25(1+24)^n - 24n - 25$$

$$= -25 + 25 . n . 24 + M(24^2) - 24n - 25$$

$$= -576n + M(576)$$

$$= M(576).$$

EXAMPLES. XXX. b.

1. Shew that $10^n + 3 . 4^{n+2} + 5$ is divisible by 9.
2. Shew that $2 . 7^n + 3 . 5^n - 5$ is a multiple of 24.
3. Shew that $4 . 6^n + 5^{n+1}$ when divided by 20 leaves remainder 9.
4. Shew that $8 . 7^n + 4^{n+2}$ is of the form $24(2r-1)$.

5. If p is prime, shew that $2\,\underline{|p-3}+1$ is a multiple of p.

6. Shew that $a^{4b+1}-a$ is divisible by 30.

7. Shew that the highest power of 2 contained in $\underline{|2^r-1}$ is 2^r-r-1.

8. Shew that $3^{4n+2}+5^{2n+1}$ is a multiple of 14.

9. Shew that $3^{2n+5}+160n^2-56n-243$ is divisible by 512.

10. Prove that the sum of the coefficients of the odd powers of x in the expansion of $(1+x+x^2+x^3+x^4)^{n-1}$, when n is a prime number other than 5, is divisible by n.

11. If n is a prime number greater than 7, shew that n^6-1 is divisible by 504.

12. If n is an odd number, prove that $n^6+3n^4+7n^2-11$ is a multiple of 128.

13. If p is a prime number, shew that the coefficients of the terms of $(1+x)^{p-1}$ are alternately greater and less by unity than some multiple of p.

14. If p is a prime, shew that the sum of the $(p-1)^{\text{th}}$ powers of any p numbers in arithmetical progression, wherein the common difference is not divisible by p, is less by 1 than a multiple of p.

15. Shew that $a^{12}-b^{12}$ is divisible by 91, if a and b are both prime to 91.

16. If p is a prime, shew that $\underline{|p-2}\,\underline{|2r-1}-1$ is divisible by p.

17. If $n-1$, $n+1$ are both prime numbers greater than 5, shew that $n(n^2-4)$ is divisible by 120, and $n^2(n^2+16)$ by 720. Also shew that n must be of the form $30t$ or $30t+12$.

18. Shew that the highest power of n which is contained in $\underline{|n^r-1}$ is equal to $\dfrac{n^r-nr+r-1}{n-1}$.

19. If p is a prime number, and a prime to p, and if a square number c^2 can be found such that c^2-a is divisible by p, shew that $a^{\frac{1}{2}(p-1)}-1$ is divisible by p.

20. Find the general solution of the congruence

$$98x-1\equiv 0 \pmod{139}.$$

21. Shew that the sum of the squares of all the numbers less than a given number N and prime to it is

$$\frac{N^3}{3}\left(1-\frac{1}{a}\right)\left(1-\frac{1}{b}\right)\left(1-\frac{1}{c}\right)\ldots+\frac{N}{6}(1-a)(1-b)(1-c)\ldots,$$

and the sum of the cubes is

$$\frac{N^4}{4}\left(1-\frac{1}{a}\right)\left(1-\frac{1}{b}\right)\left(1-\frac{1}{c}\right)\ldots+\frac{N^2}{4}(1-a)(1-b)(1-c)\ldots,$$

$a, b, c\ldots$ being the different prime factors of N.

22. If p and q are any two positive integers, shew that $\lfloor\underline{pq}$ is divisible by $(\lfloor\underline{p})^q . \lfloor q$ and by $(\lfloor\underline{q})^p . \lfloor\underline{p}$.

23. Shew that the square numbers which are also triangular are given by the squares of the coefficients of the powers of x in the expansion of $\dfrac{1}{1-6x+x^2}$, and that the square numbers which are also pentagonal by the coefficients of the powers of x in the expansion of

$$\frac{1}{1-10x+x^2}.$$

24. Shew that the sum of the fourth powers of all the numbers less than N and prime to it is

$$\frac{N^5}{5}\left(1-\frac{1}{a}\right)\left(1-\frac{1}{b}\right)\left(1-\frac{1}{c}\right)\ldots+\frac{N^3}{3}(\dot{1}-a)(1-b)(1-b)\ldots$$
$$-\frac{N}{30}(1-a^3)(1-b^3)(1-c^3)\ldots,$$

$a, b, c,\ldots$ being the different prime factors of N.

25. If $\phi(N)$ is the number of integers which are less than N and prime to it, and if x is prime to N, shew that

$$x^{\phi(N)}-1\equiv 0 \pmod{N}.$$

26. If $d_1, d_2, d_3, \ldots$ denote the divisors of a number N, then

$$\phi(d_1)+\phi(d_2)+\phi(d_3)+\ldots=N.$$

Shew also that

$$\phi(1)\frac{x}{1+x^2}-\phi(3)\frac{x^3}{1+x^6}+\phi(5)\frac{x^5}{1+x^{10}}-\ldots \text{ ad inf.}=\frac{x(1-x^2)}{(1+x^2)^2}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Suppose that the successive convergents are formed in a similar way; let the numerators be denoted by p_1, p_2, p_3 ..., and the denominators by q_1, q_2, q_3, ...

Assume that the law of formation holds for the n^{th} convergent; that is, suppose

$$p_n = a_n p_{n-1} + b_n p_{n-2}, \quad q_n = a_n q_{n-1} + b_n q_{n-2}.$$

The $(n+1)^{\text{th}}$ convergent differs from the n^{th} only in having $a_n + \frac{b_{n+1}}{a_{n+1}}$ in the place of a_n; hence

the $(n+1)^{\text{th}}$ convergent

$$= \frac{\left(a_n + \frac{b_{n+1}}{a_{n+1}}\right) p_{n-1} + b_n p_{n-2}}{\left(a_n + \frac{b_{n+1}}{a_{n+1}}\right) q_{n-1} + b_n q_{n-2}} = \frac{p_n + \frac{b_{n+1}}{a_{n+1}} p_{n-1}}{q_n + \frac{b_{n+1}}{a_{n+1}} q_{n-1}} = \frac{a_{n+1} p_n + b_{n+1} p_{n-1}}{a_{n+1} q_n + b_{n+1} q_{n-1}}.$$

If therefore we put

$$p_{n+1} = a_{n+1} p_n + b_{n+1} p_{n-1}, \quad q_{n+1} = a_{n+1} q_n + b_{n+1} q_{n-1},$$

we see that the numerator and denominator of the $(n+1)^{\text{th}}$ convergent follow the law which was supposed to hold in case of the n^{th}. But the law does hold in the case of the third convergent; hence it holds for the fourth; and so on; therefore it holds universally.

*439. In the case of the continued fraction

$$\frac{b_1}{a_1 -} \quad \frac{b_2}{a_2 -} \quad \frac{b_3}{a_3 -} \cdots\cdots$$

we may prove that

$$p_n = a_n p_{n-1} - b_n p_{n-2}, \quad q_n = a_n q_{n-1} - b_n q_{n-2};$$

a result which may be deduced from that of the preceding article by changing the sign of b_n.

*440. In the continued fraction

$$\frac{b_1}{a_1 +} \quad \frac{b_2}{a_2 +} \quad \frac{b_3}{a_3 +} \cdots\cdots,$$

we have seen that

$$p_n = a_n p_{n-1} + b_n p_{n-2}, \quad q_n = a_n q_{n-1} + b_n q_{n-2}.$$

$$\therefore \quad \frac{p_{n+1}}{q_{n+1}} - \frac{p_n}{q_n} = \frac{(a_{n+1}p_n + b_{n+1}p_{n-1})\,q_n - (a_{n+1}q_n + b_{n+1}q_{n-1})\,p_n}{q_{n+1}q_n}$$

$$= -\frac{b_{n+1}q_{n-1}}{q_{n+1}}\left(\frac{p_n}{q_n} - \frac{p_{n-1}}{q_{n-1}}\right);$$

but $$\frac{b_{n+1}q_{n-1}}{q_{n+1}} = \frac{b_{n+1}q_{n-1}}{a_{n+1}q_n + b_{n+1}q_{n-1}},$$

and is therefore a proper fraction; hence $\frac{p_{n+1}}{q_{n+1}} - \frac{p_n}{q_n}$ is numerically less than $\frac{p_n}{q_n} - \frac{p_{n-1}}{q_{n-1}}$, and is of opposite sign.

By reasoning as in Art. 335, we may shew that every convergent of an odd order is greater than the continued fraction, and every convergent of an even order is less than the continued fraction; hence every convergent of an odd order is greater than every convergent of an even order.

Thus $\frac{p_{2n+1}}{q_{2n+1}} - \frac{p_{2n}}{q_{2n}}$ is positive and less than $\frac{p_{2n-1}}{q_{2n-1}} - \frac{p_{2n}}{q_{2n}}$; hence

$$\frac{p_{2n+1}}{q_{2n+1}} < \frac{p_{2n-1}}{q_{2n-1}}.$$

Also $\frac{p_{2n-1}}{q_{2n-1}} - \frac{p_{2n}}{q_{2n}}$ is positive and less than $\frac{p_{2n-1}}{q_{2n-1}} - \frac{p_{2n-2}}{q_{2n-2}}$; hence

$$\frac{p_{2n}}{q_{2n}} > \frac{p_{2n-2}}{q_{2n-2}}.$$

Hence the convergents of an odd order are all greater than the continued fraction but continually decrease, and the convergents of an even order are all less than the continued fraction but continually increase.

Suppose now that the number of components is infinite, then the convergents of an odd order must tend to some finite limit, and the convergents of an even order must also tend to some finite limit; if these limits are equal the continued fraction tends to *one* definite limit; if they are not equal, the odd convergents tend to one limit, and the even convergents tend to a different limit, and the continued fraction may be said to be *oscillating;* in this case the continued fraction is the symbolical representation of two quantities, one of which is the limit of the odd, and the other that of the even convergents.

*441. *To shew that the continued fraction* $\dfrac{b_1}{a_1+}\ \dfrac{b_2}{a_2+}\ \dfrac{b_3}{a_3+}\ \ldots$ *has a definite value if the limit of* $\dfrac{a_n a_{n+1}}{b_{n+1}}$ *when* n *is infinite is greater than zero.*

The continued fraction will have a definite value when n is infinite if the difference of the limits of $\frac{p_{n+1}}{q_{n+1}}$ and $\frac{p_n}{q_n}$ is equal to zero.

Now $$\frac{p_{n+1}}{q_{n+1}} - \frac{p_n}{q_n} = -\frac{b_{n+1}q_{n-1}}{q_{n+1}}\left(\frac{p_n}{q_n} - \frac{p_{n-1}}{q_{n-1}}\right);$$

whence we obtain

$$\frac{p_{n+1}}{q_{n+1}} - \frac{p_n}{q_n} - (-1)^{n-1}\frac{b_{n+1}q_{n-1}}{q_{n+1}}\cdot\frac{b_n q_{n-2}}{q_n}\ldots\ldots\frac{b_4 q_2}{q_4}\cdot\frac{b_3 q_1}{q_3}\left(\frac{p_2}{q_2} - \frac{p_1}{q_1}\right).$$

But $$\frac{b_{n+1}q_{n-1}}{q_{n+1}} = \frac{b_{n+1}q_{n-1}}{a_{n+1}q_n + b_{n+1}q_{n-1}} = \frac{1}{\dfrac{a_{n+1}q_n}{b_{n+1}q_{n-1}} + 1};$$

and $$\frac{a_{n+1}q_n}{b_{n+1}q_{n-1}} = \frac{a_{n+1}(a_n q_{n-1} + b_n q_{n-2})}{b_{n+1}q_{n-1}} = \frac{a_n a_{n+1}}{b_{n+1}} + \frac{a_{n+1}b_n q_{n-2}}{b_{n+1}q_{n-1}};$$

also neither of these terms can be negative; hence if the limit of $\frac{a_n a_{n+1}}{b_{n+1}}$ is greater than zero so also is the limit of $\frac{a_{n+1}q_n}{b_{n+1}q_{n-1}}$; in which case the limit of $\frac{b_{n+1}q_{n-1}}{q_{n+1}}$ is less than 1; and therefore $\frac{p_{n+1}}{q_{n+1}} - \frac{p_n}{q_n}$ is the limit of the product of an infinite number of proper fractions, and must therefore be equal to zero; that is, $\frac{p_{n+1}}{q_{n+1}}$ and $\frac{p_n}{q_n}$ tend to the same limit; which proves the proposition.

For example, in the continued fraction

$$\frac{1^2}{3+}\ \frac{2^2}{5+}\ \frac{3^2}{7+}\ \cdots\cdots\ \frac{n^2}{2n+1+}\ \cdots,$$

$$Lim\,\frac{a_n a_{n+1}}{b_{n+1}} = Lim\,\frac{(2n+1)(2n+3)}{(n+1)^2} = 4;$$

and therefore the continued fraction tends to a definite limit.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Cor. If the number of the components is infinite, the convergents form an infinite series of proper fractions in ascending order of magnitude; and in this case the continued fraction must tend to a definite limit which cannot exceed unity.

*443. From the formula

$$p_n = a_n p_{n-1} + b_n p_{n-2}, \quad q_n = a_n q_{n-1} + b_n q_{n-2},$$

we may always determine in succession as many of the convergents as we please. In certain cases, however, a general expression can be found for the n^{th} convergent.

Example. To find the n^{th} convergent to $\dfrac{6}{5-}\ \dfrac{6}{5-}\ \dfrac{6}{5-}\ \ldots\ldots$

We have $p_n = 5p_{n-1} - 6p_{n-2}$; hence the numerators form a recurring series any three consecutive terms of which are connected by the relation

$$p_n - 5p_{n-1} + 6p_{n-2}.$$

Let $$S = p_1 + p_2 x + p_3 x^2 + \ldots + p_n x^{n-1} + \ldots;$$

then, as in Art. 325, we have $S = \dfrac{p_1 + (p_2 - 5p_1)\, x}{1 - 5x + 6x^2}$.

But the first two convergents are $\dfrac{6}{5}, \ \dfrac{30}{19}$;

$$\therefore\ S = \frac{6}{1 - 5x + 6x^2} = \frac{18}{1 - 3x} - \frac{12}{1 - 2x};$$

whence $$p_n = 18 \,.\, 3^{n-1} - 12 \,.\, 2^{n-1} = 6\,(3^n - 2^n).$$

Similarly if $$S' = q_1 + q_2 x + q_3 x^2 + \ldots + q_n x^{n-1} + \ldots,$$

we find $$S' = \frac{5 - 6x}{1 - 5x + 6x^2} = \frac{9}{1 - 3x} - \frac{4}{1 - 2x};$$

whence $$q_n = 9 \,.\, 3^{n-1} - 4 \,.\, 2^{n-1} = 3^{n+1} - 2^{n+1}$$

$$\therefore\ \frac{p_n}{q_n} = \frac{6\,(3^n - 2^n)}{3^{n+1} - 2^{n+1}}.$$

This method will only succeed when a_n and b_n are constant for all values of n. Thus in the case of the continued fraction $\dfrac{b}{a+}\ \dfrac{b}{a+}\ \dfrac{b}{a+}\ \ldots$, we may shew that the numerators of the successive convergents are the coefficients of the powers of x in the expansion of $\dfrac{b}{1 - ax - bx^2}$, and the denominators are the coefficients of the powers of x in the expansion of $\dfrac{a + bx}{1 - ax - bx^2}$.

*444. For the investigation of the general values of p_n and q_n the student is referred to works on *Finite Differences*; it is only in special cases that these values can be found by *Algebra*. The following method will sometimes be found useful.

Example. Find the value of $\cfrac{1}{1+}\ \cfrac{2}{2+}\ \cfrac{3}{3+}\cdots\cdots$

The same law of formation holds for p_n and q_n; let us take u_n to denote either of them; then $$u_n = nu_{n-1} + nu_{n-2},$$

or $$u_n - (n+1)\,u_{n-1} = -(u_{n-1} - nu_{n-2}).$$

Similarly, $$u_{n-1} - nu_{n-2} = -(u_{n-2} - \overline{n-1}\,u_{n-3}).$$

$$\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots$$

$$u_3 - 4u_2 = -(u_2 - 3u_1);$$

whence by multiplication, we obtain

$$u_n - (n+1)\,u_{n-1} = (-1)^{n-2}(u_2 - 3u_1).$$

The first two convergents are $\frac{1}{1}$, $\frac{2}{4}$; hence

$$p_n - (n+1)\,p_{n-1} = (-1)^{n-1}, \quad q_n - (n+1)\,q_{n-1} = (-1)^{n-2}.$$

Thus $$\frac{p_n}{\lfloor n+1} - \frac{p_{n-1}}{\lfloor n} = \frac{(-1)^{n-1}}{\lfloor n+1}, \qquad \frac{q_n}{\lfloor n+1} - \frac{q_{n-1}}{\lfloor n} = \frac{(-1)^{n-2}}{\lfloor n+1},$$

$$\frac{p_{n-1}}{\lfloor n} - \frac{p_{n-2}}{\lfloor n-1} = \frac{(-1)^{n-2}}{\lfloor n}, \qquad \frac{q_{n-1}}{\lfloor n} - \frac{q_{n-2}}{\lfloor n-1} = \frac{(-1)^{n-3}}{\lfloor n},$$

$$\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots\cdots$$

$$\frac{p_2}{\lfloor 3} - \frac{p_1}{\lfloor 2} = -\frac{1}{\lfloor 3}, \qquad \frac{q_2}{\lfloor 3} - \frac{q_1}{\lfloor 2} = \frac{1}{\lfloor 3},$$

$$\frac{p_1}{\lfloor 2} = \frac{1}{\lfloor 2}, \qquad \frac{q_1}{\lfloor 2} = \frac{1}{2} = 1 - \frac{1}{\lfloor 2};$$

whence, by addition

$$\frac{p_n}{\lfloor n+1} = \frac{1}{\lfloor 2} - \frac{1}{\lfloor 3} + \frac{1}{\lfloor 4} - \cdots\cdots + \frac{(-1)^{n-1}}{\lfloor n+1};$$

$$\frac{q_n}{\lfloor n+1} = 1 - \frac{1}{\lfloor 2} + \frac{1}{\lfloor 3} - \frac{1}{\lfloor 4} + \cdots\cdots + \frac{(-1)^{n-2}}{\lfloor n+1}.$$

By making n infinite, we obtain

$$Lim\,\frac{p_n}{q_n} = \frac{1}{e} \div \left(1 - \frac{1}{e}\right) = \frac{1}{e-1},$$

which is therefore the value of the given expression.

*445. *If every component of* $\frac{b_1}{a_1+}\ \frac{b_2}{a_2+}\ \frac{b_3}{a_3+}\ \ldots$ *is a proper fraction with integral numerator and denominator, the continued fraction is incommensurable.*

For if possible, suppose that the continued fraction is commensurable and equal to $\frac{B}{A}$, where A and B are positive integers; then $\frac{B}{A}=\frac{b_1}{a_1+f_1}$, where f_1 denotes the infinite continued fraction $\frac{b_2}{a_2+}\ \frac{b_3}{a_3+}\ \ldots$; hence $f_1=\frac{Ab_1-Ba_1}{B}=\frac{C}{B}$ suppose. Now A, B, a_1, b_1 are integers and f_1 is positive, therefore C is a positive integer. Similarly $\frac{C}{B}=\frac{b_2}{a_2+f_2}$, where f_2 denotes the infinite continued fraction $\frac{b_3}{a_3+}\ \frac{b_4}{a_4+}\ \ldots$; hence $f_2=\frac{Bb_2-Ca_2}{C}=\frac{D}{C}$ suppose; and as before, it follows that D is a positive integer; and so on.

Again, $\frac{B}{A}, \frac{C}{B}, \frac{D}{C}, \ldots$ are proper fractions; for $\frac{B}{A}$ is less than $\frac{b_1}{a_1}$, which is a proper fraction; $\frac{C}{B}$ is less than $\frac{b_2}{a_2}$; $\frac{D}{C}$ is less than $\frac{b_3}{a_3}$; and so on.

Thus A, B, C, D, ... form an *infinite* series of *positive integers* in *descending* order of magnitude; which is absurd. Hence the given fraction cannot be commensurable.

The above result still holds if some of the components are not proper fractions, provided that from and after a fixed component all the others are proper fractions.

For suppose that $\frac{b_n}{a_n}$ and all the succeeding components are proper fractions; thus, as we have just proved, the infinite continued fraction beginning with $\frac{b_n}{a_n}$ is incommensurable; denote it by k, then the complete quotient corresponding to $\frac{p_n}{q_n}$ is $\frac{k}{1}$, and therefore the value of the continued fraction is $\frac{p_{n-1}+kp_{n-2}}{q_{n-1}+kq_{n-2}}$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

6. Shew that

$$\left(a+\frac{1}{2a+}\ \frac{1}{2a+}\cdots\right)^2+\left(a-\frac{1}{2a-}\ \frac{1}{2a-}\cdots\right)^2=2a^2$$

and $$\left(a+\frac{1}{2a+}\ \frac{1}{2a+}\cdots\right)\left(a-\frac{1}{2a-}\ \frac{1}{2a-}\cdots\right)=a^2-\frac{1}{2a^2-}\ \frac{1}{2a^2-}\cdots$$

7. In the continued fraction

$$\frac{b}{a+}\ \frac{b}{a+}\ \frac{b}{a+}\cdots\cdots,$$

shew that $$p_{n+1}=bq_n,\quad bq_{n+1}-ap_{n+1}=b^2q_{n-1}.$$

8. Shew that $$\frac{b}{a+}\ \frac{b}{a+}\ \frac{b}{a+}\cdots\cdots=b.\frac{a^x-\beta^x}{a^{x+1}-\beta^{x+1}},$$

x being the number of components, and a, β the roots of the equation

$$k^2-ak-b=0.$$

9. Prove that the product of the continued fractions

$$a+\frac{1}{b+}\ \frac{1}{c+}\ \frac{1}{d+}\ \frac{1}{a+}\cdots\quad -d+\frac{1}{-c+}\ \frac{1}{-b+}\ \frac{1}{-a+}\ \frac{1}{-d+}\cdots,$$

is equal to -1.

Shew that

10. $$\frac{1}{1-}\ \frac{4}{5-}\ \frac{9}{13-}\ \frac{64}{25-}\cdots\cdots\frac{(n^2-1)^2}{n^2+(n+1)^2}=\frac{(n+1)(n+2)(2n+3)}{6}.$$

11. $$\frac{2}{1-}\ \frac{3}{5-}\ \frac{8}{7-}\cdots\cdots\frac{n^2-1}{2n+1}=\frac{n(n+3)}{2}.$$

12. $$\frac{2}{2-}\ \frac{3}{3-}\ \frac{4}{4-}\cdots\cdots\frac{n+1}{n+1-}\ \frac{n+2}{n+2}=1+1+\underline{|}2+\underline{|}3+\ldots+|n.$$

13. $$\frac{1}{1-}\ \frac{1}{3-}\ \frac{2}{4-}\ \frac{3}{5-}\cdots\cdots\frac{n-1}{n+1-}\cdots\cdots=e-1.$$

14. $$\frac{4}{1+}\ \frac{6}{2+}\ \frac{8}{3+}\cdots\cdots\frac{2n+2}{n+}\cdots\cdots=\frac{2(e^2-1)}{e^2+1}.$$

15. $$\frac{3.3}{1+}\ \frac{3.4}{2+}\ \frac{3.5}{3+}\cdots\cdots\frac{3(n+2)}{n+}\cdots\cdots=\frac{6(2e^3+1)}{5e^3-2}.$$

16. If $u_1=\frac{a}{b}$, $u_2=\frac{b}{a+b}$, $u_3=\frac{a+b}{a+2b}$,....., each successive fraction being formed by taking the denominator and the sum of the numerator and denominator of the preceding fraction for its numerator and denominator respectively, shew that $u_\infty=\frac{\sqrt{5}-1}{2}$.

17. Prove that the n^{th} convergent to the continued fraction

$$\frac{r}{r+1-}\ \frac{r}{r+1-}\ \frac{r}{r+1-}\ \ldots\ldots \text{ is } \frac{r^{n+1}-r}{r^{n+1}-1}.$$

18. Find the value of $\dfrac{a_1}{a_1+1-}\ \dfrac{a_2}{a_2+1-}\ \dfrac{a_3}{a_3+1-}\ \ldots\ldots,$

$a_1, a_2, a_3, \ldots$ being positive and greater than unity.

19. Shew that the n^{th} convergent to $1-\dfrac{1}{4-}\ \dfrac{1}{4-}\ \ldots$ is equal to the $(2n-1)^{\text{th}}$ convergent to $\dfrac{1}{1+}\ \dfrac{1}{2+}\ \dfrac{1}{1+}\ \dfrac{1}{2+}\ \ldots\ldots$

20. Shew that the $3n^{\text{th}}$ convergent to

$$\frac{1}{5-}\ \frac{1}{2-}\ \frac{1}{1-}\ \frac{1}{5-}\ \frac{1}{2-}\ \frac{1}{1-}\ \frac{1}{5-}\ \ldots\ldots \text{ is } \frac{n}{3n+1}.$$

21. Shew that $\dfrac{1}{2+}\ \dfrac{2}{3+}\ \dfrac{3}{4+}\ \ldots\ldots = \dfrac{3-e}{e-2}$;

hence shew that e lies between $2\frac{2}{3}$ and $2\frac{8}{11}$.

CONVERSION OF SERIES INTO CONTINUED FRACTIONS.

*447. It will be convenient here to write the series in the form

$$\frac{1}{u_1}+\frac{1}{u_2}+\frac{1}{u_3}+\ldots\ldots+\frac{1}{u_n}.$$

Put $$\frac{1}{u_r}+\frac{1}{u_{r+1}}=\frac{1}{u_r+x_r};$$

then $$(u_r+x_r)(u_{r+1}+u_r)=u_r u_{r+1},$$

$$\therefore\ x_r=-\frac{u_r^2}{u_r+u_{r+1}}$$

Hence $$\frac{1}{u_1}+\frac{1}{u_2}=\frac{1}{u_1-\dfrac{u_1^2}{u_1+u_2}}=\frac{1}{u_1-}\ \frac{u_1^2}{u_1+u_2}$$

Similarly,

$$\frac{1}{u_1}+\frac{1}{u_2}+\frac{1}{u_3}=\frac{1}{u_1}+\frac{1}{u_2+x_2}=\frac{1}{u_1-}\ \frac{u_1^{\,2}}{u_1+u_2+x_2}.$$

$$=\frac{1}{u_1-}\ \frac{u_1^{\,2}}{u_1+u_2-}\ \frac{u_2^{\,2}}{u_2+u_3},$$

and so on; hence generally

$$\frac{1}{u_1}+\frac{1}{u_2}+\frac{1}{u_3}+\ldots\ldots+\frac{1}{u_n}$$

$$=\frac{1}{u_1-}\ \frac{u_1^{\,2}}{u_1+u_2-}\ \frac{u_2^{\,2}}{u_2+u_3-}\ \ldots\ldots\ \frac{u^2_{\,n-1}}{u_{n-1}+u_n}.$$

Example 1. Express as a continued fraction the series

$$\frac{1}{a_0}-\frac{x}{a_0a_1}+\frac{x^2}{a_0a_1a_2}-\ldots\ldots+(-1)^n\frac{x^n}{a_0a_1a_2\ldots a_n}.$$

Put $$\frac{1}{a_n}-\frac{x}{a_na_{n+1}}=\frac{1}{a_n+y_n};$$

then $$(a_n+y_n)\,(a_{n+1}-x)=a_na_{n+1};$$

$$\therefore\quad y_n=\frac{a_nx}{a_{n+1}-x}.$$

Hence $$\frac{1}{a_0}-\frac{x}{a_0a_1}=\frac{1}{a_0+y_0}=\frac{1}{a_0+}\ \frac{a_0x}{a_1-x}.$$

Again, $$\frac{1}{a_0}-\frac{x}{a_0a_1}+\frac{x^2}{a_0a_1a_2}=\frac{1}{a_0}-\frac{x}{a_0}\left(\frac{1}{a_1}-\frac{x}{a_1a_2}\right)=\frac{1}{a_0}-\frac{x}{a_0\,(a_1+y_1)}$$

$$=\frac{1}{a_0+}\ \frac{a_0x}{a_1+y_1-x}$$

$$=\frac{1}{a_0+}\ \frac{a_0x}{a_1-x+}\ \frac{a_1x}{a_2-x};$$

and generally $$\frac{1}{a_0}-\frac{x}{a_0a_1}+\frac{x^2}{a_0a_1a_2}-\ldots+(-1)^n\frac{x^n}{a_0a_1a_2\ldots a_n}$$

$$=\frac{1}{a_0+}\ \frac{a_0x}{a_1-x+}\ \frac{a_1x}{a_2-x+}\ \ldots\ldots\ \frac{a_{n-1}x}{a_n-x}.$$

Example 2. Express $\log(1+x)$ as a continued fraction.

We have $$\log(1+x)=x-\frac{x^2}{2}+\frac{x^3}{3}-\frac{x^4}{4}+\ldots\ldots.$$

The required expression is most simply deduced from the continue fraction equivalent to the series

$$\frac{x}{a_1}-\frac{x^2}{a_2}+\frac{x^3}{a_3}-\frac{x^4}{a_4}+\ldots\ldots.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

*EXAMPLES. XXXI. b.

Shew that

1. $\dfrac{1}{u_0}-\dfrac{1}{u_1}+\dfrac{1}{u_2}-\dfrac{1}{u_3}+\ldots\ldots+(-1)^n\dfrac{1}{u_n}$

$$=\frac{1}{u_0+}\ \frac{{u_0}^2}{u_1-u_0+}\ \frac{{u_1}^2}{u_2-u_1+}\ \ldots\ldots\ \frac{{u^2}_{n-1}}{u_n-u_{n-1}}.$$

2. $\dfrac{1}{a_0}+\dfrac{x}{a_0a_1}+\dfrac{x^2}{a_0a_1a_2}+\ldots\ldots+\dfrac{x^n}{a_0a_1a_2\ldots a_n}$

$$=\frac{1}{a_0-}\ \frac{a_0x}{a_1+x-}\ \frac{a_1x}{a_2+x-}\ \ldots\ldots\ \frac{a_{n-1}x}{a_n+x}.$$

3. $\dfrac{r-1}{r-2}=\dfrac{r}{r-}\ \dfrac{r+1}{r+1-}\ \dfrac{r+2}{r+2-}\ \ldots\ldots$

4. $\dfrac{2n}{n+1}=\dfrac{1}{1-}\ \dfrac{1}{4-}\ \dfrac{1}{1-}\ \dfrac{1}{4-}$ ..... to n quotients.

5. $1+\dfrac{1}{2}+\dfrac{1}{3}+\ldots\ldots+\dfrac{1}{n+1}=\dfrac{1}{1-}\ \dfrac{1}{3-}\ \dfrac{4}{5-}\ \dfrac{9}{7-}\ \ldots\ldots\ \dfrac{n^2}{2n+1}.$

6. $\dfrac{1}{1^2}+\dfrac{1}{2^2}+\ldots\ldots+\dfrac{1}{(n+1)^2}=\dfrac{1}{1-}\ \dfrac{1^4}{1^2+2^2-}\ \ldots\ldots\ \dfrac{n^4}{n^2+(n+1)^2}.$

7. $e^x=1+\dfrac{x}{1-}\ \dfrac{x}{x+2-}\ \dfrac{2x}{x+3-}\ \dfrac{3x}{x+4-}\ \ldots\ldots$

8. $\dfrac{1}{a}-\dfrac{1}{ab}+\dfrac{1}{abc}-\dfrac{1}{abcd}+\ldots=\dfrac{1}{a+}\ \dfrac{a}{b-1+}\ \dfrac{b}{c-1+}\ \dfrac{c}{d-1+}\ldots\ldots$

9. $1+\dfrac{1}{r}+\dfrac{1}{r^4}+\dfrac{1}{r^9}+\dfrac{1}{r^{16}}+\ldots=1+\dfrac{1}{r-}\ \dfrac{r}{r^3+1-}\ \dfrac{r^3}{r^5+1-}\ \dfrac{r^5}{r^7+1-}\ldots$

10. $\dfrac{a_1}{a_1+}\ \dfrac{a_2}{a_2+}\ \dfrac{a_3}{a_3+}\ \ldots\ldots\ \dfrac{a_n}{a_n}=\dfrac{1}{1+}\ \dfrac{1}{a_1+}\ \dfrac{a_1}{a_2+}\ \dfrac{a_2}{a_3+}\ \ldots\ldots\ \dfrac{a_{n-2}}{a_{n-1}}.$

11. If $P=\dfrac{a}{a+}\ \dfrac{b}{b+}\ \dfrac{c}{c+}\ldots\ldots$, $Q=\dfrac{a}{b+}\ \dfrac{b}{c+}\ \dfrac{c}{d+}\ldots\ldots$,

shew that $$P(a+1+Q)=a+Q.$$

12. Shew that $\dfrac{1}{q_1}-\dfrac{x}{q_1q_2}+\dfrac{x^2}{q_2q_3}-\dfrac{x^3}{q_3q_4}+\ldots$ is equal to the continued fraction $\dfrac{1}{a_1+}\ \dfrac{x}{a_2+}\ \dfrac{x}{a_3+}\ \dfrac{x}{a_4+}\ldots$, where q_1, q_2, q_3, ... are the denominators of the successive convergents.

CHAPTER XXXII.

PROBABILITY.

449. DEFINITION. If an event can happen in a ways and fail in b ways, and each of these ways is equally likely, the **probability**, or the **chance**, of its happening is $\frac{a}{a+b}$, and that of its failing is $\frac{b}{a+b}$.

For instance, if in a lottery there are 7 prizes and 25 blanks, the chance that a person holding 1 ticket will win a prize is $\frac{7}{32}$, and his chance of not winning is $\frac{25}{32}$.

450. The reason for the mathematical definition of probability may be made clear by the following considerations.

If an event can happen in a ways and fail to happen in b ways, and all these ways are equally likely, we can assert that the chance of its happening is to the chance of its failing as a to b. Thus if the chance of its happening is represented by ka, where k is an undetermined constant, then the chance of its failing will be represented by kb.

$\therefore$ chance of happening + chance of failing $= k(a+b)$

Now the event is certain to happen or to fail; therefore the sum of the chances of happening and failing must represent *certainty*. If therefore we agree to take certainty as our unit, we have

$$1 = k(a+b), \quad \text{or} \quad k = \frac{1}{a+b};$$

$\therefore$ the chance that the event will happen is $\frac{a}{a+b}$,

and the chance that the event will not happen is $\frac{b}{a+b}$.

COR. If p is the probability of the happening of an event, the probability of its not happening is $1-p$.

451. Instead of saying that the chance of the happening of an event is $\frac{a}{a+b}$, it is sometimes stated that *the odds are* a *to* b *in favour of the event, or* b *to* a *against the event.*

452. The definition of probability in Art. 449 may be given in a slightly different form which is sometimes useful. If c is the total number of cases, each being equally likely to occur, and of these a are favourable to the event, then the probability that the event will happen is $\frac{a}{c}$, and the probability that it will not happen is $1-\frac{a}{c}$

Example 1. What is the chance of throwing a number greater than 4 with an ordinary die whose faces are numbered from 1 to 6?

There are 6 possible ways in which the die can fall, and of these two are favourable to the event required;

$$\text{therefore the required chance} = \frac{2}{6} = \frac{1}{3}.$$

Example 2. From a bag containing 4 white and 5 black balls a man draws 3 at random; what are the odds against these being all black?

The total number of ways in which 3 balls can be drawn is ${}^9C_3$, and the number of ways of drawing 3 black balls is ${}^5C_3$; therefore the chance of drawing 3 black balls

$$= \frac{{}^5C_3}{{}^9C_3} = \frac{5.4.3}{9.8.7} = \frac{5}{42}.$$

Thus the odds against the event are 37 to 5.

Example 3. Find the chance of throwing at least one ace in a single throw with two dice.

The possible number of cases is 6×6, or 36.

An ace on one die may be associated with any of the 6 numbers on the other die, and the remaining 5 numbers on the first die may each be associated with the ace on the second die; thus the number of favourable cases is 11.

Therefore the required chance is $\frac{11}{36}$.

Or we may reason as follows:

There are 5 ways in which each die can be thrown so as *not* to give an ace; hence 25 throws of the two dice will exclude aces. That is, the chance of *not* throwing one or more aces is $\frac{25}{36}$; so that the chance of throwing one ace at least is $1-\frac{25}{36}$, or $\frac{11}{36}$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

that A will happen is $\dfrac{a}{a+b+c+\ldots}$. Similarly the chance that B will happen is $\dfrac{b}{a+b+c+\ldots}$; and so on.

454. From the examples we have given it will be seen that the solution of the easier kinds of questions in Probability requires nothing more than a knowledge of the definition of Probability, and the application of the laws of Permutations and Combinations.

EXAMPLES. XXXII. a.

1. In a single throw with two dice find the chances of throwing (1) five, (2) six.

2. From a pack of 52 cards two are drawn at random; find the chance that one is a knave and the other a queen.

3. A bag contains 5 white, 7 black, and 4 red balls: find the chance that three balls drawn at random are all white.

4. If four coins are tossed, find the chance that there should be two heads and two tails.

5. One of two events must happen: given that the chance of the one is two-thirds that of the other, find the odds in favour of the other.

6. If from a pack four cards are drawn, find the chance that they will be the four honours of the same suit.

7. Thirteen persons take their places at a round table, shew that it is five to one against two particular persons sitting together.

8. There are three events A, B, C, one of which must, and only one can, happen; the odds are 8 to 3 against A, 5 to 2 against B: find the odds against C.

9. Compare the chances of throwing 4 with one die, 8 with two dice, and 12 with three dice.

10. In shuffling a pack of cards, four are accidentally dropped; find the chance that the missing cards should be one from each suit.

11. A has 3 shares in a lottery containing 3 prizes and 9 blanks; B has 2 shares in a lottery containing 2 prizes and 6 blanks: compare their chances of success.

12. Shew that the chances of throwing six with 4, 3, or 2 dice respectively are as 1 : 6 : 18.

13. There are three works, one consisting of 3 volumes, one of 4, and the other of 1 volume. They are placed on a shelf at random; prove that the chance that volumes of the same works are all together is $\frac{3}{140}$.

14. *A* and *B* throw with two dice; if *A* throws 9, find *B*'s chance of throwing a higher number.

15. The letters forming the word *Clifton* are placed at random in a row: what is the chance that the two vowels come together?

16. In a hand at whist what is the chance that the 4 kings are held by a specified player?

17. There are 4 shillings and 3 half-crowns placed at random in a line: shew that the chance of the extreme coins being both half-crowns is $\frac{1}{7}$. Generalize this result in the case of n shillings and n half-crowns.

455. We have hitherto considered only those occurrences which in the language of Probability are called *Simple* events. When two or more of these occur in connection with each other, the joint occurrence is called a *Compound* event.

For example, suppose we have a bag containing 5 white and 8 black balls, and two drawings, each of three balls, are made from it successively. If we wish to estimate the chance of drawing first 3 white and then 3 black balls, we should be dealing with a compound event.

In such a case the result of the second drawing might or might not be *dependent* on the result of the first. If the balls are not replaced after being drawn, then if the first drawing gives 3 white balls, the ratio of the black to the white balls remaining is greater than if the first drawing had not given three white; thus the chance of drawing 3 black balls at the second trial is affected by the result of the first. But if the balls are replaced after being drawn, it is clear that the result of the second drawing is not in any way affected by the result of the first.

We are thus led to the following definition:

Events are said to be **dependent** or **independent** according as the occurrence of one does or does not affect the occurrence of the others. Dependent events are sometimes said to be *contingent*.

456. *If there are two independent events the respective probabilities of which are known, to find the probability that both will happen.*

Suppose that the first event may happen in a ways and fail in b ways, all these cases being equally likely; and suppose that the second event may happen in a' ways and fail in b' ways, all these ways being equally likely. Each of the $a+b$ cases may be associated with each of the $a'+b'$ cases, to form $(a+b)(a'+b')$ compound cases all equally likely to occur.

In aa' of these both events happen, in bb' of them both fail, in ab' of them the first happens and the second fails, and in $a'b$ of them the first fails and the second happens. Thus

$\frac{aa'}{(a+b)(a'+b')}$ is the chance that both events happen;

$\frac{bb'}{(a+b)(a'+b')}$ is the chance that both events fail;

$\frac{ab'}{(a+b)(a'+b')}$ is the chance that the first happens and the second fails;

$\frac{a'b}{(a+b)(a'+b')}$ is the chance that the first fails and the second happens.

Thus if the respective chances of two independent events are p and p', the chance that both will happen is pp'. Similar reasoning will apply in the case of any number of independent events. Hence it is easy to see that if p_1, p_2, p_3, ... are the respective chances that a number of independent events will separately happen, the chance that they will all happen is $p_1p_2p_3\ldots$; the chance that the two first will happen and the rest fail is $p_1p_2(1-p_3)(1-p_4)\ldots$; and similarly for any other particular case.

457. If p is the chance that an event will happen in one trial, the chance that it will happen in any assigned succession of r trials is p^r; this follows from the preceding article by supposing

$$p_1 = p_2 = p_3 - \ldots\ldots - p.$$

To find the chance that some one at least of the events will happen we proceed thus: the chance that all the events fail is $(1-p_1)(1-p_2)(1-p_3)\ldots$, and except in this case some one of the events must happen; hence the required chance is

$$1-(1-p_1)(1-p_2)(1-p_3).$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

events can happen together is aa', and the probability of their concurrence is $\dfrac{aa'}{(a+b)(a'+b')}$.

Thus if p is the probability of the first event, and p' the contingent probability that the second will follow, the probability of the concurrence of the two events is pp'.

Example 1. In a hand at whist find the chance that a specified player holds both the king and queen of trumps.

Denote the player by A; then the chance that A has the king is clearly $\frac{13}{52}$; for this particular card can be dealt in 52 different ways, 13 of which fall to A. The chance that, when he has the king, he can also hold the queen is then $\frac{12}{51}$; for the queen can be dealt in 51 ways, 12 of which fall to A.

Therefore the chance required $= \frac{13}{52} \times \frac{12}{51} = \frac{1}{17}$.

Or we might reason as follows:

The number of ways in which the king and the queen can be dealt to A is equal to the number of permutations of 13 things 2 at a time, or $13 \cdot 12$. And similarly the total number of ways in which the king and queen can be dealt is $52 \cdot 51$.

Therefore the chance $= \dfrac{13 \cdot 12}{52 \cdot 51} = \dfrac{1}{17}$, as before.

Example 2. Two drawings, each of 3 balls, are made from a bag containing 5 white and 8 black balls, *the balls not being replaced before the second trial:* find the chance that the first drawing will give 3 white and the second 3 black balls.

At the first trial, 3 balls may be drawn in ${}^{13}C_3$ ways;
and 3 white balls may be drawn in ${}^{5}C_3$ ways;
therefore the chance of 3 white at first trial $= \dfrac{5 \cdot 4}{1 \cdot 2} \div \dfrac{13 \cdot 12 \cdot 11}{1 \cdot 2 \cdot 3} = \dfrac{5}{143}$.

When 3 white balls have been drawn and removed, the bag contains 2 white and 8 black balls,
therefore at the second trial 3 balls may be drawn in ${}^{10}C_3$ ways·
and 3 black balls may be drawn in ${}^{8}C_3$ ways;
therefore the chance of 3 black at the second trial

$$= \frac{8 \cdot 7 \cdot 6}{1 \cdot 2 \cdot 3} \div \frac{10 \cdot 9 \cdot 8}{1 \cdot 2 \cdot 3} = \frac{7}{15};$$

therefore the chance of the compound event

$$= \frac{5}{143} \times \frac{7}{15} = \frac{7}{429}.$$

The student should compare this solution with that of Ex. 1, Art. 457.

459. *If an event can happen in two or more different ways* which are mutually exclusive, *the chance that it will happen is the sum of the chances of its happening in these different ways.*

This is sometimes regarded as a self-evident proposition arising immediately out of the definition of probability. It may, however, be proved as follows:

Suppose the event can happen in two ways which cannot concur; and let $\frac{a_1}{b_1}$, $\frac{a_2}{b_2}$ be the chances of the happening of the event in these two ways respectively. Then out of $b_1 b_2$ cases there are $a_1 b_2$ in which the event may happen in the first way, and $a_2 b_1$ ways in which the event may happen in the second; *and these ways cannot concur.* Therefore in all, out of $b_1 b_2$ cases there are $a_1 b_2 + a_2 b_1$ cases favourable to the event; hence the chance that the event will happen in one or other of the two ways is

$$\frac{a_1 b_2 + a_2 b_1}{b_1 b_2} = \frac{a_1}{b_1} + \frac{a_2}{b_2}.$$

Similar reasoning will apply whatever be the number of exclusive ways in which the event can happen.

Hence if an event can happen in n ways which are mutually exclusive, and if $p_1, p_2, p_3, \ldots p_n$ are the probabilities that the event will happen in these different ways respectively, the probability that it will happen in some one of these ways is

$$p_1 + p_2 + p_3 + \ldots\ldots + p_n.$$

Example 1. Find the chance of throwing 9 at least in a single throw with two dice.

9 can be made up in 4 ways, and thus the chance of throwing 9 is $\frac{4}{36}$.

10 can be made up in 3 ways, and thus the chance of throwing 10 is $\frac{3}{36}$.

11 can be made up in 2 ways, and thus the chance of throwing 11 is $\frac{2}{36}$.

12 can be made up in 1 way, and thus the chance of throwing 12 is $\frac{1}{36}$.

Now the chance of throwing a number not less than 9 is the sum of these separate chances;

$$\therefore \text{ the required chance} = \frac{4+3+2+1}{36} = \frac{5}{18}.$$

Example 2. One purse contains 1 sovereign and 3 shillings, a second purse contains 2 sovereigns and 4 shillings, and a third contains 3 sovereigns and 1 shilling. If a coin is taken out of one of the purses selected at random, find the chance that it is a sovereign.

Since each purse is equally likely to be taken, the chance of selecting the first is $\frac{1}{3}$; and the chance of then drawing a sovereign is $\frac{1}{4}$; hence the chance of drawing a sovereign so far as it depends upon the first purse is $\frac{1}{3} \times \frac{1}{4}$, or $\frac{1}{12}$. Similarly the chance of drawing a sovereign so far as it depends on the second purse is $\frac{1}{3} \times \frac{2}{6}$, or $\frac{1}{9}$; and from the third purse the chance of drawing a sovereign is $\frac{1}{3} \times \frac{3}{4}$, or $\frac{1}{4}$;

$$\therefore \text{ the required chance} = \frac{1}{12} + \frac{1}{9} + \frac{1}{4} = \frac{4}{9}.$$

460. In the preceding article we have seen that the probability of an event may sometimes be considered as the sum of the probabilities of two or more separate events; but it is very important to notice that the probability of one or other of a series of events is the sum of the probabilities of the separate events *only when the events are mutually exclusive*, that is, when the occurrence of one is incompatible with the occurrence of any of the others.

Example. From 20 tickets marked with the first 20 numerals, one is drawn at random: find the chance that it is a multiple of 3 or of 7.

The chance that the number is a multiple of 3 is $\frac{6}{20}$, and the chance that it is a multiple of 7 is $\frac{2}{20}$; and *these events are mutually exclusive*, hence the required chance is $\frac{6}{20} + \frac{2}{20}$, or $\frac{2}{5}$.

But if the question had been: *find the chance that the number is a multiple of* 3 *or of* 5, it would have been incorrect to reason as follows:

Because the chance that the number is a multiple of 3 is $\frac{6}{20}$, and the chance that the number is a multiple of 5 is $\frac{4}{20}$, therefore the chance that it is a multiple of 3 or 5 is $\frac{6}{20} + \frac{4}{20}$, or $\frac{1}{2}$. For the number on the ticket might be a multiple *both* of 3 and of 5, so that the two events considered are not mutually exclusive.

461. It should be observed that the distinction between simple and compound events is in many cases a purely artificial

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

7. Four persons draw each a card from an ordinary pack: find the chance (1) that a card is of each suit, (2) that no two cards are of equal value.

8. Find the chance of throwing six with a single die at least once in five trials.

9. The odds that a book will be favourably reviewed by three independent critics are 5 to 2, 4 to 3, and 3 to 4 respectively; what is the probability that of the three reviews a majority will be favourable?

10. A bag contains 5 white and 3 black balls, and 4 are successively drawn out and not replaced; what is the chance that they are alternately of different colours?

11. In three throws with a pair of dice, find the chance of throwing doublets at least once.

12. If 4 whole numbers taken at random are multiplied together shew that the chance that the last digit in the product is 1, 3, 7, or 9 is $\frac{16}{625}$.

13. In a purse are 10 coins, all shillings except one which is a sovereign; in another are ten coins all shillings. Nine coins are taken from the former purse and put into the latter, and then nine coins are taken from the latter and put into the former: find the chance that the sovereign is still in the first purse.

14. If two coins are tossed 5 times, what is the chance that there will be 5 heads and 5 tails?

15. If 8 coins are tossed, what is the chance that one and only one will turn up head?

16. A, B, C in order cut a pack of cards, replacing them after each cut, on condition that the first who cuts a spade shall win a prize: find their respective chances.

17. A and B draw from a purse containing 3 sovereigns and 4 shillings: find their respective chances of first drawing a sovereign, the coins when drawn not being replaced.

18. A party of n persons sit at a round table, find the odds against two specified individuals sitting next to each other.

19. A is one of 6 horses entered for a race, and is to be ridden by one of two jockeys B and C. It is 2 to 1 that B rides A, in which case all the horses are equally likely to win; if C rides A, his chance is trebled: what are the odds against his winning?

20. If on an average 1 vessel in every 10 is wrecked, find the chance that out of 5 vessels expected 4 at least will arrive safely.

462. *The probability of the happening of an event in one trial being known, required the probability of its happening once, twice, three times, ... exactly in* n *trials.*

Let p be the probability of the happening of the event in a single trial, and let $q = 1 - p$; then the probability that the event will happen exactly r times in n trials is the $(r+1)^{\text{th}}$ term in the expansion of $(q+p)^n$.

For if we select any particular set of r trials out of the total number n, the chance that the event will happen in every one of *these* r trials and fail in all the rest is $p^r q^{n-r}$ [Art. 456], and as a set of r trials can be selected in ${}^nC_r$ ways, all of which are equally applicable to the case in point, the required chance is

$$ {}^nC_r p^r q^{n-r}. $$

If we expand $(p+q)^n$ by the Binomial Theorem, we have

$$ p^n + {}^nC_1 p^{n-1} q + {}^nC_2 p^{n-2} q^2 + \ldots + {}^nC_{n-r} p^r q^{n-r} + \ldots + q^n; $$

thus the terms of this series will represent respectively the probabilities of the happening of the event exactly n times, $n-1$ times, $n-2$ times, ... in n trials.

463. If the event happens n times, or fails only once, twice, ... $(n-r)$ times, it happens r times or more; therefore the chance that it happens *at least* r times in n trials is

$$ p^n + {}^nC_1 p^{n-1} q + {}^nC_2 p^{n-2} q^2 + \ldots + {}^nC_{n-r} p^r q^{n-r}, $$

or the sum of the first $n-r+1$ terms of the expansion of $(p+q)^n$.

Example 1. In four throws with a pair of dice, what is the chance of throwing doublets twice at least?

In a single throw the chance of doublets is $\frac{6}{36}$, or $\frac{1}{6}$; and the chance of failing to throw doublets is $\frac{5}{6}$. Now the required event follows if doublets are thrown four times, three times, or twice; therefore the required chance is the sum of the first three terms of the expansion of $\left(\frac{1}{6}+\frac{5}{6}\right)^4$.

$$ \text{Thus the chance } = \frac{1}{6^4}(1 + 4 \,.\, 5 + 6 \,.\, 5^2) = \frac{19}{144}. $$

Example 2. A bag contains a certain number of balls, some of which are white; a ball is drawn and replaced, another is then drawn and replaced; and so on: if p is the chance of drawing a white ball in a single trial, find the number of white balls that is most likely to have been drawn in n trials.

The chance of drawing exactly r white balls is ${}^nC_r p^r q^{n-r}$, and we have to find for what value of r this expression is greatest.

Now $${}^nC_r p^r q^{n-r} > {}^nC_{r-1} p^{r-1} q^{n-(r-1)},$$

so long as $$(n-r+1)p > rq,$$

or $$(n+1)p > (p+q)r.$$

But $p+q=1$; hence the required value of r is the greatest integer in $p(n+1)$.

If n is such that pn is an integer, the most likely case is that of pn successes and qn failures.

464. Suppose that there are n tickets in a lottery for a prize of £x; then since each ticket is equally likely to win the prize, and a person who possessed all the tickets *must* win, the money value of each ticket is £$\frac{x}{n}$; in other words this would be a fair sum to pay for each ticket; hence a person who possessed r tickets might reasonably expect £$\frac{rx}{n}$ as the price to be paid for his tickets by any one who wished to buy them; that is, he would estimate £$\frac{r}{n}x$ as the worth of his chance. It is convenient then to introduce the following definition:

If p represents a person's chance of success in any venture and M the sum of money which he will receive in case of success, the sum of money denoted by pM is called his **expectation.**

465. In the same way that *expectation* is used in reference to a person, we may conveniently use the phrase *probable value* applied to things.

Example 1. One purse contains 5 shillings and 1 sovereign: a second purse contains 6 shillings. Two coins are taken from the first and placed in the second; then 2 are taken from the second and placed in the first: find the probable value of the contents of each purse.

The chance that the sovereign is in the first purse is equal to the sum of the chances that it has moved twice and that it has not moved at all;

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

466. We shall now give two problems which lead to useful and interesting results.

Example 1. Two players A and B want respectively m and n points of winning a set of games; their chances of winning a single game are p and q respectively, where the sum of p and q is unity; the stake is to belong to the player who first makes up his set: determine the probabilities in favour of each player.

Suppose that A wins in *exactly* $m+r$ games; to do this he must win the last game and $m-1$ out of the preceding $m+r-1$ games. The chance of this is ${}^{m+r-1}C_{m-1}\, p^{m-1} q^r p$, or ${}^{m+r-1}C_{m-1}\, p^m q^r$.

Now the set will necessarily be decided in $m+n-1$ games, and A may win his m games in *exactly* m games, or $m+1$ games, ..., or $m+n-1$ games; therefore we shall obtain the chance that A wins the set by giving to r the values $0, 1, 2, \ldots n-1$ in the expression ${}^{m+r-1}C_{m-1}\, p^m q^r$. Thus A's chance is

$$p^m \left\{1 + mq + \frac{m(m+1)}{1.2} q^2 + \ldots + \frac{\lfloor m+n-2}{\lfloor m-1 \, \lfloor n-1} q^{n-1}\right\};$$

similarly B's chance is

$$q^n \left\{1 + np + \frac{n(n+1)}{1.2} p^2 + \ldots + \frac{\lfloor m+n-2}{\lfloor m-1 \, \lfloor n-1} p^{n-1}\right\}.$$

This question is known as the "Problem of Points," and has engaged the attention of many of the most eminent mathematicians since the time of Pascal. It was originally proposed to Pascal by the Chevalier de Méré in 1654, and was discussed by Pascal and Fermat, but they confined themselves to the case in which the players were supposed to be of equal skill: their results were also exhibited in a different form. The formulæ we have given are assigned to Montmort, as they appear for the first time in a work of his published in 1714. The same result was afterwards obtained in different ways by Lagrange and Laplace, and by the latter the problem was treated very fully under various modifications.

Example 2. There are n dice with f faces marked from 1 to f; if these are thrown at random, what is the chance that the sum of the numbers exhibited shall be equal to p?

Since any one of the f faces may be exposed on any one of the n dice, the number of ways in which the dice may fall is f^n.

Also the number of ways in which the numbers thrown will have p for their sum is equal to the coefficient of x^p in the expansion of

$$(x^1 + x^2 + x^3 + \ldots + x^f)^n;$$

for this coefficient arises out of the different ways in which n of the indices $1, 2, 3, \ldots f$ can be taken so as to form p by addition.

Now the above expression $= x^n (1 + x + x^2 + \ldots + x^{f-1})^n$

$$= x^n \left(\frac{1 - x^f}{1 - x}\right)^n.$$

We have therefore to find the coefficient of x^{p-n} in the expansion of

$$(1 - x^f)^n (1 - x)^{-n}.$$

Now $$(1 - x^f)^n = 1 - nx^f + \frac{n(n-1)}{1.2} x^{2f} - \frac{n(n-1)(n-2)}{1.2.3} x^{3f} + \ldots;$$

and $$(1 - x)^{-n} = 1 + nx + \frac{n(n+1)}{1.2} x^2 + \frac{n(n+1)(n+2)}{1.2.3} x^3 + \ldots$$

Multiply these series together and pick out the coefficient of x^{p-n} in the product; we thus obtain

$$\frac{n(n+1)\ldots(p-1)}{\underline{|p-n}} - n \cdot \frac{n(n+1)\ldots(p-f-1)}{\underline{|p-n-f}}$$

$$+ \frac{n(n-1)}{1.2} \cdot \frac{n(n+1)\ldots(p-2f-1)}{\underline{|p-n-2f}} - \ldots,$$

where the series is to continue so long as no negative factors appear. The required probability is obtained by dividing this series by f^n.

This problem is due to De Moivre and was published by him in 1730; it illustrates a method of frequent utility.

Laplace afterwards obtained the same formula, but in a much more laborious manner; he applied it in an attempt to demonstrate the existence of a primitive cause which has made the planets to move in orbits close to the ecliptic, and in the same direction as the earth round the sun. On this point the reader may consult Todhunter's *History of Probability*, Art. 987.

EXAMPLES. XXXII. c.

1. In a certain game A's skill is to B's as 3 to 2: find the chance of A winning 3 games at least out of 5.

2. A coin whose faces are marked 2, 3 is thrown 5 times: what is the chance of obtaining a total of 12?

3. In each of a set of games it is 2 to 1 in favour of the winner of the previous game: what is the chance that the player who wins the first game shall win three at least of the next four?

4. There are 9 coins in a bag, 5 of which are sovereigns and the rest are unknown coins of equal value; find what they must be if the probable value of a draw is 12 shillings.

5. A coin is tossed n times, what is the chance that the head will present itself an odd number of times?

6. From a bag containing 2 sovereigns and 3 shillings a person is allowed to draw 2 coins indiscriminately; find the value of his expectation.

7. Six persons throw for a stake, which is to be won by the one who first throws head with a penny; if they throw in succession, find the chance of the fourth person.

8. Counters marked 1, 2, 3 are placed in a bag, and one is withdrawn and replaced. The operation being repeated three times, what is the chance of obtaining a total of 6?

9. A coin whose faces are marked 3 and 5 is tossed 4 times: what are the odds against the sum of the numbers thrown being less than 15?

10. Find the chance of throwing 10 exactly in one throw with 3 dice.

11. Two players of equal skill, A and B, are playing a set of games; they leave off playing when A wants 3 points and B wants 2. If the stake is £16, what share ought each to take?

12. A and B throw with 3 dice: if A throws 8, what is B's chance of throwing a higher number?

13. A had in his pocket a sovereign and four shillings; taking out two coins at random he promises to give them to B and C. What is the worth of C's expectation?

14. In five throws with a single die what is the chance of throwing (1) three aces *exactly*, (2) three aces at least.

15. A makes a bet with B of 5s. to 2s. that in a single throw with two dice he will throw seven before B throws four. Each has a pair of dice and they throw simultaneously until one of them wins: find B's expectation.

16. A person throws two dice, one the common cube, and the other a regular tetrahedron, the number on the lowest face being taken in the case of the tetrahedron; what is the chance that the sum of the numbers thrown is not less than 5?

17. A bag contains a coin of value M, and a number of other coins whose aggregate value is m. A person draws one at a time till he draws the coin M: find the value of his expectation.

18. If $6n$ tickets numbered 0, 1, 2, ... $6n-1$ are placed in a bag, and three are drawn out, shew that the chance that the sum of the numbers on them is equal to $6n$ is

$$\frac{3n}{(6n-1)(6n-2)}.$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

times. Hence the probability that the sovereign came from the first purse is $\frac{5}{11}$, and the probability that it came from the second is $\frac{6}{11}$.

*469. It is important that the student's attention should be directed to the nature of the assumption that has been made in the preceding article. Thus, to take a particular instance, although in 60 throws with a perfectly symmetrical die it may not happen that ace is thrown exactly 10 times, yet it will doubtless be at once admitted that if the number of throws is continually increased the ratio of the number of aces to the number of throws will tend more and more nearly to the limit $\frac{1}{6}$. There is no reason why one face should appear oftener than another; hence in the long run the number of times that each of the six faces will have appeared will be approximately equal.

The above instance is a particular case of a general theorem which is due to James Bernoulli, and was first given in the *Ars Conjectandi*, published in 1713, eight years after the author's death. Bernoulli's theorem may be enunciated as follows:

If p *is the probability that an event happens in a single trial, then if the number of trials is indefinitely increased, it becomes a certainty that the limit of the ratio of the number of successes to the number of trials is equal to* p*; in other words, if the number of trials is* N, *the number of successes may be taken to be* pN.

See Todhunter's *History of Probability*, Chapter VII. A proof of Bernoulli's theorem is given in the article *Probability* in the *Encyclopædia Britannica*.

*470. *An observed event has happened through some one of a number of mutually exclusive causes: required to find the probability of any assigned cause being the true one.*

Let there be n causes, and *before the event took place* suppose that the probability of the existence of these causes was estimated at $P_1, P_2, P_3, \ldots P_n$. Let p_r denote the probability that when the r^{th} cause exists the event will follow: *after the event has occurred* it is required to find the probability that the r^{th} cause was the true one.

Consider a very great number N of trials; then the first cause exists in $P_1 N$ of these, and out of this number the event follows in $p_1 P_1 N$; similarly there are $p_2 P_2 N$ trials in which the event follows from the second cause; and so on for each of the other causes. Hence the number of trials in which the event follows is

$$(p_1 P_1 + p_2 P_2 + \dots + p_n P_n) N, \text{ or } N \Sigma (pP);$$

and the number in which the event was due to the r^{th} cause is $p_r P_r N$; hence *after* the event the probability that the r^{th} cause was the true one is

$$p_r P_r N \div N \Sigma (pP);$$

that is, the probability that the event was produced by the r^{th} cause is

$$\frac{p_r P_r}{\Sigma (pP)}.$$

*471. It is necessary to distinguish clearly between the probability of the existence of the several causes estimated *before* the event, and the probability *after the event has happened* of any assigned cause being the true one. The former are usually called *a priori* probabilities and are represented by $P_1, P_2, P_3, \dots P_n$; the latter are called *a posteriori* probabilities, and if we denote them by $Q_1, Q_2, Q_3, \dots Q_n$, we have proved that

$$Q_r = \frac{p_r P_r}{\Sigma (pP)};$$

where p_r denotes the probability of the event on the hypothesis of the existence of the r^{th} cause.

From this result it appears that $\Sigma (Q) = 1$, which is otherwise evident as the event has happened from one and only one of the causes.

We shall now give another proof of the theorem of the preceding article which does not depend on the principle enunciated in Art. 469.

*472. *An observed event has happened through some one of a number of mutually exclusive causes: required to find the probability of any assigned cause being the true one.*

Let there be n causes, and *before the event took place* suppose that the probability of the existence of these causes was estimated at $P_1, P_2, P_3, \dots P_n$. Let p_r denote the probability that when the r^{th} cause exists the event will follow; then the *antecedent* probability that the event would follow from the r^{th} cause is $p_r P_r$.

Let Q_r be the *a posteriori* probability that the r^{th} cause was the true one; then the probability that the r^{th} cause was the true one is proportional to the probability that, if in existence, this cause would produce the event;

$$\frac{Q_1}{p_1P_1}=\frac{Q_2}{p_2P_2}=\ \dots\ =\frac{Q_n}{p_nP_n}=\frac{\Sigma(Q)}{\Sigma(pP)}=\frac{1}{\Sigma(pP)};$$

$$Q_r=\frac{p_rP_r}{\Sigma(pP)}.$$

Hence it appears that in the present class of problems the product P_rp_r, will have to be correctly estimated as a first step; in many cases, however, it will be found that P_1, P_2, P_3, ... are all equal, and the work is thereby much simplified.

E*xample.* There are 3 bags each containing 5 white balls and 2 black balls, and 2 bags each containing 1 white ball and 4 black balls: a black ball having been drawn, find the chance that it came from the first group.

Of the five bags, 3 belong to the first group and 2 to the second; hence

$$P_1=\frac{3}{5},\quad P_2=\frac{2}{5}.$$

If a bag is selected from the first group the chance of drawing a black ball is $\frac{2}{7}$; if from the second group the chance is $\frac{4}{5}$; thus $p_1=\frac{2}{7}$, $p_2=\frac{4}{5}$;

$$\therefore\ p_1P_1=\frac{6}{35},\quad p_2P_2=\frac{8}{25}.$$

Hence the chance that the black ball came from one of the first group is

$$\frac{6}{35}\div\left(\frac{6}{35}+\frac{8}{25}\right)=\frac{15}{43}.$$

*473. When an event has been observed, we are able by the method of Art. 472 to estimate the probability of any particular cause being the true one; we may then estimate the probability of the event happening in a second trial, or we may find the probability of some other event.

For example, p_r is the chance that the event will happen from the r^{th} cause if in existence, and the chance that the r^{th} cause is the true one is Q_r; hence on a second trial the chance that the event will happen from the r^{th} cause is p_rQ_r. Therefore the chance that the event will happen from some one of the causes on a second trial is $\Sigma(pQ)$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

*474. We shall now shew how the theory of probability may be applied to estimate the truth of statements attested by witnesses whose credibility is assumed to be known. We shall suppose that each witness states what he believes to be the truth, whether his statement is the result of observation, or deduction, or experiment; so that any mistake or falsehood must be attributed to errors of judgment and not to wilful deceit.

The class of problems we shall discuss furnishes a useful intellectual exercise, and although the results cannot be regarded as of any practical importance, it will be found that they confirm the verdict of common sense.

*475. When it is asserted that the probability that a person speaks the truth is p, it is meant that a large number of statements made by him has been examined, and that p is the ratio of those which are true to the whole number.

*476. Two independent witnesses, A and B, whose probabilities of speaking the truth are p and p' respectively, agree in making a certain statement: what is the probability that the statement is true?

Here the observed event is the fact that A and B make the same statement. Before the event there are four hypotheses; for A and B may both speak truly; or A may speak truly, B falsely; or A may speak falsely, B truly; or A and B may both speak falsely. The probabilities of these four hypotheses are

$$pp', \quad p(1-p'), \quad p'(1-p), \quad (1-p)(1-p') \text{ respectively.}$$

Hence after the observed event, in which A and B make the same statement, the probability that the statement is true is to the probability that it is false as pp' to $(1-p)(1-p')$; that is, the probability that the joint statement is true is

$$\frac{pp'}{pp' + (1-p)(1-p')}.$$

Similarly if a third person, whose probability of speaking the truth is p'', makes the same statement, the probability that the statement is true is

$$\frac{pp'p''}{pp'p'' + (1-p)(1-p')(1-p'')};$$

and so on for any number of persons.

*477. In the preceding article it has been supposed that we have no knowledge of the event except the statement made by A and B; if we have information from other sources as to the probability of the truth or falsity of the statement, this must be taken into account in estimating the probability of the various hypotheses.

For instance, if A and B agree in stating a fact, of which the *a priori* probability is P, then we should estimate the probability of the truth and falsity of the statement by

$$Ppp' \text{ and } (1-P)(1-p)(1-p') \text{ respectively.}$$

Example. There is a raffle with 12 tickets and two prizes of £9 and £3. A, B, C, whose probabilities of speaking the truth are $\frac{1}{2}$, $\frac{2}{3}$, $\frac{3}{5}$ respectively, report the result to D, who holds one ticket. A and B assert that he has won the £9 prize, and C asserts that he has won the £3 prize; what is D's expectation?

Three cases are possible; D may have won £9, £3, or *nothing*, for A, B, C may all have spoken falsely.

Now with the notation of Art. 472, we have the *a priori* probabilities

$$P_1 = \frac{1}{12}, \quad P_2 = \frac{1}{12}, \quad P_3 = \frac{10}{12};$$

also $$p_1 = \frac{1}{2}\times\frac{2}{3}\times\frac{2}{5} - \frac{4}{30}, \quad p_2 = \frac{1}{2}\times\frac{1}{3}\times\frac{3}{5} = \frac{3}{30}, \quad p_3 = \frac{1}{2}\times\frac{1}{3}\times\frac{2}{5} = \frac{2}{30};$$

$$\therefore \frac{Q_1}{4} = \frac{Q_2}{3} = \frac{Q_3}{20} = \frac{1}{27};$$

hence D's expectation $= \frac{4}{27}$ of £9 $+ \frac{3}{27}$ of £3 $=$ £1. 13*s*. 4*d*.

*478. With respect to the results proved in Art. 476, it should be noticed that it was assumed that the statement can be made in two ways only, so that if all the witnesses tell falsehoods they agree in telling the *same* falsehood.

If this is not the case, let us suppose that c is the chance that the two witnesses A and B will agree in telling the same falsehood; then the probability that the statement is true is to the probability that it is false as pp' to $c(1-p)(1-p')$.

As a general rule, it is extremely improbable that two independent witnesses will tell the same falsehood, so that c is usually very small; also it is obvious that the quantity c becomes smaller as the number of witnesses becomes greater. These considerations increase the probability that a statement asserted by two or more independent witnesses is true, even though the credibility of each witness is small.

Example. *A* speaks truth 3 times out of 4, and *B* 7 times out of 10; they both assert that a white ball has been drawn from a bag containing 6 balls all of different colours: find the probability of the truth of the assertion.

There are two hypotheses; (i) their coincident testimony is true, (ii) it is false.

Here $$P_1=\frac{1}{6}, \quad P_2=\frac{5}{6};$$

$$p_1=\frac{3}{4}\times\frac{7}{10}, \quad p_2=\frac{1}{25}\times\frac{1}{4}\times\frac{3}{10},$$

for in estimating p_2 we must take into account the chance that *A* and *B* will both select the white ball when it has not been drawn; this chance is

$$\frac{1}{5}\times\frac{1}{5} \text{ or } \frac{1}{25}.$$

Now the probabilities of the two hypotheses are as P_1p_1 to P_2p_2, and therefore as 35 to 1; thus the probability that the statement is true is $\frac{35}{36}$.

*479. The cases we have considered relate to the probability of the truth of *concurrent* testimony; the following is a case of *traditionary* testimony.

If *A* states that a certain event took place, having received an account of its occurrence or non-occurrence from *B*, what is the probability that the event did take place?

The event happened (1) if they both spoke the truth, (2) if they both spoke falsely; and the event did not happen if only one of them spoke the truth.

Let p, p' denote the probabilities that *A* and *B* speak the truth; then the probability that the event did take place is

$$pp'+(1-p)(1-p'),$$

and the probability that it did not take place is

$$p(1-p')+p'(1-p).$$

*480. The solution of the preceding article is that which has usually been given in text-books; but it is open to serious objections, for the assertion that the given event happened if both *A* and *B* spoke falsely is not correct except on the supposition that the statement can be made only in two ways. Moreover, although it is expressly stated that *A* receives his account from *B*, this cannot generally be taken for granted as it rests on *A*'s testimony.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

11. A speaks the truth 2 out of 3 times, and B 4 times out of 5; they agree in the assertion that from a bag containing 6 balls of different colours a red ball has been drawn: find the probability that the statement is true.

12. One of a pack of 52 cards has been lost; from the remainder of the pack two cards are drawn and are found to be spades; find the chance that the missing card is a spade.

13. There is a raffle with 10 tickets and two prizes of value £5 and £1 respectively. A holds one ticket and is informed by B that he has won the £5 prize, while C asserts that he has won the £1 prize: what is A's expectation, if the credibility of B is denoted by $\frac{2}{3}$, and that of C by $\frac{3}{4}$?

14. A purse contains four coins; two coins having been drawn are found to be sovereigns: find the chance (1) that all the coins are sovereigns, (2) that if the coins are replaced another drawing will give a sovereign.

15. P makes a bet with Q of £8 to £120 that three races will be won by the three horses A, B, C, against which the betting is 3 to 2, 4 to 1, and 2 to 1 respectively. The first race having been won by A, and it being known that the second race was won either by B, or by a horse D against which the betting was 2 to 1, find the value of P's expectation.

16. From a bag containing n balls, all either white or black, all numbers of each being equally likely, a ball is drawn which turns out to be white; this is replaced, and another ball is drawn, which also turns out to be white. If this ball is replaced, prove that the chance of the next draw giving a black ball is $\frac{1}{2}(n-1)(2n+1)^{-1}$.

17. If mn coins have been distributed into m purses, n into each, find (1) the chance that two specified coins will be found in the same purse; and (2) what the chance becomes when r purses have been examined and found not to contain either of the specified coins.

18. A, B are two inaccurate arithmeticians whose chance of solving a given question correctly are $\frac{1}{8}$ and $\frac{1}{12}$ respectively; if they obtain the same result, and if it is 1000 to 1 against their making the same mistake, find the chance that the result is correct.

19. Ten witnesses, each of whom makes but one false statement in six, agree in asserting that a certain event took place; shew that the odds are five to one in favour of the truth of their statement, even although the *a priori* probability of the event is as small as $\frac{1}{5^9+1}$.

*481. The application of Geometry to questions of Probability requires, in general, the aid of the Integral Calculus; there are, however, many easy questions which can be solved by Elementary Geometry.

Example 1. From each of two equal lines of length l a portion is cut off at random, and removed: what is the chance that the sum of the remainders is less than l?

Place the lines parallel to one another, and suppose that after cutting, the right-hand portions are removed. Then the question is equivalent to asking what is the chance that the sum of the right-hand portions is greater than the sum of the left-hand portions. It is clear that the first sum is equally likely to be greater or less than the second; thus the required probability is $\frac{1}{2}$.

COR. Each of two lines is known to be of length not exceeding l: the chance that their sum is not greater than l is $\frac{1}{2}$.

Example 2. If three lines are chosen at random, prove that they are just as likely as not to denote the sides of a possible triangle.

Of three lines one *must* be equal to or greater than each of the other two; denote its length by l. Then all we know of the other two lines is that the length of each lies between 0 and l. But if each of two lines is known to be of random length between 0 and l, it is an even chance that their sum is greater than l. [Ex. 1, Cor.]

Thus the required result follows.

Example 3. Three tangents are drawn at random to a given circle: shew that the odds are 3 to 1 against the circle being *inscribed* in the triangle formed by them.



Draw three random lines P, Q, R, in the same plane as the circle, and draw to the circle the six tangents parallel to these lines.

Then of the 8 triangles so formed it is evident that the circle will be escribed to 6 and inscribed in 2; and as this is true whatever be the original directions of P, Q, R, the required result follows.

*482. Questions in Probability may sometimes be conveniently solved by the aid of co-ordinate Geometry.

Example. On a rod of length $a+b+c$, lengths a, b are measured at random: find the probability that no point of the measured lines will coincide.

Let AB be the line, and suppose $AP=x$ and $PQ=a$; also let a be measured from P towards B, so that x must be less than $b+c$. Again let $AP'=y$, $P'Q'=b$, and suppose $P'Q'$ measured from P' towards B, then y must be less than $a+c$.

Now in favourable cases we must have $AP'>AQ$, or else $AP>AQ'$,

hence $$y>a+x, \text{ or } x>b+y \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1).$$

Again for all the cases possible, we must have

$$\left.\begin{aligned} x>0, \text{ and } <b+c \\ y>0, \text{ and } <a+c \end{aligned}\right\} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2).$$

Take a pair of rectangular axes and make OX equal to $b+c$, and OY equal to $a+c$.

Draw the line $y=a+x$, represented by TML in the figure; and the line $x=b+y$ represented by KR.





Then YM, KX are each equal to c, OM, OT are each equal to a.

The conditions (1) are only satisfied by points in the triangles MYL and KXR, while the conditions (2) are satisfied by any points within the rectangle OX, OY;

$\therefore$ the required chance $$= \frac{c^2}{(a+c)(b+c)}.$$

*483. We shall close this chapter with some Miscellaneous Examples.

Example 1. A box is divided into m equal compartments into which n balls are thrown at random; find the probability that there will be p compartments each containing a balls, q compartments each containing b balls, r compartments each containing c balls, and so on, where

$$pa+qb+rc+\ldots\ldots=n.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

In the particular case when $k=2$,

the required chance $$=\frac{1}{n}\left\{\frac{n(n+1)}{2}\right\}^2 \div \frac{n(n+1)(2n+1)}{6}$$

$$=\frac{3(n+1)}{2(2n+1)}.$$

If n is indefinitely large, the chance is equal to the limit, when n is infinite, of $$\frac{1}{n}\cdot\frac{n^{k+2}}{k+2}\div\frac{n^{k+1}}{k+1};$$

and thus the chance is $$\frac{k+1}{k+2}.$$

(ii) If the balls are not replaced,

$$p_r=\frac{r}{n}\cdot\frac{r-1}{n-1}\cdot\frac{r-2}{n-2}\cdots\cdots\frac{r-k+1}{n-k+1};$$

and $$Q_r=\frac{p_r}{\Sigma p_r}=\frac{(r-k+1)(r-k+2)\ldots\ldots(r-1)r}{\sum_{r=0}^{r=n}(r-k+1)(r-k+2)\ldots\ldots(r-1)r}$$

$$=(k+1)\frac{(r-k+1)(r-k+2)\ldots\ldots(r-1)r}{(n-k+1)(n-k+2)\ldots\ldots(n-1)n(n+1)}.$$ [Art. 394.]

The chance that the next drawing will give a white ball $=\sum_{r=0}^{r=n}\frac{r-k}{n-k}Q_r$

$$=\frac{k+1}{(n-k)(n-k+1)\ldots\ldots n(n+1)}\sum_{r=0}^{r=n}(r-k)(r-k+1)\ldots\ldots(r-1)r$$

$$=\frac{k+1}{(n-k)(n-k+1)\ldots\ldots n(n+1)}\cdot\frac{(n-k)(n-k+1)\ldots\ldots n(n+1)}{k+2}$$

$$=\frac{k+1}{k+2},$$

which is independent of the number of balls in the bag at first.

Example 3. A person writes n letters and addresses n envelopes; if the letters are placed in the envelopes at random, what is the probability that every letter goes wrong?

Let u_n denote the number of ways in which all the letters go wrong, and let $abcd\ldots$ represent that arrangement in which all the letters are in their own envelopes. Now if a in any other arrangement occupies the place of an assigned letter b, this letter must either occupy a's place or some other.

(i) Suppose b occupies a's place. Then the number of ways in which all the remaining $n-2$ letters can be displaced is u_{n-2}, and therefore the numbers of ways in which a may be displaced by interchange with some one of the other $n-1$ letters, and the rest be all displaced is $(n-1)u_{n-2}$.

(ii) Suppose a occupies b's place, and b does not occupy a's. Then in arrangements satisfying the required conditions, since a is fixed in b's place, the letters b, c, d, ... must be all displaced, which can be done in u_{n-1} ways; therefore the number of ways in which a occupies the place of another letter but not by interchange with that letter is $(n-1)\,u_{n-1}$;

$$\therefore\ u_n=(n-1)\,(u_{n-1}+u_{n-2});$$

from which, by the method of Art. 444, we find $u_n - nu_{n-1}=(-1)^n(u_2-u_1)$.

Also $u_1=0$, $u_2=1$; thus we finally obtain

$$u_n=\lfloor\underline{n}\left\{\frac{1}{\lfloor\underline{2}}-\frac{1}{\lfloor\underline{3}}+\frac{1}{\lfloor\underline{4}}-\ldots+\frac{(-1)^n}{\lfloor\underline{n}}\right\}.$$

Now the total number of ways in which the n things can be put in n places is $\lfloor\underline{n}$; therefore the required chance is

$$\frac{1}{\lfloor\underline{2}}-\frac{1}{\lfloor\underline{3}}+\frac{1}{\lfloor\underline{4}}-\ldots+\frac{(-1)^n}{\lfloor\underline{n}}.$$

The problem here involved is of considerable interest, and in some of its many modifications has maintained a permanent place in works on the Theory of Probability. It was first discussed by Montmort, and it was generalised by De Moivre, Euler, and Laplace.

*484. The subject of Probability is so extensive that it is impossible here to give more than a sketch of the principal algebraical methods. An admirable collection of problems, illustrating every algebraical process, will be found in Whitworth's *Choice and Chance;* and the reader who is acquainted with the Integral Calculus may consult Professor Crofton's article *Probability* in the *Encyclopædia Britannica.* A complete account of the origin and development of the subject is given in Todhunter's *History of the Theory of Probability from the time of Pascal to that of Laplace.*

The practical applications of the theory of Probability to commercial transactions are beyond the scope of an elementary treatise; for these we may refer to the articles *Annuities* and *Insurance* in the *Encyclopædia Britannica.*

*EXAMPLES. XXXII. e.

1. What are the odds in favour of throwing at least 7 in a single throw with two dice?

2. In a purse there are 5 sovereigns and 4 shillings. If they are drawn out one by one, what is the chance that they come out sovereigns and shillings alternately, beginning with a sovereign?

3. If on an average 9 ships out of 10 return safe to port, what is the chance that out of 5 ships expected at least 3 will arrive?

4. In a lottery all the tickets are blanks but one; each person draws a ticket, and retains it: shew that each person has an equal chance of drawing the prize.

5. One bag contains 5 white and 3 red balls, and a second bag contains 4 white and 5 red balls. From one of them, chosen at random, two balls are drawn: find the chance that they are of different colours.

6. Five persons A, B, C, D, E throw a die in the order named until one of them throws an ace: find their relative chances of winning, supposing the throws to continue till an ace appears.

7. Three squares of a chess board being chosen at random, what is the chance that two are of one colour and one of another?

8. A person throws two dice, one the common cube, and the other a regular tetrahedron, the number on the lowest face being taken in the case of the tetrahedron; find the average value of the throw, and compare the chances of throwing 5, 6, 7.

9. A's skill is to B's as 1 : 3; to C's as 3 : 2; and to D's as 4 : 3: find the chance that A in three trials, one with each person, will succeed twice at least.

10. A certain stake is to be won by the first person who throws an ace with an octahedral die: if there are 4 persons what is the chance of the last?

11. Two players A, B of equal skill are playing a set of games; A wants 2 games to complete the set, and B wants 3 games: compare their chances of winning.

12. A purse contains 3 sovereigns and two shillings: a person draws one coin in each hand and looks at one of them, which proves to be a sovereign; shew that the other is equally likely to be a sovereign or a shilling.

13. A and B play for a prize; A is to throw a die first, and is to win if he throws 6. If he fails B is to throw, and to win if he throws 6 or 5. If he fails, A is to throw again and to win with 6 or 5 or 4, and so on: find the chance of each player.

14. Seven persons draw lots for the occupancy of the six seats in a first class railway compartment: find the chance (1) that two specified persons obtain opposite seats, (2) that they obtain adjacent seats on the same side.

15. A number consists of 7 digits whose sum is 59; prove that the chance of its being divisible by 11 is $\frac{4}{21}$.

16. Find the chance of throwing 12 in a single throw with 3 dice.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

26. There are two purses, one containing three sovereigns and a shilling, and the other containing three shillings and a sovereign. A coin is taken from one (it is not known which) and dropped into the other; and then on drawing a coin from each purse, they are found to be two shillings. What are the odds against this happening again if two more are drawn, one from each purse?

27. If a triangle is formed by joining three points taken at random in the circumference of a circle, prove that the odds are 3 to 1 against its being acute-angled.

28. Three points are taken at random on the circumference of a circle: what is the chance that the sum of any two of the arcs so determined is greater than the third?

29. A line is divided at random into three parts, what is the chance that they form the sides of a possible triangle?

30. Of two purses one originally contained 25 sovereigns, and the other 10 sovereigns and 15 shillings. One purse is taken by chance and 4 coins drawn out, which prove to be all sovereigns: what is the chance that this purse contains only sovereigns, and what is the probable value of the next draw from it?

31. On a straight line of length a two points are taken at random; find the chance that the distance between them is greater than b.

32. A straight line of length a is divided into three parts by two points taken at random; find the chance that no part is greater than b.

33. If on a straight line of length $a+b$ two lengths a, b are measured at random, the chance that the common part of these lengths shall not exceed c is $\frac{c^2}{ab}$, where c is less than a or b; also the chance that the smaller length b lies entirely within the larger a is $\frac{a-b}{a}$.

34. If on a straight line of length $a+b+c$ two lengths a, b are measured at random, the chance of their having a common part which shall not exceed d is $\frac{(c+d)^2}{(c+a)(c+b)}$, where d is less than either a or b.

35. Four passengers, A, B, C, D, entire strangers to each other, are travelling in a railway train which contains l first-class, m second-class, and n third-class compartments. A and B are gentlemen whose respective *a priori* chances of travelling first, second, or third class are represented in each instance by λ, μ, ν; C and D are ladies whose similar *a priori* chances are each represented by l, m, n. Prove that, for all values of λ, μ, ν (except in the particular case when $\lambda : \mu : \nu = l : m : n$), A and B are more likely to be found both in the company of the same lady than each with a different one.

CHAPTER XXXIII.

DETERMINANTS.

485. THE present chapter is devoted to a brief discussion of determinants and their more elementary properties. The slight introductory sketch here given will enable a student to avail himself of the advantages of determinant notation in Analytical Geometry, and in some other parts of Higher Mathematics; fuller information on this branch of Analysis may be obtained from Dr Salmon's *Lessons Introductory to the Modern Higher Algebra*, and Muir's *Theory of Determinants*.

486. Consider the two homogeneous linear equations

$$a_1x + b_1y = 0,$$

$$a_2x + b_2y = 0;$$

multiplying the first equation by b_2, the second by b_1, subtracting and dividing by x, we obtain

$$a_1b_2 - a_2b_1 = 0.$$

This result is sometimes written

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = 0,$$

and the expression on the left is called a **determinant**. It consists of two rows and two columns, and in its expanded form each term is the product of two quantities; it is therefore said to be of the *second order*.

The letters a_1, b_1, a_2, b_2 are called the *constituents* of the determinant, and the terms a_1b_2, a_2b_1 are called the *elements*.

487. Since

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = a_1b_2 - a_2b_1 = \begin{vmatrix} a_1 & a_2 \\ b_1 & b_2 \end{vmatrix},$$

it follows that *the value of the determinant is not altered by changing the rows into columns, and the columns into rows.*

488. Again, it is easily seen that

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = - \begin{vmatrix} b_1 & a_1 \\ b_2 & a_2 \end{vmatrix}, \text{ and } \begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = - \begin{vmatrix} a_2 & b_2 \\ a_1 & b_1 \end{vmatrix};$$

that is, *if we interchange two rows or two columns of the determinant, we obtain a determinant which differs from it only in sign.*

489. Let us now consider the homogeneous linear equations

$$a_1x + b_1y + c_1z = 0,$$
$$a_2x + b_2y + c_2z = 0,$$
$$a_3x + b_3y + c_3z = 0.$$

By eliminating x, y, z, we obtain as in Ex. 2, Art. 16,

$$a_1(b_2c_3 - b_3c_2) + b_1(c_2a_3 - c_3a_2) + c_1(a_2b_3 - a_3b_2) = 0,$$

or
$$a_1 \begin{vmatrix} b_2 & c_2 \\ b_3 & c_3 \end{vmatrix} + b_1 \begin{vmatrix} c_2 & a_2 \\ c_3 & a_3 \end{vmatrix} + c_1 \begin{vmatrix} a_2 & b_2 \\ a_3 & b_3 \end{vmatrix} = 0.$$

This eliminant is usually written

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} = 0,$$

and the expression on the left being a determinant which consists of three rows and three columns is called a determinant of the *third order*

490. By a rearrangement of terms the expanded form of the above determinant may be written

$$a_1(b_2c_3 - b_3c_2) + a_2(b_3c_1 - b_1c_3) + a_3(b_1c_2 - b_2c_1),$$

or
$$a_1 \begin{vmatrix} b_2 & b_3 \\ c_2 & c_3 \end{vmatrix} + a_2 \begin{vmatrix} b_3 & b_1 \\ c_3 & c_1 \end{vmatrix} + a_3 \begin{vmatrix} b_1 & b_2 \\ c_1 & c_2 \end{vmatrix};$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

492. The determinant $\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$

$$-a_1(b_2c_3-b_3c_2)+b_1(c_2a_3-c_3a_2)+c_1(a_2b_3-a_3b_2)$$
$$=-b_1(a_2c_3-a_3c_2)-a_1(c_2b_3-c_3b_2)-c_1(b_2a_3-b_3a_2);$$

hence

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} = - \begin{vmatrix} b_1 & a_1 & c_1 \\ b_2 & a_2 & c_2 \\ b_3 & a_3 & c_3 \end{vmatrix}.$$

Thus it appears that *if two adjacent columns, or rows, of the determinant are interchanged, the sign of the determinant is changed, but its value remains unaltered.*

If for the sake of brevity we denote the determinant

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$$

by $(a_1b_2c_3)$, then the result we have just obtained may be written

$$(b_1a_2c_3) = -(a_1b_2c_3).$$

Similarly we may shew that

$$(c_1a_2b_3) = -(a_1c_2b_3) = +(a_1b_2c_3).$$

493. *If two rows or two columns of the determinant are identical the determinant vanishes.*

For let D be the value of the determinant, then by interchanging two rows or two columns we obtain a determinant whose value is $-D$; but the determinant is unaltered; hence $D=-D$, that is $D=0$. Thus we have the following equations,

$$a_1A_1-a_2A_2+a_3A_3=D,$$
$$b_1A_1-b_2A_2+b_3A_3=0,$$
$$c_1A_1-c_2A_2+c_3A_3=0.$$

494. *If each constituent in any row, or in any column, is multiplied by the same factor, then the determinant is multiplied by that factor.*

For $\begin{vmatrix} ma_1 & b_1 & c_1 \\ ma_2 & b_2 & c_2 \\ ma_3 & b_3 & c_3 \end{vmatrix}$

$$= -ma_1 . A_1 - ma_2 . A_2 + ma_3 . A_3$$
$$= m(a_1A_1 - a_2A_2 + a_3A_3);$$

which proves the proposition.

Cor. If each constituent of one row, or column, is the same multiple of the corresponding constituent of another row, or column, the determinant vanishes.

495. *If each constituent in any row, or column, consists of two terms, then the determinant can be expressed as the sum of two other determinants.*

Thus we have

$$\begin{vmatrix} a_1 + \alpha_1 & b_1 & c_1 \\ a_2 + \alpha_2 & b_2 & c_2 \\ a_3 + \alpha_3 & b_3 & c_3 \end{vmatrix} = \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} + \begin{vmatrix} \alpha_1 & b_1 & c_1 \\ \alpha_2 & b_2 & c_2 \\ \alpha_3 & b_3 & c_3 \end{vmatrix};$$

for the expression on the left

$$= -(a_1 + \alpha_1) A_1 - (a_2 + \alpha_2) A_2 + (a_3 + \alpha_3) A_3$$
$$= (a_1A_1 - a_2A_2 + a_3A_3) + (\alpha_1A_1 - \alpha_2A_2 + \alpha_3A_3);$$

which proves the proposition.

In like manner if each constituent in any one row, or column, consists of m terms, the determinant can be expressed as the sum of m other determinants.

Similarly, we may shew that

$$\begin{vmatrix} a_1 + \alpha_1 & b_1 + \beta_1 & c_1 \\ a_2 + \alpha_2 & b_2 + \beta_2 & c_2 \\ a_3 + \alpha_3 & b_3 + \beta_3 & c_3 \end{vmatrix}$$

$$= \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} + \begin{vmatrix} a_1 & \beta_1 & c_1 \\ a_2 & \beta_2 & c_2 \\ a_3 & \beta_3 & c_3 \end{vmatrix} + \begin{vmatrix} \alpha_1 & b_1 & c_1 \\ \alpha_2 & b_2 & c_2 \\ \alpha_3 & b_3 & c_3 \end{vmatrix} + \begin{vmatrix} \alpha_1 & \beta_1 & c_1 \\ \alpha_2 & \beta_2 & c_2 \\ \alpha_3 & \beta_3 & c_3 \end{vmatrix}.$$

These results may easily be generalised; thus if the constituents of the three columns consist of m, n, p terms respectively, the determinant can be expressed as the sum of mnp determinants.

Example 1. Shew that $\begin{vmatrix} b+c & a-b & a \\ c+a & b-c & b \\ a+b & c-a & c \end{vmatrix} = 3abc - a^3 - b^3 - c^3$

The given determinant

$$= \begin{vmatrix} b & a & a \\ c & b & b \\ a & c & c \end{vmatrix} - \begin{vmatrix} b & b & a \\ c & c & b \\ a & a & c \end{vmatrix} + \begin{vmatrix} c & a & a \\ a & b & b \\ b & c & c \end{vmatrix} - \begin{vmatrix} c & b & a \\ a & c & b \\ b & a & c \end{vmatrix}.$$

Of these four determinants the first three vanish, Art. 493; thus the expression reduces to the last of the four determinants; hence its value

$$- - \{c(c^2 - ab) - b(ac - b^2) + a(a^2 - bc)\}$$
$$= 3abc - a^3 - b^3 - c^3$$

Example 2. Find the value of $\begin{vmatrix} 67 & 19 & 21 \\ 39 & 13 & 14 \\ 81 & 24 & 26 \end{vmatrix}$.

We have

$$\begin{vmatrix} 67 & 19 & 21 \\ 39 & 13 & 14 \\ 81 & 24 & 26 \end{vmatrix} = \begin{vmatrix} 10+57 & 19 & 21 \\ 0+39 & 13 & 14 \\ 9+72 & 24 & 26 \end{vmatrix} = \begin{vmatrix} 10 & 19 & 21 \\ 0 & 13 & 14 \\ 9 & 24 & 26 \end{vmatrix} + \begin{vmatrix} 57 & 19 & 21 \\ 39 & 13 & 14 \\ 72 & 24 & 26 \end{vmatrix}$$

$$= \begin{vmatrix} 10 & 19 & 21 \\ 0 & 13 & 14 \\ 9 & 24 & 26 \end{vmatrix} = \begin{vmatrix} 10 & 19 & 19+2 \\ 0 & 13 & 13+1 \\ 9 & 24 & 24+2 \end{vmatrix} = \begin{vmatrix} 10 & 19 & 2 \\ 0 & 13 & 1 \\ 9 & 24 & 2 \end{vmatrix}$$

$$= 10 \begin{vmatrix} 13 & 1 \\ 24 & 2 \end{vmatrix} + 9 \begin{vmatrix} 19 & 2 \\ 13 & 1 \end{vmatrix} = 20 - 63 = -43.$$

496. Consider the determinant

$$\begin{vmatrix} a_1 + pb_1 + qc_1 & b_1 & c_1 \\ a_2 + pb_2 + qc_2 & b_2 & c_2 \\ a_3 + pb_3 + qc_3 & b_3 & c_3 \end{vmatrix};$$

as in the last article we can shew that it is equal to

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix} + \begin{vmatrix} pb_1 & b_1 & c_1 \\ pb_2 & b_2 & c_2 \\ pb_3 & b_3 & c_3 \end{vmatrix} + \begin{vmatrix} qc_1 & b_1 & c_1 \\ qc_2 & b_2 & c_2 \\ qc_3 & b_3 & c_3 \end{vmatrix};$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

and of the four determinants into which this may be resolved there is one which does not vanish, namely

$$\begin{vmatrix} pb_1 & -qc_1 & ra_1 \\ pb_2 & -qc_2 & ra_2 \\ pb_3 & -qc_3 & ra_3 \end{vmatrix}.$$

Example 1. Find the value of $\begin{vmatrix} 29 & 26 & 22 \\ 25 & 31 & 27 \\ 63 & 54 & 46 \end{vmatrix}$.

The given determinant

$$= \begin{vmatrix} 3 & 26 & -4 \\ -6 & 31 & -4 \\ 9 & 54 & -8 \end{vmatrix} = -3\times 4\times \begin{vmatrix} 1 & 26 & 1 \\ -2 & 31 & 1 \\ 3 & 54 & 2 \end{vmatrix} = 12\times -\begin{vmatrix} 1 & 26 & 1 \\ 3 & 5 & 0 \\ 1 & 2 & 0 \end{vmatrix}$$

$$-12\begin{vmatrix} 1 & 1 & 26 \\ 0 & -3 & 5 \\ 0 & 1 & 2 \end{vmatrix} = -12\begin{vmatrix} -3 & 5 \\ 1 & 2 \end{vmatrix} = 132.$$

[*Explanation.* In the first step of the reduction keep the second column unaltered; for the first new column diminish each constituent of the first column by the corresponding constituent of the second; for the third new column diminish each constituent of the third column by the corresponding constituent of the second. In the second step take out the factors 3 and -4. In the third step keep the first row unaltered; for the second new row diminish the constituents of the second by the corresponding ones of the first; for the third new row diminish the constituents of the third by twice the corresponding constituents of the first. The remaining steps will be easily seen.]

Example 2. Shew that $\begin{vmatrix} a-b-c & 2a & 2a \\ 2b & b-c-a & 2b \\ 2c & 2c & c-a-b \end{vmatrix} = (a+b+c)^3$

The given determinant

$$= \begin{vmatrix} a+b+c & a+b+c & a+b+c \\ 2b & b-c-a & 2b \\ 2c & 2c & c-a-b \end{vmatrix} = (a+b+c)\times \begin{vmatrix} 1 & 1 & 1 \\ 2b & b-c-a & 2b \\ 2c & 2c & c-a-b \end{vmatrix}$$

$$= (a+b+c)\times \begin{vmatrix} 1 & 0 & 0 \\ 2b & -b-c-a & 0 \\ 2c & 0 & -c-a-b \end{vmatrix}$$

$$-(a+b+c)\times \begin{vmatrix} -b-c-a & 0 \\ 0 & -c-a-b \end{vmatrix} = (a+b+c)^3.$$

[*Explanation.* In the first new determinant the first row is the sum of the constituents of the three rows of the original determinant, the second and third rows being unaltered. In the third of the new determinants the first column remains unaltered, while the second and third columns are obtained by subtracting the constituents of the first column from those of the second and third respectively. The remaining transformations are sufficiently obvious.]

497. Before shewing how to express the product of two determinants as a determinant, we shall investigate the value of

$$\begin{vmatrix} a_1\alpha_1 + b_1\beta_1 + c_1\gamma_1 & a_1\alpha_2 + b_1\beta_2 + c_1\gamma_2 & a_1\alpha_3 + b_1\beta_3 + c_1\gamma_3 \\ a_2\alpha_1 + b_2\beta_1 + c_2\gamma_1 & a_2\alpha_2 + b_2\beta_2 + c_2\gamma_2 & a_2\alpha_3 + b_2\beta_3 + c_2\gamma_3 \\ a_3\alpha_1 + b_3\beta_1 + c_3\gamma_1 & a_3\alpha_2 + b_3\beta_2 + c_3\gamma_2 & a_3\alpha_3 + b_3\beta_3 + c_3\gamma_3 \end{vmatrix}.$$

From Art. 495, we know that the above determinant can be expressed as the sum of 27 determinants, of which it will be sufficient to give the following specimens:

$$\begin{vmatrix} a_1\alpha_1 & a_1\alpha_2 & a_1\alpha_3 \\ a_2\alpha_1 & a_2\alpha_2 & a_2\alpha_3 \\ a_3\alpha_1 & a_3\alpha_2 & a_3\alpha_3 \end{vmatrix}, \quad \begin{vmatrix} a_1\alpha_1 & b_1\beta_2 & c_1\gamma_3 \\ a_2\alpha_1 & b_2\beta_2 & c_2\gamma_3 \\ a_3\alpha_1 & b_3\beta_2 & c_3\gamma_3 \end{vmatrix}, \quad \begin{vmatrix} a_1\alpha_1 & c_1\gamma_2 & b_1\beta_3 \\ a_2\alpha_1 & c_2\gamma_2 & b_2\beta_3 \\ a_3\alpha_1 & c_3\gamma_2 & b_3\beta_3 \end{vmatrix},$$

these are respectively equal to

$$\alpha_1\alpha_2\alpha_3 \begin{vmatrix} a_1 & a_1 & a_1 \\ a_2 & a_2 & a_2 \\ a_3 & a_3 & a_3 \end{vmatrix}, \quad \alpha_1\beta_2\gamma_3 \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}, \quad \alpha_1\beta_3\gamma_2 \begin{vmatrix} a_1 & c_1 & b_1 \\ a_2 & c_2 & b_2 \\ a_3 & c_3 & b_3 \end{vmatrix};$$

the first of which vanishes; similarly it will be found that 21 out of the 27 determinants vanish. The six determinants that remain are equal to

$$(\alpha_1\beta_2\gamma_3 - \alpha_1\beta_3\gamma_2 + \alpha_2\beta_3\gamma_1 - \alpha_2\beta_1\gamma_3 + \alpha_3\beta_1\gamma_2 - \alpha_3\beta_2\gamma_1) \times \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$$

that is,

$$\begin{vmatrix} \alpha_1 & \beta_1 & \gamma_1 \\ \alpha_2 & \beta_2 & \gamma_2 \\ \alpha_3 & \beta_3 & \gamma_3 \end{vmatrix} \times \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix};$$

hence the given determinant can be expressed as the product of two other determinants.

498. *The product of two determinants is a determinant.*

Consider the two linear equations

$$\left.\begin{aligned} a_1X_1 + b_1X_2 = 0 \\ a_2X_1 + b_2X_2 = 0 \end{aligned}\right\} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1),$$

where
$$\left.\begin{aligned} X_1 &= a_1x_1 + a_2x_2 \\ X_2 &= \beta_1x_1 + \beta_2x_2 \end{aligned}\right\} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots(2).$$

Substituting for X_1 and X_2 in (1), we have

$$\left.\begin{aligned} (a_1a_1 + b_1\beta_1)\,x_1 + (a_1a_2 + b_1\beta_2)\,x_2 &= 0 \\ (a_2a_1 + b_2\beta_1)\,x_1 + (a_2a_2 + b_2\beta_2)\,x_2 &= 0 \end{aligned}\right\} \quad \ldots\ldots\ldots\ldots\ldots(3).$$

In order that equations (3) may simultaneously hold for values of x_1 and x_2 other than zero, we must have

$$\begin{vmatrix} a_1a_1 + b_1\beta_1 & a_1a_2 + b_1\beta_2 \\ a_2a_1 + b_2\beta_1 & a_2a_2 + b_2\beta_2 \end{vmatrix} = 0 \quad \ldots\ldots\ldots\ldots(4).$$

But equations (3) will hold if equations (1) hold, and this will be the case either if

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots(5),$$

or if
$$X_1 = 0 \text{ and } X_2 = 0;$$

which last condition requires that

$$\begin{vmatrix} a_1 & \beta_1 \\ a_2 & \beta_2 \end{vmatrix} = 0 \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots(6).$$

Hence if equations (5) and (6) hold, equation (4) must also hold; and therefore the determinant in (4) must contain as factors the determinants in (5) and (6); and a consideration of the dimensions of the determinants shews that the remaining factor of (4) must be numerical; hence

$$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix} \times \begin{vmatrix} a_1 & \beta_1 \\ a_2 & \beta_2 \end{vmatrix} = \begin{vmatrix} a_1a_1 + b_1\beta_1 & a_1a_2 + b_1\beta_2 \\ a_2a_1 + b_2\beta_1 & a_2a_2 + b_2\beta_2 \end{vmatrix},$$

the numerical factor, by comparing the coefficients of $a_1b_2a_1\beta_2$ on the two sides of the equations, being seen to be unity.

COR. $$\begin{vmatrix} a_1 & b_1 \\ a_2 & b_2 \end{vmatrix}^2 = \begin{vmatrix} a_1^2 + b_1^2 & a_1a_2 + b_1b_2 \\ a_1a_2 + b_1b_2 & a_2^2 + b_2^2 \end{vmatrix}.$$

The above method of proof is perfectly general, and holds whatever be the order of the determinants.

Since the value of a determinant is not altered when we write the rows as columns, and the columns as rows, the product of two determinants may be expressed as a determinant in several ways; but these will all give the same result on expansion.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

12. Without expanding the determinants, prove that

$$\begin{vmatrix} a & b & c \\ x & y & z \\ p & q & r \end{vmatrix} = \begin{vmatrix} y & b & q \\ x & a & p \\ z & c & r \end{vmatrix} = \begin{vmatrix} x & y & z \\ p & q & r \\ a & b & c \end{vmatrix}.$$

13. Solve the equations:

(1) $\begin{vmatrix} a & a & x \\ m & m & m \\ b & x & b \end{vmatrix} = 0.$ (2) $\begin{vmatrix} 15-2x & 11 & 10 \\ 11-3x & 17 & 16 \\ 7-x & 14 & 13 \end{vmatrix} = 0.$

Prove the following identities:

14. $\begin{vmatrix} b+c & c+a & a+b \\ q+r & r+p & p+q \\ y+z & z+x & x+y \end{vmatrix} = 2 \begin{vmatrix} a & b & c \\ p & q & r \\ x & y & z \end{vmatrix}.$

15. $\begin{vmatrix} 1 & a & a^2 \\ 1 & b & b^2 \\ 1 & c & c^2 \end{vmatrix} = (b-c)(c-a)(a-b).$

16. $\begin{vmatrix} 1 & 1 & 1 \\ a & b & c \\ a^3 & b^3 & c^3 \end{vmatrix} = (b-c)(c-a)(a-b)(a+b+c).$

17. $\begin{vmatrix} x & y & z \\ x^2 & y^2 & z^2 \\ yz & zx & xy \end{vmatrix} = (y-z)(z-x)(x-y)(yz+zx+xy).$

18. $\begin{vmatrix} -2a & a+b & a+c \\ b+a & -2b & b+c \\ c+a & c+b & -2c \end{vmatrix} = 4(b+c)(c+a)(a+b).$

19. $\begin{vmatrix} (b+c)^2 & a^2 & a^2 \\ b^2 & (c+a)^2 & b^2 \\ c^2 & c^2 & (a+b)^2 \end{vmatrix} = 2abc(a+b+c)^3$

20. Express as a determinant $\begin{vmatrix} 0 & c & b \\ c & 0 & a \\ b & a & 0 \end{vmatrix}^2$.

21. Find the condition that the equation $lx+my+nz=0$ may be satisfied by the three sets of values (a_1, b_1, c_1) (a_2, b_2, c_2) (a_3, b_3, c_3); and shew that it is the same as the condition that the three equations

$$a_1x+b_1y+c_1z=0, \quad a_2x+b_2y+c_2z=0, \quad a_3x+b_3y+c_3z=0$$

may be simultaneously satisfied by l, m, n.

22. Find the value of

$$\begin{vmatrix} a^2+\lambda^2 & ab+c\lambda & ca-b\lambda \\ ab-c\lambda & b^2+\lambda^2 & bc+a\lambda \\ ca+b\lambda & bc-a\lambda & c^2+\lambda^2 \end{vmatrix} \times \begin{vmatrix} \lambda & c & -b \\ -c & \lambda & a \\ b & -a & \lambda \end{vmatrix}.$$

23. Prove that $\begin{vmatrix} a+ib & c+id \\ -c+id & a-ib \end{vmatrix} \times \begin{vmatrix} a-i\beta & \gamma-i\delta \\ -\gamma-i\delta & a+i\beta \end{vmatrix}$,

where $i=\sqrt{-1}$, can be written in the form

$$\begin{vmatrix} A-iB & C-iD \\ -C-iD & A+iB \end{vmatrix};$$

hence deduce the following theorem, due to Euler:

The product of two sums each of four squares can be expressed as the sum of four squares.

Prove the following identities:

24. $$\begin{vmatrix} 1 & bc+ad & b^2c^2+a^2d^2 \\ 1 & ca+bd & c^2a^2+b^2d^2 \\ 1 & ab+cd & a^2b^2+c^2d^2 \end{vmatrix}$$

$$= -(b-c)(c-a)(a-b)(a-d)(b-d)(c-d).$$

25. $$\begin{vmatrix} bc-a^2 & ca-b^2 & ab-c^2 \\ -bc+ca+ab & bc-ca+ab & bc+ca-ab \\ (a+b)(a+c) & (b+c)(b+a) & (c+a)(c+b) \end{vmatrix}$$

$$= 3(b-c)(c-a)(a-b)(a+b+c)(bc+ca+ab).$$

26. $$\begin{vmatrix} (a-x)^2 & (a-y)^2 & (a-z)^2 \\ (b-x)^2 & (b-y)^2 & (b-z)^2 \\ (c-x)^2 & (c-y)^2 & (c-z)^2 \end{vmatrix}$$

$$= 2(b-c)(c-a)(a-b)(y-z)(z-x)(x-y).$$

27. Find in the form of a determinant the condition that the expression

$$ua^2+v\beta^2+w\gamma^2+2u'\beta\gamma+2v'\gamma a+2w'a\beta$$

may be the product of two factors of the first degree in a, β, γ

28. Solve the equation

$$\begin{vmatrix} u+a^2x & w'+abx & v'+acx \\ w'+abx & v+b^2x & u'+bcx \\ v'+acx & u'+bcx & w+c^2x \end{vmatrix} = 0,$$

expressing the result by means of determinants.

499. The properties of determinants may be usefully employed in solving simultaneous linear equations.

Let the equations be

$$a_1x+b_1y+c_1z+d_1=0,$$
$$a_2x+b_2y+c_2z+d_2=0,$$
$$a_3x+b_3y+c_3z+d_3=0;$$

multiply them by A_1, $-A_2$, A_3 respectively and add the results, A_1, A_2, A_3 being minors of a_1, a_2, a_3 in the determinant

$$D=\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$$

The coefficients of y and z vanish in virtue of the relations proved in Art. 493, and we obtain

$$(a_1A_1-a_2A_2+a_3A_3)x+(d_1A_1-d_2A_2+d_3A_3)=0.$$

Similarly we may shew that

$$(b_1B_1-b_2B_2+b_3B_3)y+(d_1B_1-d_2B_2+d_3B_3)=0,$$

and

$$(c_1C_1-c_2C_2+c_3C_3)z+(d_1C_1-d_2C_2+d_3C_3)=0.$$

Now $$a_1A_1-a_2A_2+a_3A_3=-(b_1B_1-b_2B_2+b_3B_3)$$
$$=c_1C_1-c_2C_2+c_3C_3=D;$$

hence the solution may be written

$$\frac{x}{\begin{vmatrix} d_1 & b_1 & c_1 \\ d_2 & b_2 & c_2 \\ d_3 & b_3 & c_3 \end{vmatrix}}=\frac{-y}{\begin{vmatrix} d_1 & a_1 & c_1 \\ d_2 & a_2 & c_2 \\ d_3 & a_3 & c_3 \end{vmatrix}}=\frac{z}{\begin{vmatrix} d_1 & a_1 & b_1 \\ d_2 & a_2 & b_2 \\ d_3 & a_3 & b_3 \end{vmatrix}}=\frac{-1}{\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}}$$

or more symmetrically

$$\frac{x}{\begin{vmatrix} b_1 & c_1 & d_1 \\ b_2 & c_2 & d_2 \\ b_3 & c_3 & d_3 \end{vmatrix}}=\frac{-y}{\begin{vmatrix} a_1 & c_1 & d_1 \\ a_2 & c_2 & d_2 \\ a_3 & c_3 & d_3 \end{vmatrix}}=\frac{z}{\begin{vmatrix} a_1 & b_1 & d_1 \\ a_2 & b_2 & d_2 \\ a_3 & b_3 & d_3 \end{vmatrix}}=\frac{-1}{\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}}.$$

500. Suppose we have the system of four homogeneous linear equations :

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

The left-hand member of this equation is a determinant which consists of n rows and n columns, and is called a determinant of the n^{th} order.

The discussion of this more general form of determinant is beyond the scope of the present work; it will be sufficient here to remark that the properties which have been established in the case of determinants of the second and third orders are quite general, and are capable of being extended to determinants of any order.

For example, the above determinant of the n^{th} order is equal to

$$a_1A_1 - b_1B_1 + c_1C_1 - d_1D_1 + \ldots + (-1)^{n-1} k_1K_1,$$

or
$$a_1A_1 - a_2A_2 + a_3A_3 - a_4A_4 + \ldots + (-1)^{n-1} a_nA_n,$$

according as we develop it from the first row or the first column. Here the capital letters stand for the minors of the constituents denoted by the corresponding small letters, and are themselves determinants of the $(n-1)^{\text{th}}$ order. Each of these may be expressed as the sum of a number of determinants of the $(n-2)^{\text{th}}$ order; and so on; and thus the expanded form of the determinant may be obtained.

Although we may always develop a determinant by means of the process described above, it is not always the simplest method, especially when our object is not so much to find the value of the whole determinant, as to find the signs of its several elements.

502. The expanded form of the determinant

$$\begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}$$

$$= a_1b_2c_3 - a_1b_3c_2 + a_2b_3c_1 - a_2b_1c_3 + a_3b_1c_2 - a_3b_2c_1;$$

and it appears that each element is the product of three factors, one taken from each row, and one from each column; also the signs of half the terms are + and of the other half −. The signs of the several elements may be obtained as follows. The first element $a_1b_2c_3$, in which the suffixes follow the arithmetical order, is positive; we shall call this the leading element; every other element may be obtained from it by suitably interchanging the suffixes. The sign + or − is to be prefixed to any element ac-

cording as it can be deduced from the leading element by an even or odd number of permutations of two suffixes; for instance, the element $a_3b_2c_1$ is obtained by interchanging the suffixes 1 and 3, therefore its sign is negative; the element $a_3b_1c_2$ is obtained by first interchanging the suffixes 1 and 3, and then the suffixes 1 and 2, hence its sign is positive.

503. The determinant whose leading element is $a_1b_2c_3d_4$ may thus be expressed by the notation

$$\Sigma \pm a_1b_2c_3d_4 . \quad ,$$

the $\Sigma \pm$ placed before the leading element indicating the aggregate of all the elements which can be obtained from it by suitable interchanges of suffixes and adjustment of signs.

Sometimes the determinant is still more simply expressed by enclosing the leading element within brackets; thus $(a_1b_2c_3d_4 \ldots)$ is used as an abbreviation of $\Sigma \pm a_1b_2c_3d_4$.

Example. In the determinant $(a_1b_2c_3d_4e_5)$ what sign is to be prefixed to the element $a_4b_3c_1d_5e_2$?

From the leading element by permuting the suffixes of a and d we get $a_4b_2c_3d_1e_5$; from this by permuting the suffixes of b and c we have $a_4b_3c_2d_1e_5$; by permuting the suffixes of c and d we have $a_4b_3c_1d_2e_5$; finally by permuting the suffixes of d and e we obtain the required element $a_4b_3c_1d_5e_2$; and since we have made four permutations the sign of the element is positive.

504. If in Art. 501, each of the constituents $b_1, c_1, \ldots k_1$ is equal to zero the determinant reduces to a_1A_1; in other words it is equal to the product of a_1 and a determinant of the $(n-1)^{\text{th}}$ order, and we easily infer the following general theorem.

If each of the constituents of the first row or column of a determinant is zero except the first, and if this constituent is equal to m, *the determinant is equal to* m *times that determinant of lower order which is obtained by omitting the first column and first row.*

Also since by suitable interchange of rows and columns any constituent can be brought into the first place, it follows that if *any* row or column has all its constituents except one equal to zero, the determinant can immediately be expressed as a determinant of lower order.

This is sometimes useful in the reduction and simplification of determinants.

Example. Find the value of

$$\begin{vmatrix} 30 & 11 & 20 & 38 \\ 6 & 3 & 0 & 9 \\ 11 & -2 & 36 & 3 \\ 19 & 6 & 17 & 22 \end{vmatrix}.$$

Diminish each constituent of the first column by twice the corresponding constituent in the second column, and each constituent of the fourth column by three times the corresponding constituent in the second column, and we obtain

$$\begin{vmatrix} 8 & 11 & 20 & 5 \\ 0 & 3 & 0 & 0 \\ 15 & -2 & 36 & 9 \\ 7 & 16 & 17 & 4 \end{vmatrix},$$

and since the second row has three zero constituents this determinant

$$=3\begin{vmatrix} 8 & 20 & 5 \\ 15 & 36 & 9 \\ 7 & 17 & 4 \end{vmatrix} =3\begin{vmatrix} 8 & 20 & 5 \\ 8 & 19 & 5 \\ 7 & 17 & 4 \end{vmatrix} =3\begin{vmatrix} 0 & 1 & 0 \\ 8 & 19 & 5 \\ 7 & 17 & 4 \end{vmatrix} =-3\begin{vmatrix} 8 & 5 \\ 7 & 4 \end{vmatrix} =9.$$

505. The following examples shew artifices which are occasionally useful.

Example 1. Prove that

$$\begin{vmatrix} a & b & c & d \\ b & a & d & c \\ c & d & a & b \\ d & c & b & a \end{vmatrix} =(a+b+c+d)(a-b+c-d)(a-b-c+d)(a+b-c-d).$$

By adding together all the rows we see that $a+b+c+d$ is a factor of the determinant; by adding together the first and third rows and subtracting from the result the sum of the second and fourth rows we see that $a-b+c-d$ is also a factor; similarly it can be shewn that $a-b-c+d$ and $a+b-c-d$ are factors; the remaining factor is numerical, and, from a comparison of the terms involving a^4 on each side, is easily seen to be unity; hence we have the required result.

Example 2. Prove that

$$\begin{vmatrix} 1 & 1 & 1 & 1 \\ a & b & c & d \\ a^2 & b^2 & c^2 & d^2 \\ a^3 & b^3 & c^3 & d^3 \end{vmatrix} =(a-b)(a-c)(a-d)(b-c)(b-d)(c-d).$$

The given determinant vanishes when $b=a$, for then the first and second columns are identical; hence $a-b$ is a factor of the determinant [Art. 514]. Similarly each of the expressions $a-c$, $a-d$, $b-c$, $b-d$, $c-d$ is a factor of the determinant; the determinant being of six dimensions, the remaining factor must be numerical; and, from a comparison of the terms involving bc^2d^3 on each side, it is easily seen to be unity; hence we obtain the required result.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Solve the equations:

12.
$$x+y+z=1,$$
$$ax+by+cz=k,$$
$$a^2x+b^2y+c^2z=k^2.$$

13.
$$ax+by+cz=k,$$
$$a^2x+b^2y+c^2z=k^2,$$
$$a^3x+b^3y+c^3z=k^3$$

14.
$$x+y+z+u=1,$$
$$ax+by+cz+du=k,$$
$$a^2x+b^2y+c^2z+d^2u=k^2,$$
$$a^3x+b^3y+c^3z+d^3u=k^3$$

15. Prove that

$$\begin{vmatrix} b+c-a-d & bc-ad & bc(a+d)-ad(b+c) \\ c+a-b-d & ca-bd & ca(b+d)-bd(c+a) \\ a+b-c-d & ab-cd & ab(c+d)-cd(a+b) \end{vmatrix}$$
$$= -2(b-c)(c-a)(a-b)(a-d)(b-d)(c-d).$$

16. Prove that

$$\begin{vmatrix} a^2 & a^2-(b-c)^2 & bc \\ b^2 & b^2-(c-a)^2 & ca \\ c^2 & c^2-(a-b)^2 & ab \end{vmatrix}$$
$$=-(b-c)(c-a)(a-b)(a+b+c)(a^2+b^2+c^2).$$

17. Shew that

$$\begin{vmatrix} a & b & c & d & e & f \\ f & a & b & c & d & e \\ e & f & a & b & c & d \\ d & e & f & a & b & c \\ c & d & e & f & a & b \\ b & c & d & e & f & a \end{vmatrix} = \begin{vmatrix} A & B & C \\ C & A & B \\ B & C & A \end{vmatrix},$$

where
$$A=a^2-d^2+2ce-2bf,$$
$$B=e^2-b^2+2ac-2df,$$
$$C=c^2-f^2+2ae-2bd.$$

18. If a determinant is of the n^{th} order, and if the constituents of its first, second, third, ...n^{th} rows are the first n figurate numbers of the first, second, third, ...n^{th} orders, shew that its value is unity..

CHAPTER XXXIV.

MISCELLANEOUS THEOREMS AND EXAMPLES.

506. We shall begin this chapter with some remarks on the permanence of algebraical form, briefly reviewing the fundamental laws which have been established in the course of the work.

507. In the exposition of algebraical principles we proceed analytically: at the outset we do not lay down new names and new ideas, but we begin from our knowledge of abstract Arithmetic; we prove certain laws of operation which are capable of verification in every particular case, and the *general* theory of these operations constitutes the science of Algebra.

Hence it is usual to speak of *Arithmetical Algebra* and *Symbolical Algebra*, and to make a distinction between them. In the former we define our symbols in a sense arithmetically intelligible, and thence deduce fundamental laws of operation; in the latter we assume the laws of Arithmetical Algebra to be true in all cases, whatever the nature of the symbols may be, and so find out what meaning must be attached to the symbols in order that they may obey these laws. Thus gradually, as we transcend the limits of ordinary Arithmetic, new results spring up, new language has to be employed, and interpretations given to symbols which were not contemplated in the original definitions. At the same time, from the way in which the general laws of Algebra are established, we are assured of their permanence and universality, even when they are applied to quantities not arithmetically intelligible.

508. Confining our attention to positive integral values of the symbols, the following laws are easily established from *a priori* arithmetical definitions.

I. **The Law of Commutation,** which we enunciate as follows:

(i) *Additions and subtractions may be made in any order.*

Thus $$a+b-c=a-c+b=b-c+a.$$

(ii) *Multiplications and divisions may be made in any order.*

Thus $$a\times b=b\times a;$$

$$a\times b\times c=b\times c\times a=a\times c\times b;\text{ and so on.}$$

$$ab\div c=a\times b\div c=(a\div c)\times b=(b\div c)\times a.$$

II. **The Law of Distribution,** which we enunciate as follows:

Multiplications and divisions may be distributed over additions and subtractions.

Thus $$(a-b+c)\,m=am-bm+cm,$$

$$(a-b)(c-d)=ac-ad-bc+bd.$$

[See *Elementary Algebra*, Arts. 33, 35.]

And since division is the reverse of multiplication, the distributive law for division requires no separate discussion.

III. **The Laws of Indices.**

(i) $$a^m\times a^n=a^{m+n},$$

$$a^m\div a^n=a^{m-n}$$

(ii) $$(a^m)^n=a^{mn}$$

[See *Elementary Algebra*, Art. 233 to 235.]

These laws are *laid down* as fundamental to our subject, having been proved on the supposition that the symbols employed are positive and integral, and that they are restricted in such a way that the operations above indicated are arithmetically intelligible. If these conditions do not hold, by the principles of Symbolical Algebra we assume the laws of Arithmetical Algebra to be true in every case and accept the interpretation to which this assumption leads us. By this course we are assured that the laws of Algebraical operation are self-consistent, and that they include in their generality the particular cases of ordinary Arithmetic.

509. From the law of commutation we deduce the rules for the removal and insertion of brackets [*Elementary Algebra*, Arts. 21, 22]; and by the aid of these rules we establish the law

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Also since every rational function involves no operations but those above mentioned, it follows that a rational function of a complex number is in general a complex number.

Expressions of the form a^{x+iy}, $\log(x+iy)$ cannot be fully treated without Trigonometry; but by the aid of De Moivre's theorem, it is easy to shew that such functions can be reduced to complex numbers of the form $A+iB$.

The expression e^{x+iy} is of course included in the more general form a^{x+iy}, but another mode of treating it is worthy of attention.

We have seen in Art. 220 that

$$e^x = Lim\left(1+\frac{x}{n}\right)^n, \text{ when } n \text{ is infinite,}$$

x being any real quantity; the quantity e^{x+iy} may be similarly defined by means of the equation

$$e^{x+iy} = Lim\left(1+\frac{x+iy}{n}\right)^n, \text{ when } n \text{ is infinite,}$$

x and y being any real quantities.

The development of the theory of complex numbers will be found fully discussed in Chapters x. and xi. of Schlömilch's *Handbuch der algebraischen Analysis.*

513. We shall now give some theorems and examples illustrating methods which will often be found useful in proving identities, and in the Theory of Equations.

514. *To find the remainder when any* rational integral *function of* x *is divided by* x – a.

Let $f(x)$ denote any rational integral function of x; divide $f(x)$ by $x-a$ until a remainder is obtained which does not involve x; let Q be the quotient, and R the remainder; then

$$f(x) = Q(x-a)+R.$$

Since R does not involve x it will remain unaltered whatever value we give to x; put $x=a$, then

$$f(a) = Q\times 0 + R;$$

now Q is finite for finite values of x, hence

$$R = f(a).$$

COR. If $f(x)$ is exactly divisible by $x-a$, then $R=0$, that is $f(a)=0$; hence *if a rational integral function of* x *vanishes when* x = a, *it is divisible by* x − a.

515. The proposition contained in the preceding article is so useful that we give another proof of it which has the advantage of exhibiting the form of the quotient.

Suppose that the function is of n dimensions, and let it be denoted by

$$p_0x^n + p_1x^{n-1} + p_2x^{n-2} + p_3x^{n-3} + \ldots + p_n,$$

then the quotient will be of $n-1$ dimensions; denote it by

$$q_0x^{n-1} + q_1x^{n-2} + q_2x^{n-3} + \ldots + q_{n-1};$$

let R be the remainder not containing x; then

$$p_0x^n + p_1x^{n-1} + p_2x^{n-2} + p_3x^{n-3} + \ldots + p_n = (x-a)(q_0x^{n-1} + q_1x^{n-2} + q_2x^{n-3} + \ldots + q_{n-1}) + R.$$

Multiplying out and equating the coefficients of like powers of x, we have

$$q_0 = p_0;$$
$$q_1 - aq_0 = p_1, \text{ or } q_1 = aq_0 + p_1;$$
$$q_2 - aq_1 = p_2, \text{ or } q_2 = aq_1 + p_2;$$
$$q_3 - aq_2 = p_3, \text{ or } q_3 = aq_2 + p_3;$$
$$\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots$$
$$R - aq_{n-1} = p_n, \text{ or } R = aq_{n-1} + p_n;$$

thus each successive coefficient in the quotient is formed by multiplying by a the coefficient last formed, and adding the next coefficient in the dividend. The process of finding the successive terms of the quotient and the remainder may be arranged thus:

p_0	p_1	p_2	p_3	p_{n-1}	p_n
	aq_0	aq_1	aq_2	aq_{n-2}	aq_{n-1}
q_0	q_1	q_2	q_3	q_{n-1}	R

Thus $R = aq_{n-1} + p_n = a(aq_{n-2} + p_{n-1}) + p_n = \ldots$
$$= p_0a^n + p_1a^{n-1} + p_2a^{n-2} + \ldots + p_n.$$

If the divisor is $x+a$ the same method can be used, only in this case the multiplier is $-a$.

Example. Find the quotient and remainder when $3x^7 - x^6 + 31x^4 + 21x + 5$ is divided by $x + 2$.

Here the multiplier is -2, and we have

$$\begin{array}{rrrrrrrr} 3 & -1 & 0 & 31 & 0 & 0 & 21 & 5 \\ & -6 & 14 & -28 & -6 & 12 & -24 & 6 \\ \hline 3 & -7 & 14 & 3 & -6 & 12 & -3 & 11 \end{array}$$

Thus the quotient is $3x^6 - 7x^5 + 14x^4 + 3x^3 - 6x^2 + 12x - 3$, and the remainder is 11.

516. In the preceding example the work has been abridged by writing down only the coefficients of the several terms, zero coefficients being used to represent terms corresponding to powers of x which are absent. This method of *Detached Coefficients* may frequently be used to save labour in elementary algebraical processes, particularly when the functions we are dealing with are rational and integral. The following is another illustration.

Example. Divide $3x^5 - 8x^4 - 5x^3 + 26x^2 - 33x + 26$ by $x^3 - 2x^2 - 4x + 8$.

$$\begin{array}{l} 1+2+4-8)\,3-8-5+26-33+26\,(3-2+3 \\ \qquad\qquad 3+6+12-24 \\ \qquad\qquad \hline \qquad\quad -2+7+2-33 \\ \qquad\quad -2-4-8+16 \\ \qquad\qquad \hline \qquad\qquad\quad 3-6-17+26 \\ \qquad\qquad\quad 3+6+12-24 \\ \qquad\qquad\quad \hline \qquad\qquad\qquad -5+2 \end{array}$$

Thus the quotient is $3x^2 - 2x + 3$ and the remainder is $-5x + 2$.

It should be noticed that in writing down the divisor, the sign of every term *except the first* has been changed; this enables us *to replace the process of subtraction by that of addition* at each successive stage of the work.

517. The work may be still further abridged by the following arrangement, which is known as Horner's *Method of Synthetic Division.*

$$\begin{array}{r|l} 1 & 3-8-5+26-33+26 \\ 2 & \quad 6+12-24 \\ 4 & \qquad 4-8+16 \\ -8 & \qquad\quad 6+12-24 \\ \hline & 3-2+3+0-5+2 \end{array}$$

[*Explanation.* The column of figures to the left of the vertical line consists of the coefficients of the divisor, the sign of each after the first being changed; the second horizontal line is obtained by multiplying 2, 4, -8 by 3, the first term of the quotient. We then add the terms in the second column to the right of the vertical line; this gives -2, which is the coefficient of the second term of the quotient. With the coefficient thus obtained

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Put $z=0$, then $A=3$, being the coefficient of x^2y in the expansion of $(x+y)^3$

Put $x=y=z=1$, and we get $27=3+(3\times 6)+B$; whence $B=6$.

Thus $(x+y+z)^3$

$$-x^3+y^3+z^3+3x^2y+3xy^2+3y^2z+3yz^2+3z^2x+3zx^2+6xyz.$$

520. A function is said to be *alternating* with respect to its variables, when its sign but not its value is altered by the interchange of any pair of them. Thus $x-y$ and

$$a^2(b-c)+b^2(c-a)+c^2(a-b)$$

are alternating functions.

It is evident that there can be no linear alternating function involving more than two variables, and also that the product of a symmetrical function and an alternating function must be an alternating function.

521. Symmetrical and alternating functions may be concisely denoted by writing down one of the terms and prefixing the symbol Σ; thus Σa stands for the sum of all the terms of which a is the type, Σab stands for the sum of all the terms of which ab is the type; and so on. For instance, if the function involves four letters a, b, c, d,

$$\Sigma a=a+b+c+d;$$

$$\Sigma ab=ab+ac+ad+bc+bd+cd;$$

and so on.

Similarly if the function involves three letters a, b, c,

$$\Sigma a^2(b-c)=a^2(b-c)+b^2(c-a)+c^2(a-b);$$

$$\Sigma a^2bc=a^2bc+b^2ca+c_2ab;$$

and so on.

It should be noticed that when there are three letters involved Σa^2b does not consist of three terms, but of six: thus

$$\Sigma a^2b=a^2b+a^2c+b^2c+b^2a+c^2a+c^2b.$$

The symbol Σ may also be used to imply summation with regard to two or more sets of letters; thus

$$\Sigma yz(b-c)=yz(b-c)+zx(c-a)+xy(a-b).$$

522. The above notation enables us to express in an abridged form the products and powers of symmetrical expressions: thus

$$(a+b+c)^3 = \Sigma a^3 + 3\Sigma a^2 b + 6abc\,;$$

$$(a+b+c+d)^3 = \Sigma a^3 + 3\Sigma a^2 b + 6\Sigma abc;$$

$$(a+b+c)^4 = \Sigma a^4 + 4\Sigma a^3 b + 6\Sigma a^2 b^2 + 12\Sigma a^2 bc;$$

$$\Sigma a \times \Sigma a^2 = \Sigma a^3 + \Sigma a^2 b.$$

Example 1. Prove that

$$(a+b)^5 - a^5 - b^5 = 5ab\,(a+b)\,(a^2+ab+b^2).$$

Denote the expression on the left by E; then E is a function of a which vanishes when $a=0$; hence a is a factor of E; similarly b is a factor of E. Again E vanishes when $a=-b$, that is $a+b$ is a factor of E; and therefore E contains $ab\,(a+b)$ as a factor. The remaining factor must be of two dimensions, and, since it is symmetrical with respect to a and b, it must be of the form $Aa^2+Bab+Ab^2$; thus

$$(a+b)^5 - a^5 - b^5 = ab\,(a+b)\,(Aa^2+Bab+Ab^2),$$

where A and B are independent of a and b.

Putting $a=1$, $b=1$, we have $15=2A+B$;

putting $a=2$, $b=-1$, we have $15=5A-2B$;

whence $A=5$, $B=5$; and thus the required result at once follows.

Example 2. Find the factors of

$$(b^3+c^3)\,(b-c)+(c^3+a^3)\,(c-a)+(a^3+b^3)\,(a-b).$$

Denote the expression by E; then E is a function of a which vanishes when $a=b$, and therefore contains $a-b$ as a factor [Art. 514]. Similarly it contains the factors $b-c$ and $c-a$; thus E contains $(b-c)\,(c-a)\,(a-b)$ as a factor.

Also since E is of the fourth degree the remaining factor must be of the first degree; and since it is a symmetrical function of a, b, c, it must be of the form $M\,(a+b+c)$. [Art. 518];

$$\therefore\ E = M\,(b-c)\,(c-a)\,(a-b)\,(a+b+c).$$

To obtain M we may give to a, b, c any values that we find most convenient; thus by putting $a=0$, $b=1$, $c=2$, we find $M=1$, and we have the required result.

Example 3. Shew that

$$(x+y+z)^5 - x^5 - y^5 - z^5 = 5\,(y+z)\,(z+x)\,(x+y)\,(x^2+y^2+z^2+yz+zx+xy).$$

Denote the expression on the left by E; then E vanishes when $y=-z$, and therefore $y+z$ is a factor of E; similarly $z+x$ and $x+y$ are factors; therefore E contains $(y+z)\,(z+x)\,(x+y)$ as a factor. Also since E is of the

fifth degree the remaining factor is of the second degree, and, since it is symmetrical in x, y, z, it must be of the form

$$A(x^2+y^2+z^2)+B(yz+zx+xy).$$

Put $x=y=z=1$; thus $10=A+B$;

put $x=2,\ y=1,\ z=0$; thus $35=5A+2B$;

whence $A=B=5$,

and we have the required result.

523. We collect here for reference a list of identities which are useful in the transformation of algebraical expressions; many of these have occurred in Chap. XXIX. of the *Elementary Algebra*.

$$\Sigma bc(b-c)=-(b-c)(c-a)(a-b).$$

$$\Sigma a^2(b-c)=-(b-c)(c-a)(a-b).$$

$$\Sigma a(b^2-c^2)=(b-c)(c-a)(a-b).$$

$$\Sigma a^3(b-c)=-(b-c)(c-a)(a-b)(a+b+c).$$

$$a^3+b^3+c^3-3abc=(a+b+c)(a^2+b^2+c^2-bc-ca-ab).$$

This identity may be given in another form,

$$a^3+b^3+c^3-3abc=\frac{1}{2}(a+b+c)\{(b-c)^2+(c-a)^2+(a-b)^2\}.$$

$$(b-c)^3+(c-a)^3+(a-b)^3=3(b-c)(c-a)(a-b).$$

$$(a+b+c)^3-a^3-b^3-c^3=3(b+c)(c+a)(a+b).$$

$$\Sigma bc(b+c)+2abc=(b+c)(c+a)(a+b).$$

$$\Sigma a^2(b+c)+2abc=(b+c)(c+a)(a+b).$$

$$(a+b+c)(bc+ca+ab)-abc=(b+c)(c+a)(a+b).$$

$$2b^2c^2+2c^2a^2+2a^2b^2-a^4-b^4-c^4$$
$$-(a+b+c)(b+c-a)(c+a-b)(a+b-c).$$

EXAMPLES. XXXIV. a.

1. Find the remainder when $3x^5+11x^4+90x^2-19x+53$ is divided by $x+5$.

2. Find the equation connecting a and b in order that

$$2x^4-7x^3+ax+b$$

may be divisible by $x-3$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

25. $(b+c)^3+(c+a)^3+(a+b)^3-3(b+c)(c+a)(a+b)$
$=2(a^3+b^3+c^3-3abc).$

26. If $x=b+c-a$, $y=c+a-b$, $z=a+b-c$, shew that
$$x^3+y^3+z^3-3xyz=4(a^3+b^3+c^3-3abc).$$

27. Prove that the value of $a^3+b^3+c^3-3abc$ is unaltered if we substitute $s-a$, $s-b$, $s-c$ for a, b, c respectively, where
$$3s=2(a+b+c).$$

Find the value of

28. $\dfrac{a}{(a-b)(a-c)(x-a)}+\dfrac{b}{(b-c)(b-a)(x-b)}+\dfrac{c}{(c-a)(c-b)(x-c)}$.

29. $\dfrac{a^2-b^2-c^2}{(a-b)(a-c)}+\dfrac{b^2-c^2-a^2}{(b-c)(b-a)}+\dfrac{c^2-a^2-b^2}{(c-a)(c-b)}$.

30. $\dfrac{(a+p)(a+q)}{(a-b)(a-c)(a+x)}+\dfrac{(b+p)(b+q)}{(b-c)(b-a)(b+x)}+\dfrac{(c+p)(c+q)}{(c-a)(c-b)(c+x)}$.

31. $\Sigma\dfrac{bcd}{(a-b)(a-c)(a-d)}$.

32. $\Sigma\dfrac{a^4}{(a-b)(a-c)(a-d)}$.

33. If $x+y+z=s$, and $xyz=p^2$, shew that
$$\left(\frac{p}{ys}-\frac{y}{p}\right)\left(\frac{p}{zs}-\frac{z}{p}\right)+\left(\frac{p}{zs}-\frac{z}{p}\right)\left(\frac{p}{xs}-\frac{x}{p}\right)+\left(\frac{p}{xs}-\frac{x}{p}\right)\left(\frac{p}{ys}-\frac{y}{p}\right)=\frac{4}{s}.$$

Miscellaneous Identities.

524. Many identities can be readily established by making use of the properties of the cube roots of unity; as usual these will be denoted by 1, ω, ω^2.

Example. Shew that
$$(x+y)^7-x^7-y^7=7xy(x+y)(x^2+xy+y^2)^2.$$

The expression, E, on the left vanishes when $x=0$, $y=0$, $x+y=0$; hence it must contain $xy(x+y)$ as a factor.

Putting $x=\omega y$, we have
$$E=\{(1+\omega)^7-\omega^7-1\}y^7=\{(-\omega^2)^7-\omega^7-1\}y^7$$
$$=(-\omega^2-\omega-1)y^7=0;$$

hence E contains $x-\omega y$ as a factor; and similarly we may shew that it contains $x-\omega^2 y$ as a factor; that is, E is divisible by
$$(x-\omega y)(x-\omega^2 y), \text{ or } x^2+xy+y^2.$$

Further, E being of seven, and $xy(x+y)(x^2+xy+y^2)$ of five dimensions, the remaining factor must be of the form $A(x^2+y^2)+Bxy$; thus

$$(x+y)^7-x^7-y^7=xy(x+y)(x^2+xy+y^2)(Ax^2+Bxy+Ay^2).$$

Putting $x=1$, $y=1$, we have $21=2A+B$;

putting $x=2$, $y=-1$, we have $21=5A-2B$;

whence $A=7$, $B=7$;

$$\therefore\ (x+y)^7-x^7-y^7=7xy(x+y)(x^2+xy+y^2)^2.$$

525. We know from elementary Algebra that

$$a^3+b^3+c^3-3abc=(a+b+c)(a^2+b^2+c^2-bc-ca-ab);$$

also we have seen in Ex. 3, Art. 110, that

$$a^2+b^2+c^2-bc-ca-ab=(a+\omega b+\omega^2 c)(a+\omega^2 b+\omega c);$$

hence $a^3+b^3+c^3-3abc$ can be resolved into three linear factors; thus

$$a^3+b^3+c^3-3abc=(a+b+c)(a+\omega b+\omega^2 c)(a+\omega^2 b+\omega c).$$

Example. Shew that the product of

$$a^3+b^3+c^3-3abc \text{ and } x^3+y^3+z^3-3xyz$$

can be put into the form $A^3+B^3+C^3-3ABC$.

The product $=(a+b+c)(a+\omega b+\omega^2 c)(a+\omega^2 b+\omega c)$

$$\times(x+y+z)(x+\omega y+\omega^2 z)(x+\omega^2 y+\omega z).$$

By taking these six factors in the pairs $(a+b+c)(x+y+z)$;

$(a+\omega b+\omega^2 c)(x+\omega^2 y+\omega z)$; and $(a+\omega^2 b+\omega c)(x+\omega y+\omega^2 z)$,

we obtain the three partial products

$$A+B+C,\ A+\omega B+\omega^2 C,\ A+\omega^2 B+\omega C,$$

where $A=ax+by+cz$, $B=bx+cy+az$, $C=cx+ay+bz$.

Thus the product $=(A+B+C)(A+\omega B+\omega^2 C)(A+\omega^2 B+\omega C)$

$$=A^3+B^3+C^3-3ABC.$$

526. In order to find the values of expressions involving a, b, c when these quantities are connected by the equation $a+b+c=0$, we might employ the substitution

$$a=h+k,\quad b=\omega h+\omega^2 k,\quad c=\omega^2 h+\omega k.$$

If however the expressions involve a, b, c symmetrically the method exhibited in the following example is preferable.

Example. If $a+b+c=0$, shew that

$$6\,(a^5+b^5+c^5)=5\,(a^3+b^3+c^3)\,(a^2+b^2+c^2).$$

We have identically

$$(1+ax)\,(1+bx)\,(1+cx)=1+px+qx^2+rx^3,$$

where $$p=a+b+c,\ q=bc+ca+ab,\ r=abc.$$

Hence, using the condition given,

$$(1+ax)\,(1+bx)\,(1+cx)=1+qx^2+rx^3.$$

Taking logarithms and equating the coefficients of x^n, we have

$$\frac{(-1)^{n-1}}{n}(a^n+b^n+c^n)=\text{coefficient of } x^n \text{ in the expansion of } \log(1+qx^2+rx^3)$$

$$-\text{coefficient of } x^n \text{ in } \quad (qx^2+rx^3)-\frac{1}{2}(qx^2+rx^3)^2+\frac{1}{3}(qx^2+rx^3)^3-\ldots$$

By putting $n=2,\ 3,\ 5$ we obtain

$$-\frac{a^2+b^2+c^2}{2}=q,\ \frac{a^3+b^3+c^3}{3}=r,\ \frac{a^5+b^5+c^5}{5}=-qr;$$

whence $$\frac{a^5+b^5+c^5}{5}=\frac{a^3+b^3+c^3}{3}\cdot\frac{a^2+b^2+c^2}{2},$$

and the required result at once follows.

If $a=\beta-\gamma,\ b=\gamma-\alpha,\ c=\alpha-\beta$, the given condition is satisfied; hence we have identically for all values of α, β, γ

$$6\,\{(\beta-\gamma)^5+(\gamma-\alpha)^5+(\alpha-\beta)^5\}$$
$$=5\,\{(\beta-\gamma)^3+(\gamma-\alpha)^3+(\alpha-\beta)^3\}\,\{(\beta-\gamma)^2+(\gamma-\alpha)^2+(\alpha-\beta)^2\}$$

that is,

$$(\beta-\gamma)^5+(\gamma-\alpha)^5+(\alpha-\beta)^5=5\,(\beta-\gamma)\,(\gamma-\alpha)\,(\alpha-\beta)\,(\alpha^2+\beta^2+\gamma^2-\beta\gamma-\gamma\alpha-\alpha\beta);$$

compare Ex. 3, Art. 522.

EXAMPLES. XXXIV. b.

1. If $(a+b+c)^3=a^3+b^3+c^3$, shew that when n is a positive integer $(a+b+c)^{2n+1}=a^{2n+1}+b^{2n+1}+c^{2n+1}$

2. Shew that

$$(a+\omega b+\omega^2 c)^3+(a+\omega^2 b+\omega c)^3=(2a-b-c)\,(2b-c-a)\,(2c-a-b).$$

3. Shew that $(x+y)^n-x^n-y^n$ is divisible by $xy\,(x^2+xy+y^2)$, if n is an odd positive integer not a multiple of 3.

4. Shew that

$$a^3\,(bz-cy)^3+b^3\,(cx-az)^3+c^3\,(ay-bx)^3=3abc\,(bz-cy)\,(cx-az)\,(ay-bx).$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

If $a+b+c+d=0$, shew that

23. $$\frac{a^5+b^5+c^5+d^5}{5}=\frac{a^3+b^3+c^3+d^3}{3}\cdot\frac{a^2+b^2+c^2+d^2}{2}.$$

24. $$(a^3+b^3+c^3+d^3)^2=9\,(bcd+cda+dab+abc)^2$$
$$=9\,(bc-ad)\,(ca-bd)\,(ab-cd).$$

25. If $2s=a+b+c$ and $2\sigma^2=a^2+b^2+c^2$, prove that
$$\Sigma\,(s-b)\,(s-c)\,(\sigma^2-a^2)+5abcs=(s^2-\sigma^2)\,(4s^2+\sigma^2).$$

26. Shew that $(x^3+6x^2y+3xy^2-y^3)^3+(y^3+6xy^2+3x^2y-x^3)^3$
$$-27xy\,(x+y)\,(x^2+xy+y^2)^3.$$

27. Shew that $\Sigma\,\dfrac{a^5}{(a-b)\,(a-c)\,(a-d)}$
$$-a^2+b^2+c^2+d^2+ab+ac+ad+bc+bd+cd.$$

28. Resolve into factors
$$2a^2b^2c^2+(a^3+b^3+c^3)\,abc+b^3c^3+c^3a^3+a^3b^3.$$

ELIMINATION.

527. In Chapter XXXIII. we have seen that the eliminant of a system of linear equations may at once be written down in the form of a determinant. General methods of elimination applicable to equations of any degree will be found discussed in treatises on the Theory of Equations; in particular we may refer the student to Chapters IV. and VI. of Dr Salmon's *Lessons Introductory to the Modern Higher Algebra*, and to Chap. XIII. of Burnside and Panton's *Theory of Equations*.

These methods, though theoretically complete, are not always the most convenient in practice. We shall therefore only give a brief explanation of the general theory, and shall then illustrate by examples some methods of elimination that are more practically useful.

528. Let us first consider the elimination of one unknown quantity between two equations.

Denote the equations by $f(x)=0$ and $\phi(x)=0$, and suppose that, if necessary, the equations have been reduced to a form in which $f(x)$ and $\phi(x)$ represent rational integral functions of x. Since these two functions vanish simultaneously there must be some value of x which satisfies both the given equations; hence

the eliminant expresses the condition that must hold between the coefficients in order that the equations may have a common root.

Suppose that $x=\alpha$, $x=\beta$, $x=\gamma$,... are the roots of $f(x)=0$, then *one* at least of the quantities $\phi(\alpha)$, $\phi(\beta)$, $\phi(\gamma)$, ... must be equal to zero; hence the eliminant is

$$\phi(\alpha)\,\phi(\beta)\,\phi(\gamma) \qquad =0.$$

The expression on the left is a symmetrical function of the roots of the equation $f(x)=0$, and its value can be found by the methods explained in treatises on the *Theory of Equations*.

529. We shall now explain three general methods of elimination: it will be sufficient for our purpose to take a simple example, but it will be seen that in each case the process is applicable to equations of any degree.

The principle illustrated in the following example is due to Euler.

Example. Eliminate x between the equations

$$ax^3+bx^2+cx+d=0,\ fx^2+gx+h=0.$$

Let $x+k$ be the factor corresponding to the root common to both equations, and suppose that

$$ax^3+bx^2+cx+d=(x+k)\,(ax^2+lx+m),$$

and

$$fx^2+gx+h=(x+k)\,(fx+n),$$

k, l, m, n being unknown quantities.

From these equations, we have identically

$$(ax^3+bx^2+cx+d)\,(fx+n)=(ax^2+lx+m)\,(fx^2+gx+h).$$

Equating coefficients of like powers of x, we obtain

$$\begin{aligned}
fl \qquad & -an+ag-bf=0,\\
gl+fm & -bn+ah-cf=0,\\
hl+gm & -cn \qquad -df=0,\\
hm & -dn \qquad =0.
\end{aligned}$$

From these linear equations by eliminating the unknown quantities l, m, n, we obtain the determinant

$$\begin{vmatrix} f & 0 & a & ag-bf \\ g & f & b & ah-cf \\ h & g & c & -df \\ 0 & h & d & 0 \end{vmatrix}=0.$$

530. The eliminant of the equations $f(x)=0$, $\phi(x)=0$ can be very easily expressed as a determinant by Sylvester's *Dialytic Method of Elimination*. We shall take the same example as before.

Example. Eliminate x between the equations

$$ax^3+bx^2+cx+d=0,\ fx^2+gx+h=0.$$

Multiply the first equation by x, and the second equation by x and x^2 in succession; we thus have 5 equations between which we can eliminate the 4 quantities x^4, x^3, x^2, x regarded as distinct variables. The equations are

$$\begin{aligned}
ax^3+bx^2+cx+d&=0,\\
ax^4+bx^3+cx^2+dx&=0,\\
fx^2+gx+h&=0,\\
fx^3+gx^2+hx&=0,\\
fx^4+gx^3+hx^2&=0.
\end{aligned}$$

Hence the eliminant is

$$\begin{vmatrix} 0 & a & b & c & d \\ a & b & c & d & 0 \\ 0 & 0 & f & g & h \\ 0 & f & g & h & 0 \\ f & g & h & 0 & 0 \end{vmatrix} = 0.$$

531. The principle of the following method is due to Bezout; it has the advantage of expressing the result as a determinant of lower order than either of the determinants obtained by the preceding methods. We shall choose the same example as before, and give Cauchy's mode of conducting the elimination.

Example. Eliminate x between the equations

$$ax^3+bx^2+cx+d=0,\ fx^2+gx+h=0.$$

From these equations, we have

$$\frac{a}{f}=\frac{bx^2+cx+d}{gx^2+hx},$$

$$\frac{ax+b}{fx+g}=\frac{cx+d}{hx};$$

whence $$(ag-bf)\,x^2+(ah-cf)\,x-df=0,$$

and $$(ah-cf)\,x^2+(bh-cg-df)\,x-dg=0.$$

Combining these two equations with

$$fx^2+gx+h=0,$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Example 2. Eliminate x, y, z between the equations

$$y^2+z^2=ayz,\ z^2+x^2=bzx,\ x^2+y^2=cxy.$$

We have $$\frac{y}{z}+\frac{z}{y}=a,\ \frac{z}{x}+\frac{x}{z}=b,\ \frac{x}{y}+\frac{y}{x}=c;$$

by multiplying together these three equations we obtain,

$$2+\frac{y^2}{z^2}+\frac{z^2}{y^2}+\frac{z^2}{x^2}+\frac{x^2}{z^2}+\frac{x^2}{y^2}+\frac{y^2}{x2}=abc;$$

hence $$2+(a^2-2)+(b^2-2)+(c^2-2)=abc;$$

$$\therefore\ a^2+b^2+c^2-4=abc.$$

Example 3. Eliminate x, y between the equations

$$x^2-y^2=px-qy,\ 4xy=qx+py,\ x^2+y^2=1.$$

Multiplying the first equation by x, and the second by y, we obtain

$$x^3+3xy^2=p\,(x^2+y^2);$$

hence, by the third equation,

$$p=x^3+3xy^2$$

Similarly $$q=3x^2y+y^3.$$

Thus $$p+q=(x+y)^3,\ p-q=(x-y)^3;$$

$$\therefore\ (p+q)^{\frac{2}{3}}+(p-q)^{\frac{2}{3}}=(x+y)^2+(x-y)^2-2\,(x^2+y^2);$$

$$\therefore\ (p+q)^{\frac{2}{3}}+(p-q)^{\frac{2}{3}}=2.$$

Example 4. Eliminate x, y, z between the equations

$$\frac{y}{z}-\frac{z}{y}=a,\ \frac{z}{x}-\frac{x}{z}=b,\ \frac{x}{y}-\frac{y}{x}=c.$$

We have $$a+b+c=\frac{x\,(y^2-z^2)+y\,(z^2-x^2)+z\,(x^2-y^2)}{xyz}$$

$$\therefore\ =\frac{(y-z)\,(z-x)\,(x-y)}{xyz}.$$

If we change the sign of x, the signs of b and c are changed, while the sign of a remains unaltered;

hence $$a-b-c=\frac{(y-z)\,(z+x)\,(x+y)}{xyz}.$$

Similarly, $$b-c-a=\frac{(y+z)\,(z-x)\,(x+y)}{xyz},$$

and $$c-a-b=\frac{(y+z)\,(z+x)\,(x-y)}{xyz}.$$

$$\therefore\ (a+b+c)(b+c-a)(c+a-b)(a+b-c) = -\frac{(y^2-z^2)^2(z^2-x^2)^2(x^2-y^2)^2}{x^4y^4z^4}$$

$$= -\left(\frac{y}{z}-\frac{z}{y}\right)^2\left(\frac{z}{x}-\frac{x}{z}\right)^2\left(\frac{x}{y}-\frac{y}{x}\right)^2$$

$$= -a^2b^2c^2.$$

$$\therefore\ 2b^2c^2+2c^2a^2+2a^2b^2-a^4-b^4-c^4+a^2b^2c^2=0.$$

EXAMPLES. XXXIV. c.

1. Eliminate m from the equations

$$m^2x-my+a=0, \quad my+x=0.$$

2. Eliminate m, n from the equations

$$m^2x-my+a=0, \quad n^2x-ny+a=0, \quad mn+1=0.$$

3. Eliminate m, n between the equations

$$nx-ny=a(m^2-n^2), \quad nx+my=2amn, \quad m^2+n^2=1.$$

4. Eliminate p, q, r from the equations

$$p+q+r=0, \quad a(qr+rp+pq)=2a-x,$$
$$apqr=y, \qquad qr=-1.$$

5. Eliminate x from the equations

$$ax^2-2a^2x+1=0, \quad a^2+x^2-3ax=0.$$

6. Eliminate m from the equations

$$y+mx=a(1+m), \quad my-x=a(1-m).$$

7. Eliminate x, y, z from the equations

$$yz=a^2, \quad zx=b^2, \quad xy=c^2, \quad x^2+y^2+z^2=d^2.$$

8. Eliminate p, q from the equations

$$x(p+q)=y, \quad p-q=k(1+pq), \quad xpq=a.$$

9. Eliminate x, y from the equations

$$x-y=a, \quad x^2-y^2=b^2, \quad x^3-y^3=c^3.$$

10. Eliminate x, y from the equations

$$x+y=a, \quad x^2+y^2=b^2, \quad x^4+y^4=c^4.$$

11. Eliminate x, y, z, u from the equations

$$x=by+cz+du, \quad y=cz+du+ax,$$
$$z=du+ax+by, \quad u=ax+by+cz.$$

12. Eliminate x, y, z from the equations

$$x+y+z=0, \quad x^2+y^2+z^2=a^2,$$
$$x^3+y^3+z^3=b^3, \quad x^5+y^5+z^5=c^5.$$

13. Eliminate x, y, z from the equations

$$\frac{x}{y}+\frac{y}{z}+\frac{z}{x}=a, \qquad \frac{x}{z}+\frac{y}{x}+\frac{z}{y}=b, \qquad \left(\frac{x}{y}+\frac{y}{z}\right)\left(\frac{y}{z}+\frac{z}{x}\right)\left(\frac{z}{x}+\frac{x}{y}\right)=c.$$

14. Eliminate x, y, z from the equations

$$\frac{x^2(y+z)}{a^3}=\frac{y^2(z+x)}{b^3}=\frac{z^2(x+y)}{c^3}=\frac{xyz}{abc}=1.$$

15. Eliminate x, y from the equations

$$4(x^2+y^2)=ax+by, \quad 2(x^2-y^2)=ax-by, \quad xy=c^2.$$

16. Eliminate x, y, z from the equations

$$(y+z)^2=4a^2yz, \quad (z+x)^2=4b^2zx, \quad (x+y)^2=4c^2xy.$$

17. Eliminate x, y, z from the equations

$$(x+y-z)(x-y+z)=ayz, \quad (y+z-x)(y-z+x)=bzx,$$
$$(z+x-y)(z-x+y)=cxy.$$

18. Eliminate x, y from the equations

$$x^2y=a, \quad x(x+y)=b, \quad 2x+y=c.$$

19. Shew that $(a+b+c)^3-4(b+c)(c+a)(a+b)+5abc=0$ is the eliminant of

$$ax^2+by^2+cz^2=ax+by+cz=yz+zx+xy=0.$$

20. Eliminate x, y from the equations

$$ax^2+by^2=ax+by=\frac{xy}{x+y}=c.$$

21. Shew that $b^3c^3+c^3a^3+a^3b^3=5a^2b^2c^2$ is the eliminant of

$$ax+yz=bc, \quad by+zx=ca, \quad cz+xy=ab, \quad xyz=abc.$$

22. Eliminate x, y, z from

$$x^2+y^2+z^2=x+y+z=1,$$
$$\frac{a}{x}(x-p)=\frac{b}{y}(y-q)=\frac{c}{z}(z-r).$$

23. Employ Bezout's method to eliminate x, y from

$$ax^3+bx^2y+cxy^2+dy^3=0, \quad a'x^3+b'x^2y+c'xy^2+d'y^3=0.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

538. *Every equation of the* nth *degree has* n *roots, and no more.*

Denote the given equation by $f(x)=0$, where

$$f(x)=p_0x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_n.$$

The equation $f(x)=0$ has a root, real or imaginary; let this be denoted by a_1; then $f(x)$ is divisible by $x-a_1$, so that

$$f(x)=(x-a_1)\,\phi_1(x),$$

where $\phi_1(x)$ is a rational integral function of $n-1$ dimensions. Again, the equation $\phi_1(x)=0$ has a root, real or imaginary; let this be denoted by a_2; then $\phi_1(x)$ is divisible by $x-a_2$, so that

$$\phi_1(x)=(x-a_2)\,\phi_2(x),$$

where $\phi_2(x)$ is a rational integral function of $n-2$ dimensions.

Thus $$f(x)=(x-a_1)\,(x-a_2)\,\phi_2(x).$$

Proceeding in this way, we obtain, as in Art. 309,

$$f(x)=p_0(x-a_1)\,(x-a_2)\ldots\ldots(x-a_n).$$

Hence the equation $f(x)=0$ has n roots, since $f(x)$ vanishes when x has any of the values $a_1, a_2, a_3, \ldots a_n$.

Also the equation cannot have more than n roots; for if x has any value different from any of the quantities $a_1, a_2, a_3, \ldots a_n$, all the factors on the right are different from zero, and therefore $f(x)$ cannot vanish for that value of x.

In the above investigation some of the quantities $a_1, a_2, a_3, \ldots a_n$ may be equal; in this case, however, we shall suppose that the equation has still n roots, although these are not all different.

539. *To investigate the relations between the roots and the coefficients in any equation.*

Let us denote the equation by

$$x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_{n-1}x+p_n=0,$$

and the roots by $a, b, c, \ldots\ldots k$; then we have identically

$$x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_{n-1}x+p_n$$
$$=(x-a)\,(x-b)\,(x-c)\ldots\ldots(x-k);$$

hence, with the notation of Art. 163, we have

$$x^n+p_1x^{n-1}+p_2x^{n-2}+\quad\ldots+p_{n-1}x+p_n$$
$$=x^n-S_1x^{n-1}+S_2x^{n-2}-\quad\ldots+(-1)^{n-1}S_{n-1}x+(-1)^nS_n.$$

Equating coefficients of like powers of x in this identity,

$-p_1 = S_1 =$ sum of the roots;

$p_2 = S_2 =$ sum of the products of the roots taken two at a time;

$-p_3 = S_3 =$ sum of the products of the roots taken three at a time;

....

$(-1)^n p_n = S_n =$ product of the roots.

If the coefficient of x^n is p_0, then on dividing each term by p_0, the equation becomes

$$x^n + \frac{p_1}{p_0} x^{n-1} + \frac{p_2}{p_0} x^{n-2} + \ldots\ldots + \frac{p_{n-1}}{p_0} x + \frac{p_n}{p_0} = 0,$$

and, with the notation of Art. 521, we have

$$\Sigma a = -\frac{p_1}{p_0}, \quad \Sigma ab = \frac{p_2}{p_0}, \quad \Sigma abc = -\frac{p_3}{p_0}, \quad \ldots, \quad abc\ldots k = (-1)^n \frac{p_n}{p_0}$$

Example 1. Solve the equations

$$x + ay + a^2 z = a^3, \quad x + by + b^2 z = b^3, \quad x + cy + c^2 z = c^3.$$

From these equations we see that a, b, c are the values of t which satisfy the cubic equation

$$t^3 - zt^2 - yt - x = 0;$$

hence $$z = a + b + c, \quad y = -(bc + ca + ab), \quad x = abc.$$

Example 2. If a, b, c are the roots of the equation $x^3 + p_1 x^2 + p_2 x + p_3 = 0$, form the equation whose roots are a^2, b^2, c^2.

The required equation is $$(y - a^2)(y - b^2)(y - c^2) = 0,$$

or $$(x^2 - a^2)(x^2 - b^2)(x^2 - c^2) = 0, \text{ if } y = x^2;$$

that is, $$(x - a)(x - b)(x - c)(x + a)(x + b)(x + c) = 0.$$

But $$(x - a)(x - b)(x - c) = x^3 + p_1 x^2 + p_2 x + p_3;$$

hence $$(x + a)(x + b)(x + c) = x^3 - p_1 x^2 + p_2 x - p_3.$$

Thus the required equation is

$$(x^3 + p_1 x^2 + p_2 x + p_3)(x^3 - p_1 x^2 + p_2 x - p_3) = 0,$$

or $$(x^3 + p_2 x)^2 - (p_1 x^2 + p_3)^2 = 0,$$

or $$x^6 + (2p_2 - p_1^2) x^4 + (p_2^2 - 2p_1 p_3) x^2 - p_3^2 = 0;$$

and if we replace x^2 by y, we obtain

$$y^3 + (2p_2 - p_1^2) y^2 + (p_2^2 - 2p_1 p_3) y - p_3^2 = 0.$$

540. The student might suppose that the relations established in the preceding article would enable him to solve any proposed equation; for the number of the relations is equal to the number of the roots. A little reflection will shew that is this not the case; for suppose we eliminate any $n-1$ of the quantities $a, b, c, \ldots k$ and so obtain an equation to determine the remaining one; then since these quantities are involved symmetrically in each of the equations, it is clear that we shall always obtain an equation having the same coefficients; this equation is therefore the original equation with some one of the roots $a, b, c, \ldots k$ substituted for x.

Let us take for example the equation

$$x^3 + p_1 x^2 + p_2 x + p_3 = 0;$$

and let a, b, c be the roots; then

$$a + b + c = -p_1,$$
$$ab + ac + bc = \quad p_2,$$
$$abc = -p_3.$$

Multiply these equations by a^2, $-a$, 1 respectively and add; thus

$$a^3 = -p_1 a^2 - p_2 a - p_3,$$

that is
$$a^3 + p_1 a^2 + p_2 a + p_3 = 0,$$

which is the original equation with a in the place of x.

The above process of elimination is quite general, and is applicable to equations of any degree.

541. If two or more of the roots of an equation are connected by an assigned relation, the properties proved in Art. 539 will sometimes enable us to obtain the complete solution.

Example 1. Solve the equation $4x^3 - 24x^2 + 23x + 18 = 0$, having given that the roots are in arithmetical progression.

Denote the roots by $a-b$, a, $a+b$; then the sum of the roots is $3a$; the sum of the products of the roots two at a time is $3a^2 - b^2$; and the product of the roots is $a(a^2 - b^2)$; hence we have the equations

$$3a = 6, \quad 3a^2 - b^2 = \frac{23}{4}, \quad a(a^2 - b^2) = -\frac{9}{2};$$

from the first equation we find $a = 2$, and from the second $b = \pm\frac{5}{2}$, and since these values satisfy the third, the three equations are consistent. Thus the roots are $-\frac{1}{2}$, 2, $\frac{9}{2}$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

From these equations we have

$$-pq = \Sigma a^2b + 3\,(abc + abd + acd + bcd)$$

$$-\Sigma a^2b - 3r;$$

$$\Sigma a^2b = 3r - pq.$$

EXAMPLES. XXXV. a.

Form the equation whose roots are

1. $\frac{2}{3}, \frac{3}{2}, \pm\sqrt{3}$.

2. $0, 0, 2, 2, -3, 3$.

3. $2, 2, -2, -2, 0, 5$.

4. $a+b, a-b, -a+b, -a-b$.

Solve the equations:

5. $x^4 - 16x^3 + 86x^2 - 176x + 105 = 0$, two roots being 1 and 7.

6. $4x^3 + 16x^2 - 9x - 36 = 0$, the sum of two of the roots being zero.

7. $4x^3 + 20x^2 - 23x + 6 = 0$, two of the roots being equal.

8. $3x^3 - 26x^2 + 52x - 24 = 0$, the roots being in geometrical progression.

9. $2x^3 - x^2 - 22x - 24 = 0$, two of the roots being in the ratio of 3 : 4.

10. $24x^3 + 46x^2 + 9x - 9 = 0$, one root being double another of the roots.

11. $8x^4 - 2x^3 - 27x^2 + 6x + 9 = 0$, two of the roots being equal but opposite in sign.

12. $54x^3 - 39x^2 - 26x + 16 = 0$, the roots being in geometrical progression.

13. $32x^3 - 48x^2 + 22x - 3 = 0$, the roots being in arithmetical progression.

14. $6x^4 - 29x^3 + 40x^2 - 7x - 12 = 0$, the product of two of the roots being 2.

15. $x^4 - 2x^3 - 21x^2 + 22x + 40 = 0$, the roots being in arithmetical progression.

16. $27x^4 - 195x^3 + 494x^2 - 520x + 192 = 0$, the roots being in geometrical progression.

17. $18x^3 + 81x^2 + 121x + 60 = 0$, one root being half the sum of the other two.

18. If a, b, c are the roots of the equation $x^3 - px^2 + qx - r = 0$, find the value of

(1) $\dfrac{1}{a^2} + \dfrac{1}{b^2} + \dfrac{1}{c^2}$. (2) $\dfrac{1}{b^2c^2} + \dfrac{1}{c^2a^2} + \dfrac{1}{a^2b^2}$.

19. If a, b, c are the roots of $x^3 + qx + r = 0$, find the value of

(1) $(b-c)^2 + (c-a)^2 + (a-b)^2$ (2) $(b+c)^{-1} + (c+a)^{-1} + (a+b)^{-1}$

20. Find the sum of the squares and of the cubes of the roots of

$$x^4 + qx^2 + rx + s = 0.$$

21. Find the sum of the fourth powers of the roots of

$$x^3 + qx + r = 0.$$

543. *In an equation with real coefficients imaginary roots occur in pairs.*

Suppose that $f(x) = 0$ is an equation with real coefficients, and suppose that it has an imaginary root $a + ib$; we shall shew that $a - ib$ is also a root.

The factor of $f(x)$ corresponding to these two roots is

$$(x - a - ib)\,(x - a + ib), \text{ or } (x-a)^2 + b^2.$$

Let $f(x)$ be divided by $(x-a)^2 + b^2$; denote the quotient by Q, and the remainder, if any, by $Rx + R'$; then

$$f(x) = Q\{(x-a)^2 + b^2\} + Rx + R'.$$

In this identity put $x = a + ib$, then $f(x) = 0$ by hypothesis; also $(x-a)^2 + b^2 = 0$; hence $R(a + ib) + R' = 0$.

Equating to zero the real and imaginary parts,

$$Ra + R' = 0, \quad Rb = 0.$$

and b by hypothesis is not zero,

$$\therefore \quad R = 0 \text{ and } R' = 0.$$

Hence $f(x)$ is exactly divisible by $(x-a)^2 + b^2$, that is, by

$$(x - a - ib)\,(x - a + ib);$$

hence $x = a - ib$ is also a root.

544. In the preceding article we have seen that if the equation $f(x) = 0$ has a pair of imaginary roots $a \pm ib$, then $(x-a)^2 + b^2$ is a factor of the expression $f(x)$.

Suppose that $a \pm ib$, $c \pm id$, $e \pm ig, \ldots$ are the imaginary roots of the equation $f(x) = 0$, and that $\phi(x)$ is the product of the quadratic factors corresponding to these imaginary roots; then

$$\phi(x) = \{(x-a)^2 + b^2\}\{(x-c)^2 + d^2\}\{(x-e)^2 + g^2\}.$$

Now each of these factors is positive for every real value of x; hence $\phi(x)$ is always positive for real values of x.

545. As in Art. 543 we may shew that in an equation with *rational* coefficients, surd roots enter in pairs; that is, if $a + \sqrt{b}$ is a root then $a - \sqrt{b}$ is also a root.

Example 1. Solve the equation $6x^4 - 13x^3 - 35x^2 - x + 3 = 0$, having given that one root is $2 - \sqrt{3}$.

Since $2 - \sqrt{3}$ is a root, we know that $2 + \sqrt{3}$ is also a root, and corresponding to this pair of roots we have the quadratic factor $x^2 - 4x + 1$.

Also $$6x^4 - 13x^3 - 35x^2 - x + 3 = (x^2 - 4x + 1)(6x^2 + 11x + 3);$$

hence the other roots are obtained from

$$6x^2 + 11x + 3 = 0, \text{ or } (3x+1)(2x+3) = 0;$$

thus the roots are $$-\frac{1}{3}, -\frac{3}{2}, 2+\sqrt{3}, 2-\sqrt{3}.$$

Example 2. Form the equation of the fourth degree with rational coefficients, one of whose roots is $\sqrt{2} + \sqrt{-3}$.

Here we must have $\sqrt{2} + \sqrt{-3}$, $\sqrt{2} - \sqrt{-3}$ as one pair of roots, and $-\sqrt{2} + \sqrt{-3}$, $-\sqrt{2} - \sqrt{-3}$ as another pair.

Corresponding to the first pair we have the quadratic factor $x^2 - 2\sqrt{2}x + 5$, and corresponding to the second pair we have the quadratic factor

$$x^2 + 2\sqrt{2}x + 5.$$

Thus the required equation is

$$(x^2 + 2\sqrt{2}x + 5)(x^2 - 2\sqrt{2}x + 5) = 0,$$

or $$(x^2 + 5)^2 - 8x^2 = 0,$$

or $$x^4 + 2x^2 + 25 = 0.$$

Example 3. Shew that the equation

$$\frac{A^2}{x-a} + \frac{B^2}{x-b} + \frac{C^2}{x-c} + \ldots + \frac{H^2}{x-h} = k,$$

has no imaginary roots.

If possible let $p + iq$ be a root; then $p - iq$ is also a root. Substitute these values for x and subtract the first result from the second; thus

$$q\left\{\frac{A^2}{(p-a)^2+q^2} + \frac{B^2}{(p-b)^2+q^2} + \frac{C^2}{(p-c)^2+q^2} + \ldots + \frac{H^2}{(p-h)^2+q^2}\right\} = 0;$$

which is impossible unless $q = 0$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Hence we see that in the product

(i) an ambiguity replaces each continuation of sign in the original polynomial;

(ii) the signs before and after an ambiguity or set of ambiguities are unlike;

(iii) a change of sign is introduced at the end.

Let us take the most unfavourable case and suppose that all the ambiguities are replaced by continuations; from (ii) we see that the number of changes of sign will be the same whether we take the upper or the lower signs; let us take the upper; thus the number of changes of sign cannot be less than in

$$+ + - - + - - - + - + - +,$$

and this series of signs is the same as in the original polynomial with an additional change of sign at the end.

If then we suppose the factors corresponding to the negative and imaginary roots to be already multiplied together, each factor $x - a$ corresponding to a positive root introduces at least one change of sign; therefore no equation can have more positive roots than it has changes of sign.

Again, the roots of the equation $f(-x) = 0$ are equal to those of $f(x) = 0$ but opposite to them in sign; therefore the negative roots of $f(x) = 0$ are the positive roots of $f(-x) = 0$; but the number of these positive roots cannot exceed the number of changes of sign in $f(-x)$; that is, the number of negative roots of $f(x) = 0$ cannot exceed the number of changes of sign in $f(-x)$.

Example. Consider the equation $x^9 + 5x^8 - x^3 + 7x + 2 = 0$.

Here there are two changes of sign, therefore there are at most two positive roots.

Again $f(-x) = -x^9 + 5x^8 + x^3 - 7x + 2$, and here there are three changes of sign, therefore the given equation has at most three negative roots, and therefore it must have at least four imaginary roots.

EXAMPLES. XXXV. b.

Solve the equations:

1. $3x^4 - 10x^3 + 4x^2 - x - 6 = 0$, one root being $\dfrac{1 + \sqrt{-3}}{2}$.

2. $6x^4 - 13x^3 - 35x^2 - x + 3 = 0$, one root being $2 - \sqrt{3}$.

3. $x^4 + 4x^3 + 5x^2 + 2x - 2 = 0$, one root being $-1 + \sqrt{-1}$.

4. $x^4+4x^3+6x^2+4x+5=0$, one root being $\sqrt{-1}$.

5. Solve the equation $x^5-x^4+8x^2-9x-15=0$, one root being $\sqrt{3}$ and another $1-2\sqrt{-1}$.

Form the equation of lowest dimensions with rational coefficients, one of whose roots is

6. $\sqrt{3}+\sqrt{-2}$.

7. $-\sqrt{-1}+\sqrt{5}$.

8. $-\sqrt{2}-\sqrt{-2}$.

9. $\sqrt{5+2\sqrt{6}}$.

10. Form the equation whose roots are $\pm 4\sqrt{3}$, $5\pm 2\sqrt{-1}$.

11. Form the equation whose roots are $1\pm\sqrt{-2}$, $2\pm\sqrt{-3}$.

12. Form the equation of the eighth degree with rational coefficients one of whose roots is $\sqrt{2}+\sqrt{3}+\sqrt{-1}$.

13. Find the nature of the roots of the equation

$$3x^4+12x^2+5x-4=0.$$

14. Shew that the equation $2x^7-x^4+4x^3-5=0$ has at least four imaginary roots.

15. What may be inferred respecting the roots of the equation

$$x^{10}-4x^6+x^4-2x-3=0?$$

16. Find the least possible number of imaginary roots of the equation $x^9-x^5+x^4+x^2+1=0$.

17. Find the condition that $x^3-px^2+qx-r=0$ may have

(1) two roots equal but of opposite sign;

(2) the roots in geometrical progression.

18. If the roots of the equation $x^4+px^3+qx^2+rx+s=0$ are in arithmetical progression, shew that $p^3-4pq+8r=0$; and if they are in geometrical progression, shew that $p^2s=r^2$.

19. If the roots of the equation $x^n-1=0$ are $1, \alpha, \beta, \gamma, \ldots$, shew that

$$(1-\alpha)(1-\beta)(1-\gamma)\ldots\ldots=n.$$

If a, b, c are the roots of the equation $x^3-px^2+qx-r=0$, find the value of

20. Σa^2b^2.

21. $(b+c)(c+a)(a+b)$.

22. $\Sigma\left(\frac{b}{c}+\frac{c}{b}\right)$.

23. Σa^2b.

If a, b, c, d are the roots of $x^4+px^3+qx^2+rx+s=0$, find the value of

24. Σa^2bc.

25. Σa^4.

548. *To find the value of* f(x + h), *when* f(x) *is a rational integral function of* x.

Let $f(x) = p_0x^n + p_1x^{n-1} + p_2x^{n-2} + \ldots\ldots + p_{n-1}x + p_n$; then

$$f(x+h) = p_0(x+h)^n + p_1(x+h)^{n-1} + p_2(x+h)^{n-2} + \ldots\ldots + p_{n-1}(x+h) + p_n.$$

Expanding each term and arranging the result in ascending powers of h, we have

$$\begin{aligned} & p_0x^n + p_1x^{n-1} + p_2x^{n-2} + \ldots + p_{n-1}x + p_n \\ & + h\{np_0x^{n-1} + (n-1)p_1x^{n-2} + (n-2)p_2x^{n-3} + \ldots + p_{n-1}\} \\ & + \frac{h^2}{\lfloor 2}\{n(n-1)p_0x^{n-2} + (n-1)(n-2)p_1x^{n-3} + \ldots + 2p_{n-2}\} \\ & + \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots \\ & + \frac{h^n}{\lfloor n}\{n(n-1)(n-2)\ldots 2.1p_0\}. \end{aligned}$$

This result is usually written in the form

$$f(x+h) = f(x) + hf'(x) + \frac{h^2}{\lfloor 2}f''(x) + \frac{h^3}{\lfloor 3}f'''(x) + \ldots + \frac{h^n}{\lfloor n}f^n(x),$$

and the functions $f'(x)$, $f''(x)$, $f'''(x)$,... are called the *first, second, third,... derived functions* of $f(x)$

The student who knows the elements of the Differential Calculus will see that the above expansion of $f(x+h)$ is only a particular case of *Taylor's Theorem;* the functions $f'(x)$, $f''(x)$, $f'''(x)$ may therefore be written down at once by the ordinary rules for differentiation: thus to obtain $f'(x)$ from $f(x)$ we multiply each term in $f(x)$ by the index of x in that term and then diminish the index by unity.

Similarly by successive differentiations we obtain $f''(x)$, $f'''(x)$,

By writing $-h$ in the place of h, we have

$$f(x-h) = f(x) - hf'(x) + \frac{h^2}{\lfloor 2}f''(x) - \frac{h^3}{\lfloor 3}f'''(x) + \ldots + (-1)^n\frac{h^n}{\lfloor n}f^n(x).$$

The function $f(x+h)$ is evidently symmetrical with respect to x and h; hence

$$f(x+h) = f(h) + xf'(h) + \frac{x^2}{\lfloor 2}f''(h) + \ldots + \frac{x^n}{\lfloor n}f^n(h).$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Example. Find the result of changing x into $x+3$ in the expression

$$2x^4-x^3-2x^2+5x-1.$$

Here we divide successively by $x-3$.

2	−1	−2	5	−1
	6	15	39	132
	5	13	44	131 $=q_4$
	6	33	138	
	11	46	182 $=q_3$	
	6	51		
	17	97 $=q_2$		
	6			
	23 $=q_1$			

Or more briefly thus:

2	−1	−2	5	−1
2	5	13	44	131
2	11	46	182	
2	17	97		
2	23			
2				

Hence the result is $2x^4+23x^3+97x^2+182x+131$. Compare Art. 548.

It may be remarked that Horner's process is chiefly useful in *numerical* work.

550. *If the variable* x *changes continuously from* a *to* b *the function* f (x) *will change continuously from* f (a) *to* f (b).

Let c and $c+h$ be any two values of x lying between a and b. We have

$$f(c+h)-f(c)=hf'(c)+\frac{h^2}{\lfloor 2}f''(c)+\ldots+\frac{h^n}{\lfloor n}f^n(c);$$

and by taking h small enough the difference between $f(c+h)$ and $f(c)$ can be made as small as we please; hence to a small change in the variable x there corresponds a small change in the function $f(x)$, and therefore as x changes gradually from a to b, the function $f(x)$ changes gradually from $f(a)$ to $f(b)$.

551. It is important to notice that we have not proved that $f(x)$ always increases from $f(a)$ to $f(b)$, or decreases from $f(a)$ to $f(b)$, but that it passes from one value to the other without any sudden change; sometimes it may be increasing and at other times it may be decreasing.

The student who has a knowledge of the elements of Curve-tracing will in any particular example find it easy to follow the gradual changes of value of $f(x)$ by drawing the curve $y=f(x)$.

552. *If* f (a) *and* f (b) *are of contrary signs then one root of the equation* f (x) = 0 *must lie between* a *and* b.

As x changes gradually from a to b, the function $f(x)$ changes gradually from $f(a)$ to $f(b)$, and therefore must pass through all

intermediate values; but since $f(a)$ and $f(b)$ have contrary signs the value zero must lie between them; that is, $f(x)=0$ for some value of x between a and b.

It does not follow that $f(x)=0$ has *only one* root between a and b; neither does it follow that if $f(a)$ and $f(b)$ have the *same* sign $f(x)=0$ has no root between a and b.

553. *Every equation of an odd degree has at least one real root whose sign is opposite to that of its last term.*

In the function $f(x)$ substitute for x the values $+\infty$, 0, $-\infty$ successively, then

$$f(+\infty)=+\infty, \quad f(0)=p_n, \quad f(-\infty)=-\infty.$$

If p_n is positive, then $f(x)=0$ has a root lying between 0 and $-\infty$, and if p_n is negative $f(x)=0$ has a root lying between 0 and $+\infty$.

554. *Every equation which is of an even degree and has its last term negative has at least two real roots, one positive and one negative.*

For in this case

$$f(+\infty)=+\infty, \quad f(0)=p_n, \quad f(-\infty)=+\infty;$$

but p_n is negative; hence $f(x)=0$ has a root lying between 0 and $+\infty$, and a root lying between 0 and $-\infty$.

555. *If the expressions* f(a) *and* f(b) *have contrary signs, an odd number of roots of* f(x) = 0 *will lie between* a *and* b; *and if* f(a) *and* f(b) *have the same sign, either no root or an even number of roots will lie between* a *and* b.

Suppose that a is greater than b, and that $\alpha, \beta, \gamma, \ldots \kappa$ represent all the roots of $f(x)=0$ which lie between a and b. Let $\phi(x)$ be the quotient when $f(x)$ is divided by the product $(x-\alpha)(x-\beta)(x-\gamma)\ldots(x-\kappa)$; then

$$f(x)=(x-\alpha)(x-\beta)(x-\gamma)\ldots(x-\kappa)\phi(x).$$

Hence
$$f(a)=(a-\alpha)(a-\beta)(a-\gamma)\ldots(a-\kappa)\phi(a).$$
$$f(b)=(b-\alpha)(b-\beta)(b-\gamma)\ldots(b-\kappa)\phi(b).$$

Now $\phi(a)$ and $\phi(b)$ must be of the same sign, for otherwise a root of the equation $\phi(x)=0$, and therefore of $f(x)=0$, would lie between a and b [Art. 552], which is contrary to the hypo-

thesis. Hence if $f(a)$ and $f(b)$ have contrary signs, the expressions

$$(a-\alpha)(a-\beta)(a-\gamma)\ldots(a-\kappa),$$
$$(b-\alpha)(b-\beta)(b-\gamma)\ldots(b-\kappa)$$

must have contrary signs. Also the factors in the first expression are all positive, and the factors in the second are all negative; hence the number of factors must be odd, that is the number of roots $\alpha, \beta, \gamma, \ldots \kappa$ must be odd.

Similarly if $f(a)$ and $f(b)$ have the same sign the number of factors must be even. In this case the given condition is satisfied if $\alpha, \beta, \gamma, \ldots \kappa$ are all greater than a, or less than b; thus it does not necessarily follow that $f(x)=0$ has a root between a and b.

556. If $a, b, c, \ldots k$ are the roots of the equation $f(x)=0$, then

$$f(x)=p_0(x-a)(x-b)(x-c)\ldots(x-k).$$

Here the quantities $a, b, c, \ldots k$ are not necessarily unequal. If r of them are equal to a, s to b, t to c, ..., then

$$f(x)=p_0(x-a)^r(x-b)^s(x-c)^t$$

In this case it is convenient still to speak of the equation $f(x)=0$ as having n roots, each of the equal roots being considered a distinct root.

557. *If the equation* $\mathrm{f(x)=0}$ *has* r *roots equal to* a, *then the equation* $\mathrm{f'(x)=0}$ *will have* $\mathrm{r-1}$ *roots equal to* a.

Let $\phi(x)$ be the quotient when $f(x)$ is divided by $(x-a)^r$; then $f(x)=(x-a)^r\phi(x)$.

Write $x+h$ in the place of x; thus

$$f(x+h)=(x-a+h)^r\phi(x+h);$$

$$\cdot\ f(x)+hf'(x)+\frac{h^2}{\underline{2}}f''(x)+\ldots$$

$$=\left\{(x-a)^r+r(x-a)^{r-1}h+\ldots\right\}\left\{\phi(x)+h\phi'(x)+\frac{h^2}{\underline{2}}\phi''(x)+\ldots\right\}.$$

In this identity, by equating the coefficients of h, we have

$$f'(x)=r(x-a)^{r-1}\phi(x)+(x-a)^r\phi'(x).$$

Thus $f'(x)$ contains the factor $x-a$ repeated $r-1$ times; that is, the equation $f'(x)=0$ has $r-1$ roots equal to a.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

560. We have seen that if the equation $f(x)=0$ has r roots equal to a, the equation $f'(x)=0$ has $r-1$ roots equal to a. But $f''(x)$ is the first derived function of $f'(x)$; hence the equation $f''(x)=0$ must have $r-2$ roots equal to a; similarly the equation $f'''(x)=0$ must have $r-3$ roots equal to a; and so on. These considerations will sometimes enable us to discover the equal roots of $f(x)=0$ with less trouble than the method of Art. 559.

561. *If* a, b, c, ...k *are the roots of the equation* f(x) = 0, *to prove that*

$$f'(x)=\frac{f(x)}{x-a}+\frac{f(x)}{x-b}+\frac{f(x)}{x-c}+\ldots+\frac{f(x)}{x-k}.$$

We have $f(x)=(x-a)(x-b)(x-c)\ldots(x-k)$;

writing $x+h$ in the place of x,

$$f(x+h)=(x-a+h)(x-b+h)(x-c+h)\ldots(x-k+h)\ldots(1).$$

But $$f(x+h)=f(x)+hf'(x)+\frac{h^2}{\underline{2}}f''(x)+\ldots;$$

hence $f'(x)$ is equal to the coefficient of h in the right-hand member of (1); therefore, as in Art. 163,

$$f'(x)=(x-b)(x-c)\ldots(x-k)+(x-a)(x-c)\ldots(x-k)+\cdots;$$

that is, $$f'(x)=\frac{f(x)}{x-a}+\frac{f(x)}{x-b}+\frac{f(x)}{x-c}+\ldots+\frac{f(x)}{x-k}.$$

562. The result of the preceding article enables us very easily to find the sum of an assigned power of the roots of an equation.

Example. If S_k denote the sum of the k^{th} powers of the roots of the equation

$$x^5+px^4+qx^2+t=0,$$

find the value of S_4, S_6 and S_{-4}.

Let $$f(x)=x^5+px^4+qx^2+t;$$

then $$f'(x)=5x^4+4px^3+2qx.$$

Now $$\frac{f(x)}{x-a}=x^4+(a+p)x^3+(a^2+ap)x^2+(a^3+a^2p+q)x+a^4+a^3p+aq;$$

and similar expressions hold for

$$\frac{f(x)}{x-b},\quad\frac{f(x)}{x-c},\quad\frac{f(x)}{x-d},\quad\frac{f(x)}{x-e}.$$

Hence by addition,

$$5x^4+4px^3+2qx=5x^4+(S_1+5p)\,x^3+(S_2+pS_1)\,x^2 + (S_3+pS_2+5q)\,x+(S_4+pS_3+qS_1).$$

By equating coefficients,

$$S_1+5p=4p, \text{ whence } S_1=-p;$$
$$S_2+pS_1=0, \text{ whence } S_2=p^2;$$
$$S_3+pS_2+5q=2q, \text{ whence } S_3=-p^3-3q;$$
$$S_4+pS_3+qS_1=0, \text{ whence } S_4=p^4+4pq.$$

To find the value of S_k for other values of k, we proceed as follows.

Multiplying the given equation by x^{k-5},

$$x^k+px^{k-1}+qx^{k-3}+tx^{k-5}=0.$$

Substituting for x in succession the values a, b, c, d, e and adding the results, we obtain $S_k+pS_{k-1}+qS_{k-3}+tS_{k-5}=0$.

Put $k=5$; thus $S_5+pS_4+qS_2+5t=0$,

whence $S_5=-p^5-5p^2q-5t$.

Put $k=6$; thus $S_6+pS_5+qS_3+tS_1=0$,

whence $S_6=p^6+6p^3q+3q^2+6pt$.

To find S_{-4}, put $k=4, 3, 2, 1$ in succession; then

$$S_4+pS_3+qS_1+tS_{-1}=0, \text{ whence } S_{-1}=0;$$
$$S_3+pS_2+5q+tS_{-2}=0, \text{ whence } S_{-2}=-\frac{2q}{t};$$
$$S_2+pS_1+qS_{-1}+tS_{-3}=0, \text{ whence } S_{-3}=0;$$
$$S_1+5p+qS_{-2}+tS_{-4}=0, \text{ whence } S_{-4}=\frac{2q^2}{t^2}-\frac{4p}{t}$$

563. When the coefficients are numerical we may also proceed as in the following example.

Example. Find the sum of the fourth powers of the roots of

$$x^3-2x^2+x-1=0.$$

Here
$$f(x)=x^3-2x^2+x-1,$$
$$f'(x)=3x^2-4x+1.$$

Also
$$\frac{f'(x)}{f(x)}=\frac{1}{x-a}+\frac{1}{x-b}+\frac{1}{x-c}$$
$$=\Sigma\left(\frac{1}{x}+\frac{a}{x^2}+\frac{a^2}{x^3}+\frac{a^3}{x^4}+\dots\right)$$
$$=\frac{3}{x}+\frac{S_1}{x^2}+\frac{S_2}{x^3}+\frac{S_3}{x^4}+\dots;$$

hence S_4 is equal to the coefficient of $\frac{1}{x^5}$ in the quotient of $f'(x)$ by $f(x)$, which is very conveniently obtained by the method of synthetic division as follows:

$$\begin{array}{r|l} 1 & 3-4+1 \\ 2 & \quad 6-3+3 \\ -1 & \quad\quad 4-2+2 \\ 1 & \quad\quad\quad 4-2+2 \\ \hline & 3+2+2+5+10+\ldots\ldots \end{array}$$

Hence the quotient is $\frac{3}{x}+\frac{2}{x^2}+\frac{2}{x^3}+\frac{5}{x^4}+\frac{10}{x^5}+\ldots\ldots;$

thus $$S_4=10.$$

EXAMPLES. XXXV. c.

1. If $f(x)=x^4+10x^3+39x^2+76x+65$, find the value of $f(x-4)$.

2. If $f(x)=x^4-12x^3+17x^2-9x+7$, find the value of $f(x+3)$.

3. If $f(x)=2x^4-13x^2+10x-19$, find the value of $f(x+1)$.

4. If $f(x)=x^4+16x^3+72x^2+64x-129$, find the value of $f(x-4)$.

5. If $f(x)=ax^8+bx^5+cx+d$, find the value of $f(x+h)-f(x-h)$.

6. Shew that the equation $10x^3-17x^2+x+6=0$ has a root between 0 and -1.

7. Shew that the equation $x^4-5x^3+3x^2+35x-70=0$ has a root between 2 and 3 and one between -2 and -3.

8. Shew that the equation $x^4-12x^2+12x-3=0$ has a root between -3 and -4 and another between 2 and 3.

9. Shew that $x^5+5x^4-20x^2-19x-2=0$ has a root between 2 and 3, and a root between -4 and -5.

Solve the following equations which have equal roots:

10. $x^4-9x^2+4x+12=0.$ **11.** $x^4-6x^3+12x^2-10x+3=0.$

12. $x^5-13x^4+67x^3-171x^2+216x-108=0.$

13. $x^5-x^3+4x^2-3x+2=0.$ **14.** $8x^4+4x^3-18x^2+11x-2=0.$

15. $x^6-3x^5+6x^3-3x^2-3x+2=0.$

16. $x^6-2x^5-4x^4+12x^3-3x^2-18x+18=0.$

17. $x^4-(a+b)x^3-a(a-b)x^2+a^2(a+b)x-a^3b=0.$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

If the proposed equation is

$$p_0x^n + p_1x^{n-1} + p_2x^{n-2} + \ldots\ldots + p_{n-1}x + p_n = 0,$$

then it is evident that the required equation will be

$$p_0y^n - p_1y^{n-1} + p_2y^{n-2} - \ldots + (-1)^{n-1}p_{n-1}y + (-1)^n p_n = 0,$$

which is obtained from the original equation by *changing the sign of every alternate term beginning with the second.*

566. *To transform an equation into another whose roots are equal to those of the proposed equation multiplied by a given quantity.*

Let $f(x) = 0$ be the proposed equation, and let q denote the given quantity. Put $y = qx$, so that $x - \frac{y}{q}$, then the required equation is $f\left(\frac{y}{q}\right) = 0$.

The chief use of this transformation is to clear an equation of fractional coefficients.

Example. Remove fractional coefficients from the equation

$$2x^3 - \frac{3}{2}x^2 - \frac{1}{8}x + \frac{3}{16} = 0.$$

Put $x = \frac{y}{q}$ and multiply each term by q^3; thus

$$2y^3 - \frac{3}{2}qy^2 - \frac{1}{8}q^2y + \frac{3}{16}q^3 = 0.$$

By putting $q = 4$ all the terms become integral, and on dividing by 2, we obtain

$$y^3 - 3y^2 - y + 6 = 0.$$

567. *To transform an equation into another whose roots are the reciprocals of the roots of the proposed equation.*

Let $f(x) = 0$ be the proposed equation; put $y - \frac{1}{x}$, so that $x = \frac{1}{y}$; then the required equation is $f\left(\frac{1}{y}\right) = 0$.

One of the chief uses of this transformation is to obtain the values of expressions which involve symmetrical functions of negative powers of the roots.

Example 1. If a, b, c are the roots of the equation

$$x^3 - px^2 + qx - r = 0,$$

find the value of $$\frac{1}{a^2} + \frac{1}{b^2} + \frac{1}{c^2}.$$

Write $\frac{1}{y}$ for x, multiply by y^3, and change all the signs; then the resulting equation $$ry^3 - qy^2 + py - 1 = 0,$$

has for its roots $$\frac{1}{a}, \frac{1}{b}, \frac{1}{c};$$

hence $$\Sigma \frac{1}{a} = \frac{q}{r}, \quad \Sigma \frac{1}{ab} = \frac{p}{r};$$

$$\therefore \quad \Sigma \frac{1}{a^2} = \frac{q^2 - 2pr}{r^2}.$$

Example 2. If a, b, c are the roots of

$$x^3 + 2x^2 - 3x - 1 = 0,$$

find the value of $$a^{-3} + b^{-3} + c^{-3}.$$

Writing $\frac{1}{y}$ for x, the transformed equation is

$$y^3 + 3y^2 - 2y - 1 = 0;$$

and the given expression is equal to the value of S_3 in this equation.

Here $$S_1 = -3;$$

$$S_2 = (-3)^2 - 2(-2) = 13;$$

and $$S_3 + 3S_2 - 2S_1 - 3 = 0;$$

whence we obtain $$S_3 = -42.$$

568. If an equation is unaltered by changing x into $\frac{1}{x}$, it is called a *reciprocal equation.*

If the given equation is

$$x^n + p_1 x^{n-1} + p_2 x^{n-2} + \ldots\ldots + p_{n-2} x^2 + p_{n-1} x + p_n = 0,$$

the equation obtained by writing $\frac{1}{x}$ for x, and clearing of fractions is

$$p_n x^n + p_{n-1} x^{n-1} + p_{n-2} x^{n-2} + \ldots + p_2 x^2 + p_1 x + 1 = 0.$$

If these two equations are the same, we must have

$$p_1 = \frac{p_{n-1}}{p_n}, \quad p_2 = \frac{p_{n-2}}{p_n}, \quad \ldots, \quad p_{n-2} = \frac{p_2}{p_n}, \quad p_{n-1} = \frac{p_1}{p_n}, \quad p_n = \frac{1}{p_n};$$

from the last result we have $p_n = \pm 1$, and thus we have two classes of reciprocal equations.

(i) If $p_n = 1$, then

$$p_1 = p_{n-1}, \quad p_2 = p_{n-2}, \quad p_3 = p_{n-3}, \ldots\ldots ;$$

that is, the coefficients of terms equidistant from the beginning and end are equal.

(ii) If $p_n = -1$, then

$$p_1 = -p_{n-1}, \quad p_2 = -p_{n-2}, \quad p_3 = -p_{n-3}, \ldots\ldots,$$

hence if the equation is of $2m$ dimensions $p_m = -p_m$, or $p_m = 0$. In this case the coefficients of terms equidistant from the beginning and end are equal in magnitude and opposite in sign, and if the equation is of an even degree the middle term is wanting.

569. Suppose that $f(x) = 0$ is a reciprocal equation.

If $f(x) = 0$ is of the first class and of an odd degree it has a root -1; so that $f(x)$ is divisible by $x + 1$. If $\phi(x)$ is the quotient, then $\phi(x) = 0$ is a reciprocal equation of the first class and of an even degree.

If $f(x) = 0$ is of the second class and of an odd degree, it has a root $+1$; in this case $f(x)$ is divisible by $x - 1$, and as before $\phi(x) = 0$ is a reciprocal equation of the first class and of an even degree.

If $f(x) = 0$ is of the second class and of an even degree, it has a root $+1$ and a root -1; in this case $f(x)$ is divisible by $x^2 - 1$, and as before $\phi(x) = 0$ is a reciprocal equation of the first class and of an even degree.

Hence *any reciprocal equation is of an even degree with its last term positive, or can be reduced to this form;* which may therefore be considered as the standard form of reciprocal equations.

570. *A reciprocal equation of the standard form can be reduced to an equation of half its dimensions.*

Let the equation be

$$ax^{2m} + bx^{2m-1} + cx^{2m-2} + \ldots + kx^m + \ldots + cx^2 + bx + a = 0;$$

dividing by x^m and rearranging the terms, we have

$$a\left(x^m + \frac{1}{x^m}\right) + b\left(x^{m-1} + \frac{1}{x^{m-1}}\right) + c\left(x^{m-2} + \frac{1}{x^{m-2}}\right) + \ldots + k = 0.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

Example. Find the equation whose roots exceed by 2 the roots of the equation $4x^4+32x^3+83x^2+76x+21=0$.

The required equation will be obtained by substituting $x-2$ for x in the proposed equation; hence in Horner's process we employ $x+2$ as divisor, and the calculation is performed as follows:

4	32	83	76	21
4	24	35	6	| 9
4	16	3	| 0	
4	8	| −13		
4	| 0			
4				

Thus the transformed equation is

$$4x^4-13x^2+9=0, \quad \text{or} \quad (4x^2-9)(x^2-1)=0.$$

The roots of this equation are $+\frac{3}{2}$, $-\frac{3}{2}$, $+1$, -1; hence the roots of the proposed equation are

$$\frac{1}{2}, \quad \frac{7}{2}, \quad -1, \quad -3.$$

573. The chief use of the substitution in the preceding article is to remove some assigned term from an equation.

Let the given equation be

$$p_0x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots+p_{n-1}x+p_n=0;$$

then if $y=x-h$, we obtain the new equation

$$p_0(y+h)^n+p_1(y+h)^{n-1}+p_2(y+h)^{n-2}+\ldots+p_n=0,$$

which, when arranged in descending powers of y, becomes

$$p_0y^n+(np_0h+p_1)y^{n-1}+\left\{\frac{n(n-1)}{\underline{|2}}p_0h^2+(n-1)p_1h+p_2\right\}y^{n-2}+\ldots=0.$$

If the term to be removed is the second, we put $np_0h+p_1=0$, so that $h=-\frac{p_1}{np_0}$; if the term to be removed is the third we put

$$\frac{n(n-1)}{\underline{|2}}p_0h^2+(n-1)p_1h+p_2=0,$$

and so obtain a quadratic to find h; and similarly we may remove any other assigned term.

Sometimes it will be more convenient to proceed as in the following example.

Example. Remove the second term from the equation

$$px^3+qx^2+rx+s=0.$$

Let α, β, γ be the roots, so that $\alpha+\beta+\gamma=\frac{q}{p}$. Then if we increase each of the roots by $\frac{q}{3p}$, in the transformed equation the sum of the roots will be equal to $-\frac{q}{p}+\frac{q}{p}$; that is, the coefficient of the second term will be zero.

Hence the required transformation will be effected by substituting $x-\frac{q}{3p}$ for x in the given equation.

574. From the equation $f(x)=0$ we may form an equation whose roots are connected with those of the given equation by some assigned relation.

Let y be a root of the required equation and let $\phi(x, y)=0$ denote the assigned relation; then the transformed equation can be obtained either by expressing x as a function of y by means of the equation $\phi(x, y)=0$ and substituting this value of x in $f(x)=0$; or by eliminating x between the equations $f(x)=0$ and $\phi(x, y)=0$.

Example 1. If a, b, c are the roots of the equation $x^3+px^2+qx+r=0$, form the equation whose roots are

$$a-\frac{1}{bc},\ b-\frac{1}{ca},\ c-\frac{1}{ab}.$$

When $x=a$ in the given equation, $y=a-\frac{1}{bc}$ in the transformed equation;

but
$$a-\frac{1}{bc}=a-\frac{a}{abc}=a+\frac{a}{r};$$

and therefore the transformed equation will be obtained by the substitution

$$y=x+\frac{x}{r},\quad \text{or}\quad x=\frac{ry}{1+r};$$

thus the required equation is

$$r^2y^3+pr(1+r)y^2+q(1+r)^2y+(1+r)^3=0.$$

Example 2. Form the equation whose roots are the squares of the differences of the roots of the cubic

$$x^3+qx+r=0.$$

Let a, b, c be the roots of the cubic; then the roots of the required equation are
$$(b-c)^2,\quad (c-a)^2,\quad (a-b)^2.$$

Now $$(b-c)^2=b^2+c^2-2bc=a^2+b^2+c^2-a^2-\frac{2abc}{a}$$

$$=(a+b+c)^2-2(bc+ca+ab)-a^2-\frac{2abc}{a}$$

$$=-2q-a^2+\frac{2r}{a};$$

also when $x=a$ in the given equation, $y=(b-c)^2$ in the transformed equation;

$$\therefore\quad y=-2q-x^2+\frac{2r}{x}.$$

Thus we have to eliminate x between the equations

$$x^3+qx+r=0,$$

and $$x^3+(2q+y)x-2r=0.$$

By subtraction $$(q+y)x=3\mathrm{r};\quad \text{or}\quad x=\frac{3\mathrm{r}}{q+y}.$$

Substituting and reducing, we obtain

$$y^3+6qy^2+9q^2y+27r^2+4q^3=0.$$

Cor. If a, b, c are real, $(b-c)^2$, $(c-a)^2$, $(a-b)^2$ are all positive; therefore $27r^2+4q^3$ is negative.

Hence in order that the equation $x^3+qx+r=0$ may have all its roots real $27r^2+4q^3$ must be negative, that is $\left(\frac{r}{2}\right)^2+\left(\frac{q}{3}\right)^3$ must be negative.

If $27r^2+4q^3=0$ the transformed equation has one root zero, therefore the original equation has two equal roots.

If $27r^2+4q^3$ is positive, the transformed equation has a negative root [Art. 553], therefore the original equation must have two imaginary roots, since it is only such a pair of roots which can produce a negative root in the transformed equation.

EXAMPLES. XXXV. d.

1. Transform the equation $x^3-4x^2+\frac{1}{4}x-\frac{1}{9}=0$ into another with integral coefficients, and unity for the coefficient of the first term.

2. Transform the equation $3x^4-5x^3+x^2-x+1=0$ into another the coefficient of whose first term is unity.

Solve the equations:

3. $2x^4+x^3-6x^2+x+2=0.$

4. $x^4-10x^3+26x^2-10x+1=0.$

5. $x^5-5x^4+9x^3-9x^2+5x-1=0.$

6. $4x^6-24x^5+57x^4-73x^3+57x^2-24x+4=0.$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

Cubic Equations.

575. The general type of a cubic equation is

$$x^3 + Px^2 + Qx + R = 0,$$

but as explained in Art. 573 this equation can be reduced to the simpler form $x^3 + qx + r = 0,$

which we shall take as the standard form of a cubic equation.

576. To solve the equation $x^3 + qx + r = 0$.

Let $x = y + z$; then

$$x^3 = y^3 + z^3 + 3yz\,(y + z) = y^3 + z^3 + 3yzx,$$

and the given equation becomes

$$y^3 + z^3 + (3yz + q)\,x + r = 0.$$

At present y, z are any two quantities subject to the condition that their sum is equal to one of the roots of the given equation; if we further suppose that they satisfy the equation $3yz + q = 0$, they are completely determinate. We thus obtain

$$y^3 + z^3 = -r, \quad y^3 z^3 = -\frac{q^3}{27};$$

hence y^3, z^3 are the roots of the quadratic

$$t^2 + rt - \frac{q^3}{27} = 0.$$

Solving this equation, and putting

$$y^3 = -\frac{r}{2} + \sqrt{\frac{r^2}{4} + \frac{q^3}{27}} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (1),$$

$$z^3 = -\frac{r}{2} - \sqrt{\frac{r^2}{4} + \frac{q^3}{27}} \quad \ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots (2),$$

we obtain the value of x from the relation $x = y + z$; thus

$$x = \left\{-\frac{r}{2} + \sqrt{\frac{r^2}{4} + \frac{q^3}{27}}\right\}^{\frac{1}{3}} + \left\{-\frac{r}{2} - \sqrt{\frac{r^2}{4} + \frac{q^3}{27}}\right\}^{\frac{1}{3}}.$$

The above solution is generally known as *Cardan's Solution*, as it was first published by him in the *Ars Magna*, in 1545. Cardan obtained the solution from Tartaglia; but the solution of the cubic seems to have been due originally to Scipio Ferreo, about

1505. An interesting historical note on this subject will be found at the end of Burnside and Panton's *Theory of Equations*.

577. By Art. 110, each of the quantities on the right-hand side of equations (1) and (2) of the preceding article has three cube roots, hence it would appear that x has *nine* values; this, however, is not the case. For since $yz = -\frac{q}{3}$, the cube roots are to be taken in pairs so that the product of each pair is rational. Hence if y, z denote the values of any pair of cube roots which fulfil this condition, the only other admissible pairs will be ωy, $\omega^2 z$ and $\omega^2 y$, ωz, where ω, ω^2 are the imaginary cube roots of unity. Hence the roots of the equation are

$$y + z, \quad \omega y + \omega^2 z, \quad \omega^2 y + \omega z.$$

Example. Solve the equation $x^3 - 15x = 126$.

Put $y + z$ for x, then

$$y^3 + z^3 + (3yz - 15)\, x = 126;$$

put $$3yz - 15 = 0,$$

then $$y^3 + z^3 = 126;$$

also $$y^3 z^3 = 125;$$

hence y^3, z^3 are the roots of the equation

$$t^2 - 126t + 125 = 0;$$

$$y^3 = 125, \quad z^3 = 1;$$

$$y = 5, \quad z = 1.$$

Thus $$y + z = 5 + 1 = 6;$$

$$\omega y + \omega^2 z = \frac{-1 + \sqrt{-3}}{2} \cdot 5 + \frac{-1 - \sqrt{-3}}{2}$$

$$= -3 + 2\sqrt{-3};$$

$$\omega^2 y + \omega z = -3 - 2\sqrt{-3};$$

and the roots are $$6, \quad -3 + 2\sqrt{-3}, \quad -3 - 2\sqrt{-3}.$$

578. To explain the reason why we apparently obtain *nine* values for x in Art. 576, we observe that y and z are to be found from the equations $y^3 + z^3 + r = 0$, $yz = -\frac{q}{3}$; but in the process of solution the second of these was changed into $y^3 z^3 = -\frac{q^3}{27}$, which

would also hold if $yz = -\frac{\omega q}{3}$, or $yz = -\frac{\omega^2 q}{3}$; hence the other six values of x are solutions of the cubics

$$x^3 + \omega q x + r = 0, \quad x^3 + \omega^2 q x + r = 0.$$

579. We proceed to consider more fully the roots of the equation $x^3 + qx + r = 0$.

(i) If $\frac{r^2}{4} + \frac{q^3}{27}$ is positive, then y^3 and z^3 are both real; let y and z represent their arithmetical cube roots, then the roots are

$$y + z, \quad \omega y + \omega^2 z, \quad \omega^2 y + \omega z.$$

The first of these is real, and by substituting for ω and ω^2 the other two become

$$-\frac{y+z}{2} + \frac{y-z}{2}\sqrt{-3}, \quad -\frac{y+z}{2} - \frac{y-z}{2}\sqrt{-3}.$$

(ii) If $\frac{r^2}{4} + \frac{q^3}{27}$ is zero, then $y^3 = z^3$; in this case $y = z$, and the roots become $2y$, $y(\omega + \omega^2)$, $y(\omega + \omega^2)$, or $2y$, $-y$, $-y$.

(iii) If $\frac{r^2}{4} + \frac{q^3}{27}$ is negative, then y^3 and z^3 are imaginary expressions of the form $a + ib$ and $a - ib$. Suppose that the cube roots of these quantities are $m + in$ and $m - in$; then the roots of the cubic become

$$\begin{aligned} &m + in + m - in, && \text{or } 2m; \\ &(m + in)\omega + (m - in)\omega^2, && \text{or } -m - n\sqrt{3}; \\ &(m + in)\omega^2 + (m - in)\omega, && \text{or } -m + n\sqrt{3}; \end{aligned}$$

which are all real quantities. As however there is no general arithmetical or algebraical method of finding the exact value of the cube root of imaginary quantities [Compare Art. 89], the solution obtained in Art. 576 is of little practical use when the roots of the cubic are all real and unequal.

This case is sometimes called the *Irreducible Case* of Cardan's solution.

580. In the *irreducible case* just mentioned the solution may be completed by Trigonometry as follows. Let the solution be

$$x = (a + ib)^{\frac{1}{3}} + (a - ib)^{\frac{1}{3}};$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

by eliminating a and b from these equations, we obtain

$$(pk-r)^2=(2k+p^2-q)(k^2-s),$$

or
$$2k^3-qk^2+2(pr-s)k+p^2s-qs-r^2=0.$$

From this cubic equation one real value of k can always be found [Art. 553]; thus a and b are known. Also

$$(x^2+px+k)^2=(ax+b)^2;$$

$$\therefore\ x^2+px+k=\pm(ax+b);$$

and the values of x are to be obtained from the two quadratics

$$x^2+(p-a)x+(k-b)=0,$$

and
$$x^2+(p+a)x+(k+b)=0.$$

Example. Solve the equation

$$x^4-2x^3-5x^2+10x-3=0.$$

Add $a^2x^2+2abx+b^2$ to each side of the equation, and assume

$$x^4-2x^3+(a^2-5)x^2+2(ab+5)x+b^2-3=(x^2-x+k)^2;$$

then by equating coefficients, we have

$$a^2=2k+6,\quad ab=-k-5,\quad b^2=k^2+3;$$

$$\cdot\quad (2k+6)(k^2+3)=(k+5)^2;$$

$$\cdot\quad 2k^3+5k^2-4k-7=0.$$

By trial, we find that $k=-1$; hence $a^2=4$, $b^2=4$, $ab=-4$.

But from the assumption, it follows that

$$(x^2-x+k)^2=(ax+b)^2$$

Substituting the values of k, a and b, we have the two equations

$$x^2-x-1=\pm(2x-2);$$

that is,
$$x^2-3x+1=0,\quad \text{and}\quad x^2+x-3=0;$$

whence the roots are
$$\frac{3\pm\sqrt{5}}{2},\quad \frac{-1\pm\sqrt{13}}{2}.$$

583. The following solution was given by Descartes in 1637.

Suppose that the biquadratic equation is reduced to the form

$$x^4+qx^2+rx+s=0;$$

assume
$$x^4+qx^2+rx+s=(x^2+kx+l)(x^2-kx+m);$$

then by equating coefficients, we have

$$l+m-k^2=q, \quad k(m-l)=r, \quad lm=s.$$

From the first two of these equations, we obtain

$$2m=k^2+q+\frac{r}{k}, \qquad 2l=k^2+q-\frac{r}{k};$$

hence substituting in the third equation,

$$(k^3+qk+r)(k^3+qk-r)=4sk^2,$$

or
$$k^6+2qk^4+(q^2-4s)k^2-r^2=0.$$

This is a cubic in k^2 which always has one real positive solution [Art. 553]; thus when k^2 is known the values of l and m are determined, and the solution of the biquadratic is obtained by solving the two quadratics

$$x^2+kx+l=0, \text{ and } x^2-kx+m=0.$$

Example. Solve the equation

$$x^4-2x^2+8x-3=0.$$

Assume $x^4-2x^2+8x-3=(x^2+kx+l)(x^2-kx+m)$;

then by equating coefficients, we have

$$l+m-k^2=-2, \quad k(m-l)=8, \quad lm=-3;$$

whence we obtain $(k^3-2k+8)(k^3-2k-8)=-12k^2$,

or
$$k^6-4k^4+16k^2-64=0.$$

This equation is clearly satisfied when $k^2-4=0$, or $k=\pm 2$. It will be sufficient to consider one of the values of k; putting $k=2$, we have

$$m+l=2, \quad m-l=4; \text{ that is, } l=-1, \quad m=3.$$

Thus $x^4-2x^2+8x-3=(x^2+2x-1)(x^2-2x+3)$;

hence $x^2+2x-1=0$, and $x^2-2x+3=0$;

and therefore the roots are $-1\pm\sqrt{2}$, $1\pm\sqrt{-2}$.

584. The general algebraical solution of equations of a degree higher than the fourth has not been obtained, and Abel's demonstration of the impossibility of such a solution is generally accepted by Mathematicians. If, however, the coefficients of an equation are numerical, the value of any real root may be found to any required degree of accuracy by Horner's Method of approximation, a full account of which will be found in treatises on the *Theory of Equations*.

585. We shall conclude with the discussion of some miscellaneous equations.

Example 1. Solve the equations:

$$x+y+z+u=0,$$
$$ax+by+cz+du=0,$$
$$a^2x+b^2y+c^2z+d^2u=0,$$
$$a^3x+b^3y+c^3z+d^3u=k.$$

Multiply these equations, beginning from the lowest, by 1, p, q, r respectively; p, q, r being quantities which are at present undetermined. Assume that they are such that the coefficients of y, z, u vanish; then

$$x(a^3+pa^2+qa+r)=k,$$

whilst b, c, d are the roots of the equation

$$t^3+pt^2+qt+r=0.$$

Hence $$a^3+pa^2+qa+r=(a-b)(a-c)(a-d);$$

and therefore $$(a-b)(a-c)(a-d)\,x=k.$$

Thus the value x is found, and the values of y, z, u can be written down by symmetry.

COR. If the equations are

$$x+y+z+u=1,$$
$$ax+by+cz+du=k,$$
$$a^2x+b^2y+c^2z+d^2u=k^2,$$
$$a^3x+b^3y+c^3z+d^3u=k^3,$$

by proceeding as before, we have

$$x(a^3+pa^2+qa+r)=k^3+pk^2+qk+r;$$
$$\therefore\quad (a-b)(a-c)(a-d)\,x=(k-b)(k-c)(k-d).$$

Thus the value of x is found, and the values of y, z, u can be written down by symmetry.

The solution of the above equations has been facilitated by the use of *Undetermined Multipliers*.

Example 2. Shew that the roots of the equation

$$(x-a)(x-b)(x-c)-f^2(x-a)-g^2(x-b)-h^2(x-c)+2fgh=0$$

are all real.

From the given equation, we have

$$(x-a)\{(x-b)(x-c)-f^2\}-\{g^2(x-b)+h^2(x-c)-2fgh\}=0.$$

Let p, q be the roots of the quadratic

$$(x-b)(x-c)-f^2=0,$$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

This equation when cleared of fractions is of the *second* degree in θ, and is satisfied by the *three* values $\theta=\lambda$, $\theta=\mu$, $\theta=\nu$, in virtue of the given equations; hence it must be an identity. [Art. 310.]

To find the value of x, multiply up by $a+\theta$, and then put $a+\theta=0$;

thus
$$x=-\frac{(-a-\lambda)(-a-\mu)(-a-\nu)}{(b-a)(c-a)};$$

that is,
$$x=\frac{(a+\lambda)(a+\mu)(a+\nu)}{(a-b)(a-c)}.$$

By symmetry, we have
$$y=\frac{(b+\lambda)(b+\mu)(b+\nu)}{(b-c)(b-a)},$$

and
$$z=\frac{(c+\lambda)(c+\mu)(c+\nu)}{(c-a)(c-b)}.$$

EXAMPLES. XXXV. e.

Solve the following equations:

1. $x^3-18x=35$.

2. $x^3+72x-1720=0$.

3. $x^3+63x-316=0$.

4. $x^3+21x+342=0$.

5. $28x^3-9x^2+1=0$.

6. $x^3-15x^2-33x+847=0$.

7. $2x^3+3x^2+3x+1=0$.

8. Prove that the real root of the equation $x^3+12x-12=0$ is $2\sqrt[3]{2}-\sqrt[3]{4}$.

Solve the following equations:

9. $x^4-3x^2-42x-40=0$.

10. $x^4-10x^2-20x-16=0$.

11. $x^4+8x^3+9x^2-8x-10=0$.

12. $x^4+2x^3-7x^2-8x+12=0$.

13. $x^4-3x^2-6x-2=0$.

14. $x^4-2x^3-12x^2+10x+3=0$.

15. $4x^4-20x^3+33x^2-20x+4=0$.

16. $x^5-6x^4-17x^3+17x^2+6x-1=0$.

17. $x^4+9x^3+12x^2-80x-192=0$, which has equal roots.

18. Find the relation between q and r in order that the equation $x^3+qx+r=0$ may be put into the form $x^4=(x^2+ax+b)^2$.

Hence solve the equation
$$8x^3-36x+27=0.$$

19. If $x^3+3px^2+3qx+r$ and $x^2+2px+q$ have a common factor, shew that

$$4(p^2-q)(q^2-pr)-(pq-r)^2=0.$$

If they have two common factors, shew that

$$p^2-q=0, \quad q^2-pr=0.$$

20. If the equation $ax^3+3bx^2+3cx+d=0$ has two equal roots, shew that each of them is equal to $\dfrac{bc-ad}{2(ac-b^2)}$.

21. Shew that the equation $x^4+px^3+qx^2+rx+s=0$ may be solved as a quadratic if $r^2=p^2s$.

22. Solve the equation

$$x^6-18x^4+16x^3+28x^2-32x+8=0,$$

one of whose roots is $\sqrt{6}-2$.

23. If α, β, γ, δ are the roots of the equation

$$x^4+qx^2+rx+s=0,$$

find the equation whose roots are $\beta+\gamma+\delta+(\beta\gamma\delta)^{-1}$, &c.

24. In the equation $x^4-px^3+qx^2-rx+s=0$, prove that if the sum of two of the roots is equal to the sum of the other two $p^3-4pq+8r=0$; and that if the product of two of the roots is equal to the product of the other two $r^2=p^2s$.

25. The equation $x^5-209x+56=0$ has two roots whose product is unity: determine them.

26. Find the two roots of $x^5-409x+285=0$ whose sum is 5.

27. If a, b, c,...k are the roots of

$$x^n+p_1x^{n-1}+p_2x^{n-2}+\ldots\ldots+p_{n-1}x+p_n=0,$$

shew that

$$(1+a^2)(1+b^2)\ldots\ldots(1+k^2)=(1-p_2+p_4-\ldots)^2+(p_1-p_3+p_5-\ldots)^2.$$

28. The sum of two roots of the equation

$$x^4-8x^3+21x^2-20x+5=0$$

is 4; explain why on attempting to solve the equation from the knowledge of this fact the method fails.

MISCELLANEOUS EXAMPLES.

1. If s_1, s_2, s_3 are the sums of n, $2n$, $3n$ terms respectively of an arithmetical progression, shew that $s_3 = 3(s_2 - s_1)$.

2. Find two numbers such that their difference, sum and product, are to one another as 1, 7, 24.

3. In what scale of notation is 25 doubled by reversing the digits?

4. Solve the equations:

(1) $(x+2)(x+3)(x-4)(x-5) = 44$.

(2) $x(y+z)+2=0, \quad y(z-2x)+21=0, \quad z(2x-y)=5$.

5. In an A. P., of which a is the first term, if the sum of the first p terms $=0$, shew that the sum of the next q terms

$$= -\frac{a(p+q)q}{p-1}.$$

[R. M. A. Woolwich.]

6. Solve the equations:

(1) $(a+b)(ax+b)(a-bx) = (a^2x - b^2)(a+bx)$.

(2) $x^{\frac{1}{3}} + (2x-3)^{\frac{1}{3}} = \{12(x-1)\}^{\frac{1}{3}}$ [India Civil Service.]

7. Find an arithmetical progression whose first term is unity such that the second, tenth and thirty-fourth terms form a geometric series.

8. If α, β are the roots of $x^2 + px + q = 0$, find the values of

$$\alpha^2 + \alpha\beta + \beta^2, \ \alpha^3 + \beta^3, \ \alpha^4 + \alpha^2\beta^2 + \beta^4.$$

9. If $2x = a + a^{-1}$ and $2y = b + b^{-1}$, find the value of

$$xy + \sqrt{(x^2-1)(y^2-1)}.$$

10. Find the value of

$$\frac{(4+\sqrt{15})^{\frac{3}{2}} + (4-\sqrt{15})^{\frac{3}{2}}}{(6+\sqrt{35})^{\frac{3}{2}} - (6-\sqrt{35})^{\frac{3}{2}}}.$$

[R. M. A. Woolwich.]

11. If α and β are the imaginary cube roots of unity, shew that

$$\alpha^4 + \beta^4 + \alpha^{-1}\beta^{-1} = 0.$$

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

23. Find the sum of the products of the integers 1, 2, 3, ... n taken two at a time, and shew that it is equal to half the excess of the sum of the cubes of the given integers over the sum of their squares.

24. A man and his family consume 20 loaves of bread in a week. If his wages were raised 5 per cent., and the price of bread were raised $2\frac{1}{2}$ per cent., he would gain $6d.$ a week. But if his wages were lowered $7\frac{1}{2}$ per cent., and bread fell 10 per cent., then he would lose $1\frac{1}{2}d.$ a week: find his weekly wages and the price of a loaf.

25. The sum of four numbers in arithmetical progression is 48 and the product of the extremes is to the product of the means as 27 to 35: find the numbers.

26. Solve the equations:

(1) $a(b-c)x^2+b(c-a)x+c(a-b)=0.$

(2) $\dfrac{(x-a)(x-b)}{x-a-b}=\dfrac{(x-c)(x-d)}{x-c-d}.$ [MATH. TRIPOS.]

27. If $\sqrt{a-x}+\sqrt{b-x}+\sqrt{c-x}=0$, shew that

$$(a+b+c+3x)(a+b+c-x)=4(bc+ca+ab);$$

and if $\sqrt[3]{a}+\sqrt[3]{b}+\sqrt[3]{c}=0$, shew that $(a+b+c)^3=27abc.$

28. A train, an hour after starting, meets with an accident which detains it an hour, after which it proceeds at three-fifths of its former rate and arrives 3 hours after time: but had the accident happened 50 miles farther on the line, it would have arrived $1\frac{1}{2}$ hrs. sooner: find the length of the journey.

29. Solve the equations:

$$2x+y=2z,\ \ 9z-7x=6y,\ \ x^3+y^3+z^3=216.$$

[R. M. A. WOOLWICH.]

30. Six papers are set in examination, two of them in mathematics: in how many different orders can the papers be given, provided only that the two mathematical papers are not successive?

31. In how many ways can £5. 4$s.$ 2$d.$ be paid in exactly 60 coins, consisting of half-crowns, shillings and fourpenny-pieces?

32. Find a and b so that $x^3+ax^2+11x+6$ and $x^3+bx^2+14x+8$ may have a common factor of the form $x^2+px+q.$

[LONDON UNIVERSITY.]

33. In what time would A, B, C together do a work if A alone could do it in six hours more, B alone in one hour more, and C alone in twice the time?

34. If the equations $ax+by=1$, $cx^2+dy^2=1$ have only one solution prove that $\frac{a^2}{c}+\frac{b^2}{d}=1$, and $x=\frac{a}{c}$, $y=\frac{b}{d}$. [MATH. TRIPOS.]

35. Find by the Binomial Theorem the first five terms in the expansion of $(1-2x+2x^2)^{-\frac{1}{2}}$.

36. If one of the roots of $x^2+px+q=0$ is the square of the other, shew that $p^3-q(3p-1)+q^2=0$.

[PEMB. COLL. CAMB.]

37. Solve the equation

$$x^4-5x^2-6x-5=0.$$

[QUEEN'S COLL. OX.]

38. Find the value of a for which the fraction

$$\frac{x^3-ax^2+19x-a-4}{x^3-(a+1)\,x^2+23x-a-7}$$

admits of reduction. Reduce it to its lowest terms. [MATH. TRIPOS.]

39. If a, b, c, x, y, z are real quantities, and

$$(a+b+c)^2=3(bc+ca+ab-x^2-y^2-z^2),$$

shew that $a=b=c$, and $x=0$, $y=0$, $z=0$.

[CHRIST'S COLL. CAMB.]

40. What is the greatest term in the expansion of $\left(1-\frac{2}{3}x\right)^{-\frac{3}{2}}$ when the value of x is $\frac{6}{7}$? [EMM. COLL. CAMB.]

41. Find two numbers such that their sum multiplied by the sum of their squares is 5500, and their difference multiplied by the difference of their squares is 352. [CHRIST'S COLL. CAMB.]

42. If $x=\lambda a$, $y=(\lambda-1)\,b$, $z=(\lambda-3)\,c$, $\lambda=\frac{1+b^2+3c^2}{a^2+b^2+c^2}$, express $x^2+y^2+z^2$ in its simplest form in terms of a, b, c.

[SIDNEY COLL. CAMB.]

43. Solve the equations:

(1) $x^4+3x^2=16x+60$.

(2) $y^2+z^2-x=z^2+x^2-y=x^2+y^2-z=1$.

[CORPUS COLL. OX.]

44. If x, y, z are in harmonical progression, shew that

$$\log(x+z)+\log(x-2y+z)=2\log(x-z).$$

45. Shew that

$$\frac{1}{2}+\frac{1.3}{2.4}\left(\frac{1}{4}\right)+\frac{1.3.5}{2.4.6}\left(\frac{1}{4}\right)^2+\ldots\ldots=\frac{4}{3}(2-\sqrt{3})\sqrt{3}.$$

[EMM. COLL. CAMB.]

46. If $$\frac{3x+2y}{3a-2b}=\frac{3y+2z}{3b-2c}=\frac{3z+2x}{3c-2a},$$

then will $$5(x+y+z)(5c+4b-3a)=(9x+8y+13z)(a+b+c).$$

[CHRIST'S COLL. CAMB.]

47. With 17 consonants and 5 vowels, how many words of four letters can be formed having 2 different vowels in the middle and 1 consonant (repeated or different) at each end?

48. A question was lost on which 600 persons had voted; the same persons having voted again on the same question, it was carried by twice as many as it was before lost by, and the new majority was to the former as 8 to 7: how many changed their minds? [ST JOHN'S COLL. CAMB.]

49. Shew that

$$\log\frac{(1+x)^{\frac{1-x}{2}}}{(1-x)^{\frac{1+x}{2}}}=x+\frac{5x^3}{2.3}+\frac{9x^5}{4.5}+\frac{13x^7}{6.7}+\ldots$$

[CHRIST'S COLL. CAMB.]

50. A body of men were formed into a hollow square, three deep, when it was observed, that with the addition of 25 to their number a solid square might be formed, of which the number of men in each side would be greater by 22 than the square root of the number of men in each side of the hollow square: required the number of men.

51. Solve the equations:

(1) $\sqrt[m]{(a+x)^2}+2\sqrt[m]{(a-x)^2}=3\sqrt[m]{a^2-x^2}$.

(2) $(x-a)^{\frac{1}{2}}(x-b)^{\frac{1}{2}}-(x-c)^{\frac{1}{2}}(x-d)^{\frac{1}{2}}=(a-c)^{\frac{1}{2}}(b-d)^{\frac{1}{2}}$

52. Prove that

$$\sqrt[3]{4}=1+\frac{2}{6}+\frac{2.5}{6.12}+\frac{2.5.8}{6.12.18}+\ldots\ldots$$

[SIDNEY COLL. CAMB.]

53. Solve $\sqrt[3]{6(5x+6)}-\sqrt[3]{5(6x-11)}=1$.

[QUEENS' COLL. CAMB.]

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

65. If the roots of the equation

$$\left(1-q+\frac{p^2}{2}\right)x^2+p\,(1+q)\,x+q\,(q-1)+\frac{p^2}{2}=0$$

are equal, shew that $p^2=4q$. [R. M. A. WOOLWICH.]

66. If $a^2+b^2=7ab$, shew that

$$\log\left\{\frac{1}{3}(a+b)\right\}=\frac{1}{2}(\log a+\log b).$$

[QUEEN'S COLL. OX.]

67. If n is a root of the equation

$$x^2(1-ac)-x(a^2+c^2)-(1+ac)=0,$$

and if n harmonic means are inserted between a and c, shew that the difference between the first and last mean is equal to $ac(a-c)$.

[WADHAM COLL. OX.]

68. If ${}^{n+2}C_8 : {}^{n-2}P_4=57:16$, find n.

69. A person invests a certain sum in a $6\frac{1}{2}$ per cent. Government loan: if the price had been £3 less he would have received $\frac{1}{3}$ per cent. more interest on his money; at what price was the loan issued?

70. Solve the equation:

$$\{(x^2+x+1)^3-(x^2+1)^3-x^3\}\,\{(x^2-x+1)^3-(x^2+1)^3+x^3\}$$
$$-3\{(x^4+x^2+1)^3-(x^4+1)^3-x^6\}.$$

[MERTON COLL. OX.]

71. If by eliminating x between the equation

$$x^2+ax+b=0 \quad \text{and} \quad xy+l(x+y)+m=0,$$

a quadratic in y is formed whose roots are the same as those of the original quadratic in x, then either $a=2l$, and $b=m$, or $b+m=al$.

[R. M. A. WOOLWICH.]

72. Given $\log 2=\cdot30103$, and $\log 3=\cdot47712$, solve the equations:

(1) $6^x=\frac{10}{3}-6^{-x}$ (2) $\sqrt{5^x}+\sqrt{5^{-x}}=\frac{29}{10}$.

73. Find two numbers such that their sum is 9, and the sum of their fourth powers 2417. [LONDON UNIVERSITY.]

74. *A* set out to walk at the rate of 4 miles an hour; after he had been walking $2\frac{3}{4}$ hours, *B* set out to overtake him and went $4\frac{1}{2}$ miles the first hour, $4\frac{3}{4}$ miles the second, 5 the third, and so gaining a quarter of a mile every hour. In how many hours would he overtake *A*?

75. Prove that the integer next above $(\sqrt{3}+1)^{2m}$ contains 2^{m+1} as a factor.

76. The series of natural numbers is divided into groups 1 ; 2, 3, 4 ; 5, 6, 7, 8, 9 ; and so on : prove that the sum of the numbers in the n^{th} group is $(n-1)^3+n^3$.

77. Shew that the sum of n terms of the series

$$\frac{1}{2}+\frac{1}{\underline{|2}}\left(\frac{1}{2}\right)^2+\frac{1.3}{\underline{|3}}\left(\frac{1}{2}\right)^3+\frac{1.3.5}{\underline{|4}}\left(\frac{1}{2}\right)^4+\ldots\ldots$$

is equal to $1-\dfrac{1.3.5.7\ldots\ldots(2n-1)}{2^n\,\underline{|n}}$.

[R. M. A. Woolwich.]

78. Shew that the coefficient of x^n in the expansion of $\dfrac{1+2x}{1-x+x^2}$ is

$$(-1)^{\frac{n}{3}},\ 3(-1)^{\frac{n-1}{3}},\ 2(-1)^{\frac{n-2}{3}},$$

according as n is of the form $3m$, $3m+1$, $3m+2$.

79. Solve the equations :

(1) $\dfrac{x}{a}=\dfrac{y}{b}=\dfrac{z}{c}=\dfrac{xyz}{x+y+z}$.

(2) $\dfrac{x}{y}+\dfrac{y}{z}+\dfrac{z}{x}=\dfrac{y}{x}+\dfrac{z}{y}+\dfrac{x}{z}=x+y+z=3$.

[Univ. Coll. Ox.]

80. The value of xyz is $7\frac{1}{2}$ or $3\frac{3}{5}$ according as the series a, x, y, z, b is arithmetic or harmonic : find the values of a and b assuming them to be positive integers. [Merton Coll. Ox.]

81. If $ay-bx=c\sqrt{(x-a)^2+(y-b)^2}$, shew that no real values of x and y will satisfy the equation unless $c^2<a^2+b^2$.

82. If $(x+1)^2$ is greater than $5x-1$ and less than $7x-3$, find the integral value of x.

83. If P is the number of integers whose logarithms have the characteristic p, and Q the number of integers the logarithms of whose reciprocals have the characteristic $-q$, shew that

$$\log_{10}P-\log_{10}Q=p-q+1.$$

84. In how many ways may 20 shillings be given to 5 persons so that no person may receive less than 3 shillings ?

85. A man wishing his two daughters to receive equal portions when they came of age bequeathed to the elder the accumulated interest of a certain sum of money invested at the time of his death in 4 per cent. stock at 88 ; and to the younger he bequeathed the accumulated interest of a sum less than the former by £3500 invested at the same time in the 3 per cents. at 63. Supposing their ages at the time of their father's death to have been 17 and 14, what was the sum invested in each case, and what was each daughter's fortune ?

86. A number of three digits in scale 7 when expressed in scale 9 has its digits reversed in order: find the number.

[ST JOHN'S COLL. CAMB.]

87. If the sum of m terms of an arithmetical progression is equal to the sum of the next n terms, and also to the sum of the next p terms; prove that $(m+n)\left(\frac{1}{m}-\frac{1}{p}\right)=(m+p)\left(\frac{1}{m}-\frac{1}{n}\right)$.

[ST JOHN'S COLL. CAMB.]

88. Prove that

$$\frac{1}{(y-z)^2}+\frac{1}{(z-x)^2}+\frac{1}{(x-y)^2}=\left(\frac{1}{y-z}+\frac{1}{z-x}+\frac{1}{x-y}\right)^2.$$

[R. M. A. WOOLWICH.]

89. If m is negative, or positive and greater than 1, shew that

$$1^m+3^m+5^m+\ldots\ldots+(2n-1)^m>n^{m+1}$$

[EMM. COLL. CAMB.]

90. If each pair of the three equations

$$x^2-p_1x+q_1=0,\quad x^2-p_2x+q_2=0,\quad x^2-p_3x+q_3=0,$$

have a common root, prove that

$$p_1^2+p_2^2+p_3^2+4(q_1+q_2+q_3)=2(p_2p_3+p_3p_1+p_1p_2).$$

[ST JOHN'S COLL. CAMB.]

91. A and B travelled on the same road and at the same rate from Huntingdon to London. At the 50th milestone from London, A overtook a drove of geese which were proceeding at the rate of 3 miles in 2 hours; and two hours afterwards met a waggon, which was moving at the rate of 9 miles in 4 hours. B overtook the same drove of geese at the 45th milestone, and met the waggon exactly 40 minutes before he came to the 31st milestone. Where was B when A reached London?

[ST JOHN'S COLL. CAMB.]

92. If $a+b+c+d=0$, prove that

$$abc+bcd+cda+dab=\sqrt{(bc-ad)(ca-bd)(ab-cd)}.$$

[R. M. A. WOOLWICH.]

93. An A. P., a G. P., and an H. P. have a and b for their first two terms: shew that their $(n+2)$th terms will be in G. P. if

$$\frac{b^{2n+2}-a^{2n+2}}{ba(b^{2n}-a^{2n})}=\frac{n+1}{n}$$

[MATH. TRIPOS.]

94. Shew that the coefficient of x^n in the expansion of $\frac{x}{(x-a)(x-b)}$ in ascending power of x is $\frac{a^n-b^n}{a-b}\cdot\frac{1}{a^nb^n}$; and that the coefficient of x^{2n} in the expansion of $\frac{(1+x^2)^n}{(1-x)^3}$ is $2^{n-1}(n^2+4n+2)$.

[EMM. COLL. CAMB.]

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

105. Shew that the expansion of $\sqrt{\frac{1-\sqrt{1-x^2}}{2}}$

is $$\frac{x}{2}+\frac{1.3}{2.4}\cdot\frac{x^3}{6}+\frac{1.3.5.7}{2.4.6.8}\cdot\frac{x^5}{10}+\ldots\ldots$$

106. If α, β are roots of the equations

$$x^2+px+q=0, \quad x^{2n}+p^nx^n+q^n=0,$$

where n is an even integer, shew that $\frac{\alpha}{\beta}, \frac{\beta}{\alpha}$ are roots of

$$x^n+1+(x+1)^n=0.$$ [PEMB. COLL. CAMB.]

107. Find the difference between the squares of the infinite continued fractions

$$a+\frac{b}{2a+}\,\frac{b}{2a+}\,\frac{b}{2a+}\ldots\ldots, \quad \text{and} \quad c+\frac{d}{2c+}\,\frac{d}{2c+}\,\frac{d}{2c+}\ldots\ldots$$

[CHRIST'S COLL. CAMB.]

108. A sum of money is distributed amongst a certain number of persons. The second receives 1*s.* more than the first, the third 2*s.* more than the second, the fourth 3*s.* more than the third, and so on. If the first person gets 1*s.* and the last person £3. 7*s.*, what is the number of persons and the sum distributed?

109. Solve the equations·

(1) $$\frac{x}{a}+\frac{y+z}{b+c}=\frac{y}{b}+\frac{z+x}{c+a}=\frac{z}{c}+\frac{x+y}{a+b}=2.$$

(2) $$\frac{x^2+y^2}{xy}+x^2+y^2=13\tfrac{1}{3}, \quad \frac{xy}{x^2+y^2}+xy=3\tfrac{3}{10}.$$

110. If a and b are positive and unequal, prove that

$$a^n-b^n>n(a-b)(ab)^{\frac{n-1}{2}}$$

[ST CATH. COLL. CAMB.]

111. Express $\frac{763}{396}$ as a continued fraction; hence find the least values of x and y which satisfy the equation $396x-763y=12$.

112. To complete a certain work, a workman A alone would take m times as many days as B and C working together; B alone would take n times as many days as A and C together; C alone would take p times as many days as A and B together: shew that the numbers of days in which each would do it alone are as $m+1 : n+1 : p+1$.

Prove also $$\frac{m}{m+1}+\frac{n}{n+1}+\frac{p}{p+1}=2.$$ [R. M. A. WOOLWICH.]

113. The expenses of a hydropathic establishment are partly constant and partly vary with the number of boarders. Each boarder pays £65 a year, and the annual profits are £9 a head when there are 50 boarders, and £10. 13*s.* 4*d.* when there are 60: what is the profit on each boarder when there are 80?

114. If $x^2y=2x-y$, and x^2 is not greater than 1, shew that

$$4\left(x^2+\frac{x^6}{3}+\frac{x^{10}}{5}+\ldots\right)=y^2+\frac{y^4}{2}+\frac{y^6}{3}+\ldots$$

[PETERHOUSE, CAMB.]

115. If $\frac{x}{a^2-y^2}=\frac{y}{a^2-x^2}=\frac{1}{b}$, and $xy=c^2$, shew that when a and c are unequal,

$$(a^2-c^2)^2-b^2c^2=0, \text{ or } a^2+c^2-b^2=0.$$

116. If $$(1+x+x^2)^{3r}=1+k_1x+k_2x^2+$$

and $$(x-1)^{3r}=x^{3r}-c_1x^{3r-1}+c_2x^{3r-2} \quad \ldots,$$

prove that (1) $1-k_1+k_2-\ldots\ldots-1$,

(2) $1-k_1c_1+k_2c_2-\ldots\ldots=\pm\frac{\lfloor 3r}{\lfloor r \lfloor 2r}$.

[R. M. A. WOOLWICH.]

117. Solve the equations:

(1) $(x-y)^2+2ab=ax+by, \quad xy+ab=bx+ay.$

(2) $x^2-y^2+z^2=6, \quad 2yz-zx+2xy=13, \quad x-y+z=2.$

118. If there are n positive quantities $a_1, a_2, \ldots a_n$, and if the square roots of all their products taken two together be found, prove that

$$\sqrt{a_1a_2}+\sqrt{a_1a_3}+\ldots\ldots<\frac{n-1}{2}(a_1+a_2+\ldots\ldots+a_n);$$

hence prove that the arithmetic mean of the square roots of the products two together is less than the arithmetic mean of the given quantities. [R. M. A. WOOLWICH.]

119. If $b^2x^4+a^2y^4=a^2b^2$, and $a^2+b^2=x^2+y^2=1$, prove that

$$b^4x^6+a^4y^6=(b^2x^4+a^2y^4)^2.$$ [INDIA CIVIL SERVICE.]

120. Find the sum of the first n terms of the series whose r^{th} terms are (1) $\frac{2r+1}{r^2(r+1)^2}$, (2) $(a+r^2b)\,x^{n-r}$.

[ST JOHN'S COLL. CAMB.]

121. Find the greatest value of $\frac{x+2}{2x^2+3x+6}$.

122. Solve the equations:

(1) $1+x^4=7(1+x)^4$.

(2) $3xy+2z=xz+6y=2yz+3x=0$.

123. If a_1, a_2, a_3, a_4 are any four consecutive coefficients of an expanded binomial, prove that

$$\frac{a_1}{a_1+a_2}+\frac{a_3}{a_3+a_4}=\frac{2a_2}{a_2+a_3}.$$ [QUEENS' COLL. CAMB.]

124. Separate $\dfrac{x^3+7x^2-x-8}{(x^2+x+1)(x^2-3x-1)}$ into partial fractions; and find the general term when $\dfrac{3x-8}{x^2-4x-4}$ is expanded in ascending powers of x.

125. In the recurring series

$$\frac{5}{4}-\frac{1}{2}x+2x^2+lx^3+5x^4+7x^5+\ldots\ldots$$

the scale of relation is a quadratic expression; determine the unknown coefficient of the fourth term and the scale of relation, and give the general term of the series. [R. M. A. WOOLWICH.]

126. If x, y, z are unequal, and if

$$2a-3y=\frac{(z-x)^2}{y}, \text{ and } 2a-3z=\frac{(x-y)^2}{z},$$

then will $$2a-3x=\frac{(y-z)^2}{x}, \text{ and } x+y+z=a.$$ [MATH. TRIPOS.]

127. Solve the equations:

(1) $xy+6=2x-x^2$, $xy-9=2y-y^2$.

(2) $(ax)^{\log a}=(by)^{\log b}$, $b^{\log x}=a^{\log y}$.

128. Find the limiting values of

(1) $x\sqrt{x^2+a^2}-\sqrt{x^4+a^4}$, when $x=\infty$.

(2) $\dfrac{\sqrt{a+2x}-\sqrt{3x}}{\sqrt{3a+x}-2\sqrt{x}}$, when $x=a$. [LONDON UNIVERSITY.]

129. There are two numbers whose product is 192, and the quotient of the arithmetical by the harmonical mean of their greatest common measure and least common multiple is $3\frac{2}{4}\frac{5}{8}$: find the numbers.
[R. M. A. WOOLWICH.]

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

139. Sum to n terms:

(1) $(2n-1)+2(2n-3)+3(2n-5)+\ldots.$

(2) The squares of the terms of the series 1, 3, 6, 10, 15....

(3) The odd terms of the series in (2). [TRIN. COLL. CAMB.]

140. If α, β, γ are the roots of the equation $x^3+qx+r=0$ prove that $3(\alpha^2+\beta^2+\gamma^2)(\alpha^5+\beta^5+\gamma^5)=5(\alpha^3+\beta^3+\gamma^3)(\alpha^4+\beta^4+\gamma^4)$.
[ST JOHN'S COLL. CAMB.]

141. Solve the equations:

(1) $\left.\begin{aligned} x(3y-5)&=4 \\ y(2x+7)&=27 \end{aligned}\right\}$.

(2) $\left.\begin{aligned} x^3+y^3+z^3&=495 \\ x+y+z&=15 \\ xyz&=105 \end{aligned}\right\}$.

[TRIN. COLL. CAMB.]

142. If a, b, c are the roots of the equation $x^3+qx^2+r=0$, form the equation whose roots are $a+b-c$, $b+c-a$, $c+a-b$.

143. Sum the series:

(1) $n+(n-1)x+(n-2)x^2+\ldots+2x^{n-2}+x^{n-1}$;

(2) $3-x-2x^2-16x^3-28x^4-676x^5+\ldots$ to infinity;

(3) $6+9+14+23+40+\ldots$ to n terms.
[OXFORD MODS.]

144. Eliminate x, y, z from the equations

$$x^{-1}+y^{-1}+z^{-1}=a^{-1}, \quad x+y+z=b.$$

$$x^2+y^2+z^2=c^2, \quad x^3+y^3+z^3=d^3,$$

and shew that if x, y, z are all finite and numerically unequal, b cannot be equal to d. [R. M. A. WOOLWICH.]

145. The roots of the equation $3x^2(x^2+8)+16(x^3-1)=0$ are not all unequal: find them. [R. M. A. WOOLWICH.]

146. A traveller set out from a certain place, and went 1 mile the first day, 3 the second, 5 the next, and so on, going every day 2 miles more than he had gone the preceding day. After he had been gone three days, a second sets out, and travels 12 miles the first day, 13 the second, and so on. In how many days will the second overtake the first? Explain the double answer.

147. Find the value of

$$\frac{1}{3+}\,\frac{1}{2+}\,\frac{1}{1+}\,\frac{1}{3+}\,\frac{1}{2+}\,\frac{1}{1+}\ldots.$$

148. Solve the equation

$$x^3+3ax^2+3(a^2-bc)x+a^3+b^3+c^3-3abc=0.$$

[INDIA CIVIL SERVICE.]

149. If n is a prime number which will divide neither a, b, nor $a+b$, prove that $a^{n-2}b-a^{n-3}b^2+a^{n-4}b^3-\quad+ab^{n-2}$ exceeds by 1 a multiple of n. [ST JOHN'S COLL. CAMB.]

150. Find the n^{th} term and the sum to n terms of the series whose sum to infinity is $(1-abx^2)(1-ax)^{-2}(1-bx)^{-2}$.

[OXFORD MODS.]

151. If a, b, c are the roots of the equation $x^3+px+q=0$, find the equation whose roots are $\dfrac{b^2+c^2}{a}$, $\dfrac{c^2+a^2}{b}$, $\dfrac{a^2+b^2}{c}$.

[TRIN. COLL. CAMB.]

152. Prove that

$$(y+z-2x)^4+(z+x-2y)^4+(x+y-2z)^4=18(x^2+y^2+z^2-yz-zx-xy)^2.$$

[CLARE COLL. CAMB.]

153. Solve the equations:

(1) $x^3-30x+133=0$, by Cardan's method.

(2) $x^5-4x^4-10x^3+40x^2+9x-36=0$, having roots of the form

$$\pm a,\ \pm b,\ c.$$

154. It is found that the quantity of work done by a man in an hour varies directly as his pay per hour and inversely as the square root of the number of hours he works per day. He can finish a piece of work in six days when working 9 hours a day at 1*s.* per hour. How many days will he take to finish the same piece of work when working 16 hours a day at 1*s.* 6*d.* per hour?

155. If s_n denote the sum to n terms of the series

$$1.2+2.3+3.4+\ldots,$$

and σ_{n-1} that to $n-1$ terms of the series

$$\frac{1}{1.2.3.4}+\frac{1}{2.3.4.5}+\frac{1}{3.4.5.6}+\ldots,$$

shew that $$18s_n\sigma_{n-1}-s_n+2=0.$$

[MAGD. COLL. OX.]

156. Solve the equations:

(1) $(12x-1)(6x-1)(4x-1)(3x-1)=5.$

(2) $$\frac{1}{5}\frac{(x+1)(x-3)}{(x+2)(x-4)}+\frac{1}{9}\frac{(x+3)(x-5)}{(x+4)(x-6)}-\frac{2}{13}\frac{(x+5)(x-7)}{(x+6)(x-8)}=\frac{92}{585}.$$

[ST JOHN'S COLL. CAMB.]

157. A cottage at the beginning of a year was worth £250, but it was found that by dilapidations at the end of each year it lost ten per cent. of the value it had at the beginning of each year after what number of years would the value of the cottage be reduced below £25? Given $\log_{10} 3 = \cdot 4771213$. [R. M. A. WOOLWICH.]

158. Shew that the infinite series

$$1+\frac{1}{4}+\frac{1.4}{4.8}+\frac{1.4.7}{4.8.12}+\frac{1.4.7.10}{4.8.12.16}+\ldots,$$

$$1+\frac{2}{6}+\frac{2.5}{6.12}+\frac{2.5.8}{6.12.18}+\frac{2.5.8.11}{6.12.18.24}+\ldots,$$

are equal. [PETERHOUSE, CAMB.]

159. Prove the identity

$$\left\{1-\frac{x}{a}+\frac{x(x-a)}{a\beta}-\frac{x(x-a)(x-\beta)}{a\beta\gamma}+\ldots\right\}$$
$$\left\{1+\frac{x}{a}+\frac{x(x+a)}{a\beta}+\frac{x(x+a)(x+\beta)}{a\beta\gamma}+\ldots\right\}$$
$$=1-\frac{x^2}{a^2}+\frac{x^2(x^2-a^2)}{a^2\beta^2}-\frac{x^2(x^2-a^2)(x^2-\beta^2)}{a^2\beta^2\gamma^2}+\ldots.$$

[TRIN. COLL. CAMB.]

160. If n is a positive integer greater than 1, shew that

$$n^5-5n^3+60n^2-56n$$

is a multiple of 120. [WADHAM COLL. OX.]

161. A number of persons were engaged to do a piece of work which would have occupied them 24 hours if they had commenced at the same time; but instead of doing so, they commenced at equal intervals and then continued to work till the whole was finished, the payment being proportional to the work done by each: the first comer received eleven times as much as the last; find the time occupied.

162. Solve the equations:

(1) $$\frac{x}{y^2-3}=\frac{y}{x^2-3}=\frac{-7}{x^3+y^3}.$$

(2) $$y^2+z^2-x(y+z)=a^2,$$
$$z^2+x^2-y(z+x)=b^2,$$
$$x^2+y^2-z(x+y)=c^2.$$

[PEMB. COLL. CAMB.]

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

171. Shew that $n^7-7n^5+14n^3-8n$ is divisible by 840, if n is an integer not less than 3.

172. Solve the equations:

(1) $\sqrt{x^2+12y}+\sqrt{y^2+12x}=33,\ x+y=23.$

(2) $\dfrac{u(y-x)}{z-u}=a,\ \dfrac{z(y-x)}{z-u}=b,\ \dfrac{y(u-z)}{x-y}=c,\ \dfrac{x(u-z)}{x-y}=d.$

[MATH. TRIPOS.]

173. If s be the sum of n positive unequal quantities $a, b, c\ldots$, then

$$\frac{s}{s-a}+\frac{s}{s-b}+\frac{s}{s-c}+\ldots>\frac{n^2}{n-1}.$$ [MATH. TRIPOS.]

174. A merchant bought a quantity of cotton; this he exchanged for oil which he sold. He observed that the number of cwt. of cotton, the number of gallons of oil obtained for each cwt., and the number of shillings for which he sold each gallon formed a descending geometrical progression. He calculated that if he had obtained one cwt. more of cotton, one gallon more of oil for each cwt., and 1*s.* more for each gallon, he would have obtained £508. 9*s.* more; whereas if he had obtained one cwt. less of cotton, one gallon less of oil for each cwt., and 1*s.* less for each gallon, he would have obtained £483. 13*s.* less: how much did he actually receive?

175. Prove that

$$\Sigma(b+c-a-x)^4(b-c)(a-x)=16(b-c)(c-a)(a-b)(x-a)(x-b)(x-c).$$

[JESUS COLL. CAMB.]

176. If α, β, γ are the roots of the equation $x^3-px^2+r=0$, find the equation whose roots are $\dfrac{\beta+\gamma}{\alpha}, \dfrac{\gamma+\alpha}{\beta}, \dfrac{\alpha+\beta}{\gamma}$. [R. M. A. WOOLWICH.]

177. If any number of factors of the form a^2+b^2 are multiplied together, shew that the product can be expressed as the sum of two squares.

Given that $(a^2+b^2)(c^2+d^2)(e^2+f^2)(g^2+h^2)=p^2+q^2$, find p and q in terms of a, b, c, d, e, f, g, h. [LONDON UNIVERSITY.]

178. Solve the equations

$$x^2+y^2=61,\ x^3-y^3=91.$$ [R. M. A. WOOLWICH.]

179. A man goes in for an Examination in which there are four papers with a maximum of m marks for each paper; shew that the number of ways of getting $2m$ marks on the whole is

$$\frac{1}{3}(m+1)(2m^2+4m+3).$$ [MATH. TRIPOS.]

180. If α, β are the roots of $x^2+px+1=0$, and γ, δ are the roots of $x^2+qx+1=0$; shew that $(\alpha-\gamma)(\beta-\gamma)(\alpha+\delta)(\beta+\delta)=q^2-p^2$.

[R. M. A. WOOLWICH.]

181. Shew that if a_m be the coefficient of x^m in the expansion of $(1+x)^n$, then whatever n be,

$$a_0-a_1+a_2-\ldots+(-1)^{m-1}a_{m-1}=\frac{(n-1)(n-2)\ldots(n-m+1)}{\lfloor m-1}(-1)^{m-1}$$

[NEW COLL. OX.]

182. A certain number is the product of three prime factors, the sum of whose squares is 2331. There are 7560 numbers (including unity) which are less than the number and prime to it. The sum of its divisors (including unity and the number itself) is 10560. Find the number. [CORPUS COLL. CAMB.]

183. Form an equation whose roots shall be the products of every two of the roots of the equation $x^3-ax^2+bx+c=0$.

Solve completely the equation

$$2x^5+x^4+x+2=12x^3+12x^2.$$

[R. M. A. WOOLWICH.]

184. Prove that if n is a positive integer,

$$n^n-n(n-2)^n+\frac{n(n-1)}{\lfloor 2}(n-4)^n-\ldots\ldots=2^n\lfloor n.$$

185. If $(6\sqrt{6}+14)^{2n+1}=N$, and if F be the fractional part of N, prove that $NF=20^{2n+1}$ [EMM. COLL. CAMB.]

186. Solve the equations:

(1) $x+y+z=2,\ x^2+y^2+z^2=0,\ x^3+y^3+z^3=-1.$

(2) $x^2-(y-z)^2=a^2,\ y^2-(z-x)^2=b^2,\ z^2-(x-y)^2=c^2.$

[CHRIST'S COLL. CAMB.]

187. At a general election the whole number of Liberals returned was 15 more than the number of English Conservatives, the whole number of Conservatives was 5 more than twice the number of English Liberals. The number of Scotch Conservatives was the same as the number of Welsh Liberals, and the Scotch Liberal majority was equal to twice the number of Welsh Conservatives, and was to the Irish Liberal majority as 2 : 3. The English Conservative majority was 10 more than the whole number of Irish members. The whole number of members was 652, of whom 60 were returned by Scotch constituencies. Find the numbers of each party returned by England, Scotland, Ireland, and Wales, respectively. [ST JOHN'S COLL. CAMB.]

188. Shew that $a^5(c-b)+b^5(a-c)+c^5(b-a)$

$$=(b-c)(c-a)(a-b)(\Sigma a^3+\Sigma a^2b+abc).$$

189. Prove that $\begin{vmatrix} a^3 & 3a^2 & 3a & 1 \\ a^2 & a^2+2a & 2a+1 & 1 \\ a & 2a+1 & a+2 & 1 \\ 1 & 3 & 3 & 1 \end{vmatrix} = (a-1)^6$. [BALL. COLL. OX.]

190. If $\frac{1}{a}+\frac{1}{c}+\frac{1}{a-b}+\frac{1}{c-b}=0$, prove that a, b, c are in harmonical progression, unless $b=a+c$. [TRIN. COLL. CAMB.]

191. Solve the equations:

(1) $x^3-13x^2+15x+189=0$, having given that one root exceeds another root by 2.

(2) $x^4-4x^2+8x+35=0$, having given that one root is $2+\sqrt{-3}$. [R. M. A. WOOLWICH.]

192. Two numbers a and b are given; two others a_1, b_1 are formed by the relations $3a_1=2a+b$, $3b_1=a+2b$; two more a_2, b_2 are formed from a_1, b_1 in the same manner, and so on; find a_n, b_n in terms of a and b, and prove that when n is infinite, $a_n=b_n$. [R. M. A. WOOLWICH.]

193. If $x+y+z+w=0$, shew that

$$wx(w+x)^2+yz(w-x)^2+wy(w+y)^2$$
$$+zx(w-y)^2+wz(w+z)^2+xy(w-z)^2+4xyzw=0.$$

[MATH. TRIPOS.]

194. If $a+\frac{bc-a^2}{a^2+b^2+c^2}$ be not altered in value by interchanging a pair of the letters a, b, c not equal to each other, it will not be altered by interchanging any other pair; and it will vanish if $a+b+c=1$.

[MATH. TRIPOS.]

195. On a quadruple line of rails between two termini A and B, two down trains start at 6.0 and 6.45, and two up trains at 7.15 and 8.30. If the four trains (regarded as points) all pass one another simultaneously, find the following equations between x_1, x_2, x_3, x_4, their rates in miles per hour,

$$\frac{3x_2}{x_2-x_1}=\frac{4m+5x_3}{x_1+x_3}=\frac{4m+10x_4}{x_1+x_4},$$

where m is the number of miles in AB. [TRIN. COLL. CAMB.]

196. Prove that, rejecting terms of the third and higher orders,

$$\frac{(1-x)^{-\frac{1}{2}}+(1-y)^{-\frac{1}{2}}}{1+\sqrt{(1-x)(1-y)}}=1+\frac{1}{2}(x+y)+\frac{1}{8}(3x^2+xy+3y^2).$$

[TRIN. COLL. CAMB.]

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

206. If α, β, γ are the roots of $x^3+qx+r=0$, find the value of

$$\frac{m\alpha+n}{m\alpha-n}+\frac{m\beta+n}{m\beta-n}+\frac{m\gamma+n}{m\gamma-n}$$

in terms of m, n, q, r. [QUEENS' COLL. CAMB.]

207. In England one person out of 46 is said to die every year, and one out of 33 to be born. If there were no emigration, in how many years would the population double itself at this rate? Given

$$\log 2=\cdot 3010300,\ \log 1531=3\cdot 1849752,\ \log 1518=3\cdot 1812718.$$

208. If $(1+x+x^2)^n=a_0+a_1x+a_2x^2+\ldots\ldots$, prove that

$$a_r-na_{r-1}+\frac{n(n-1)}{1.2}a_{r-2}-\ldots\ldots+(-1)^r\frac{n!}{r!\,(n-r)!}a_0=0,$$

unless r is a multiple of 3. What is its value in this case?

[ST JOHN'S COLL. CAMB.]

209. In a mixed company consisting of Poles, Turks, Greeks, Germans and Italians, the Poles are one less than one-third of the number of Germans, and three less than half the number of Italians. The Turks and Germans outnumber the Greeks and Italians by 3; the Greeks and Germans form one less than half the company; while the Italians and Greeks form seven-sixteenths of the company: determine the number of each nation.

210. Find the sum to infinity of the series whose n^{th} term is

$$(n+1)n^{-1}(n+2)^{-1}(-x)^{n+1}$$ [OXFORD MODS.]

211. If n is a positive integer, prove that

$$n-\frac{n(n^2-1)}{\underline{|2}}+\frac{n(n^2-1)(n^2-2^2)}{\underline{|2}\,\underline{|3}}-\ldots\ldots$$

$$+(-1)^r\frac{n(n^2-1)(n^2-2^2)\ldots\ldots(n^2-r^2)}{\underline{|r}\,\underline{|r+1}}+\ldots\ldots-(-1)^{n+1}$$

[PEMB. COLL. CAMB.]

212. Find the sum of the series:

(1) 6, 24, 60, 120, 210, 336,..... to n terms.

(2) $4-9x+16x^2-25x^3+36x^4-49x^5+\ldots\ldots$ to inf.

(3) $\frac{1.3}{2}+\frac{3.5}{2^2}+\frac{5.7}{2^3}+\frac{7.9}{2^4}+$ to inf.

213. Solve the equation $\begin{vmatrix} 4x & 6x+2 & 8x+1 \\ 6x+2 & 9x+3 & 12x \\ 8x+1 & 12x & 16x+2 \end{vmatrix}=0.$

[KING'S COLL. CAMB.]

214. Shew that

(1) $a^2(1+b^2)+b^2(1+c^2)+c^2(1+a^2)>6abc$,

(2) $n(a^{p+q}+b^{p+q}+c^{p+q}+\ldots)>(a^p+b^p+c^p+\ldots)(a^q+b^q+c^q+\ldots)$,

the number of quantities a, b, c,... being n.

215. Solve the equations

$$\left.\begin{aligned} yz&=a(y+z)+\alpha\\ zx&=a(z+x)+\beta\\ xy&=a(x+y)+\gamma \end{aligned}\right\}.$$

[TRIN. COLL. CAMB.]

216. If n be a prime number, prove that

$$1(2^{n-1}+1)+2\left(3^{n-1}+\frac{1}{2}\right)+3\left(4^{n-1}+\frac{1}{3}\right)+\ldots+(n-1)\left(n^{n-1}+\frac{1}{n-1}\right)$$

is divisible by n. [QUEEN'S COLL. OX.]

217. In a shooting competition a man can score 5, 4, 3, 2, or 0 points for each shot: find the number of different ways in which he can score 30 in 7 shots. [PEMB. COLL. CAMB.]

218. Prove that the expression $x^5-bx^3+cx^2+dx-e$ will be the product of a complete square and a complete cube if

$$\frac{12b}{5}=\frac{9d}{b}=\frac{5e}{c}=\frac{d^2}{c^2}.$$

219. A bag contains 6 black balls and an unknown number, not greater than six, of white balls; three are drawn successively and not replaced and are all found to be white; prove that the chance that a black ball will be drawn next is $\frac{677}{909}$. [JESUS COLL. CAMB.]

220. Shew that the sum of the products of every pair of the squares of the first n whole numbers is $\frac{1}{360}n(n^2-1)(4n^2-1)(5n+6)$.

[CAIUS COLL. CAMB.]

221. If $\frac{a^2(b-c)}{x-a}+\frac{\beta^2(c-a)}{x-b}+\frac{\gamma^2(a-b)}{x-c}-0$ has equal roots, prove that $a(b-c)\pm\beta(c-a)\pm\gamma(a-b)=0$.

222. Prove that when n is a positive integer,

$$n=2^{n-1}-\frac{n-2}{1}2^{n-3}+\frac{(n-3)(n-4)}{\underline{|2}}2^{n-5}-\frac{(n-4)(n-5)(n-6)}{\underline{|3}}2^{n-7}+\ldots.$$

[CLARE COLL. CAMB.]

223. Solve the equations:

(1) $x^2+2yz=y^2+2zx=z^2+2xy+3=76.$

(2) $$\left.\begin{aligned} x+y+z&=a+b+c \\ \frac{x}{a}+\frac{y}{b}+\frac{z}{c}&=3 \\ ax+by+cz&=bc+ca+ab \end{aligned}\right\}.$$

[CHRIST'S COLL. CAMB.]

224. Prove that if each of m points in one straight line be joined to each of n in another by straight lines terminated by the points, then, excluding the given points, the lines will intersect $\frac{1}{4}mn(m-1)(n-1)$ times. [MATH. TRIPOS.]

225. Having given $y=x+x^2+x^5$, expand x in the form

$$y+ay^2+by^3+cy^4+dy^5+\ldots\ldots;$$

and shew that $a^2d-3abc+2b^3=-1$. [BALL. COLL. OX.]

226. A farmer spent three equal sums of money in buying calves, pigs, and sheep. Each calf cost £1 more than a pig and £2 more than a sheep; altogether he bought 47 animals. The number of pigs exceeded that of the calves by as many sheep as he could have bought for £9: find the number of animals of each kind.

227. Express $\log 2$ in the form of the infinite continued fraction

$$\frac{1}{1+}\ \frac{1}{1+}\ \frac{2^2}{1+}\ \frac{3^2}{1+}\ \ldots\ldots\ \frac{n^2}{1+}\ \ldots\ldots$$ [EULER.]

228. In a certain examination six papers are set, and to each are assigned 100 marks as a maximum. Shew that the number of ways in which a candidate may obtain forty per cent. of the whole number of marks is

$$\frac{\lfloor 1}{\lfloor 5}\left\{\frac{\lfloor 245}{\lfloor 240}-6\,.\,\frac{\lfloor 144}{\lfloor 139}+15\,.\,\frac{\lfloor 43}{\lfloor 38}\right\}.$$ [OXFORD MODS.]

229. Test for convergency

$$\frac{x}{2}+\frac{1\,.\,3}{2\,.\,4}\,.\,\frac{x^3}{6}+\frac{1\,.\,3\,.\,5\,.\,7}{2\,.\,4\,.\,6\,.\,8}\,.\,\frac{x^5}{10}+\frac{1\,.\,3\,.\,5\,.\,7\,.\,9\,.\,11}{2\,.\,4\,.\,6\,.\,8\,.\,10\,.\,12}\,.\,\frac{x^7}{14}+\ldots\ldots$$

230. Find the scale of relation, the n^{th} term, and the sum of n terms of the recurring series $1+6+40+288+\ldots\ldots$

Shew also that the sum of n terms of the series formed by taking for its r^{th} term the sum of r terms of this series is

$$\frac{2}{3^2}(2^{2n}-1)+\frac{4}{7^2}(2^{3n}-1)-\frac{5n}{21}.$$ [CAIUS COLL. CAMB.]

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

240. Shew that the equation

$$\sqrt{ax+a}+\sqrt{bx+\beta}+\sqrt{cx+\gamma}=0$$

reduces to a simple equation if $\sqrt{a}\pm\sqrt{b}\pm\sqrt{c}=0$.

Solve the equation

$$\sqrt{6x^2-15x-7}+\sqrt{4x^2-8x-11}-\sqrt{2x^2-5x+5}=2x-3.$$

241. A bag contains 3 red and 3 green balls, and a person draws out 3 at random. He then drops 3 blue balls into the bag, and again draws out 3 at random. Shew that he may just lay 8 to 3 with advantage to himself against the 3 latter balls being all of different colours. [PEMB. COLL. CAMB.]

242. Find the sum of the fifth powers of the roots of the equation $x^4-7x^2+4x-3=0$. [LONDON UNIVERSITY.]

243. A Geometrical and Harmonical Progression have the same p^{th}, q^{th}, r^{th} terms a, b, c respectively: shew that

$$a(b-c)\log a+b(c-a)\log b+c(a-b)\log c=0.$$

[CHRIST'S COLL. CAMB.]

244. Find four numbers such that the sum of the first, third and fourth exceeds that of the second by 8; the sum of the squares of the first and second exceeds the sum of the squares of the third and fourth by 36; the sum of the products of the first and second, and of the third and fourth is 42; the cube of the first is equal to the sum of the cubes of the second, third, and fourth.

245. If T_n, T_{n+1}, T_{n+2} be 3 consecutive terms of a recurring series connected by the relation $T_{n+2}=aT_{n+1}-bT_n$, prove that

$$\frac{1}{b^n}\{T^2_{n+1}-aT_nT_{n+1}+bT_n^2\}=\text{a constant.}$$

246. Eliminate x, y, z from the equations:

$$\left.\begin{aligned}\frac{1}{x}+\frac{1}{y}+\frac{1}{z}&=\frac{1}{a}, & x^2+y^2+z^2&=b^2,\\ x^3+y^3+z^3&=c^3, & xyz&=d^3.\end{aligned}\right\}$$

[EMM. COLL. CAMB.]

247. Shew that the roots of the equation

$$x^4-px^3+qx^2-rx+\frac{r^2}{p^2}=0$$

are in proportion. Hence solve $x^4-12x^3+47x^2-72x+36=0$.

248. A can hit a target four times in 5 shots; B three times in 4 shots; and C twice in 3 shots. They fire a volley: what is the probability that two shots at least hit? And if two hit what is the probility that it is C who has missed? [ST CATH. COLL. CAMB.]

249. Sum each of the following series to n terms:

(1) $1+0-1+0+7+28+79+\ldots\ldots;$

(2) $-\frac{2.2}{1.2.3.4}+\frac{1.2^2}{2.3.4.5}+\frac{6.2^3}{3.4.5.6}+\frac{13.2^4}{4.5.6.7}+\ldots\ldots;$

(3) $3+x+9x^2+x^3+33x^4+x^5+129x^6+$

[SECOND PUBLIC EXAM. OX.]

250. Solve the equations:

(1) $\left.\begin{aligned} y^2+yz+z^2&=ax,\\ z^2+zx+x^2&=ay,\\ x^2+xy+y^2&=az. \end{aligned}\right\}$ (2) $\left.\begin{aligned} x(y+z-x)&=a,\\ y(z+x-y)&=b,\\ z(x+y-z)&=c. \end{aligned}\right\}$

[PETERHOUSE, CAMB.]

251. If $\frac{1}{a}+\frac{1}{b}+\frac{1}{c}=\frac{1}{a+b+c}$, and n is an odd integer, shew that

$$\frac{1}{a^n}+\frac{1}{b^n}+\frac{1}{c^n}=\frac{1}{a^n+b^n+c^n}.$$

If $u^6-v^6+5u^2v^2(u^2-v^2)+4uv(1-u^4v^4)=0$, prove that

$$(u^2-v^2)^6=16u^2v^2(1-u^8)(1-v^8).$$ [PEMB. COLL. CAM

252. If $x+y+z=3p$, $yz+zx+xy=3q$, $xyz=r$, prove that

$$(y+z-x)(z+x-y)(x+y-z)=-27p^3+36pq-8r,$$

and $$(y+z-x)^3+(z+x-y)^3+(x+y-z)^3=27p^3-24r.$$

253. Find the factors, linear in x, y, z, of

$$\{a(b+c)x^2+b(c+a)y^2+c(a+b)z^2\}^2-4abc(x^2+y^2+z^2)(ax^2+by^2+cz^2).$$

[CAIUS COLL. CAMB.]

254. Shew that $\left(\frac{x^2+y^2+z^2}{x+y+z}\right)^{x+y+z}>x^xy^yz^z>\left(\frac{x+y+z}{3}\right)^{x+y+z}$.

[ST JOHN'S COLL. CAMB.]

255. By means of the identity $\left\{1-\frac{4x}{(1+x)^2}\right\}^{-\frac{1}{2}}=\frac{1+x}{1-x}$, prove that

$$\sum_{r=1}^{r=n}(-1)^{n-r}\frac{(n+r-1)!}{r!\,(r-1)!\,(n-r)!}=1.$$

[PEMB. COLL. CAMB.]

256. Solve the equations:

(1) $ax+by+z=zx+ay+b=yz+bx+a=0.$

(2) $$\left.\begin{aligned} x+y+z-u &= 12,\\ x^2+y^2-z^2-u^2 &= 6,\\ x^3+y^3-z^3+u^3 &= 218,\\ xy+zu &= 45. \end{aligned}\right\}$$

257. If $p=q$ nearly, and $n>1$, shew that

$$\frac{(n+1)p+(n-1)q}{(n-1)p+(n+1)q}=\left(\frac{p}{q}\right)^{\frac{1}{n}}.$$

If $\frac{p}{q}$ agree with unity as far as the r^{th} decimal place, to how many places will this approximation in general be correct? [MATH. TRIPOS.]

258. A lady bought 54 lbs. of tea and coffee; if she had bought five-sixths of the quantity of tea and four-fifths of the quantity of coffee she would have spent nine-elevenths of what she had actually spent; and if she had bought as much tea as she did coffee and *vice-versâ*, she would have spent 5*s*. more than she did. Tea is more expensive than coffee, and the price of 6 lbs. of coffee exceeds that of 2 lbs. of tea by 5*s*.; find the price of each.

259. If s_n represent the sum of the products of the first n natural numbers taken two at a time, then

$$\frac{2}{3!}+\frac{11}{4!}+\ldots\ldots+\frac{s_{n-1}}{n!}+\ldots\ldots=\frac{11}{24}e.$$

[CAIUS COLL. CAMB.]

260. If $$\frac{P}{pa^2+2qab+rb^2}=\frac{Q}{pac+q(bc-a^2)-rab}=\frac{R}{pc^2-2qca+ra^2},$$

prove that P, p; Q, q; and R, r may be interchanged without altering the equalities. [MATH. TRIPOS.]

261. If $\alpha+\beta+\gamma=0$, shew that

$$\alpha^{n+3}+\beta^{n+3}+\gamma^{n+3}=\alpha\beta\gamma(\alpha^n+\beta^n+\gamma^n)+\frac{1}{2}(\alpha^2+\beta^2+\gamma^2)(\alpha^{n+1}+\beta^{n+1}+\gamma^{n+1}).$$

[CAIUS COLL. CAMB.]

262. If $\alpha, \beta, \gamma, \delta$ be the roots of the equation

$$x^4+px^3+qx^2+rx+s=0,$$

find in terms of the coefficients the value of $\Sigma(\alpha-\beta)^2(\gamma-\delta)^2$.

[LONDON UNIVERSITY.]

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

270. Find the real roots of the equations

$$x^2+v^2+w^2=a^2, \quad vw+u(y+z)=bc,$$

$$y^2+w^2+u^2=b^2, \quad wu+v(z+x)=ca,$$

$$z^2+u^2+v^2=c^2, \quad uv+w(x+y)=ab.$$

[MATH. TRIPOS.]

271. It is a rule in Gaelic that no consonant or group of consonants can stand immediately between a strong and a weak vowel; the strong vowels being a, o, u; and the weak vowels e and i. Shew that the whole number of Gaelic words of $n+3$ letters each, which can be formed of n consonants and the vowels aeo is $\frac{2\lfloor n+3}{n+2}$ where no letter is repeated in the same word. [CAIUS COLL. CAMB.]

272. Shew that if $x^2+y^2=2z^2$, where x, y, z are integers, then

$$2x=r(l^2+2lk-k^2), \quad 2y=r(k^2+2lk-l^2), \quad 2z=r(l^2+k^2)$$

where r, l, and k are integers. [CAIUS COLL. CAMB.]

273. Find the value of $\frac{1}{1+}\ \frac{1}{1+}\ \frac{2}{3+}\ \frac{4}{5+}\ \frac{6}{7+}\ldots\ldots$ to inf.

[CHRIST'S COLL. CAMB.]

274. Sum the series:

(1) $\frac{x^2}{2.3}+\frac{2x^3}{3.4}+\frac{3x^4}{4.5}+\ldots\ldots$ to inf.

(2) $\frac{\lfloor 1}{a+1}+\frac{\lfloor 2}{(a+1)(a+2)}+\ldots\ldots+\frac{\lfloor n}{(a+1)(a+2)\ldots(a+n)}$.

275. Solve the equations:

(1) $2xyz+3=(2x-1)(3y+1)(4z-1)+12$
$=(2x+1)(3y-1)(4z+1)+80=0.$

(2) $3ux-2vy=vx+uy=3u^2+2v^2=14$; $xy=10uv$.

276. Shew that $\begin{vmatrix} a^2+\lambda & ab & ac & ad \\ ab & b^2+\lambda & bc & bd \\ ac & bc & c^2+\lambda & cd \\ ad & bd & cd & d^2+\lambda \end{vmatrix}$

is divisible by λ^3 and find the other factor. [CORPUS COLL. CAMB.]

277. If $a, b, c, \ldots$ are the roots of the equation

$$x^n + p_1 x^{n-1} + p_2 x^{n-2} + \ldots + p_{n-1} x + p_n = 0;$$

find the sum of $a^3 + b^3 + c^3 + \ldots$, and shew that

$$\frac{a^2}{b} + \frac{b^2}{a} + \frac{a^2}{c} + \frac{c^2}{a} + \frac{b^2}{c} + \frac{c^2}{b} + \ldots = p_1 - \frac{p_{n-1}(p_1^2 - 2p_2)}{p_n}.$$

[St John's Coll. Camb.]

278. By the expansion of $\frac{1+2x}{1-x^3}$, or otherwise, prove that

$$1 - 3n + \frac{(3n-1)(3n-2)}{1.2} - \frac{(3n-2)(3n-3)(3n-4)}{1.2.3} + \frac{(3n-3)(3n-4)(3n-5)(3n-6)}{1.2.3.4} - \&c. = (-1)^n,$$

when n is an integer, and the series stops at the first term that vanishes.

[Math. Tripos.]

279. Two sportsmen A and B went out shooting and brought home 10 birds. The sum of the squares of the number of shots was 2880, and the product of the numbers of shots fired by each was 48 times the product of the numbers of birds killed by each. If A had fired as often as B and B as often as A, then B would have killed 5 more birds than A: find the number of birds killed by each.

280. Prove that $8(a^3 + b^3 + c^3)^2 > 9(a^2 + bc)(b^2 + ca)(c^2 + ab)$.

[Pemb. Coll. Camb.]

281. Shew that the n^{th} convergent to

$$\frac{2}{3} - \frac{4}{4} - \frac{6}{5} \quad \ldots \text{ is } 2 - \frac{2^{n+1}}{\Sigma_0^n 2^r (n-r)!}.$$

What is the limit of this when n is infinite? [King's Coll. Camb.]

282. If $\frac{p_n}{q_n}$ is the n^{th} convergent to the continued fraction

$$\frac{1}{a+}\ \frac{1}{b+}\ \frac{1}{c+}\ \frac{1}{a+}\ \frac{1}{b+}\ \frac{1}{c+}\ \ldots$$

shew that $p_{3n+3} = bp_{3n} + (bc+1)\, q_{3n}$. [Queens' Coll. Camb.]

283. Out of n straight lines whose lengths are 1, 2, 3, ... n inches respectively, the number of ways in which four may be chosen which will form a quadrilateral in which a circle may be inscribed is

$$\frac{1}{48}\{2n(n-2)(2n-5) - 3 + 3(-1)^n\}.$$ [Math. Tripos.]

284. If u_2, u_3 are respectively the arithmetic means of the squares and cubes of all numbers less than n and prime to it, prove that $n^3-6nu_2+4u_3=0$, unity being counted as a prime.

[St John's Coll. Camb.]

285. If n is of the form $6m-1$ shew that $(y-z)^n+(z-x)^n+(x-y)^n$ is divisible by $x^2+y^2+z^2-yz-zx-xy$; and if n is of the form $6m+1$, shew that it is divisible by

$$(x^2+y^2+z^2-yz-zx-xy)^2.$$

286. If S is the sum of the m^{th} powers, P the sum of the products m together of the n quantities a_1, a_2, a_3, ... a_n, shew that

$$\underline{|n-1}\,.\,S>\underline{|n-m}\,.\,\underline{|m}\,.\,P.$$

[Caius Coll. Camb.]

287. Prove that if the equations

$$x^3+qx-r=0 \text{ and } rx^3-2q^2x^2-5qrx-2q^3-r^2=0$$

have a common root, the first equation will have a pair of equal roots; and if each of these is a, find all the roots of the second equation.

[India Civil Service.]

288. If $x\sqrt{2a^2-3x^2}+y\sqrt{2a^2-3y^2}+z\sqrt{2a^2-3z^2}=0$,

where a^2 stands for $x^2+y^2+z^2$, prove that

$$(x+y+z)(-x+y+z)(x-y+z)(x+y-z)=0.$$

[Trin. Coll. Camb.]

289. Find the values of x_1, x_2, ... x_n which satisfy the following system of simultaneous equations:

$$\frac{x_1}{a_1-b_1}+\frac{x_2}{a_1-b_2}+\ldots+\frac{x_n}{a_1-b_n}=1,$$

$$\frac{x_1}{a_2-b_1}+\frac{x_2}{a_2-b_2}+\ldots+\frac{x_n}{a_2-b_n}=1,$$

.....

$$\frac{x_1}{a_n-b_1}+\frac{x_2}{a_n-b_2}+\ldots+\frac{x_n}{a_n-b_n}=1.$$

[London University.]

290. Shew that $\begin{vmatrix} yz-x^2 & zx-y^2 & xy-z^2 \\ zx-y^2 & xy-z^2 & yz-x^2 \\ xy-z^2 & yz-x^2 & zx-y^2 \end{vmatrix} = \begin{vmatrix} r^2 & u^2 & u^2 \\ u^2 & r^2 & u^2 \\ u^2 & u^2 & r^2 \end{vmatrix}$,

where $r^2=x^2+y^2+z^2$, and $u^2=yz+zx+xy$.

[Trin. Coll. Camb.]

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

298. Shew that if a, b, c are positive and unequal, the equations

$$ax+yz+z=0, \quad zx+by+z=0, \quad yz+zx+c=0,$$

give three distinct triads of real values for x, y, z; and the ratio of the products of the three values of x and y is $b(b-c) : a(c-a)$.

[Oxford Mods.]

299. If

$$A=ax-by-cz, \quad D=bz+cy,$$
$$B=by-cz-ax, \quad E=cx+az,$$
$$C=cz-ax-by, \quad F=ay+bx,$$

prove that $ABC \quad AD^2-BE^2-CF^2+2DEF$

$$-(a^2+b^2+c^2)(ax+by+cz)(x^2+y^2+z^2).$$

[Second Public Exam. Oxford.]

300. A certain student found it necessary to decipher an old manuscript. During previous experiences of the same kind he had observed that the number of words he could read daily varied jointly as the number of miles he walked and the number of hours he worked during the day. He therefore gradually increased the amount of daily exercise and daily work at the rate of 1 mile and 1 hour per day respectively, beginning the first day with his usual quantity. He found that the manuscript contained 232000 words, that he counted 12000 on the first day, and 72000 on the last day; and that by the end of half the time he had counted 62000 words: find his usual amount of daily exercise and work.

ANSWERS.

I. Pages 10—12.

(1) $54b : a$. (2) $9 : 7$. (3) $bx : ay$. **2.** 18. **3.** 385, 660.
11. **5.** $5 : 13$. **6.** $5 : 6$ or $-3 : 5$.

$\frac{x}{4} - \frac{y}{2} = \frac{z}{3}$, or $\frac{x}{1} = \frac{y}{-1} = \frac{z}{0}$. **17.** $abc + 2fgh - af^2 - bg^2 - ch^2 = 0$.

3, 4, 1. **21.** -3, 4, 1. **22.** 7, 3, 2. **23.** 3, 4, 1.

$\pm a(b^2 - c^2)$, $\pm b(c^2 - a^2)$, $\pm c(a^2 - b^2)$.

$bc(b - c)$, $ca(c - a)$, $ab(a - b)$.

II. Pages 19, 20.

45. **2.** (1) 12. (2) $300a^3b$. **3.** $\frac{x^3}{y(x^2 + y^2)}$.

0, 5, $\frac{8}{7}$. **14.** 0, 3, 8. **15.** $\frac{a(b + c)}{cm - bm - 2an}$.

8. **19.** 6, 9, 10, 15. **20.** 3 gallons from A; 8 gallons from B.
45 gallons. **23.** $17 : 3$. **24.** $a = 4b$.
64 per cent. copper and 36 per cent. zinc. 3 parts of brass are taken to rts of bronze. **26.** 63 or 12 minutes.

III. Pages 26, 27.

$5\frac{1}{3}$. **2.** 9. **3.** $1\frac{1}{3}$. **4.** 2. **7.** 60.

$y = 2x - \frac{8}{x}$. **10.** $y = 5x + \frac{36}{x^2}$. **11.** 4.

$x = \frac{22}{15}z + \frac{2}{15z}$. **14.** 36. **15.** 1610 feet; 305·9 feet.

$22\frac{11}{21}$ cubic feet. **17.** $4 : 3$.
The regatta lasted 6 days; 4th, 5th, 6th days.
16, 25 years; £200, £250. **21.** 1 day 18 hours 28 minutes.
The cost is least when the rate is 12 miles an hour; and then the cost mile is $£\frac{3}{32}$, and for the journey is £9. 7*s*. 6*d*.

IV. a. PAGES 31, 32.

1. $277\frac{1}{2}$. **2.** 153. **3.** 0. **4.** $\frac{n(10-n)}{3}$. **5.** 30.

6. -42. **7.** -185. **8.** $1325\sqrt{3}$. **9.** $75\sqrt{5}$.

10. $820a$ $1680b$. **11.** $n(n+1)a-n^2b$. **12.** $\frac{21}{2}(11a-9b)$.

13. $-\frac{1}{4}, -\frac{3}{4}, \ldots, -9\frac{1}{4}$. **14.** $1, -1\frac{1}{2}, \ldots, -39$. **15.** $-33x, -31x, \ldots, x$.

16. $x^2-x+1, x^2-2x+2, \ldots, x$. **17.** n^2. **18.** 3. **19.** 5.

20. 612. **21.** 4, 9, 14. **22.** 1, 4, 7. **23.** 495. **24.** 160.

25. $\frac{p(p+1)}{2a}+pb$. **26.** $n(n+1)a-\frac{n^2}{a}$

IV. b. PAGES 35, 36.

1. 10 or -8. **2.** 8 or -13. **3.** 2, 5, 8,...

4. First term 8, number of terms 59.

5. First term $7\frac{1}{2}$, number of terms 54.

6. Instalments £51, £53, £55,... **7.** 12. **8.** 25.

9. $\frac{n}{2(1-x)}(2+\overline{n-3}\,.\sqrt{x})$. **10.** n^2. **12.** $-(p+q)$.

13. 3, 5, 7, 9. [Assume for the numbers $a-3d$, $a-d$, $a+d$, $a+3d$.]

14. 2, 4, 6, 8. **15.** $p+q-m$. **16.** 12 or -17. **17.** $6r-1$.

20. $10p-8$. **21.** 8 terms. Series $1\frac{1}{2}, 3, 4\frac{1}{2}, \ldots\ldots$

22. 3, 5, 7; 4, 5, 6. **23.** $ry=(n+1-r)x$.

V. a. PAGES 41, 42.

1. $\frac{2059}{1458}$. **2.** $\frac{1281}{512}$. **3.** $191\frac{1}{4}$. **4.** 682.

5. $\frac{1093}{45}$. **6.** $\frac{1}{4}(5^p-1)$. **7.** $\frac{9}{7}\left\{1-\left(\frac{4}{3}\right)^{2n}\right\}$. **8.** $364(\sqrt{3}+1)$.

9. $\frac{1}{2}(585\sqrt{2}-292)$. **10.** $-\frac{463}{192}$. **11.** $\frac{3}{2}, 1, \frac{2}{3}$.

12. $\frac{16}{3}, 8, \ldots, 27$. **13.** $-7, \frac{7}{2}, \ldots, \frac{7}{32}$. **14.** $\frac{64}{65}$.

15. $\frac{27}{58}$. **16.** ·999. **17.** $\frac{1}{2}$. **18.** $\frac{3(3+\sqrt{3})}{2}$.

19. $7(7+\sqrt{42})$. **20.** 2. **21.** 16, 24, 36,... **22.** 2.

23. 2. **24.** 8, 12, 18. **25.** 2, 6, 18. **28.** $6, -3, 1\frac{1}{2}, \ldots\ldots$

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

11. 30034342. **12.** 710*te*3. **13.** 2714687. **14.** $\cdot\dot{2}04\dot{6}$. **15.** 15·1*t*6.

16. 20·73. **17.** $125\cdot01\dot{2}\dot{5}$. **18.** $\frac{5}{8}$. **19.** $\frac{2}{3}, \frac{5}{8}$.

20. Nine. **21.** Four. **22.** Twelve. **23.** Eight. **24.** Eleven.

25. Twelve. **26.** Ten. **30.** $2^{11}+2^7+2^6$.

31. $3^9-3^8-3^7-3^6$ $3^5+3^3+3^2+1$.

VIII. a. PAGES 72, 73.

1. $\frac{2+\sqrt{2}+\sqrt{6}}{4}$. **2.** $\frac{3+\sqrt{6}+\sqrt{15}}{6}$.

3. $\frac{a\sqrt{b}+b\sqrt{a}-\sqrt{ab\,(a+b)}}{2ab}$. **4.** $\frac{a-1+\sqrt{a^2-1}+\sqrt{2a\,(a-1)}}{a-1}$.

5. $\frac{3\sqrt{30}+5\sqrt{15}-12-10\sqrt{2}}{7}$. **6.** $\frac{\sqrt{2}+\sqrt{3}+\sqrt{5}}{2}$.

7. $3^{\frac{5}{3}}+3^{\frac{4}{3}}.2^{\frac{1}{2}}+3.2+3^{\frac{2}{3}}.2^{\frac{3}{2}}+3^{\frac{1}{3}}.2^2+2^{\frac{5}{2}}$.

8. $5^{\frac{5}{6}}-5^{\frac{4}{6}}.2^{\frac{1}{3}}+5^{\frac{3}{6}}.2^{\frac{2}{3}}-5^{\frac{2}{6}}.2+5^{\frac{1}{6}}.2^{\frac{4}{3}}-2^{\frac{5}{3}}$.

9. $a^{\frac{11}{6}}-a^{\frac{10}{6}}b^{\frac{1}{4}}+a^{\frac{9}{6}}b^{\frac{1}{2}}-\ldots+a^{\frac{1}{6}}b^{\frac{10}{4}}-b^{\frac{11}{4}}$

10. $3^{\frac{2}{3}}+3^{\frac{1}{3}}+1$.

11. $2^3-2^2.7^{\frac{1}{4}}+2.7^{\frac{1}{2}}-7^{\frac{3}{4}}$.

12. $5^{\frac{n}{3}}+5^{\frac{10}{3}}.3^{\frac{1}{4}}+5^3.3^{\frac{2}{4}}+\ldots+5^{\frac{1}{3}}.3^{\frac{10}{4}}+3^{\frac{11}{4}}$.

13. $\frac{1-3^{\frac{2}{3}}+3^{\frac{1}{3}}}{2}$.

14. $17-3^{\frac{5}{3}}.2^{\frac{3}{2}}+3^{\frac{4}{3}}.2^2-3.2^{\frac{5}{2}}+3^{\frac{2}{3}}.2^3-3^{\frac{1}{3}}.2^{\frac{7}{2}}$.

15. $3^2.2^{\frac{1}{2}}-3^{\frac{5}{3}}.2+3^{\frac{4}{3}}.2^{\frac{3}{2}}-3.2^2+3^{\frac{2}{3}}.2^{\frac{5}{2}}-3^{\frac{1}{3}}.2^3$.

16. $\frac{1}{2}\left(3^{\frac{5}{6}}-3^{\frac{4}{6}}+3^{\frac{3}{6}}-3^{\frac{2}{6}}+3^{\frac{1}{6}}-1\right)$.

17. $\frac{2^5+2^{\frac{26}{6}}+2^{\frac{21}{6}}+2^{\frac{16}{6}}+2^{\frac{11}{6}}+2^{\frac{6}{6}}+1}{31}$.

18. $\frac{3^{\frac{3}{2}}+3^{\frac{5}{6}}+3^{\frac{1}{6}}}{8}$.

19. $\sqrt{5}+\sqrt{7}-2$.

20. $\sqrt{5}-\sqrt{7}+2\sqrt{3}$. **21.** $1+\sqrt{3}-\sqrt{2}$. **22.** $1+\sqrt{\frac{3}{2}}-\sqrt{\frac{5}{2}}$.

23. $2+\sqrt{a}-\sqrt{3b}$. **24.** $3-\sqrt{7}+\sqrt{2}-\sqrt{3}$. **25.** $1+\sqrt{3}$.

26. $2+\sqrt{5}$. **27.** $3-2\sqrt{2}$. **28.** $\sqrt{14}-2\sqrt{2}$.

29. $2\sqrt{3}+\sqrt{5}$. **30.** $3\sqrt{3}-\sqrt{6}$. **31.** $\sqrt{\frac{2a+x}{2}}+\sqrt{\frac{x}{2}}$.

32. $\sqrt{\frac{3a+b}{2}}-\sqrt{\frac{a-b}{2}}$. **33.** $\sqrt{\frac{1+a+a^2}{2}}+\sqrt{\frac{1-a+a^2}{2}}$.

34. $\frac{1}{\sqrt[4]{1-a^2}}\left(\sqrt{\frac{1+a}{2}}+\sqrt{\frac{1-a}{2}}\right)$.

35. $11+56\sqrt{3}$. **36.** 289. **37.** $\frac{1}{3}\sqrt{3}$.

38. $3\sqrt{3}+5$. **39.** 3. **40.** $8\sqrt{3}$.

41. $3+\sqrt{5}=5{\cdot}23607\cdot$ **42.** $x^2+1+\sqrt[3]{4}+x-x\sqrt[3]{2}+\sqrt[3]{2}$.

43. $3a+\sqrt{b^2-3a^2}$. **44.** $\frac{a-1}{2}$.

VIII. b. PAGES 81, 82.

1. $6-2\sqrt{6}$. **2.** -13. **3.** $e^{2\sqrt{-1}}-e^{-2\sqrt{-1}}$.

4. x^2-x+1. **5.** $\frac{3+\sqrt{-2}}{11}$. **6.** $-19-6\sqrt{10}$.

7. $-\frac{8}{29}$. **8.** $\frac{4ax\sqrt{-1}}{a^2+x^2}$. **9.** $\frac{2(3x^2-1)\sqrt{-1}}{x^2+1}$.

10. $\frac{3a^2-1}{2a}$. **11.** $\sqrt{-1}$. **12.** 100.

13. $\pm(2+3\sqrt{-1})$. **14.** $\pm(5-6\sqrt{-1})$. **15.** $\pm(1+4\sqrt{-3})$.

16. $\pm 2(1-\sqrt{-1})$. **17.** $\pm(a+\sqrt{-1})$. **18.** $\pm\{(a+b)-(a-b)\sqrt{-1}\}$.

19. $-\frac{9}{13}+\frac{19}{13}i$. **20.** $\frac{4}{7}-\frac{\sqrt{6}}{14}i$. **21.** i.

22. $\frac{1}{5}+\frac{3}{5}i$. **23.** $\frac{2b(3a^2-b^2)}{a^2+b^2}i$.

IX. a. PAGES 88—90.

1. $35x^2+13x-12=0$. **2.** $mnx^2+(n^2-m^2)x-mn=0$.

3. $(p^2-q^2)x^2+4pqx-p^2+q^2=0$. **4.** $x^2-14x+29=0$.

5. $x^2+10x+13=0$. **6.** $x^2+2px+p^2-8q=0$.

7. $x^2+6x+34=0$. **8.** $x^2+2ax+a^2+b^2=0$.

9. $x^2+a^2-2ab+b^2=0$. **10.** $6x^3+11x^2-19x+6=0$.

11. $2ax^3+(4-a^2)x^2-2ax=0$. **12.** $x^3-8x^2+17x-4=0$.

14. 3, 5. **15.** 2, $-\frac{10}{9}$. **16.** $\frac{a-b}{a+b}$.

18. $\frac{b^2-2ac}{c^2}$. **19.** $\frac{bc^4(3ac-b^2)}{a^7}$. **20.** $\frac{b^2(b^2-4ac)}{a^2c^2}$.

21. 7. **22.** -15. **23.** 0. **24.** $x^2-2(p^2-2q)x+p^2(p^2-4q)=0$.

26. (1) $\frac{b^2-2ac}{a^2c^2}$. (2) $\frac{b(b^2-3ac)}{a^3c^3}$. **27.** $nb^2=(1+n)^2ac$.

28. $a^2c^2x^2-(b^2-2ac)(a^2+c^2)x+(b^2-2ac)^2=0$.

29. $x^2-4mnx-(m^2-n^2)^2=0$.

IX. b. PAGES 92, 93.

1. 2 and -2. **5.** $bx^2-2ax+a=0$.

6. (1) $\frac{p(p^2-4q)(p^2-q)}{q}$. (2) $\frac{p^4-4p^2q+2q^2}{q^4}$. **11.** $\frac{1}{3}$.

IX. c. PAGE 96.

1. -2. **2.** ± 7. **5.** $(ln'-l'n)^2=(lm'-l'm)\,(mn'-m'n)$.

7. $(aa'-bb')^2+4\,(ha'+h'b)\,(hb'+h'a)=0$.

10. $(bb'-2ac'-2a'c)^2=(b^2-4ac)\,(b'^2-4a'c')$; which reduces to $(ac'-a'c)^2=(ab'-a'b)\,(bc'-b'c)$.

X. a. PAGES 101, 102.

1. $\frac{1}{4}, -\frac{1}{2}$. **2.** $\pm\frac{1}{3}, \pm 1$. **3.** $4, \frac{1}{4}$. **4.** $\frac{4}{9}, \frac{1}{4}$.

5. $3^n, 2^n$. **6.** $1, 2^{2n}$ **7.** $27, \frac{25}{147}$. **8.** $\frac{9}{13}, \frac{4}{13}$.

9. $\frac{1}{9}, \frac{25}{4}$. **10.** $-1, -\frac{1}{32}$. **11.** $2, 0$. **12.** ± 1.

13. -4. **14.** ± 3. **15.** 0. **16.** $\frac{1}{8}, 450$.

17. $9, -7, 1\pm\sqrt{-24}$. **18.** $2, -4, -1\pm\sqrt{71}$. **19.** $3, -\frac{3}{2}, \frac{3\pm\sqrt{-47}}{4}$.

20. $4, -\frac{7}{2}, \frac{1\pm\sqrt{65}}{4}$. **21.** $2, -8, -3\pm 3\sqrt{5}$. **22.** $3, -\frac{5}{3}, \frac{2\pm\sqrt{70}}{3}$.

23. $5, \frac{1}{3}, \frac{8\pm\sqrt{148}}{3}$. **24.** $7, -\frac{14}{3}, \frac{7\pm\sqrt{37}}{6}$. **25.** $2, \frac{1}{2}, \frac{5\pm\sqrt{201}}{4}$.

26. $5, -\frac{7}{3}, \frac{8\pm\sqrt{415}}{6}$. **27.** $1, 3$. **28.** $5, \frac{1}{2}$.

29. $1, 9, -\frac{18}{5}$. **30.** $a, \frac{a}{2}, \frac{a}{3}$. **31.** $2, \frac{9}{2}$.

32. $4, -\frac{10}{3}$. **33.** $0, 5$. **34.** $6, -\frac{5}{2}$.

35. $1, \frac{-3\pm\sqrt{5}}{2}$. **36.** $3, \frac{1}{3}, \frac{-1\pm\sqrt{-35}}{6}$. **37.** $2\pm\sqrt{3}, \frac{-1\pm\sqrt{-3}}{2}$.

38. $2, -\frac{1}{2}, 5, \frac{1}{5}$. **39.** $3a, -4a$. **40.** $\pm\frac{2a}{5}$.

41. $0, 1, 3$. **42.** $\frac{-1\pm\sqrt{17}}{2}, \frac{-1\pm\sqrt{2}}{2}$.

43. $\frac{3}{2}, \frac{2}{3}$. **44.** $3, -1$. **45.** ± 1.

46. 13. **47.** 4. **48.** $0, \frac{63a}{65}$.

49. $1, \frac{(\sqrt{a}-\sqrt{b})^2+4}{(\sqrt{a}+\sqrt{b})^2-4}$. **50.** ± 5. **51.** $5, -4, \frac{1\pm\sqrt{-75}}{2}$.

52. $-\frac{1}{3}, \frac{1\pm\sqrt{-31}}{6}$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

40. $x=0,\ \pm a\sqrt{7},\ \pm a\sqrt{13},\ \pm 3a,\ \pm a;\ y=0,\ \mp b\sqrt{7},\ \pm b\sqrt{13},\ \mp b,\ \mp 3b.$

41. $x=\pm 1,\ \pm\dfrac{2a^2}{\sqrt{16a^4-a^2-1}};\ y=\pm 2a,\ \mp\dfrac{a}{\sqrt{16a^4-a^2-1}}.$

X. c. PAGES 109, 110.

1. $x=\pm 3;\ y=\pm 5;\ z=\pm 4.$

2. $x=5;\ y=-1;\ z=7.$

3. $x=5,\ -1;\ y=1,\ -5;\ z=2.$

4. $x=8,\ -3;\ y=3;\ z=3,\ -8.$

5. $x=4,\ 3,\ \dfrac{2\pm\sqrt{151}}{3};\ y=3,\ 4,\ \dfrac{2\mp\sqrt{151}}{3};\ z=2,\ -\dfrac{11}{3}.$

6. $x=\pm 3;\ y=\mp 2;\ z=\pm 5.$

7. $x=\pm 5;\ y=\pm 1;\ z=\pm 1.$

8. $x=8,\ -8;\ y=5,\ -5;\ z=3,\ -3.$

9. $x=3;\ y=4;\ z=\dfrac{1}{2};\ u-\dfrac{1}{3}.$

10. $x=1;\ y=2;\ z=3.$

11. $x=5,\ -7;\ y=3,\ -5;\ z=6,\ -8.$

12. $x=1,\ -2;\ y=7,\ -3;\ z=3,\ -\dfrac{1}{3}\dfrac{1}{1}.$

13. $x=4,\ \dfrac{60}{7};\ y=6,\ \dfrac{6}{7}\dfrac{6}{0};\ z=2,\ -6.$

14. $x=a,\ 0,\ 0;\ y=0,\ a,\ 0;\ z=0,\ 0,\ a.$

15. $x=\dfrac{a}{\sqrt{3}},\ \dfrac{\sqrt{3}\pm\sqrt{-9}}{6}a;\ y=\dfrac{a}{\sqrt{3}},\ \dfrac{-5\sqrt{3}\pm\sqrt{-9}}{6}a;$

$z=\dfrac{a}{\sqrt{3}},\ -\dfrac{\sqrt{3}\pm\sqrt{-9}}{3}a.$

16. $x=a,\ -2a,\ \dfrac{7\pm\sqrt{-15}}{2}a;\ y=4a,\ a,\ \dfrac{-11\pm\sqrt{-15}}{2}a;$

$z=2a,\ -4a,\ (1\pm\sqrt{-15})\,a.$

X. d. PAGE 113.

1. $x=29,\ 21,\ 13,\ 5;\ y=2,\ 5,\ 8,\ 11.$

2. $x=1,\ 3,\ 5,\ 7,\ 9;\ y=24,\ 19,\ 14,\ 9,\ 4.$

3. $x=20,\ 8;\ y=1,\ 8.$

4. $x=9,\ 20,\ 31;\ y=27,\ 14,\ 1.$

5. $x=30,\ 5;\ y=9,\ 32.$

6. $x=50,\ 3;\ y=3,\ 44.$

7. $x=7p-5,\ 2;\ y=5p-4,\ 1.$

8. $x=13p-2,\ 11;\ y=6p-1,\ 5.$

9. $x=21p-9,\ 12;\ y=8p-5,\ 3.$

10. $x=17p,\ 17;\ y=13p,\ 13.$

11. $x=19p-16,\ 3;\ y=23p-19,\ 4.$

12. $x=77p-74,\ 3;\ y=30p-25,\ 5.$

13. 11 horses, 15 cows.

14. 101.

15. 56, 25 or 16, 65.

16. To pay 3 guineas and receive 21 half-crowns.

17. 1147; an infinite number of the form $1147+39\times 56p$.

18. To pay 17 florins and receive 3 half-crowns.

19. 37, 99; 77, 59; 117, 19.

20. 28 rams, 1 pig, 11 oxen; or 13 rams, 14 pigs, 13 oxen.

21. 3 sovereigns, 11 half-crowns, 13 shillings.

XI. a. PAGES 122—124.

1. 12. **2.** 224. **3.** 40320, 6375600, 10626, 11628.
4. 6720. **5.** 15. **6.** 40320; 720. **7.** 15, 360.
8. 6. **9.** 120. **10.** 720. **11.** 10626, 1771.
12. 1440. **13.** 6375600. **14.** 360, 144. **15.** 230300.
16. 1140, 231. **17.** 144. **18.** 224, 896. **19.** 848.
20. 56. **21.** 360000. **22.** 2052000. **23.** 369600.
24. 21600. **25.** $\frac{\lfloor 45}{\lfloor 10 \lfloor 15 \lfloor 20}$. **26.** 2520. **27.** 5760.
28. 3456. **29.** 2903040. **30.** 25920. **32.** 41.
33. 1956. **34.** 7.

XI. b. PAGES 131, 132.

1. (1) 1663200. (2) 129729600. (3) 3326400. **2.** 4084080.
3. 151351200. **4.** 360. **5.** 72. **6.** 125.
7. n^r. **8.** 531441. **9.** p^n. **10.** 30.
11. 1260. **12.** 3374. **13.** 455. **14.** $\frac{\lfloor a+2b+3c+d}{\lfloor a (\lfloor b)^2 (\lfloor c)^3}$.
15. 4095. **16.** 57760000. **17.** 1023. **18.** 720; 3628800.
19. 127. **20.** 315. **21.** $\frac{\lfloor mn}{(\lfloor m)^n \lfloor n}$. **22.** 64; 325. **23.** 42.
24. (1) $\frac{p(p-1)}{2} - \frac{q(q-1)}{2} + 1$; (2) $\frac{p(p-1)(p-2)}{6} - \frac{q(q-1)(q-2)}{6}$.
25. $\frac{p(p-1)(p-2)}{6} - \frac{q(q-1)(q-2)}{6} + 1$. **26.** $(p+1)^n - 1$.
27. 113; 2190. **28.** 2454. **29.** 6666600. **30.** 5199960.

XIII. a. PAGES 142, 143.

1. $x^5 - 15x^4 + 90x^3 - 270x^2 + 405x - 243$.
2. $81x^4 + 216x^3y + 216x^2y^2 + 96xy^3 + 16y^4$.
3. $32x^5 - 80x^4y + 80x^3y^2 - 40x^2y^3 + 10xy^4 - y^5$.
4. $1 - 18a^2 + 135a^4 - 540a^6 + 1215a^8 - 1458a^{10} + 729a^{12}$.
5. $x^{10} + 5x^9 + 10x^8 + 10x^7 + 5x^6 + x^5$.
6. $1 - 7xy + 21x^2y^2 - 35x^3y^3 + 35x^4y^4 - 21x^5y^5 + 7x^6y^6 - x^7y^7$
7. $16 - 48x^2 + 54x^4 - 27x^6 + \frac{81x^8}{16}$.
8. $729a^6 - 972a^5 + 540a^4 - 160a^3 + \frac{80a^2}{3} - \frac{64a}{27} + \frac{64}{729}$.
9. $1 + \frac{7x}{2} + \frac{21x^2}{4} + \frac{35x^3}{8} + \frac{35x^4}{16} + \frac{21x^5}{32} + \frac{7x^6}{64} + \frac{x^7}{128}$.

10. $\frac{64x^6}{729} - \frac{32x^4}{27} + \frac{20x^2}{3} - 20 + \frac{135}{4x^2} - \frac{243}{8x^4} + \frac{729}{64x^6}$.

11. $\frac{1}{256} + \frac{a}{16} + \frac{7a^2}{16} + \frac{7a^3}{4} + \frac{35a^4}{8} + 7a^5 + 7a^6 + 4a^7 + a^8$.

12. $1 - \frac{10}{x} + \frac{45}{x^2} - \frac{120}{x^3} + \frac{210}{x^4} - \frac{252}{x^5} + \frac{210}{x^6} - \frac{120}{x^7} + \frac{45}{x^8} - \frac{10}{x^9} + \frac{1}{x^{10}}$.

13. $-35750x^{10}$ **14.** $-112640x^9$ **15.** $-312x^2$.

16. $\frac{\lfloor 30}{\lfloor 27 \, \lfloor 3}(5x)^3 (8y)^{27}$. **17.** $40a^7b^3$. **18.** $\frac{1120}{81} a^4b^4$.

19. $\frac{10500}{x^3}$. **20.** $\frac{70x^6y^{10}}{a^2b^6}$. **21.** $2x^4 + 24x^2 + 8$.

22. $2x\,(16x^4 - 20x^2a^2 + 5a^4)$. **23.** $140\sqrt{2}$.

24. $2\,(365 - 363x + 63x^2 - x^3)$. **25.** 252. **26.** $-\frac{429}{16} x^{14}$.

27. $110565a^4$ **28.** $84a^3b^6$ **29.** 1365, -1365.

30. $\frac{189a^{17}}{8}$, $-\frac{21}{16} a^{19}$. **31.** $\frac{7}{18}$. **32.** 18564.

33. $\frac{\lfloor n}{\lfloor \frac{1}{2}(n-r) \, \lfloor \frac{1}{2}(n+r)}$. **34.** $(-1)^n \frac{\lfloor 3n}{\lfloor n \, \lfloor 2n}$.

XIII. b. PAGES 147, 148.

1. The 9^{th}. **2.** The 12^{th} **3.** The 6^{th}. **4.** The 10^{th} and 11^{th}.

5. The $3^{rd} = 6\frac{2}{3}$. **6.** The 4^{th} and $5^{th} = \frac{7}{144}$ **9.** $x=2$, $y=3$, $n=5$.

10. $1 + 8x + 20x^2 + 8x^3 - 26x^4 - 8x^5 + 20x^6 - 8x^7 + x^8$.

11. $27x^6 - 54ax^5 + 117a^2x^4 - 116a^3x^3 + 117a^4x^2 - 54a^5x + 27a^6$.

12. $\frac{\lfloor n}{\lfloor r-1 \, \lfloor n-r+1} x^{r-1}a^{n-r+1}$ **13.** $(-1)^p \frac{\lfloor 2n+1}{\lfloor p+1 \, \lfloor 2n-p} x^{2p-2n+1}$

14. 14. **15.** $2r = n$.

XIV. a. PAGE 155.

1. $1 + \frac{1}{2}x - \frac{1}{8}x^2 + \frac{1}{16}x^3$. **2.** $1 + \frac{3}{2}x + \frac{3}{8}x^2 - \frac{1}{16}x^3$.

3. $1 - \frac{2}{5}x - \frac{3}{25}x^2 - \frac{8}{125}x^3$. **4.** $1 - 2x^2 + 3x^4 - 4x^6$.

5. $1 - x - x^2 - \frac{5}{3}x^3$ **6.** $1 + x + 2x^2 + \frac{14}{3}x^3$.

7. $1 - x + \frac{3}{2}x^2 - \frac{5}{2}x^3$. **8.** $1 - x + \frac{2}{3}x^2 - \frac{10}{27}x^3$.

9. $1 + x + \frac{x^2}{6} - \frac{x^3}{54}$. **10.** $1 - 2a + \frac{5}{2}a^2 - \frac{5}{2}a^3$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

7. $\left(1-\frac{2}{3}\right)^{-n}=2^n\left(1-\frac{1}{3}\right)^{-n}$. **12.** $\frac{\lfloor 2n}{\lfloor n \lfloor n}$.

14. Deduced from $(1-x^3)-(1-x)^3=3x-3x^2$. **16.** (1) 45. (2) 6561.

18. (1) Equate coefficients of x^r in $(1+x)^n(1+x)^{-1}=(1+x)^{n-1}$.

(2) Equate absolute terms in $(1+x)^n\left(1+\frac{1}{x}\right)^{-2}=x^2(1+x)^{n-2}$

20. Series on the left $+(-1)^n q_n{}^2=$ coefficient of x^{2n} in $(1-x^2)^{-\frac{1}{2}}$.

21. $2^{2n-1}\ \frac{1}{2}\cdot\frac{\lfloor 2n}{\lfloor n \lfloor n}$.

[Use $(c_0+c_1+c_2+\ldots c_n)^2-2(c_0c_1+c_1c_2+\ldots)=c_0{}^2+c_1{}^2+c_2{}^2+\ldots c_n{}^2$].

XV. Pages 173, 174.

1. -12600. **2.** 168. **3.** 3360. **4.** $-1260a^2b^3c^4$

5. -9. **6.** 8085. **7.** 30. **8.** 1905.

9. -10. **10.** $\frac{3}{2}$. **11.** -1. **12.** $\frac{4}{81}$.

13. $\frac{59}{16}$. **14.** -1. **15.** $\frac{211}{3}$. **16.** $1-\frac{1}{2}x-\frac{7}{8}x^2$.

17. $1-2x^2+4x^3+5x^4-20x^5$. **18.** $16\left(1-\frac{3}{2}x^3+3x^4+\frac{9}{32}x^6-\frac{9}{8}x^7+\frac{9}{8}x^8\right)$.

XVI. a. Pages 178, 179.

1. 8, 6. **2.** 2, -1. **3.** $-\frac{16}{3}, \frac{1}{2}$. **4.** 4, $\frac{3}{2}$.

5. $\frac{4}{3}, -\frac{4}{5}$. **6.** $\frac{2}{5}, \frac{1}{2}, \frac{5}{2}$. **7.** $\frac{7}{3}, -3, -\frac{4}{3}, \frac{2}{3}$.

8. $6\log a+9\log b$. **9.** $\frac{2}{3}\log a+\frac{3}{2}\log b$.

10. $-\frac{4}{9}\log a+\frac{1}{3}\log b$. **11.** $-\frac{2}{3}\log a-\frac{1}{2}\log b$.

12. $-\frac{7}{12}\log a-\log b$. **13.** $\frac{1}{2}\log a$. **14.** $-5\log c$. **16.** $\log 3$.

18. $\frac{\log c}{\log a-\log b}$. **19.** $\frac{5\log c}{2\log a+3\log b}$.

20. $\frac{\log a+\log b}{2\log c-\log a+\log b}$. **21.** $x=\frac{4\log m}{\log a}, y=-\frac{\log m}{\log b}$.

22. $\log x=\frac{1}{5}(a+3b), \log y=\frac{1}{5}(a-2b)$. **24.** $\frac{\log(a-b)}{\log(a+b)}$.

XVI. b. PAGES 185, 186.

1. 4, 1, 2, 2, 1, 1, 1.

2. ·8821259, 2·8821259, 3·8821259, 5·8821259, 6·8821259.

3. 5, 2, 4, 1.

4. Second decimal place; units' place; fifth decimal place.

5. 1·8061800. **6.** 1·9242793. **7.** 1·1072100. **8.** 2·0969100.

9. 1·1583626. **10.** ·6690067. **11.** ·3597271 **12.** ·0563520.

13. 1·5052973. **14.** ·44092388. **15.** 1·948445 **16.** 191563·1.

17. 1·1998692. **18.** 1·0039238. **19.** 9·076226 **20.** 178·141516.

21. 9. **23.** 301. **24.** 3·46. **25.** 4·29. **26.** 1·206. **27.** 14·206.

28. 4·562. **29.** $x=\dfrac{\log 3}{\log 3-\log 2}$; $y=\dfrac{\log 2}{\log 3-\log 2}$.

30. $x=\dfrac{3\log 3-2\log 2}{4(\log 3-\log 2)}$; $y=\dfrac{\log 3}{4(\log 3-\log 2)}$. **31.** 1·64601.

32. $\dfrac{\log 2}{2\log 7}=\cdot 1781$; $\dfrac{2\log 7}{\log 2}=5\cdot 614$.

XVII. PAGES 195 197.

1. $\log_e 2$. **2.** $\log_e 3-\log_e 2$. **6.** ·002000000666670.

9. $e^{x^2}-e^{y^2}$. **10.** ·8450980; 1·0413927; 1·1139434. In Art. 225 put $n=50$ in (2); $n=10$ in (1); and $n=1000$ in (1) respectively.

12. $(-1)^{r-1}.\dfrac{2^r+1}{r}x^r$. **13.** $\dfrac{(-1)^{r-1}3^r+2^r}{r}x^r$.

14. $2\left\{1+\dfrac{(2x)^2}{\lfloor 2}+\dfrac{(2x)^4}{\lfloor 4}+\ldots+\dfrac{(2x)^{2r}}{\lfloor 2r}+\ldots\right\}$.

15. $1-\dfrac{x^2}{\lfloor 2}+\dfrac{x^4}{\lfloor 4}-\dfrac{x^6}{\lfloor 6}+\ldots+(-1)^r\dfrac{x^{2r}}{\lfloor 2r}+\ldots$ **18.** $\dfrac{x}{1-x}+\log_e(1-x)$.

24. ·69314718; 1·09861229; 1·60943792; $a=-\log_e\left(1-\frac{1}{10}\right)=\cdot 105360516$;

$b=-\log_e\left(1-\dfrac{4}{100}\right)=\cdot 040821995$; $c=\log_e\left(1+\dfrac{1}{80}\right)=\cdot 012422520$.

XVIII. a. PAGE 202.

1. £1146. 14*s*. 10*d*. **2.** £720. **3.** 14·2 years.

4. £6768. 7*s*. 10½*d*. **5.** 9·6 years. **8.** £496. 19*s*. 4¾*d*.

9. A little less than 7 years. **10.** £119. 16*s*. 4¾*d*.

XVIII. b. PAGE 207.

1. 6 per cent. **2.** £3137. 2*s*. 2⅔*d*. **3.** £110.

4. 3 per cent. **5.** 28⅔ years. **6.** £1275. **7.** £926. 2*s*.

8. £6755. 13*s*. **9.** £183. 18*s*. **10.** 3⅓ per cent. **11.** £616. 9*s*. 1½*d*.

13. £1308. 12*s*. 4½*d*. **15.** £4200.

XIX. a. PAGES 213, 214.

8. a^3+2b^3 is the greater. **12.** $x^3 >$ or $< x^2+x+2$, according as $x >$ or < 2.

14. The greatest value of x is 1. **15.** 4; 8.

22. $4^4 . 5^5$; when $x=3$. **23.** 9, when $x=1$.

XIX. b. PAGES 218, 219.

10. $\frac{3^3 . 5^5}{2^8} a^8$; $\sqrt{\frac{3}{5}} \cdot \sqrt[3]{\frac{2}{5}}$.

XX. PAGE 228.

1. $-\frac{10}{7}$; $-\frac{9}{4}$. **2.** 9; $\frac{1}{9}$. **3.** $\frac{1}{2}$, $\frac{5}{3}$.

4. $-\frac{15}{8}$; 6. **5.** 1; 0. **6.** 0; -30. **7.** $-\frac{3}{2}$.

8. $\log a - \log b$. **9.** 2. **10.** me^{ma} **11.** $\frac{1}{2\sqrt{a}}$.

12. $\frac{1}{3}$. **13.** -1. **14.** $\frac{\sqrt{2a}}{a\sqrt{3}+1}$. **15.** $\sqrt{a}$.

16. 0. **17.** $\frac{3}{2}$. **18.** $e^{\frac{2}{a}}$

XXI. a. PAGES 241, 242.

1. Convergent. **2.** Convergent. **3.** Convergent.

4. $x<1$, or $x=1$, convergent; $x>1$, divergent.

5. Same result as Ex. 4. **6.** Convergent. **7.** Divergent.

8. $x<1$, convergent; $x>1$, or $x=1$, divergent.

9. Divergent except when $p>2$.

10. $x<1$, or $x=1$, convergent; $x>1$, divergent.

11. If $x<1$, convergent; $x>1$, or $x=1$, divergent.

12. Same result as Ex. 11. **13.** Divergent, except when $p>1$.

14. $x<1$, or $x=1$, convergent; $x>1$, divergent.

15. Convergent. **16.** Divergent.

17. (1) Divergent. (2) Convergent.

18. (1) Divergent. (2) Convergent.

XXI. b. PAGE 252.

1. $x<1$, or $x=1$, convergent; $x>1$, divergent.

2. Same result as Ex. 1. **3.** Same result as Ex. 1.

4. $x<\frac{1}{e}$, or $x=\frac{1}{e}$, convergent; $x>\frac{1}{e}$, divergent.

5. $x<e$, convergent; $x>e$, or $x=e$, divergent.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

11. $\dfrac{1}{x-1}-\dfrac{1}{x+1}+\dfrac{3}{(x+1)^2}-\dfrac{3}{(x+1)^3}+\dfrac{2}{(x+1)^4}$.

12. $\dfrac{4}{3(1+7x)}-\dfrac{1}{3(1+4x)}$; $\dfrac{(-1)^r}{3}(4\,.\,7^r-4^r)\,x^r$.

13. $\dfrac{11}{3(1-x)}-\dfrac{4}{3(2+x)}$; $\dfrac{1}{3}\left(11+\dfrac{(-1)^{r-1}}{2^{r-1}}\right)x^r$.

14. $1+\dfrac{7}{3(x+5)}-\dfrac{7}{3(x+2)}$; $(-1)^r\dfrac{7}{3}\left(\dfrac{1}{5^{r+1}}-\dfrac{1}{2^{r+1}}\right)x^r$.

15. $\dfrac{1}{1-x}-\dfrac{1}{1+x}-\dfrac{4}{1-2x}$; $\{1+(-1)^{r-1}-2^{r+2}\}\,x^r$.

16. $\dfrac{4}{3(1+2x)}-\dfrac{1}{3(1-x)}+\dfrac{3}{(1-x)^2}$; $\dfrac{1}{3}\{9r+8+(-1)^r\,2^{r+2}\}\,x^r$.

17. $\dfrac{1}{4(1-4x)}+\dfrac{11}{4(1-4x)^2}$; $4^{r-1}(12+11r)\,x^r$.

18. $\dfrac{2}{1+x}+\dfrac{3}{(1+x)^2}-\dfrac{6}{2+3x}$; $(-1)^r\left(3r+5-\dfrac{3^{r+1}}{2^r}\right)x^r$.

19. $\dfrac{3}{2(x-1)}+\dfrac{1-3x}{2(1+x^2)}$; r even, $\dfrac{1}{2}\{(-1)^{\frac{r}{2}}-3\}\,x^r$; r odd, $-\dfrac{3}{2}\{1+(-1)^{\frac{r-1}{2}}\}\,x^r$.

20. $\dfrac{2}{(1-x)^3}-\dfrac{3}{(1-x)^2}+\dfrac{2}{1-x}$; $(r^2+1)\,x^r$.

21. $\left\{\dfrac{a^{r+2}}{(a-b)(a-c)}+\dfrac{b^{r+2}}{(b-c)(b-a)}+\dfrac{c^{r+2}}{(c-a)(c-b)}\right\}x^r$.

22. $-\dfrac{5}{(2-x)^2}-\dfrac{2}{2-x}+\dfrac{1}{(1-x)^2}+\dfrac{2}{1-x}$; $\left\{r+3-\dfrac{5r+9}{2^{r+2}}\right\}x^r$.

23. (1) $\dfrac{1}{x(1-x)}\left\{\dfrac{1}{1+x^{n+1}}-\dfrac{1}{1+x}\right\}$.

(2) $\dfrac{1}{(1-a)^2}\left\{\dfrac{1}{1+a^nx}-\dfrac{1}{1+a^{n+1}x}-\dfrac{1}{1+x}+\dfrac{1}{1+ax}\right\}$.

24. $\dfrac{1}{x(1-x)(1-x^2)}$.

25. $\dfrac{1}{(1-x)^2}\left\{\dfrac{x}{1-x}-\dfrac{x^2}{1-x^2}-\dfrac{x^{n+1}}{1-x^{n+1}}+\dfrac{x^{n+2}}{1-x^{n+2}}\right\}$.

XXIV. PAGE 272.

1. $\dfrac{1+3x}{(1-x)^2}$; $(4r+1)\,x^r$.

2. $\dfrac{2+x}{1+x-2x^2}$; $\{1+(-1)^r\,2^r\}\,x^r$.

3. $\dfrac{2-3x}{1-3x+2x^2}$; $(1+2^r)\,x^r$.

4. $\dfrac{7-20x}{1-2x-3x^2}$; $\left\{\dfrac{27}{4}(-1)^r+\dfrac{3^r}{4}\right\}x^r$.

5. $\dfrac{3-12x+11x^2}{1-6x+11x^2-6x^3}$; $(3^r+2^r+1)\,x^r$.

6. $3^{n-1}+2^{n-1}$; $\dfrac{1}{2}(3^n-1)+2^n-1$.

7. $(2\,.\,3^{n-1}-3\,.\,2^{n-1})\,x^{n-1}$; $\dfrac{2(1-3^nx^n)}{1-3x}-\dfrac{3(1-2^nx^n)}{1-2x}$.

8. $(4^{n-1}+3^{n-1})\,x^{n-1}$; $\dfrac{1-4^nx^n}{1-4x}+\dfrac{1-3^nx^n}{1-3x}$

9. $(1+3^{n-1}-2^{n-1})\,x^{n-1}$; $\dfrac{1-x^n}{1-x}+\dfrac{1-3^nx^n}{1-3x}-\dfrac{1-2^nx^n}{1-2x}$.

10. $\dfrac{8}{5}(-1)^n+\dfrac{2^{2n-3}}{5}$; $\dfrac{4}{5}\{(-1)^n-1\}+\dfrac{1}{30}(2^{2n}-1)$.

11. $u_n-3u_{n-1}+3u_{n-2}-u_{n-3}=0$; $u_n-4u_{n-1}+6u_{n-2}-4u_{n-3}+u_{n-4}=0$.

12. $S_n=S_\infty-\Sigma$, where $\Sigma=$sum to infinity beginning with $(n+1)^{\text{th}}$ term. This may easily be shewn to agree with the result in Art. 325.

13. $(2n+1)^2+\dfrac{2}{3}(2^{2n+1}+1)$.

XXV. a. Pages 277, 278.

1. $\dfrac{2}{1}, \dfrac{13}{6}, \dfrac{15}{7}, \dfrac{28}{13}, \dfrac{323}{150}, \dfrac{674}{313}$.

2. $\dfrac{1}{2}, \dfrac{2}{5}, \dfrac{7}{17}, \dfrac{9}{22}, \dfrac{43}{105}, \dfrac{95}{232}, \dfrac{613}{1497}$.

3. $\dfrac{3}{1}, \dfrac{10}{3}, \dfrac{13}{4}, \dfrac{36}{11}, \dfrac{85}{26}, \dfrac{121}{37}, \dfrac{1174}{359}$.

4. $1+\dfrac{1}{2+}\,\dfrac{1}{2+}\,\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{1+}\,\dfrac{1}{2+}\,\dfrac{1}{2}$; $\dfrac{17}{12}$.

5. $5+\dfrac{1}{4+}\,\dfrac{1}{3+}\,\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{3}$; $\dfrac{157}{30}$.

6. $\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3}$; $\dfrac{33}{109}$.

7. $\dfrac{1}{3+}\,\dfrac{1}{5+}\,\dfrac{1}{1+}\,\dfrac{1}{1+}\,\dfrac{1}{3+}\,\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{5}$; $\dfrac{11}{35}$.

8. $\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{2+}\,\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{3}$; $\dfrac{7}{19}$.

9. $1+\dfrac{1}{7+}\,\dfrac{1}{5+}\,\dfrac{1}{6+}\,\dfrac{1}{1+}\,\dfrac{1}{3}$; $\dfrac{254}{223}$.

10. $\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{3+}\,\dfrac{1}{6+}\,\dfrac{1}{1+}\,\dfrac{1}{2+}\,\dfrac{1}{1+}\,\dfrac{1}{10}$; $\dfrac{63}{208}$.

11. $4+\dfrac{1}{3+}\,\dfrac{1}{6+}\,\dfrac{1}{3}$; $\dfrac{259}{60}$.

13. $\dfrac{1}{4}, \dfrac{7}{29}, \dfrac{8}{33}, \dfrac{39}{161}, \dfrac{47}{194}$.

16. $n-1+\dfrac{1}{(n+1)+}\,\dfrac{1}{(n-1)+}\,\dfrac{1}{n+1}$; and the first three convergents are

$$\frac{n-1}{1}, \frac{n^2}{n+1}, \frac{n^3-n^2+n-1}{n^2}.$$

XXV. b. Pages 281—283.

1. $\dfrac{1}{(203)^2}$ and $\dfrac{1}{2\,(1250)^2}$.

2. $\dfrac{151}{115}$.

4. $\dfrac{1}{a+}\,\dfrac{1}{(a+1)+}\,\dfrac{1}{(a+2)+}\,\dfrac{1}{a+3}$; $\dfrac{a^2+3a+3}{a^3+3a^2+4a+2}$.

XXVI. PAGES 290, 291.

1. $x=711t+100$, $y=775t+109$; $x=100$, $y=109$.

2. $x=519t-73$, $y=455t-64$; $x=446$, $y=391$.

3. $x=393t+320$, $y=436t+355$; $x=320$, $y=355$.

4. Four. **5.** Seven. **6.** $\frac{4}{5}$, $\frac{4}{9}$.

7. $\frac{5}{12}$, $\frac{3}{8}$; $\frac{11}{12}$, $\frac{7}{8}$; or $\frac{1}{8}$, $\frac{1}{12}$; $\frac{5}{8}$, $\frac{7}{12}$.

8. £6. 13*s*. **9.** $x=9$, $y=8$, $z=3$. **10.** $x=5$, $y=6$, $z=7$.

11. $x=4$, $y=2$, $z=7$. **12.** $x=2$, $y=9$, $z=7$.

13. $x=3, 7, 2, 6, 1$; $y=11, 4, 8, 1, 5$; $z=1, 1, 2, 2, 3$.

14. $x=1, 3, 2$; $y=5, 1, 3$; $z=2, 4, 3$.

15. $280t+93$. **16.** 181, 412.

17. Denary 248, Septenary 503, Nonary 305.

18. $a=11, 10, 9, 8, 6, 4, 3$; $b=66, 30, 18, 12, 6, 3, 2$.

19. The 107th and 104th divisions, reckoning from either end.

20. 50, 41, 35 times, excluding the first time.

21. 425. **22.** 899. **23.** 1829 and 1363.

XXVII. a. PAGES 294, 295.

1. $1+\cfrac{1}{1+}\ \cfrac{1}{2+}\cdots$; $\frac{26}{15}$.

2. $2+\cfrac{1}{4+}\cdots$; $\frac{2889}{1292}$.

3. $2+\cfrac{1}{2+}\ \cfrac{1}{4+}\cdots$; $\frac{485}{198}$

4. $2+\cfrac{1}{1+}\ \cfrac{1}{4+}\cdots$; $\frac{99}{35}$.

5. $3+\cfrac{1}{3+}\ \cfrac{1}{6+}\cdots$; $\frac{3970}{1197}$.

6. $3+\cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{6+}\cdots$; $\frac{119}{33}$.

7. $3+\cfrac{1}{1+}\ \cfrac{1}{2+}\ \cfrac{1}{1+}\ \cfrac{1}{6+}\cdots$; $\frac{116}{31}$.

8. $4+\cfrac{1}{1+}\ \cfrac{1}{2+}\ \cfrac{1}{4+}\ \cfrac{1}{2+}\ \cfrac{1}{1+}\ \cfrac{1}{8+}\cdots$; $\frac{197}{42}$.

9. $3+\cfrac{1}{2+}\ \cfrac{1}{6+}\cdots$; $\frac{1351}{390}$.

10. $5+\cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{10+}\cdots$; $\frac{198}{35}$.

11. $6+\cfrac{1}{1+}\ \cfrac{1}{2+}\ \cfrac{1}{2+}\ \cfrac{1}{2+}\ \cfrac{1}{1+}\ \cfrac{1}{12+}$; $\frac{161}{24}$.

12. $12+\cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{5+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{24+}$; $\frac{253}{20}$.

13. $\cfrac{1}{4+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{2+}\ \cfrac{1}{1+}\ \cfrac{1}{1+}\ \cfrac{1}{8+}\cdots$; $\frac{12}{55}$.

14. $\cfrac{1}{5+}\ \cfrac{1}{1+}\ \cfrac{1}{2+}\ \cfrac{1}{1+}\ \cfrac{1}{10+}\cdots$; $\frac{47}{270}$.

15. $1+\cfrac{1}{10+}\ \cfrac{1}{2+}\cdots$; $\frac{5291}{4830}$.

16. $\cfrac{1}{1+}\ \cfrac{1}{3+}\ \cfrac{1}{1+}\ \cfrac{1}{16+}\ \cfrac{1}{1+}\ \cfrac{1}{3+}\ \cfrac{1}{2+}\ \cfrac{1}{3+}\ \cfrac{1}{1+}\ \cfrac{1}{16+}\cdots$; $\frac{280}{351}$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

15. $x = m^2 - 3n^2,\ y = m^2 - 2mn.$ **16.** $x = -m^2 + 2mn + n^2;\ y = m^2 - n^2.$

17. $x = 2mn,\ y = 5m^2 - n^2.$ **18.** 53, 52; 19, 16; 13, 8; 11, 4.

19. $m^2 - n^2;\ 2mn;\ m^2 + n^2.$ **20.** $m^2 - n^2;\ 2mn + n^2$

21. Hendriek, Anna; Claas, Catriin; Cornelius, Geertruij.

XXIX. a. Pages 321, 322.

1. $\frac{1}{4} n (n+1) (n+2) (n+3).$ **2.** $\frac{1}{5} n (n+1) (n+2) (n+3) (n+4).$

3. $\frac{1}{12} (3n-2) (3n+1) (3n+4) (3n+7) + \frac{56}{12} = \frac{n}{4} (27n^3 + 90n^2 + 45n - 50).$

4. $\frac{n}{4} (n+1) (n+6) (n+7).$ **5.** $\frac{n}{4} (n+1) (n+8) (n+9).$

6. $\frac{n}{n+1};\ 1.$ **7.** $\frac{n}{3n+1};\ \frac{1}{3}.$

8. $\frac{1}{12} - \frac{1}{4 (2n+1) (2n+3)};\ \frac{1}{12}.$ **9.** $\frac{1}{24} - \frac{1}{6 (3n+1) (3n+4)};\ \frac{1}{24}.$

10. $\frac{5}{4} - \frac{2n+5}{2 (n+1) (n+2)};\ \frac{5}{4}.$ **11.** $\frac{1}{6} - \frac{1}{n+3} + \frac{2}{(n+3) (n+4)};\ \frac{1}{6}.$

12. $\frac{3}{4} - \frac{2}{n+2} + \frac{1}{2 (n+1) (n+2)};\ \frac{3}{4}.$ **13.** $\frac{n}{10} (n+1) (n+2) (n+3) (2n+3).$

14. $\frac{1}{4} n^2 (n^2 - 1).$ **15.** $\frac{n}{10} (n-1) (n+1) (n+2) (2n+1).$

16. $\frac{1}{15} (n+1) (n+2) (3n^3 + 36n^2 + 151n + 240) - 32.$

17. $\frac{(n-1) n (n+1) (n+2)}{6 (2n+1)}.$ **18.** $\frac{n (n+1) (n+2)}{3} - \frac{n}{n+1}.$

19. $\frac{n (n+3)}{2} + \frac{3}{2} - \frac{2}{n+2} - \frac{1}{(n+1) (n+2)}.$ **20.** $n + 1 - \frac{1}{n+1}.$

XXIX. b. Pages 332, 333.

1. $3n^2 + n;\ n (n+1)^2.$ **2.** $5n^2 + 3n;\ \frac{1}{3} n (n+1) (5n+7).$

3. $n^2 (n+1);\ \frac{1}{12} n (n+1) (n+2) (3n+1).$

4. $-4n^2 (n-3);\ -n (n+1) (n^2 - 3n - 2).$

5. $n (n+1) (n+2) (n+4);\ \frac{1}{20} n (n+1) (n+2) (n+3) (4n+21).$

6. $\frac{1 + x^2}{(1-x)^3}.$ **7.** $\frac{1 - x + 6x^2 - 2x^3}{(1-x)^3}.$ **8.** $\frac{2 - x + x^2}{(1-x)^3}.$

9. $\frac{1-x}{(1+x)^2}.$ **10.** $\frac{1 + 11x + 11x^2 + x^3}{(1-x)^5}.$ **11.** $\frac{9}{4}.$

12. $\frac{25}{54}.$ **13.** $3 \cdot 2^n + n + 2;\ 6 (2^n - 1) + \frac{n (n+5)}{2}.$

14. $n^3-(n+1)^2$; $\frac{n}{12}(3n^3+2n^2-15n-26)$. **15.** $3^{n-1}+n$; $\frac{3^n+n^2+n-1}{2}$.

16. $2^{n+1}-n^2-2n$; $2^{n+2}-4-\frac{1}{6}n(n+1)(2n+7)$.

17. $3^n-1+\frac{1}{2}n(n+3)$; $\frac{1}{2}(3^{n+1}-3)+\frac{n(n+1)(n+5)}{6}-n$.

18. $\frac{1-x^n}{(1-x)^2}-\frac{nx^n}{1-x}$. **19.** $\frac{1-x^n}{(1-x)^3}-\frac{nx^n}{(1-x)^2}-\frac{n(n+1)x^n}{2(1-x)}$.

20. $1-\frac{1}{n+1}\cdot\frac{1}{2^n}$. **21.** $\frac{n-1}{n+2}\cdot\frac{4^{n+1}}{3}+\frac{2}{3}$.

22. $\frac{n(n+1)(3n^3+27n^2+58n+2)}{15}$. **23.** $\frac{n(n+1)(12n^3+33n^2+37n+8)}{60}$.

24. $\frac{n(n+1)(9n^2+13n+8)}{12}$. **25.** $\frac{1}{2}-\frac{1}{2}\cdot\frac{1}{1.3.5.7\ldots\ldots(2n+1)}$.

26. $1-\frac{2^{n+1}}{\lfloor n+2}$. **27.** $(n^2-n+4)2^n-4$.

28. $(n-1)3^{n+1}+3$. **29.** $\frac{1}{2}-\frac{1.3.5\ldots\ldots(2n+1)}{2.4.6\ldots\ldots(2n+2)}$.

30. $\frac{n}{n+1}\cdot 2^n$. **31.** $\frac{1}{4}-\frac{1}{2(n+1)(n+2)}\cdot\frac{1}{3^n}$.

32. $\frac{1}{2}-\frac{n+1}{\lfloor n+2}$. **33.** $1-\frac{n+4}{(n+1)(n+2)}\cdot\frac{1}{2^{n+1}}$.

XXIX. c. Pages 338—340.

1. $\frac{1}{2}(e^x-e^{-x})-x$. **2.** $1+\frac{1-x}{x}\log(1-x)$.

3. $\frac{1}{4}(e^x-e^{-x}-ie^{ix}+ie^{-ix})$. **4.** $\frac{1}{(r-2)\lfloor\overline{r-1}}$.

5. $(1+x)e^x$. **6.** $\frac{(p+q)^r}{\lfloor r}$. **7.** 1.

8. $n(2n-1)$. **9.** 0. **10.** 4.

11. $\log_e 2-\frac{1}{2}$. **12.** $3(e-1)$. **13.** $e^x-\log(1+x)$.

14. (1) $\frac{n^7}{7}+\frac{n^6}{2}+\frac{n^5}{2}-\frac{n^3}{6}+\frac{n}{42}$. (2) $\frac{n^8}{8}+\frac{n^7}{2}+\frac{7n^6}{12}-\frac{7n^4}{24}+\frac{n^2}{12}$.

15. $15e$. **17.** (1) $n+1$.

19. (1) $\frac{1}{2}\left(1-\frac{1}{1+n+n^2}\right)$; (2) $3-\frac{2+(-1)^n}{n+1}$.

20. $\frac{(1+x)^2}{2x^2}\log(1+x)-\frac{3x+2}{4x}$. **21.** $n(n+1)2^{n-3}$.

22. (1) $\frac{1}{3}\left\{1+\frac{(-1)^{n+1}}{2^{n+1}+(-1)^{n+1}}\right\}$. (2) $\frac{1}{2}\left\{\frac{3}{2}+(-1)^{n-1}\frac{2n+3}{(n+1)(n+2)}\right\}$.

XXX. a. Pages 348, 349.

1. 3, 6, 15, 42. **2.** 1617, 180, 1859. **6.** 48.
7. 23. **33.** 8987.

XXX. b. Pages 356—358.

20. $x = 139t + 61$, where t is an integer.

XXXI. a. Pages 367—369.

2. $1 + \cfrac{1}{x - \cfrac{1}{4 + \cfrac{1}{x}}}$.

18. 1; it can be shewn that $q_n = 1 + p_n$.

XXXII. a. Pages 376, 377.

1. (1) $\frac{1}{9}$; (2) $\frac{5}{36}$. **2.** $\frac{8}{663}$. **3.** $\frac{1}{56}$. **4.** $\frac{3}{8}$.

5. 2 to 3. **6.** $\frac{4}{270725}$. **8.** 43 to 34. **9.** 36 : 30 : 25.

10. $\frac{2197}{20825}$. **11.** 952 to 715. **14.** $\frac{1}{6}$. **15.** $\frac{2}{7}$.

16. $\frac{11}{4165}$. **17.** $\frac{n(n-1)}{(m+n)(m+n-1)}$.

XXXII. b. Pages 383, 384.

1. $\frac{5}{36}$. **2.** $\frac{16}{5525}$. **3.** $\frac{52}{77}$. **4.** $\frac{16}{21}$. **5.** $\frac{8}{15}$.

6. $\frac{72}{289}$. **7.** (1) $\frac{2197}{20825}$; (2) $\frac{2816}{4165}$. **8.** $\frac{4651}{7776}$. **9.** $\frac{209}{343}$.

10. $\frac{1}{7}$. **11.** $\frac{91}{216}$. **13.** $\frac{10}{19}$. **14.** $\frac{63}{256}$. **15.** $\frac{1}{32}$.

16. $\frac{16}{37}, \frac{12}{37}, \frac{9}{37}$. **17.** $\frac{22}{35}, \frac{13}{35}$. **18.** $n-3$ to 2.

19. 13 to 5. **20.** $\frac{45927}{50000}$.

XXXII. c. Pages 389, 390

1. $\frac{2133}{3125}$. **2.** $\frac{5}{16}$. **3.** $\frac{4}{9}$. **4.** Florins. **5.** $\frac{1}{2}$.

6. 17*s.* $2\frac{2}{5}$*d.* **7.** $\frac{4}{63}$. **8.** $\frac{7}{27}$. **9.** 11 to 5. **10.** $\frac{1}{8}$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

26. The determinant is equal to $\begin{vmatrix} a^2 & a & 1 \\ b^2 & b & 1 \\ c^2 & c & 1 \end{vmatrix} \times \begin{vmatrix} 1 & -2x & x^2 \\ 1 & -2y & y^2 \\ 1 & -2z & z^2 \end{vmatrix}$.

27. $\begin{vmatrix} u & w' & v' \\ w' & v & u' \\ v' & u' & w \end{vmatrix} = 0.$

28. $\begin{vmatrix} u & w' & v' \\ w' & v & u' \\ v' & u' & w \end{vmatrix} \div \begin{vmatrix} u & w' & v' & a \\ w' & v & u' & b \\ v' & u' & w & c \\ a & b & c & 0 \end{vmatrix}$.

XXXIII. b. PAGES 427, 428.

1. 1. **2.** 0; add first and second rows, third and fourth rows.

3. $(a+3)(a-1)^3$. **4.** $a^2+b^2+c^2-2bc-2ca-2ab$.

5. 6; from the first column subtract three times the third, from the second subtract twice the third, and from the fourth subtract four times the third.

6. $abcd\left(1+\frac{1}{a}+\frac{1}{b}+\frac{1}{c}+\frac{1}{d}\right)$.

7. $-(x+y+z)(y+z-x)(z+x-y)(x+y-z)$.

8. $(ax-by+cz)^2$. **9.** a^4. **12.** $x=\frac{(k-b)(k-c)}{(a-b)(a-c)}$; &c.

13. $x=\frac{k(k-b)(k-c)}{a(a-b)(a-c)}$; &c. **14.** $x=\frac{(k-b)(k-c)(k-d)}{(a-b)(a-c)(a-d)}$; &c.

XXXIV. a. PAGES 439, 440.

1. -102. **2.** $3a+b=27$.

3. x^3-2x^2+x+1; $-15x+11$. **4.** $a=3$.

5. $x^{-4}+5x^{-5}+18x^{-6}+54x^{-7}$; $147x^{-4}-356x^{-5}+90x^{-6}+432x^{-7}$

6. $(b-c)(c-a)(a-b)(a+b+c)$.

7. $-(b-c)(c-a)(a-b)(b+c)(c+a)(a+b)$.

8. $24abc$. **9.** $(b+c)(c+a)(a+b)$.

10. $(b-c)(c-a)(a-b)(a^2+b^2+c^2+bc+ca+ab)$.

11. $3abc(b+c)(c+a)(a+b)$. **12.** $12abc(a+b+c)$.

13. $80abc(a^2+b^2+c^2)$.

14. $3(b-c)(c-a)(a-b)(x-a)(x-b)(x-c)$.

28. $\frac{x}{(x-a)(x-b)(x-c)}$. **29.** 2.

30. $\frac{(p-x)(q-x)}{(a+x)(b+x)(c+x)}$. **31.** -1. **32.** $a+b+c+d$.

XXXIV. b. PAGES 442, 443.

5. 0. **7.** $A=ax+by+ay$, $B=bx-ay$.

28 $(a^2+bc)(b^2+ca)(c^2+ab)$.

XXXIV. c. PAGES 449, 450.

1. $x^3+xy^2+ay^2=0$. **2.** $x+a=0$. **3.** $x^2+y^2=a^2$.

4. $y^2=a(x-3a)$. **5.** $a^6-a^3=1$. **6.** $x^2+y^2=2a^2$

7. $b^4c^4+c^4a^4+a^4b^4=a^2b^2c^2d^2$. **8.** $y^2-4ax=k^2(x+a)^2$

9. $a^4-4ac^3+3b^4=0$. **10.** $a^4-2a^2b^2-b^4+2c^4=0$.

11. $\dfrac{a}{1+a}+\dfrac{b}{1+b}+\dfrac{c}{1+c}+\dfrac{d}{1+d}=1$. **12.** $5a^2b^3=6c^5$.

13. $ab=1+c$. **14.** $a^3+b^3+c^3+abc=0$.

15. $(a+b)^{\frac{2}{3}}-(a-b)^{\frac{2}{3}}=4c^{\frac{2}{3}}$. **16.** $a^2+b^2+c^2\pm2abc=1$.

17. $abc=(4-a-b-c)^2$. **18.** $a^2-4abc+ac^3+4b^3-b^2c^2=0$.

20. $c^2(a+b-1)^2-c(a+b-1)(a^2-2ab+b^2-a-b)+ab=0$.

22. $$\frac{1}{(a-b)cr+(a-c)bq}+\frac{1}{(b-c)ap+(b-a)cr}+\frac{1}{(c-a)bq+(c-b)ap}=\frac{1}{bcqr+carp+abpq}.$$

23. $$\begin{vmatrix} ab'-a'b & ac'-a'c & ad'-a'd \\ ac'-a'c & ad'-a'd+bc'-b'c & bd'-b'd \\ ad'-a'd & bd'-b'd & cd'-c'd \end{vmatrix}=0.$$

XXXV. a. PAGES 456, 457.

1. $6x^4-13x^3-12x^2+39x-18=0$. **2.** $x^6+2x^5-11x^4-12x^3+36x^2=0$.

3. $x^6-5x^5-8x^4+40x^3+16x^2-80x=0$.

4. $x^4-2(a^2+b^2)x^2+(a^2-b^2)^2$. **5.** 1, 3, 5, 7.

6. $\frac{3}{2}, \frac{3}{2}, -4$. **7.** $\frac{1}{2}, \frac{1}{2}, 6$. **8.** $6, 2, \frac{2}{3}$.

9. $-\frac{3}{2}, -2, 4$. **10.** $\frac{3}{2}, -\frac{3}{4}, \frac{1}{3}$. **11.** $\pm\sqrt{3}, \frac{3}{4}, -\frac{1}{2}$.

12. $\frac{8}{9}, \frac{2}{3}, \frac{1}{2}$. **13.** $\frac{1}{4}, \frac{1}{2}, \frac{3}{4}$. **14.** $\frac{4}{3}, \frac{3}{2}, 1\pm\sqrt{2}$.

15. $-4, -1, 2, 5$. **16.** $\frac{8}{9}, \frac{4}{3}, 2, 3$. **17.** $-\frac{4}{3}, -\frac{3}{2}, -\frac{5}{3}$.

18. (1) $\dfrac{q^2-2pr}{r^2}$; (2) $\dfrac{p^2-2q}{r^2}$. **19.** (1) $-6q$; (2) $\dfrac{q}{r}$.

20. $-2q, -3r$. **21.** $2q^2$.

XXXV. b. PAGES 460, 461.

1. $3, -\frac{2}{3}, \dfrac{1\pm\sqrt{-3}}{2}$. **2.** $\frac{3}{2}, \frac{1}{3}, 2\pm\sqrt{3}$.

3. $-1\pm\sqrt{2}, -1\pm\sqrt{-1}$. **4.** $\pm\sqrt{-1}, -2\pm\sqrt{-1}$.

5. $-1, \pm\sqrt{3}, 1\pm2\sqrt{-1}$. **6.** $x^4-2x^2+25=0$.

7. $x^4-8x^2+36=0$. **8.** $x^4+16=0$.

9. $x^4-10x^2+1=0$. **10.** $x^4-10x^3-19x^2+480x-1392=0$.

11. $x^4-6x^3+18x^2-26x+21=0$. **12.** $x^8-16x^6+88x^4+192x^2+144=0$.

13. One positive, one negative, two imaginary. **[Compare Art. 554.]**

15. One positive, one negative, at least four imaginary. [Compare Art. 554.]

16. Six. **17.** (1) $pq=r$; (2) $p^3r=q^3$. **20.** q^2-2pr.

21. $pq-r$. **22.** $\frac{pq}{r}-3$. **23.** $pq-3r$.

24. $pr-4s$. **25.** $p^4-4p^2q+2q^2+4pr-4s$.

XXXV. c. PAGES 470, 471.

1. $x^4-6x^3+15x^2-12x+1$. **2.** $x^4-37x^2-123x-110$.

3. $2x^4+8x^3-x^2-8x-20$. **4.** x^4-24x^2-1.

5. $16axh\,(x^6+7x^4h^2+7x^2h^4+h^6)+2bh\,(5x^4+10x^2h^2+h^4)+2ch$.

10. 2, 2, −1, −3. **11.** 1, 1, 1, 3. **12.** 3, 3, 3, 2, 2.

13. $-2, \frac{1\pm\sqrt{-3}}{2}, \frac{1\pm\sqrt{-3}}{2}$. **14.** $\frac{1}{2}, \frac{1}{2}, \frac{1}{2}, -2$.

15. 1, 1, 1, −1, −1, 2. **16.** $\pm\sqrt{3}, \pm\sqrt{3}, 1\pm\sqrt{-1}$.

17. $a, a, -a, b$. **18.** $\pm\sqrt{\frac{3}{2}}, \frac{1\pm\sqrt{-7}}{2}; \pm\sqrt{\frac{3}{2}}, \frac{1\pm\sqrt{-23}}{4}$.

19. $0, 1, -\frac{3}{2}, -\frac{5}{2}; 0, 1, -\frac{3}{2}, -\frac{5}{3}$. **20.** $n^nr^{n-2}=4p^n\,(n-2)^{n-2}$.

22. (1) −2; (2) −1. **27.** 5. **28.** 99, 795.

XXXV. d. PAGES 478, 479.

1. $y^3-24y^2+9y-24=0$. **2.** $y^4-5y^3+3y^2-9y+27=0$.

3. $1, 1, -2, -\frac{1}{2}$. **4.** $3\pm2\sqrt{2}, 2\pm\sqrt{3}$.

5. $1, \frac{1\pm\sqrt{-3}}{2}, \frac{3\pm\sqrt{5}}{2}$. **6.** $2, 2, \frac{1}{2}, \frac{1}{2}, \frac{1}{2}(1\pm\sqrt{-3})$.

7. $4, 2, \frac{4}{3}$. **8.** 6, 3, 2. **10.** $\frac{1}{4}, 1, \frac{1}{2}, -\frac{1}{5}$.

11. $y^3-2y+1=0$. **12.** $y^4-4y^2+1=0$. **13.** $y^5-7y^3+12y^2-7y=0$.

14. $y^6-60y^4-320y^3-717y^2-773y-42=0$.

15. $y^3-\frac{9y^2}{2}+\frac{13y}{2}-\frac{15}{4}=0$. **16.** $y^5+11y^4+42y^3+57y^2-13y-60=0$.

17. $y^3-8y^2+19y-15=0$. **18.** $y^4+3y^3+4y^2+3y+1=0$.

19. $y^3+33y^2+12y+8=0$. **20.** $ry^3+kqy^2+k^3=0$.

21. $y^3-q^2y^2-2qr^2y-r^4=0$. **22.** $ry^3-qy^2-1=0$.

23. $ry^3+q\,(1-r)\,y^2+(1-r)^3=0$. **24.** $y^3-2qy^2+q^2y+r^2=0$.

25. $y^3+3ry^2+(q^3+3r^2)\,y+r^3=0$.

26. $r^3y^3+3r^3y^2+(3r^2+q^3)\,ry+r\,(r^2+2q^3)=0$. **28.** $\pm1, \pm2, 5$.

THIS PAGE IS LOCKED TO FREE MEMBERS
Purchase full membership to immediately unlock this page

Know Your Bible

Forgotten Books' Full Membership provides unlimited access to more than 28,000 volumes of Christian literature for $8.99/month

Continue

*Fair use policy applies

24. Wages 15*s.*; loaf 6*d.* **25.** 6, 10, 14, 18.

26. (1) 1, $\frac{c(a-b)}{a(b-c)}$. (2) $\frac{ab(c+d)-cd(a+b)}{ab-cd}$. **28.** $88\frac{8}{9}$ miles.

29. $x=3k$, $y=4k$, $z=5k$; where $k^3=1$, so that $k=1$, ω, or ω^2. **30.** 480.

31. Either 33 half-crowns, 19 shillings, 8 fourpenny pieces;
or 37 half-crowns, 6 shillings, 17 fourpenny pieces.

32. $a=6$, $b=7$. **33.** 40 minutes.

35. $1+x+\frac{1}{2}x^2-\frac{1}{2}x^3-\frac{13}{8}x^4$.

37. $\frac{-1\pm\sqrt{-3}}{2}$, or $\frac{1\pm\sqrt{21}}{2}$. $[x^4-x-5(x^2+x+1)=0.]$

38. $a=8$; $\frac{x-4}{x-5}$. **40.** The first term.

41. 13, 9. **42.** $\frac{1+4b^2c^2+9c^2a^2+a^2b^2}{a^2+b^2+c^2}$.

43. (1) 3, -2, $\frac{-1\pm\sqrt{-39}}{2}$. [Add x^2+4 to each side.]

(2) $x=1$, $-\frac{1}{2}$, -1, 0, 0;

$x=1$, $-\frac{1}{2}$, 0, -1, 0;

$z=1$, $\frac{1}{2}$, 0, 0, -1. **47.** 5780.

48. 150 persons changed their mind; at first the minority was 250, the majority 350. **50.** 936 men.

51. (1) 0, $\frac{2^m-1}{2^m+1}a$. (2) $\frac{ad-bc}{a-b-c+d}$.

[Put $(a-c)(b-d)=\{(x-c)-(x-a)\}\{(x-d)-(x-b)\}$; then square.]

53. 6, $-\frac{161}{30}$. **55.** $m=\frac{2b\sqrt{a}}{\sqrt{a}+\sqrt{b}}$, $n=\frac{2a\sqrt{b}}{\sqrt{a}+\sqrt{b}}$.

58. (1) 1. (2) $\pm4\sqrt{2}$ [putting $x^2-16=y^4$, we find $y^4-16-4y(y^2-4)=0.$]

60. $\frac{(a-c)p}{b-c}$ males; $\frac{(b-a)p}{b-c}$ females. **63.** 0, $a+b$, $\frac{a^2+b^2}{a+b}$.

64. Common difference of the A. P. is $\frac{b-a}{n-1}$; common difference of the A.P. which is the reciprocal of the H.P. is $\frac{a-b}{ab(n-1)}$. [The r^{th} term is $\frac{a(n-r)+b(r-1)}{n-1}$; the $(n-r+1)^{\text{th}}$ term is $\frac{ab(n-1)}{a(n-r)+b(r-1)}$.]

68. 19. **69.** £78.

70. 0, $\frac{1\pm\sqrt{-3}}{2}$, $\frac{-1\pm\sqrt{-3}}{2}$.

$[(a+b)^3-a^3-b^3=3ab(a+b)$, and $(a-b)^3-a^3+b^3=-3ab(a-b).]$

72. (1) $x = \pm\dfrac{\log 3}{\log 6} - \pm\cdot 614.$ (2) $x = \pm\dfrac{2(1-2\log 2)}{1-\log 2} = \pm 1\cdot 139.$

73. 7, 2. **74.** 8 hours.

79. (1) $\dfrac{x}{a} = \dfrac{y}{b} = \dfrac{z}{c} = 0,$ or $\dfrac{a+b+c}{abc}.$ (2) $x = y = z = 1.$

80. $a = 3,\ b = 1.$ **81.** [Put $x - a = u$ and $y - b = v.$] **82.** $x = 3.$ **84.** 126.

85. Sums invested were £7700 and £3500: the fortune of each was £1400.

86. 503 in scale seven. **91.** 25 miles from London.

95. $x = 5,\ 1,\ \dfrac{15 \pm 6\sqrt{-1}}{29};\ y = 3,\ \dfrac{3}{5},\ \dfrac{25 \pm 10\sqrt{-1}}{29}.$ **96.** $\sqrt{\dfrac{5}{3}}.$ **98.** $\dfrac{1}{2e}.$

100. Generating function is $\dfrac{1+4x}{1-x-2x^2};$ sum $= \dfrac{2(1-2^n x^n)}{1-2x} - \dfrac{1-(-1)^n x^n}{1+x}.$

n^{th} term $= \{2^n + (-1)^n\}\, x^{n-1}.$

107. $a^2 + b - c^2 - d.$ **108.** 12 persons, £14. 18*s.*

109. (1) $x = a,\ y = b,\ z = c.$ (2) $x = 3,$ or $1;\ y = 1,$ or $3.$

111. $1 + \dfrac{1}{1+}\ \dfrac{1}{12+}\ \dfrac{1}{1+}\ \dfrac{1}{1+}\ \dfrac{1}{1+}\ \dfrac{1}{9};\ x = 948,\ y = 492.$ **113.** £12. 15*s.*

117. (1) $x = a,\ y = b;\ x = a,\ y = 2a;\ x = 2b,\ y = b.$

(2) $x = 3$ or $1,\ y = 2,\ z = 1$ or $3;$

$$x = \frac{-1 \pm \sqrt{29}}{2},\ y = -3;\ z = \frac{-1 \mp \sqrt{29}}{2}.$$

120. (1) $1 - \dfrac{1}{(n+1)^2}.$

(2) $\dfrac{a(x^n - 1)}{x - 1} + \dfrac{b}{(x-1)^3}\{x^{n+2} + x^{n+1} - (n+1)^2 x^2 + (2n^2 + 2n - 1)\, x - n^2\}.$

121. $\dfrac{1}{3}.$ **122.** (1) $\dfrac{-5 \pm \sqrt{-11}}{6}$ or $\dfrac{-3 \pm \sqrt{5}}{2}.$

(2) $x = 0,\ y = 0,\ z = 0;\ x = \pm 2,\ y = \pm 1,\ z = \pm 3.$

124. $\dfrac{13x - 23}{3(x^2 - 3x - 1)} - \dfrac{10x - 1}{3(x^2 + x + 1)};\ -\dfrac{r+4}{2^{r+1}}.$

125. $l = 1;$ scale of relation is $1 - x - 2x^2;$ general term is $\{2^{n-3} + (-1)^{n-1}\}\, x^{n-1}$

127. (1) $x = -6,\ 2;\ y = 9,\ -3.$ (2) $x = \dfrac{1}{a};\ y = \dfrac{1}{b}.$

128. (1) $\dfrac{a^2}{2}.$ (2) $\dfrac{2\sqrt{3}}{9}.$ **129.** 12, 16; or 48, 4.

130. (1) $x = \pm 7.$

(2) $\dfrac{x}{a} = \dfrac{y}{b} = \dfrac{z}{c} = \pm\dfrac{k}{2abc},$ where $k^2 = 2b^2c^2 + 2c^2a^2 + 2a^2b^2 - a^4 - b^4 - c^4.$

133. 11, $r - 1.$ **134.** 384 sq. yds. **136.** $a = \pm 2,\ b = 3,\ c = \pm 2.$

137. (1) $x = \pm\dfrac{7}{\sqrt{2}},\ y = \pm\dfrac{9}{\sqrt{2}}.$ (2) $\pm\dfrac{1}{\sqrt{2}};\ \pm\sqrt{\dfrac{13}{10}}.$

138. £3. 2*s.* at the first sale and £2. 12*s.* at the second sale.

139. (1) $\frac{1}{6}n(n+1)(2n+1)$. (2) $\frac{1}{60}n(n+1)(n+2)(3n^2+6n+1)$.

(3) $\frac{1}{6}n(n+1)(4n-1)$.

141. (1) $x=1$ or $\frac{14}{5}$; $y=3$ or $\frac{15}{7}$.

(2) x, y, z may have the permutations of the values 3, 5, 7.

142. $y^3+qy^2-q^2y-q^3-8r=0$.

143. (1) $\frac{x(x^n-1)}{(x-1)^2}-\frac{n}{x-1}$. (2) $\frac{3+14x-157x^2}{1+5x-50x^2-8x^3}$.

(3) $2^{n+1}+\frac{1}{2}n(n+7)-2$. **144.** $2(b^3-d^3)=3(b^2-c^2)(b-a)$.

145. $-2,\ -2,\ -2,\ \frac{2}{3}$.

146. A walks in successive days 1, 3, 5, 7, 9, | 11, 13, 15, 17, 19, 21, 23, | miles,
B walks ..... 12, 13, | 14, 15, 16, 17, 18, 19, 20, |
so that B overtakes A in 2 days and passes him on the third day; A subsequently gains on B and overtakes him on B's 9th day.

147. $\frac{\sqrt{6}-1}{5}$. **148.** $-(a+b+c),\ -(a+\omega b+\omega^2 c),\ -(a+\omega^2 b+\omega c)$.

150. n^{th} term is $\frac{n(a^n-b^n)}{a-b}x^{n-1}$; Sum$=A-B$,

where $A=\frac{a(1-na^nx^n)}{1-ax}+\frac{a^2x(1-a^{n-1}x^{n-1})}{(1-ax)^2}$, and B denotes a corresponding function of B.

151. $qy^3-2p^2y^2-5pqy-2p^3-q^2=0$.

153. (1) $-7,\ \frac{7\pm3\sqrt{-3}}{2}$. (2) $\pm1,\ \pm3,\ 4$. **154.** 3 days.

156. (1) $\frac{1}{2},\ -\frac{1}{12},\ \frac{5\pm\sqrt{-39}}{24}$. $[(12x-1)(12x-2)(12x-3)(12x-4)=120.]$

(2) $1\pm\sqrt{19}$. $\left[\frac{92}{585}=\frac{1}{5}+\frac{1}{9}-\frac{2}{13}.\right]$

157. 22 years nearly. **161.** 44 hours.

162. (1) $x^2=y^2=\frac{-7\pm\sqrt{217}}{4}$; $x=\pm1,\ \pm2$; $y=\mp2,\ \mp1$; $x=-y=\pm\sqrt{3}$

(2) $x=k(b^4+c^4-a^2b^2-a^2c^2)$, &c., where $2k^2(a^6+b^6+c^6-3a^2b^2c^2)=1$.
[It is easy to shew that $a^2x+b^2y+c^2z=0$, and
$$a^2y+b^2z+c^2x=x^3+y^3+z^3-3xyz=a^2z+b^2x+c^2y.]$$

163. $2(a+b+c)x=(bc+ca+ab)\pm\sqrt{(bc+ca+ab)^2-4abc\,(a+b+c)}$.
[Equation reduces to $(a+b+c)x^2-(bc+ca+ab)x+abc=0$.]

164. (1) $\frac{1}{12}n(n+1)(n+2)(3n+13)$. (2) $2e-5$.

THIS PAGE IS LOCKED TO FREE MEMBERS

Purchase full membership to immediately unlock this page

SAVE $3,999,994

Did you know we sell paperback books too?

To buy our entire catalog in paperback would cost over $4,000,000

Access it all now for $8.99/month

*Fair usage policy applies

Continue

223. (1) $x=y=\frac{1}{3}(\pm 15\pm\sqrt{-3})$, $z=\frac{1}{3}(\pm 15\mp 2\sqrt{-3})$;

or $x=4,\ 6,\ -4,\ -6$;
$y=6,\ 4,\ -6,\ -4$;
$z=5,\ 5,\ -5,\ -5$.

(2) $\frac{x-a}{a(b-c)}=\frac{y-b}{b(c-a)}=\frac{z-c}{c(a-b)}=\lambda$,
where $(b-c)(c-a)(a-b)\lambda=a^2+b^2+c^2-bc-ca-ab$.

226. 12 calves, 15 pigs, 20 sheep. **229.** Lim $\left\{n\left(\frac{u_n}{u_{n+1}}-1\right)\right\}=\frac{3}{2}$; convergent.

230. Scale of relation is $1-12x+32x^2$; n^{th} term $=\frac{1}{2}\{4^{n-1}+8^{n-1}\}$;

$S_n=\frac{2^{2n-1}}{3}+\frac{2^{3n-1}}{7}-\frac{5}{21}$.

231. $\frac{11}{243}$. **232.** $2x=\pm\sqrt{a^2-b^2+c^2}\pm\sqrt{a^2+b^2-c^2}$, &c.

233. $a^3+b^3+c^3=a^2(b+c)+b^2(c+a)+c^2(a+b)$.

235. (1) $(1-x)^4S=1+4x+x^2-(n+1)^3x^n+(3n^3+6n^2-4)x^{n+1}$
$(3n^3+3n^2-3n+1)x^{n+2}+n^3x^{n+3}$

(2) $\frac{1}{8}-\frac{1}{(n+1)^2(n+2)^3}$.

236. $1+a^3x^4+a^5x^8+a^8x^{12}+a^9x^{16}+a^{12}x^{20}+a^{14}x^{24}+a^{17}x^{28}+a^{17}x^{32}+a^{20}x^{36}$

237. 3 hours 51 min. **240.** 2 or $-\frac{1}{2}$. **242.** -140.

244. 3, 4, 5, 6. **246.** $a^3(c^3-3d^3)^2=(ab^2+2d^3)(ab^2-d^3)^2$

247. 2, 6, 1, 3. **248.** $\frac{6}{13}$.

249. (1) $2^{n+1}-2-\frac{1}{6}n(n+1)(2n+1)$.

(2) $\frac{2^{n+1}}{(n+1)(n+3)}-\frac{2}{3}$.

(3) $\frac{1-x^{n+1}}{1-x}+\frac{2(1-2^nx^n)}{1-4x^2}$ when n is even; $\frac{1-x^{n+1}}{1-x}+\frac{2(1-2^{n+1}x^{n+1})}{1-4x^2}$
when n is odd.

250. (1) $x=y=z=0$ or $\frac{a}{3}$. If however $x^2+y^2+z^2+yz+zx+xy=0$, then
$x+y+z=-a$, and the solution is indeterminate.

(2) $\frac{x}{a(-a+b+c)}=\frac{y}{b(a-b+c)}=\frac{z}{c(a+b-c)}$
$=\frac{1}{\pm\sqrt{(-a+b+c)(a-b+c)(a+b-c)}}$.

253. $-(Ax+By+Cz)(-Ax+By+Cz)(Ax-By+Cz)(Ax+By-Cz)$ where
$A=\sqrt{a(b-c)}$, &c.

256. (1) $x=1,\ \omega,\ \omega^2$;
$y=1,\ \omega^2,\ \omega$;
$z=-(a+b),\ -(a\omega+b\omega^2),\ -(a\omega^2+b\omega)$.

(2) $\left.\begin{matrix}x=3,\text{ or }7\\ y=7,\text{ or }3\end{matrix}\right\}\quad\left.\begin{matrix}z=6,\text{ or }-4\\ u=4,\text{ or }-6\end{matrix}\right\}$.

257. To at least $3r-2$ places. **258.** Tea, 2*s.* 6*d.*; Coffee, 1*s.* 8*d.*

262. $2q^2-6pr+24s$. **263.** 11 turkeys, 9 geese, 3 ducks.

266. (1) x, y, z have the permutations of the values

$$a,\ \frac{1}{2}a\left(b-1+\sqrt{b^2-2b-3}\right),\ \frac{1}{2}a\left(b-1-\sqrt{b^2-2b-3}\right).$$

(2) $x=y=z=1$; $x=\dfrac{a+b+c}{a-b-c}$; &c. **267.** 0.

268. 16 Clergymen of average age 45 years;
24 Doctors of average age 35 years;
20 Lawyers of average age 30 years.

269. $(a_0a_2-a_1^2)(a_2a_4-a_3^2)=(a_1a_3-a_2^2)^2$;
or $a_0a_2a_4+2a_1a_2a_3-a_0a_3^2-a_1^2a_4-a_2^3=0$.

270. $x=\pm\dfrac{a^2}{\sqrt{a^2+b^2+c^2}}$, &c. $u=\pm\dfrac{bc}{\sqrt{a^2+b^2+c^2}}$, &c. **273.** $e^{-\frac{1}{2}}$

274. (1) $\left(1-\dfrac{2}{x}\right)\log(1-x)-2$. (2) $\dfrac{1}{a-1}\left\{1-\dfrac{\lfloor n+1}{(a+1)(a+2)\ldots(a+n)}\right\}$.

275. (1) $x=\dfrac{3}{2},\ \dfrac{3}{2},\ 2$;

$y=-1,\ -\dfrac{4}{3},\ -1$;

$z=1,\ \dfrac{3}{4},\ \dfrac{3}{4}$.

(2) $x=\pm4,\ y=\pm5,\ u=\pm2,\ v=\pm1$.

$x=\pm\dfrac{5}{3}\sqrt{\dfrac{2}{3}},\ y=\mp2\sqrt{\dfrac{2}{3}},\ u=\mp\dfrac{1}{3}\sqrt{\dfrac{2}{3}},\ v=\pm\sqrt{\dfrac{2}{3}}$.

276. $a^2+b^2+c^2+d^2+\lambda$. **277.** $-p_1^3+3p_1p_2-3p_3$.

279. A, 6 birds; B, 4 birds. **281.** 2.

287. $a,\ -5a,\ -5a$. **289.** $x_1=-\dfrac{(b_1-a_1)(b_1-a_2)\ldots(b_1-a_n)}{(b_1-b_2)(b_1-b_3)\ldots(b_1-b_n)}$, &c.

291. A worked 45 days; B, 24 days; C, 10 days.

294. $(b^2+c^2-a^2)(a^2-b^2+c^2)(a^2+b^2-c^2)$.

300. Walked 3 miles, worked 4 hours a day;
or walked 4 miles, worked 3 hours a day.

CAMBRIDGE: PRINTED BY C. J. CLAY, M.A. AND SONS, AT THE UNIVERSITY PRESS.